

White Cross Offshore Windfarm Environmental Statement

Chapter 5: Project Description





| Document Code: | FLO-WHI-REP-00016-05 | | | |
|--------------------------------|--------------------------------|----------------------|--|--|
| Contractor Document Number: | PC2978-RHD-ZZ-XX- RP-Z-0384 | | | |
| Version Number: | 01 | | | |
| Date: | Issue Date 07/09/2023 | | | |
| Prepared by: | ТМ | Electronic Signature | | |
| Checked by: | СВ | Electronic Signature | | |
| Owned by: | EF | Electronic Signature | | |
| Approved by Client : | OG | Electronic Signature | | |

| Version Number | Reason for Changes | Issue | / | Major | Date of Change |
|-------------------|-----------------------|-------|---|-------|----------------|
| 00 | For Issue | | | | 16/08/2023 |
| 01 | For Issue | | | | 07/09/2023 |



Table of Contents

| 5. Pro | oject Description | 1 |
|--------|--|----|
| 5.1 | Introduction | 1 |
| 5.2 | Project Design Envelope | 2 |
| 5.3 | Overview of the Project | 3 |
| 5.4 | Landfall (Section 1) | 22 |
| 5.5 | Saunton Golf Club Trenchless Crossing (Section 2) | 31 |
| 5.6 | Onshore Cable Corridor (Sections 3, 4 & 6) | 34 |
| 5.7 | Taw Estuary Trenchless Crossing (Section 5) | 55 |
| 5.8 | Onshore Substation and Grid Connection Point (Section 7) | 57 |
| 5.9 | Operations and Maintenance | 66 |
| 5.10 | Decommissioning | 67 |

Table of Figures

| Figure 5.1 Project Location | 6 |
|--------------------------------------|----|
| Figure 5.2 Onshore Project Section 1 | |
| Figure 5.3 Onshore Project Section 2 | 10 |
| Figure 5.4 Onshore Project Section 3 | 11 |
| Figure 5.5 Onshore Project Section 4 | 12 |
| Figure 5.6 Onshore Project Section 5 | 13 |
| Figure 5.7 Onshore Project Section 6 | 14 |
| Figure 5.8 Onshore Project Section 7 | 15 |

Table of Tables

| Table 5.1 Landfall construction parameters | 29 |
|--|----|
| Table 5.2 Saunton Golf Club crossing construction parameters | 33 |
| Table 5.3 Onshore cable parameters | 35 |
| Table 5.4 Taw Estuary crossing construction parameters | 57 |
| Table 5.5 Onshore Substation construction parameters | 59 |
| Table 5.6 Grid Point of Connection construction parameters | 60 |

Appendices

- Appendix 5.A: Taw Estuary and Braunton Burrows Crossing Method Statement
- Appendix 5.B: Outline Construction Environment Management Plan
- Appendix 5.C: Outline Drainage Strategy
- Appendix 5.D: Onshore Export Cable Corridor Alignment Sheets
- Appendix 5.E: Onshore Substation Indicative Designs
- Appendix 5.F: Project Parameters Table
- Appendix 5.G: Crossing Schedule



Glossary of Acronyms

| Acronym | Definition |
|-----------------|---|
| AC | Alternating Current |
| AfL | Agreement for Lease |
| AIS | Automatic Identification System |
| AOD | Above Ordnance Datum |
| CBS | Cement Bound Sand |
| CfD | Contracts for Difference |
| EIA | Environmental Impact Assessment |
| ES | Environmental Statement |
| FEED | Front-end engineering and design |
| FFL | Finished Floor Level |
| GIS | Gas Insulated Switchgear |
| ha | Hectare |
| HDD | Horizontal Directional Drilling |
| HDPE | High Density Polyethylene |
| HGV | Heavy Goods Vehicle |
| HVAC | Heating, Ventilation and Air Conditioning |
| IDB | Internal Drainage Board |
| km | Kilometre |
| Km ² | Square kilometre |
| m | Metre |
| MHWS | Mean High Water Springs |
| MLWS | Mean Low Water Springs |
| MW | Megawatts |
| NGED | National Grid Electricity Distribution |
| OFTO | Offshore Transmission Owner |
| OLEMP | Outline Landscape & Ecology Mitigation Plan |
| OSP | Offshore Substation Platform |
| PDE | Project Design Envelope |
| SAC | Special Area of Conservation |
| SSSI | Site of Special Scientific Interest |
| TCE | The Crown Estate |
| ТСРА | Town and Country Planning Act |
| ТЈВ | Transition Joint Bay |
| UXO | Unexploded Ordnance |
| WCOWL | White Cross Offshore Windfarm Ltd |
| WTG | Wind Turbine Generator |



Glossary of Terminology

| Defined Term | Description |
|--|---|
| Agreement for Lease | An Agreement for Lease (AfL) is a non-binding agreement between a landlord and prospective tenant to grant and/or to accept a lease in the future. The AfL only gives the option to investigate a site for potential development. There is no obligation on the developer to execute a lease if they do not wish to. |
| Applicant | White Cross Offshore Wind Farm Limited |
| Department for Energy Security and Net Zero | Government department that is responsible for business, industrial strategy, science and innovation and energy and climate change policy and consent under Section 36 of the Electricity Act. |
| Dynamic cables | The floating substructures will require cables to run through the water column from their platform base at the water surface to the touchdown point on the seabed. |
| Environmental Impact Assessment | Assessment of the potential impact of the proposed Project on the physical, biological and human environment during construction, operation and decommissioning. |
| Export Cable Corridor | The area in which the export cables will be laid, either from the Offshore Substation or the inter-array cable junction box (if no offshore substation), to the NG Onshore Substation comprising both the Offshore Export Cable Corridor and Onshore Export Cable Corridor. |
| Floating substructure | The floating substructure acts as a stable and buoyant foundation for the WTG. The WTG is connected to the substructure via the transition piece and the substructure is kept in position by the mooring system. |
| Front end engineering and design | Front-end engineering and design (FEED) studies address areas of windfarm system design and develop the concept of the windfarm in advance of procurement, contracting and construction. |
| Generation Assets | The infrastructure of the Project related to the generation of electricity within the windfarm site, including wind turbine generators, substructures, mooring lines, seabed anchors and inter-array cables |
| High Voltage Alternating Current | High voltage alternating current is the bulk transmission of electricity by alternating current (AC), whereby the flow of electric charge periodically reverses direction. |
| High Voltage Direct Current | High voltage direct current is the bulk transmission of electricity by direct current, whereby the flow of electric charge is in one direction. |
| Inter-array cables | Cables which link the wind turbines to each other and the Offshore Substation Platform, or at the inter-array cables junction box (if no offshore substation). Array cables will connect the wind turbines to one and other and to the Offshore Substation (if utilised). The initial section for the inter-array cables will be freely suspended in the water column below the substructure (dynamic sections) while the on seabed sections of the cables will be buried where possible. |
| Jointing bay | Underground structures constructed at regular intervals along the Onshore Export Cable Corridor to join sections of cable and facilitate installation of the cables into the buried ducts |



| Defined Term | Description |
|--|--|
| Landfall | Where the Offshore Export Cables come ashore |
| Link boxes | Underground chambers or above ground cabinets next to the cable trench housing electrical earthing links |
| Mean high water springs | The average tidal height throughout the year of two successive high waters during those periods of 24 hours when the range of the tide is at its greatest. |
| Mean low water springs | The average tidal height throughout a year of two successive low waters during those periods of 24 hours when the range of the tide is at its greatest. |
| Mooring system | The equipment (mooring lines and seabed anchors) that keeps the floating substructure in position during operation through a fixed connection to the seabed. |
| Mitigation | Mitigation measures have been proposed where the assessment identifies that an aspect of the development is likely to give rise to significant environmental impacts, and discussed with the relevant authorities and stakeholders in order to avoid, prevent or reduce impacts to acceptable levels. |
| | For the purposes of the EIA, two types of mitigation are defined: |
| | Embedded mitigation: consisting of mitigation measures that are identified and adopted as part of the evolution of the project design, and form part of the project design that is assessed in the EIA |
| | Additional mitigation: consisting of mitigation measures that are identified during the EIA process specifically to reduce or eliminate any predicted significant effects. Additional mitigation is therefore subsequently adopted by WCOWL as the EIA process progresses. |
| National Grid Onshore Substation | Part of an electrical transmission and distribution system. Substations transform voltage from high to low, or the reverse by means of the electrical transformers. |
| National Grid Connection Point | The point at which the White Cross Offshore Windfarm connects into the distribution network at East Yelland substation and the distributed electricity network. From East Yelland substation electricity is transmitted to Alverdiscott where it enters the national transmission network. |
| Offshore Development Area | The Windfarm Site (including wind turbine generators, substructures, mooring lines, seabed anchors, inter-array cables and Offshore Substation Platform (as applicable)) and Offshore Export Cable Corridor to MHWS at the Landfall. This encompasses the part of the project that is the focus of this application and Environmental Statement and the parts of the project consented under Section 36 of the Electricity Act and the Marine and Coastal Access Act 2009. |
| Offshore Export Cables | The cables which bring electricity from the Offshore Substation Platform or the inter-array cables junction box to the Landfall. |
| Offshore Export Cable Corridor | The proposed offshore area in which the export cables will be laid, from Offshore Substation Platform or the inter-array cable junction box to the Landfall. |



| Defined Term | Description |
|-------------------------------------|--|
| Offshore Infrastructure | All of the offshore infrastructure including wind turbine generators, substructures, mooring lines, seabed anchors, Offshore Substation Platform and all cable types (export and inter-array). This encompasses the infrastructure that is the focus of this application and Environmental Statement and the parts of the project consented under Section 36 of the Electricity Act and the Marine and Coastal Access Act 2009. |
| the Offshore Project | The Offshore Project for the offshore Section 36 and Marine Licence application includes all components offshore of MHWS. This includes the infrastructure within the windfarm site (e.g. wind turbine generators, substructures, mooring lines, seabed anchors, inter-array cables and Offshore Substation Platform (as applicable)) and all infrastructure associated with the Onshore Export Cable Corridor and Landfall (up to MHWS) including the cables and associated cable protection (if required). |
| Offshore Substation Platform | A fixed structure located within the Windfarm Site, containing electrical equipment to aggregate the power from the wind turbines and convert it into a more suitable form for export to shore. |
| Offshore Transmission Assets | The aspects of the project related to the transmission of electricity from the generation assets including the Offshore Substation Platform (as applicable)) or offshore junction box, Offshore Cable Corridor to MHWS at the Landfall. |
| Offshore Transmission Owner | An OFTO, appointed in UK by Ofgem (Office of Gas and Electricity Markets), has ownership and responsibility for the transmission assets of an offshore windfarm. |
| Onshore Development Area | The onshore area above MLWS including the underground onshore export cables connecting to the White Cross Onshore Substation and onward to the NG grid connection point at East Yelland. The onshore development area will form part of a separate Planning application to the Local Planning Authority under the Town and Country Planning Act 1990. |
| Onshore Export Cables | The cables which bring electricity from MLWS at the Landfall to the White Cross Onshore Substation and onward to the NG grid connection point at East Yelland. |
| Onshore Export Cable Corridor | The proposed onshore area in which the export cables will be laid, from MLWS at the Landfall to the White Cross Onshore Substation and onward to the NG grid connection point at East Yelland. |
| Onshore Infrastructure | The combined name for all infrastructure associated with the Project from MLWS at the Landfall to the NG grid connection point at East Yelland. The onshore infrastructure will form part of a separate Planning application to the Local Planning Authority (LPA) under the Town and Country Planning Act 1990. |
| Onshore Transmission Assets | The aspects of the project related to the transmission of electricity from MLWS at the Landfall to the NG grid connection point at East Yelland including the Onshore Export Cable, the White Cross Onshore Substation and onward connection to the NG grid connection point at East Yelland. |
| the Onshore Project | The Onshore Project for the onshore TCPA application includes all components onshore of MLWS. This includes the infrastructure associated with the offshore export cable (from MLWS), landfall, onshore export |



| Defined Term | Description |
|--|---|
| | cable and associated infrastructure and new onshore substation (if required). |
| the Project | the Project is a proposed floating offshore windfarm called White Cross located in the Celtic Sea with a capacity of up to 100MW. It encompasses the project as a whole, i.e. all onshore and offshore infrastructure and activities associated with the Project. |
| Project Design Envelope | A description of the range of possible components that make up the Project design options under consideration. The Project Design Envelope, or 'Rochdale Envelope' is used to define the Project for Environmental Impact Assessment purposes when the exact parameters are not yet known but a bounded range of parameters are known for each key project aspect. |
| Transition joint bay | Underground structures at the Landfall that house the joints between the Offshore Export Cables and the onshore export cables. |
| Transition piece | The transition piece includes various functionalities such as access for maintenance, cable connection for the energy of the turbine and the corrosion protection of the entire foundation. |
| White Cross Offshore Windfarm | 100MW capacity offshore windfarm including associated onshore and offshore infrastructure. |
| White Cross Offshore Wind Farm Limited | White Cross Offshore Wind Ltd (WCOWL) is a joint venture between Cobra Instalaciones Servicios, S.A., and Flotation Energy Ltd |
| White Cross Onshore Substation | A new substation built specifically for the White Cross project. It is required to ensure electrical power produced by the offshore windfarm is compliant with NG electrical requirements at the grid connection point at East Yelland. |
| Wind Turbine Generators (WTG) | The wind turbine generators convert wind energy into electrical power. Key components include the rotor blades, nacelle (housing for electrical generator and other electrical and control equipment) and tower. The final selection of project wind turbine model will be made post-consent application. |
| Windfarm Site | The area within which the wind turbines, Offshore Substation Platform and inter-array cables will be present. |
| Works completion date | Date at which construction works are deemed to be complete and the windfarm is handed to the operations team. In reality, this may take place over a period of time. |



5. Project Description

5.1 Introduction

- This chapter of the Environmental Statement (ES) presents the description of the White Cross Offshore Windfarm Project (landward of Mean Low Water Spring (MLWS)) which is hereafter referred to as 'the Onshore Project'.
- 2. The Onshore Project is being developed by White Cross Offshore Windfarm Ltd (WCOWL) a joint venture between Cobra Instalaciones Servicios, S.A., and Flotation Energy Ltd.
- 3. This chapter provides a full description of components and installation required for construction, operation, maintenance, and decommissioning of the Onshore Project. These components have been compiled into a single over-arching Project Parameters Table in **Appendix 5.F**. The details provided inform and underpin the assessments that have been undertaken, although **Chapters 8** to **24** should be referred to for details of the realistic worst-case scenarios that apply to each topic.
- 4. Planning permission under the Town and Country Planning Act 1990 (TCPA 1990) is required for the following onshore infrastructure assets (landward of Mean Low Water Springs):
 - Onshore export cables
 - White Cross Onshore Substation
 - Onshore Export Cables (66kV or 132kV from Landfall to onshore substation and 132kV from the White Cross Onshore Substation to Grid Point of Connection)
 - Temporary main construction compound and temporary construction compounds
 - Transition Joint Bay (TJB), jointing bays, link boxes
 - Access roads and haul roads
 - Grid connection works within the existing East Yelland substation.
- 5. A separate set of consents/permission is required in order for the Offshore Project (all infrastructure and activities seaward of Mean High Water Spring (MHWS) to proceed and these have been applied for separately and a separate Environmental Impact Assessment (EIA) was undertaken as part of this. Full details are as follows:
 - Consent under the Section 36 of the Electricity Act 1989 and a Marine Licence under the Marine and Coastal Access Act 2009 (MCAA 2009) are required for the following generation assets (within the Windfarm Site):
 - Wind Turbine Generators
 - Semi-submersible floating platforms



- Subsea catenary mooring lines
- Anchoring solutions (drag embedment anchors, suction anchor or pin piles)
- Inter-array cables and associated protection
- Other associated offshore infrastructure, such as navigational markers.
- A second Marine Licence is required to enable the option for an Offshore Transmission Owner (OFTO) to be appointed under The Electricity (Competitive Tenders for Offshore Transmission Licences) Regulations 2015 for the following transmission assets:
 - Offshore Substation Platform (OSP)
 - Offshore Export Cable (to MHWS at Landfall)
 - Other associated offshore infrastructure, such as navigational markers
 - Taw Estuary Crossing (between MHWS on the northern edge to MHWS on the southern edge).
- 6. Further detail on the consenting regime and relevant legislation is presented in **Chapter 3: Policy and Legislative Context**.

5.2 Project Design Envelope

- 7. At this stage in the development of the Onshore Project, the proposed design and precise location of the components of the development are not fixed. A project design envelope (PDE) approach has been utilised in order to set parameters for the EIA. Further details of the use of a PDE or "Rochdale envelope" are provided in **Chapter 6: EIA Methodology**. This is considered a standard approach and is widely accepted by all stakeholders.
- 8. The PDE sets out a series of design options for the Onshore Project and has a reasoned best and worst case extent for a number of key parameters. The final design would lie between the minimum and the maximum extent of the consent sought, for all aspects of the Onshore Project; this includes spatial and temporal components, and the proposed methodology to be employed.
- 9. The PDE is used to establish the extent to which the Onshore Project could impact on the environment. The final detailed design of the Onshore Project will fall within this 'envelope', allowing for detailed design work to be undertaken post-consent without rendering the assessment inadequate.
- 10. Therefore, the information presented in this chapter outlines the options and flexibility required and the range of potential design, location and activity parameters upon which the subsequent impact assessment **Chapters 8 to 24** are based.



- 11. The need for flexibility in the consent is a key aspect of any large development but is particularly significant for offshore wind projects where technology continues to evolve quickly. The PDE must therefore provide sufficient flexibility to enable the Applicant and its contractors to use the most up to date, efficient and cost-effective technology and techniques in the construction, operation, maintenance and decommissioning of the Onshore Project, without compromising the surrounding environment further than the worst-case scenarios assessed in this ES.
- 12. Where appropriate, each impact assessment chapter (**Chapters 8 to 24**) contains a section detailing the realistic worst-case scenario for specific receptors and impacts. These realistic worst-case scenario sections are derived from the information provided in this chapter.
- 13. Design work is ongoing with the intention that the more detailed design work will be completed post-consent. In addition, post-consent/pre-construction site investigation will further inform the detailed design. Key aspects for which flexibility is required include:
 - Landfall construction method will be either via trenchless techniques or open-cut trenching, including potential use of cofferdams, allowing for unknown ground conditions
 - Onshore Export Cable Corridor allows for micro-siting of the cable route and, for example, crossings of existing utilities and other assets
 - Onshore substation maximum parameters allows for flexibility subject to detailed design
 - In certain areas, i.e. where trenchless techniques are to be used to install the onshore export cables, or where the Onshore Export Cables connect to the Offshore Export Cables (TJB), or to accommodate temporary construction compounds, a wider site boundary is provided
 - Construction timing and methodologies are to be fully developed once project design is finalised and installation contractors are appointed
 - Operation and maintenance activities will be adjusted to the final as-built project requirements
 - Decommissioning timing and methodologies to be fully developed once project design is finalised.

5.3 Overview of the Project

14. An illustration of the main components of the Onshore Project is provided in **Plate5.1** alongside the main components of the Offshore Project. The Offshore Export



Cable will make Landfall at Saunton Sands on the North Devon coast. The Onshore Project location is shown in **Figure 5.1**.







Plate 5.1 Project Infrastructure



| | | | | SI 70 | | |
|--|--------------|--|--|--|----------------|--|
| STAPL OA EFORD BAY | E Bio | Northam The Solution Atomic Solution Man Solution Man Solution | boding Georgeham Kowk s Boding Boding Boding Boding Construction Const | Pricken Bicking dr. Bicking dr | BIANGES SAVION | |
| | shore Develo | | | | | |
| | Export Cab | le Corrid | or Section | S | | |
| Sec | ction 1 | | | | | |
| | ction 2 | | | | | |
| Sec | ction 3 | | | | | |
| Sec | ction 4 | | | | | |
| Sec | ction 5 | | | | | |
| Sec | ction 6 | | | | | |
| Sec | ction 7 | | | | | |
| | | | | | | |
| ent: | | | Project: | | | |
| Offs | hore Wind L | td. | | /hite Cro ore Win | | |
| e: | | | | | | |
| | | Project L | ocation | | | |
| ^{ure:} 5. | 1 Drawin | ^{g No:} PC | 2978-RHD- | ZZ-XX-[| DR-Z-0725 | |
| vision: | Date: | Drawn: | Checked: | Size: | Scale: | |
| P01 | 11/08/2023 | AB | СВ | A3 | 1:30,000 | |
| | | | | | | |
| ordinate system: British National Grid | | | | | | |
| WHITE CROSS | | | | | | |



5.3.1 Overview of the Offshore Project components

- 15. The Windfarm Site is located approximately 52km north-west of the Cornwall and Devon coastline in a water depth of 69m 78m LAT and covers an area of approximately 50km². The Offshore Project will have a generating capacity of up to 100MW, and there will be a minimum of 5 and maximum of 8 Wind Turbine Generators (WTG) depending on the size and capacity of the individual WTG. The decision about the technology of WTG to use, including the individual size and capacity, will be made post consent as part of the detailed design process.
- 16. It is assumed that the WTG will be connected, via an inter-array cable, to an OSP. The requirement for and location of the OSP will also be determined post consent as part of the detailed design process. The electricity from the Windfarm Site will be transmitted by either via one or two subsea export cable(s) to shore depending on whether an OSP is required. The Offshore Export Cable will make Landfall at Saunton Sands on the North Devon coast where it will be connected to the Onshore Export Cable via a TJB located in Saunton Sands Car Park.
- 17. Further details of these offshore components are described and assessed within the separate Offshore Project application.

5.3.2 Overview of the Onshore Project components

- 18. Above MHWS at Landfall, the Offshore Export Cable will be connected to the Onshore Export Cable via a TJB located in Saunton Sands Car Park. The Onshore Export Cable travels approximately 8km at its maximum inland to a high voltage alternating current onshore substation. This will include a crossing below the Taw Estuary via trenchless technology, which is assessed as part of this Onshore ES. A new White Cross Onshore Substation will be constructed to accommodate the connection of the Offshore Project to the existing East Yelland substation and Grid Point of Connection.
- 19. The key onshore components of the Onshore Project are as follows:
 - Onshore Export Cables (2 x 66kV or 1 x 132kV from Landfall to the White Cross Onshore Substation and 132kV from the White Cross Onshore Substation to existing East Yelland substation and the Grid Point of Connection)
 - TJB, joint bays and link boxes installed along the Onshore Export Cable
 - Trenchless crossing at certain locations such as sensitive habitats and large watercourse crossings
 - Open cut trenching where possible




- Temporary main construction compound and up to four temporary construction compounds
- Temporary access roads and haul roads
- A new White Cross Onshore Substation
- Connection to the National Grid Onshore Substation and Grid Connection Point
- Permanent access to the White Cross Onshore Substation during its operation.

5.3.3 Overview of the Onshore Development Area


5.3.3.1 Onshore Development Area

- 20. The jurisdiction of onshore planning extends down to MLWS¹. Therefore, the Onshore Development Area is defined as the point from MLWS at Landfall to the Grid Point of Connection at the existing East Yelland substation. The Onshore Development Area is shown in **Figure 5.1**.
- 21. To aid environmental assessment and design development the Onshore Export Cable Corridor has been divided into seven sections as illustrated in Figures 5.2 to 5.8 and an overview provided within the following sections. Further details of the construction, operation and maintenance, and decommissioning activities are provided within Sections 5.4 to 5.10.
- 22. Indicative designs and layouts for the Onshore Export Cable Corridor and Onshore Substation are provided in **Appendix 5.D** and **Appendix 5.E**.


¹ Certain works will span across the offshore and onshore consent boundaries, through the intertidal area, such as HDD and/or open cut trenching.




| <pre>interfactor interfactor i</pre> | | | | | | | | |
|--|--------|--------|---------------------|-----|----------|---------------------|-----------|--|
| ent: | | | | Pi | roject: | | | |
| Offs | hore V | Vind L | td. | | | hite Cro ore Win | | |
| e: Onshore Project Section 1 | | | | | | | | |
| ^{ure:} 5. | 2 | Drawin | ^{g No:} PC | 229 | 978-RHD- | ZZ-XX-[| DR-Z-0726 | |
| vision: | Dat | te: | Drawn: | | Checked: | Size: | Scale: | |
| P01 | 11/08/ | 2023 | AB | | СВ | A3 | 1:6,000 | |
| | | | | | | | | |
| ordinate system: British National Grid | | | | | | | | |
| WHITE CROSS | | | | | | | | |



| In the constraint of the co | | | | | | | | | |
|---|---------|--------|---------------------|----------------------------------|----------|-----------|--|--|--|
| | | | | | | | | | |
| | | | | | | | | | |
| ent: | | | | Project: | | | | | |
| Offs | shore V | Vind L | td. | White Cross Offshore Windfarm | | | | | |
| e: Onshore Project Section 2 | | | | | | | | | |
| ^{ure:} 5. | 3 | Drawin | ^{g No:} PC | 2978-RHD | -ZZ-XX-I | DR-Z-0727 | | | |
| vision: | Dat | te: | Drawn: | Checked: | Size: | Scale: | | | |
| P01 | 11/08/ | /2023 | AB | СВ | A3 | 1:8,000 | | | |
| | | | | | | | | | |
| ordinate | system | : Brit | tish Natio | nal Grid | | | | | |
| ordinate system: British National Grid | | | | | | | | | |



| <pre>interfactor interfactor i</pre> | | | | | | | | | |
|--|----------|------|---------------------|----------------------------------|-----------|---------|-----------|--|--|
| ent: | | | | Ρ | roject: | | | | |
| Offsh | ore Win | d Li | td. | White Cross Offshore Windfarm | | | | | |
| 9: | Or | nsh | ore Proje | ec | t Section | 3 | | | |
| ^{ure:} 5.4 | Dra | wing | ^{g No:} PC | 2 | 978-RHD- | ZZ-XX-[| DR-Z-0728 | | |
| vision: | Date: | | Drawn: | | Checked: | Size: | Scale: | | |
| P01 1 | 1/08/202 | 23 | AB | | СВ | A3 | 1:12,500 | | |
| | | | | | | | | | |
| ordinate sy | ystem: | Brit | ish Natio | na | al Grid | | 1 | | |
| ordinate system: British National Grid | | | | | | | | | |




| | | | | _ | | | | | | |
|--|--------|---------|---------------------|----------------------------------|----------|---------|-----------|--|--|--|
| <pre>with the second se</pre> | | | | | | | | | | |
| ent: | | | | P | Project: | | | | | |
| Offs | hore V | Nind L | td. | White Cross Offshore Windfarm | | | | | | |
| ə: | | | | | | | | | | |
| Onshore Project Section 4 | | | | | | | | | | |
| ^{ure:} 5. | 5 | Drawin | ^{g No:} PC | 22 | 978-RHD- | ZZ-XX-[| DR-Z-0729 | | | |
| vision: | Da | te: | Drawn: | | Checked: | Size: | Scale: | | | |
| P01 | 11/08 | /2023 | AB | | СВ | A3 | 1:10,000 | | | |
| | | | | _ | | | | | | |
| ordinate | system | 1: Brit | tish Natio | na | al Grid | | | | | |
| ordinate system: British National Grid | | | | | | | | | | |



| <pre>interior interior interio</pre> | | | | | | | | | |
|--|--------|--------------------|---------------------|----------------------------------|-----------|---------|-----------|--|--|
| ent: | | | | Ρ | roject: | | | | |
| Offs | hore V | Wind L | td. | White Cross Offshore Windfarm | | | | | |
| 9: | | Onsh | ore Proje | ec | t Section | 5 | | | |
| ure: 5. | 6 | Drawin | ^{g No:} PC | 2 | 978-RHD- | ZZ-XX-[| DR-Z-0730 | | |
| vision: | Da | te: | Drawn: | | Checked: | Size: | Scale: | | |
| P01 | 11/08 | /2023 | AB | | СВ | A3 | 1:6,000 | | |
| ordinate | system | ^{1:} Brit | tish Natio | na | al Grid | | 1 | | |
| ordinate system: British National Grid | | | | | | | | | |



| <pre>interfactor interfactor i</pre> | | | | | | | | | |
|--|-------------|---------------------|----------------------------------|---------|-----------|--|--|--|--|
| ent: | | | Project: | | | | | | |
| Offs | hore Wind L | td. | White Cross Offshore Windfarm | | | | | | |
| e: | | I | | | | | | | |
| | Onsh | iore Proje | ect Section | 6 | | | | | |
| ^{ure:} 5. | 7 Drawin | ^{g No:} PC | 2978-RHD- | ZZ-XX-C | DR-Z-0731 | | | | |
| vision: | Date: | Drawn: | Checked: | Size: | Scale: | | | | |
| P01 | 11/08/2023 | AB | СВ | A3 | 1:8,000 | | | | |
| | | | | | | | | | |
| ordinate | system: Bri | tish Natio | nal Grid | | | | | | |
| | | | | | | | | | |
| WHITE CROSS | | | | | | | | | |



| <pre>inter inter i</pre> | | | | | | | | | | |
|--|-------------|---------|---------------------|----------------------------------|-----------|---------|-----------|--|--|--|
| ent: | | | | P | roject: | | | | | |
| Offs | hore \ | Wind L | td. | White Cross Offshore Windfarm | | | | | | |
| ə: | | | 1 | | | | | | | |
| | | Onsh | ore Proje | ec | t Section | 7 | | | | |
| ^{ure:} 5. | 8 | Drawin | ^{g No:} PC | 22 | 978-RHD- | ZZ-XX-[| DR-Z-0732 | | | |
| vision: | Da | ite: | Drawn: | | Checked: | Size: | Scale: | | | |
| P01 | 11/08 | /2023 | AB | | СВ | A3 | 1:6,000 | | | |
| | | | | | | | | | | |
| ordinate | system | 1: Brit | tish Natio | na | I Grid | | | | | |
| 4 | A #1 | | | | 5 | val | | | | |
| 1 | WHITE CROSS | | | | | | | | | |



5.3.3.2 Section 1 Landfall Area (from MLWS)

- 23. Section 1 runs eastwards inland from MLWS to the eastern end of the Saunton Sands Car Park. The construction methodology at Landfall (to MLWS) along the beach and into the car park will be undertaken using either open trench or a trenchless technique within the spatial extent defined by the Onshore Development Area are shown in **Figure 5.2**.
- 24. The car park is the proposed location of the temporary Landfall compound, trenchless installation rig, and the TJB. From there, it turns southeast to cross Saunton Golf Course using a trenchless technique.

5.3.3.3 Section 2 Saunton Golf Club (Trenchless Technology)

- 25. Section 2 runs southeast crossing Saunton Golf Club (see **Figure 5.3**). Access routes required for geotechnical investigation and for maintenance activities is provided from the existing access to Saunton Golf Club from Saunton Road. Careful environmental and technical consideration have been taken to determine the access routes of least impact to the operations of the Saunton Golf Club.
- 26. The Onshore Export Cable in this section will be installed using trenchless techniques within the spatial extent defined by the Onshore Development Area.

5.3.3.4 Section 3 North Fields (north of Sandy Lane Car Park)

- 27. Section 3 runs southeast and then south from the eastern edge of Saunton Golf Club through arable fields and crossing 11 field boundaries and drainage ditches before extending to the field to the north of Sandy Lane Car Park (see **Figure 5.4**).
- 28. The construction methodology within this section is still to be determined but will be undertaken using either open cut or trenchless techniques within the spatial extent defined by the Onshore Development Area. Micro-siting during detailed design will seek to ensure the route of least impact is chosen.
- 29. To the north of Section 3 is a new temporary access route that will be utilised to provide access to Onshore Development Area during the cable installation. For more details on the access strategy see **Section 5.3.3.9** Onshore Access Strategy below.

5.3.3.5 Section 4 South Fields (south of Sandy Lane Car Park)

30. Section 4 passes south extending from the east of Sandy Lane Car Park to the Taw Estuary Crossing (Figure 5.5). The Onshore Export Cable Corridor will cross from Section 3 to the pastural fields to the east of Sandy Land Car Park using trenchless technology to avoid disturbance to vegetation on the boundaries of Braunton



Burrows Special Area of Conservation (SAC) and Greenaways and Freshmarsh, Braunton Site of Special Scientific Interest (SSSI).

31. The construction methodology within this section is still to be determined but will be undertaken using either open cut or trenchless techniques within the spatial extent defined by the Onshore Development Area. Micro-siting during detailed design will seek to ensure that a route which minimise environmental impact is chosen.

5.3.3.6 Section 5 The Taw Estuary Crossing using Trenchless Technology

32. Section 5 contains the Taw Estuary Crossing and extends from the northern edge to the southern edge of the River Taw (see Figure 5.6). The methodology to install the Onshore Export Cable underneath the River is via a trenchless technique which is expected to be Horizontal Directional Drill (HDD) or Direct Pipe. A temporary construction compound will be required at both ends of this crossing to facilitate the trenchless solution. A construction method statement for the Taw Estuary Crossing is provided in **Appendix 5.A**. This crossing is also assessed in the Environmental statement (ES) submitted to support the application for the Offshore Project as the Taw Estuary is tidal so therefore there are areas which are below MLWS.

5.3.3.7 Section 6 Connection to the White Cross Onshore Substation

- 33. Section 6 runs southeast from the southern edge of the Taw Estuary Crossing towards the White Cross Onshore Substation (see Figure 5.7). The Onshore Export Cable installation methodology in this section is expected to be a combination of opencut and trenchless technique but is yet to be determined.
- 34. The crossing of the Tarka Trail and below the existing Overhead Lines from the East Yelland substation will be via a trenchless technique.

5.3.3.8 Section 7 White Cross Onshore Substation to Grid Connection Point

35. The White Cross Onshore Substation will be located to the west of the Estuary Business Park partly on the site of a former oil storage depot. Cables will exit the onshore substation running east/north for 350m towards the grid connection point at East Yelland substation. This section will be installed by a combination of open cut and trenchless techniques, including a crossing of the Tarka Trail via a trenchless technique (**Figure 5.8**).

5.3.3.9 Onshore Access Strategy

36. The access strategy for the Onshore Project has been designed to avoid Heavy Goods Vehicles (HGVs) acceding the narrow local roads, and where possible to keep



traffic associated with the construction phase of the Onshore Project within the onshore export cable construction corridor.

37. Further details of the onshore access strategy, including the proposed mitigation measures can be found in **Chapter 19: Traffic & Transport**. The proposed access routes are shown on **Appendix 19.A** *Figure 1*.

5.3.3.9.1 Early works access

- 38. In advance of the main construction activity, access will be required to undertake survey activities and other early works along the onshore cable corridor to facilitate the finalising of mitigation and construction methodologies. Some early works accesses would be required to facilitate initial works to create the construction accesses.
- 39. Early works accesses would be very short term in nature, requiring limited personnel and materials. Given their very short term and low impact nature, it is proposed that early works activities would be undertaken using vehicles capable of utilising existing access points such as field gates and the existing highways network.

5.3.3.9.2 Construction access

- 40. The proposed access strategy for construction access contains up to three points of access for HGVs from the public highway, and a haul road crossing, allowing traffic to cross the highway only.
- 41. The access locations would allow construction traffic to access and egress from the from the public highway. Where accesses are located opposite each other, they would also allow construction traffic to cross from one side of the public highway to the other i.e., to traverse along the temporary haul road and minimise trips on the local highway network.
- 42. Access to the Landfall site from the public highway is via the existing Saunton Sands car park junction with the B3231 Saunton Road. The junction operates as a priority 'T' junction, with the car park access giving way to Saunton Road. Saunton Road is subject to a 30 mph speed restriction in the vicinity of the access. A bus stop layby is provided opposite the junction.
- 43. The proposed priority access from the B3231 Saunton Road into the consolidated construction site is located west of Broad Lane / Blind Acres staggered crossroads. This junction has been designed with visibility splays of 2.4 m by 120/90m (see **Appendix 19.A, Annex 5: Outline access designs**), based on the outcome of speed surveys that identified an 85th percentile speed of 38.7 mph. The junction has



been designed to accommodate the largest anticipated construction vehicles, i.e., a 16.5 m maximum legal length articulated HGV.

- 44. Two priority junctions are proposed east and west of Sandy Lane to create a haul road crossing. The junctions have been designed to minimise impact on surrounding vegetation whilst allowing a 16.5 m maximum legal length articulated HGV to manoeuvre from east to west and vice versa. No traffic management would be proposed for Sandy Lane. Given the narrow, rural nature of Sandy Lane, 2.4 m by 40 m visibility splays are proposed (see **Appendix 19.A, Annex 5: Outline access designs**).
- 45. The construction access for the White Cross Onshore Substation would connect onto an existing private access road running south to the public highway at the B3233 West Yelland. It is not proposed to alter the existing priority junction between the B3233 West Yelland and the private access road, which already accommodates HGVs.
- 46. A haul road crossing of the Tarka Trail long distance footpath and cycleway is proposed. The crossing would utilise existing field gates on either side of the Tarka Trail and would be subject to traffic management by banksmen to ensure the safety of pedestrians and cyclists.
- 47. This strategy has been developed to minimise the impact of HGVs upon the local highway network, focussing HGVs on exiting classified roads wherever practical.
- 48. It is proposed that all construction accesses and crossings except the substation access would be temporary and following completion of construction works would be removed and reinstated.

5.3.3.9.3 Operational access

- 49. Upon completion of the construction works there will be a requirement for periodic visits to the onshore substation to undertake routine checks and carry out maintenance. The onshore substation is not however expected to be permanently manned.
- 50. These movements would typically be made by light vehicles, cars, vans, etc. However, occasional access may be required by HGVs to deliver larger components. The projects' transformers are designed not to require replacement during the lifetime of the project and as such, operational access for abnormal loads is not anticipated to be required.



5.3.4 Overview of programme

- 51. It is anticipated that the realistic worst-case for construction of the Onshore Project will take 28 months (18 months for cable installation and 16 months for the White Cross Onshore Substation Construction). The operational phase of the Onshore Project will last for 50 years, the decommissioning phase is anticipated to last up to 18 months.
- 52. A high-level development and installation programme is provided in **Plate 5.2**.



| | | 2023 | | | 2024 | | | 2025 | | | 2026 | | | | 2027 | | | | | |
|---|----|------|----|----|------|----|----|------|----|----|------|----|----|----|------|----|----|----|----|----------|
| Task | Q1 | Q2 | Q3 | Q4 | Q1 | Q2 | Q3 | Q4 | Q1 | Q2 | Q3 | Q4 | Q1 | Q2 | Q3 | Q4 | Q1 | Q2 | Q3 | Q4 |
| Submission of ES | | | | | | | | | | | | | | | | | | | | |
| FEED | | | | | | | | | | | | | | | | | | | | |
| CfD Application | | | | | | | | | | | | | | | | | | | | |
| FID | | | | | | | | | | | | | | | | | | | | |
| Detailed Design | | | | | | | | | | | | | | | | | | | | |
| Construction (Offshore) | | | | | | | | | | | | | | | | | | | | |
| Construction (Onshore) | | | | | | | | | | | | | | | | | | | | |
| Landfall | | | | | | | | | | | | | | | | | | | | |
| Golf Course Crossing | | | | | | | | | | | | | | | | | | | | |
| Onshore Export Cable Early/Enabling Works | | | | | | | | | | | | | | | | | | | | |
| Onshore Export Cable | | | | | | | | | | | | | | | | | | | | |
| Taw Estuary Crossing | | | | | | | | | | | | | | | | | | | | |
| Onshore Substation | | | | | | | | | | | | | | | | | | | | |
| Final Commissioning of WTGs | | | | | | | | | | | | | | | | | | | | |
| Start-Up of White Cross | | | | | | | | | | | | | | | | | | | | <u> </u> |

Plate 5.2: Indicative development and installation programme for the Onshore Project



5.4 Landfall (Section 1)

5.4.1 Background

- 53. Electricity from the Windfarm Site will be transmitted via subsea Offshore Export Cable.
- 54. The Landfall is the point at which the Offshore Export Cables come ashore and are joined with the Onshore Export Cables within a TJB. It is proposed for the Project that the Offshore Export Cables will make Landfall at Saunton Sands Car Park.
- 55. The choice of Saunton Sands as the location for the Landfall was the result of a site selection process, considering environmental and technical constraints. The site selection process is described in **Chapter 4: Site Selection and Assessment of Alternatives**.

5.4.2 Landfall Infrastructure

56. The Offshore Export Cable will be formed of either one or two circuits depending on whether an OSP is required. Each offshore export circuit would have three conductors (one for each phase) and a fibre-optic bundled/ wrapped into one cable (see **Plate 5.3**).






Plate 5.3: Typical 66kV dynamic cable design

- 57. If there is an OSP the Offshore Export Cable will be formed of a single 132kV Alternating Current (AC) circuit, or with no OSP the likely design will be two 66kV AC circuits. The decision over the OSP and therefore which Offshore Export Cable will not be made until the detailed design of the Offshore Project is completed which is likely to be the end of Q3 2025. Therefore, two options have been considered for the Offshore Export Cable and the worst case assessed for each impact/receptor within this ES.
- 58. The TJB will be located within the car park at Saunton Sands, therefore above MHWS. The final location of the TJB within the car park will be selected following the detailed design and will depend on the selected method for the installation of the Offshore Export Cables at landfall (see **Section 5.4.3.2**).
- 59. For both options, single 132kV or two 66kV, there will only be a single TJB. Although the TJB for the two 66kV option will need to be larger to accommodate the two Offshore Export Cables. Again, the worst-case scenario for each receptor is assessed throughout each technical chapter within the ES.



60. The Offshore Export Cables will be installed using either open-trenching, a trenchless technique, or a combination of the two. A Ground Investigation campaign will be undertaken in Q3 2023 at the Landfall providing a high degree of confidence in the feasibility of trenchless techniques at this location.

5.4.3 Construction

5.4.3.1 Site setup and establishment

- 61. A temporary onshore construction compound will be required to accommodate the drilling rig, materials and welfare facilities and would be up to 100m long by 50m wide (Stage 1 on **Appendix 5.D** *Figure 19*). The temporary onshore compound will be set within the car park at Saunton Sands, the final location will depend on which technique is used for the installation Offshore Export Cable and the location of the TJB.
- 62. When the works associated with the Landfall (to MLWS) are completed the area will be reinstated and the areas with the carpark returned to the operator in order to minimise the disruption. Only the area needed for the Saunton Golf Club Trenchless Crossing will be retained (Stage 2 on **Appendix 5.D** *Figure 19*).
- 63. Access to the onshore compound and landfall working area will be from Saunton Road (B3231) using the existing car park access road. It is not anticipated that any major works will be needed to improve this access for the Onshore Project.
- 64. The initial site setup and establishment will be undertaken outside of the peak summer holiday season, defined as July August in order to mitigate any impacts on either the local highways or the users of the car park.
- 65. Movement to site for plant and materials will be optimised in order to minimise traffic movements from the Onshore Project wherever possible.
- 66. The working hours for the Landfall (to MLWS) are the standard working hours for the Onshore Project, Monday to Friday 07.00-19.00, Saturday 07.00-13.00; however some 24 hour working we be required for the drilling associated with the trenchless cable installation methods (Options 2 and 3). A maximum of 14 days of 24 hour working for each drill has been assessed.

5.4.3.2 Cable installation

67. Cable installation methodology at the Landfall (to MLWS) will be selected based on a comparative assessment of environmental, commercial, and technical factors. Three different options have been identified which include a mix of open cut trenching and trenchless techniques, each option is presented below and has been



assessed within this ES. A final decision on this methodology will be made postconsent.

- 68. Open cut is a well-known installation methodology for underground cabling in relatively unconstrained areas. It can also be used to install a cable in a Landfall and would require an open trench to be dug out before a cable is installed and the trench refilled.
- 69. If a trenchless technique is chosen as the appropriate installation methodology at Landfall, the trenchless technique is drilled from above MHWS at the onshore construction compound and will exit either on the seabed in an exit pit at a suitable water depth or on the beach at Saunton Sands. The length of the trenchless technique will depend upon factors such as water depth, seabed topography, shallow geology/soil conditions and environmental constraints.
- 70. Further details of methods used for cable instillation at landfall are presented within the **Appendix 5.A: Braunton Burrows and Taw Estuary Crossing Method Statement**, and summarised below.
- 71. The separate Offshore Project application provide a description and assessment of the works below MLWS including the trenchless technique exit point. The ES submitted for the Offshore Project also included an assessment of the works in the intertidal zone (between MLWS and MHWS) based on the design parameters at submission.
- 72. Since the submission of the ES for the Offshore Project further progress to the design for the Landfall options has been undertaken, providing additional information allowing a more accurate assessment to be undertaken. This includes further details for the open cut option, including the use of a cable plough for installing the cable in the intertidal zone, and the addition of a second shorter option for the trenchless technique.

5.4.3.2.1 Option 1 – Piperam duct (trenchless) and open cut in intertidal zone

- 73. This option consists of a combination of a trenchless technique to cross the dunes at the edge of the Saunton Sands carpark, with open cut used across the beach and into the intertidal zone.
- 74. The compound for the trenchless section will be located at the western edge of the carpark. This will include a drive pit excavated below ground within which a Grundoram pneumatic pipe rammer will be installed (see **Plate 5.4**). A maximum of two steel casings will be installed for a distance of approximately 60m to an exit



pit located on Saunton Sands beach. Each casing will have a maximum diameter of 600mm sufficient for the installation of the Offshore Export Cable.



Plate 5.4 Typical pipe ram pneumatic hammer

- 75. A drive pit will need to be excavated within the onshore compound for the pipe ram, this will measure a maximum of 18m long by 10m wide with a depth of up to 2m. Depending on the ground conditions it may be necessary to install a concrete base in the floor of the excavations to provide a solid working base for the pipe rammer.
- 76. Once the duct(s) are fully installed, an excavator will carefully excavate the face of the ducts at the reception location, on the beach west of the dunes, in preparation for cable installation from offshore. No excavation will be undertaken within the dunes, and the reception location will be located a minimum of 10m from base of the dunes. This will ensure that there is no direct impact to the dunes from this option.
- 77. The spoil from the pipe rammer will be removed using compressed air and/or water jetting once the pipe ram has arrived at the exit pit. All spoil will be removed from site in accordance with the project Construction Environment Management Plan.
- 78. From the exit pit the installation method across the beach and intertidal zone will be by way of cable plough, from a cable lay barge for a distance of approximately 2.3km, of which 700m is above MLWS. A non-displacement type cable plough will be employed, this causes relatively little disturbance with the majority of the sediment falling back into the trench as the cable is laid. This type of cable plough is particularly suited to installing long continuous lengths of cable in a variety of ground conditions, including fine sand like that encountered at Saunton Sands.
- 79. The cable plough will be winched from the winch tractor, located on the foreshore, aligned with the duct(s) (below the dunes). The area of disturbance for the trench



will typically be 0.5m wide (based on a maximum cable diameter of 250mm for the offshore export cables) with a burial depth of 2m.

- 80. Once the cables arrive at the terminal point close to the pre-installed ducts below the dunes, the onshore winch spread will pull the cable through the ducts towards the TJB location which will be located at the western end of the carpark.
- 81. The combined timescale for the described works could be as little as 14 days. This installation process at less risk of waiting on weather than a trenchless marine spread, as the cable lay barge will be of a sufficient size to operate in moderately inclement weather. The cable plough is operated from onshore, with the plough itself subsea, installing the cable below the seabed.

5.4.3.2.2 Option 2 – HDD duct with intertidal exit

- 82. This option will utilise HDD to install a maximum of two ducts from the carpark to the intertidal zone at a depth of 0m A.O.D. The ducts will be 560mm high density polyethylene (HDPE) SDR 11 pipe, with a length for the drill of approximately 860m to MLWS.
- 83. The onshore compound will be located in the centre of the carpark. The drill rig for the HDD will be located within the onshore compound and drill from the entry pit out towards the intertidal zone and the exit pit.
- 84. The HDD exit point is in the intertidal zone, which will allow for construction activities to continue from the beach with reduced marine support. As the HDD approaches the exit point, a reception pit will be excavated to clear the exit zone of beach/marine sediments in order to prevent sedimentary material entering the bore and damaging the duct as it is pulled into the bore.
- 85. It is proposed to install the ducts from offshore to onshore to reduce the risks associated with bore collapse, and also removes the need for a second rig to be placed offshore on a jack-up barge.
- 86. The ducts will be fabricated either offsite at a local port, or at the onshore compound if there is sufficient space. The ducts will then be bought to HDD exit point prior to being installed.
- 87. Once the cables arrive at the exit point close to the pre-installed ducts, the onshore winch spread will pull the cable through the ducts towards the TJB location which will be located in the centre of the carpark.



5.4.3.2.3 Option 3 – HDD duct with offshore exit

- 88. This option will utilise HDD to install a maximum of two ducts from the carpark to exit offshore at a depth of -5m A.O.D. The ducts will be 560mm HDPE SDR 11 pipe, with a length for the drill of approximately 1850m, of which approximately 850m is above MLWS. A preliminary profile design for this option is included **Appendix 5.D** *Figure 16*.
- 89. The onshore compound will be located in the centre of the carpark. The drill rig for the HDD will be located within the onshore compound and drill from the entry pit out towards offshore and the exit pit.
- 90. With up to 7m of marine sediments/sand overlying the HDD exit point, it will be necessary to excavate (vacuum dredge) at the HDD exit point, in order to prevent debris ingress into the bore when the HDD exits the competent geology (mudstone/siltstone).
- 91. It is proposed to install the ducts from offshore to onshore to reduce the risks associated with bore collapse, and also removes the need for a second rig to be placed offshore on a jack-up barge.
- 92. The ducts will be fabricated either offsite at a local port, or at the onshore compound if there is sufficient space. The ducts will then be bought to HDD exit point prior to being installed.
- 93. Once the cables arrive at the exit point close to the pre-installed ducts, the onshore winch spread will pull the cable through the ducts towards the TJB location which will be located in the centre of the carpark.

5.4.3.3 Transition Joint Bay

- 94. The Offshore and Onshore Export Cables will be joined together in one TJB located onshore within the Landfall compound. This would have a maximum excavated area of 20m x 8m, with a reinforced concrete floor to allow winching during cable pulling and a stable surface to allow jointing.
- 95. Following cable pulling and joining activities, the joints would be buried to a depth of up to 2m using stabilised backfill, pre-excavated material or a concrete box. The remainder of the TJB will be backfilled with the pre-excavated material and returned to the pre-construction condition, so far as is reasonably possible.
- 96. The top of the TJB would sit flush with the level of the carpark, with a hatch to provide access, if required, during the operations and maintenance phase of the Onshore Project. The area above the TJB will be available to be used for parking.



5.4.3.4 Connection between Landfall and Golf Course Crossing

- 97. Whichever construction option is selected for the Landfall a section of cable installed in an open cut trench will be required to connect the TJB to the exit point for the trenchless crossing of the Saunton Golf Club (Section 2).
- 98. This will be located entirely within the carpark and will have a maximum length of 100m, the construction methodology will be that same as outlined in **Section 5.6.3.1** below. Following the completion of the works the carpark will be reinstated.

5.4.4 Landfall parameters

99. **Table 5.1** shows the main construction parameters for the Landfall up to MLWS. The Landfall below MLWS has been considered within the separate Offshore Project ES. **Figure 5.2** shows the location of the Landfall.

| Landfall | Minimum | Maximum |
|--|---|---------------------|
| Landfall installation method | Combination of trenchless techniques and open cut trench | |
| Number of Transition Joint Bays | N/A | 1 |
| Number of drills | 1 | 2 |
| Number of days for 24 hour working | 0 | 14 |
| Transition Joint Bay dimensions (length x width) (m) | 20 x 5 | 20 x 8 |
| Transition Joint Bay dimensions depth (m) | N/A | 2 |
| Onshore construction compound area (above MHWS at Landfall)(length x width) (m) | 50 x 50 (main compound plus 18 x 10 (drive pit compound for Option 1) | 100 x 50 |
| Trench dimensions for open trench down the beach to MLWS (cable plough) | N/A | 0.5m wide x 2m deep |
| Trenchless technique horizontal length (m) | 60 | 1,860 |
| Open cut trench down the beach to MLWS length (m) | N/A | 700 |

Table 5.1 Landfall construction parameters



| Landfall | Minimum | Maximum |
|---|------------------------|---------------------|
| Open cut within carpark length (m) | N/A | 100 |
| Open cut within carpark no. trenches | 1 | 2 |
| Trench dimensions for open cut trench through the carpark (each trench) | 0.89m wide x 1.6m deep | 4m wide x 1.9m deep |



5.5 Saunton Golf Club Trenchless Crossing (Section 2)

5.5.1.1 Background

- 100. The installation of the Onshore Export Cable through the Saunton Golf Club and Braunton Burrows SAC will be undertaken using a trenchless technique.
- 101. The use of a trenchless technique will avoid any direct impacts on the Braunton Burrows SAC and mitigate any disruption to the Saunton Golf Club.
- 102. The choice of a trenchless crossing of the Saunton Golf Club was the result of a site selection process, considering environmental and technical constraints. The site selection process is described in **Chapter 4: Site Selection and Assessment of Alternatives**.

5.5.1.2 Golf Club Trenchless Crossing Infrastructure

- 103. As at Landfall, the choice of whether there will be one or two Onshore Export Cables will be dependent on the detailed design of the Offshore Project and the decision about the need for an OSP.
- 104. There will be a temporary construction compound at each end of the trenchless crossing, with access to the trenchless entry via Saunton Sands Car Park and access to the trenchless exit via the main construction access from the B3231. The drill rig will be located within the carpark at Saunton Sands beach, with the direction of drilling being from west to east.
- 105. One joint bay and link box per Onshore Export Cable will be installed at each end of the trenchless section to link the Onshore Export Cable sections together.
- 106. The length of the trenchless crossing within this section is approximately 1300 m and given the restricted working area within the trenchless entry compound at Saunton Sands Car Park, it will be necessary to pull the HDPE duct from the east side of the golf course to the west, with the full length of the HDPE duct being fabricated along the right of way to the east side of the golf course.

5.5.1.3 Construction

5.5.1.3.1 Site setup and establishment

107. A temporary compound will be required at each end of the trenchless crossing, at the drilling end to accommodate the drilling rig, materials and welfare facilities and would be up to 50m long by 50m wide. The temporary compound for the entry pit will be set within the car park at Saunton Sands (Stage 2 on **Appendix 5.D** *Figure 19),* the final location will depend on which technique is used for the installation Offshore Export Cable and the location of the TJB (see **Section 5.4.3.2**).



- 108. When the works associated with the Landfall and Golf Course trenchless crossing are completed, the area will be reinstated and the areas with the carpark returned to the operator in order to minimise the disruption.
- 109. Access to the onshore compound and Landfall working area will be from Saunton Road (B3231) using the existing car park access road. It is not anticipated that any major works will be needed to improve this access for the Onshore Project.
- 110. The initial site setup and establishment will be undertaken outside of the peak summer holiday season, defined as July August in order to mitigate any impacts on either the local highways or the users of the car park.
- 111. Movement to site for plant and materials will be optimised in order to minimise traffic movements from the Onshore Project wherever possible.
- 112. The working hours for the Golf Course trenchless crossing are the standard working hours for the Onshore Project, Monday to Friday 07.00-19.00, Saturday 07.00-13.00; however, some 24 hour working we be required. A maximum of 14 days of 24 hour working for each drill has been assessed.

5.5.1.3.2 Cable installation

- 113. Cable installation methodology at the Golf Course crossing will be trenchless technique, namely either HDD or direct pipe and will be selected based on a comparative assessment of environmental, commercial, and technical factors.
- 114. The Golf Course trenchless crossing operations will commence following the completion of the Landfall works.
- 115. The trenchless technique is drilled from a temporary construction compound located in Saunton Sands Car Park and will exit at a second temporary construction compound to the east of Saunton Golf Club, outside of the Braunton Burrows SAC. The length of the trenchless technique will be approximately 1300 m from the entry point to the exit point. The stringing out of the HDPE ducting, if HDD is the selected technique, to be used for trenchless crossing will undertaken in the fields on the east side of the Golf Course.
- 116. Further details of method used for cable instillation at the Golf Course crossing are presented within the Appendix 5.A: Braunton Burrows and Taw Estuary Crossing Method Statement. A preliminary profile design for this Golf Course crossing is included Appendix 5.D Figure 17.



5.5.1.3.3 Joint Bay (JB) and Link Boxes (LB)

- 117. There will be a maximum of two joint bays and link boxes installed at each end of the trenchless crossing, one for each cable circuit. Each joint bay would comprise an excavated area of 12m x 4m with a reinforced concrete floor to allow winching during cable pulling and a stable surface to allow jointing.
- 118. Following cable pulling and joining activities, the joints would be buried to a depth of up to 1.5m using stabilised backfill, pre-excavated material or a concrete box. The remainder of the joint bay will be backfilled with the pre-excavated material and returned to the pre-construction condition, so far as is reasonably possible.
- 119. The top of the joint bay would sit flush with the existing ground level, the link boxes will include an access hatch at ground level to provide access during the operations and maintenance phase of the Onshore Project.

5.5.1.4 Saunton Golf Club crossing parameters

120. **Table 5.2** shows the main construction parameters for the crossing of the Saunton Golf Club. **Figure 5.3** shows the location of Saunton Golf Club crossing.

| Landfall | Minimum | Maximum |
|--|---|---------|
| Saunton Golf Club crossing installation method | Trenchless technique such as HDD or Direct Pipe | |
| Number of Joint Bays | 2 | 4 |
| Number of drills | 1 | 2 |
| Number of days for 24 hour working | n/a | 14 |
| Joint Bay dimensions (length x width) (m) | n/a | 12 x 4 |
| Joint Bay dimensions depth (m) | n/a | 1.5 |
| Crossing construction compound area (length x width) (m) | n/a | 50 x 50 |
| No. crossing construction compounds | n/a | 2 |
| Trenchless technique horizontal length (m) | n/a | 1,300 |

Table 5.2 Saunton Golf Club crossing construction parameters



5.6 Onshore Cable Corridor (Sections 3, 4 & 6)

5.6.1 Background

- 121. The location of the Onshore Export Cable Corridor is presented in **Appendix 5.D** *Figures 6 to 10* and is mostly between 50m to 60m wide, increasing in some places to allow for micrositing and construction equipment storage, and reduced in other areas to mitigate potential effects. The actual working width during cable construction will be 30m across most of the route, reduced to 12m at pinch points and crossings, which will be located entirely within the Onshore Export Cable Corridor.
- 122. From the Landfall at Saunton Sands (Section 1), the Onshore Export Cable Corridor travels east initially, crossing Saunton Golf Club south of Saunton village (Section 2), before turning and running south crossing agricultural and pastural farmland. It then crosses the Taw estuary (sections 3, 4, and 5). After crossing the Taw estuary, the cable corridor runs to the onshore substation (section 6) before connecting to East Yelland Substation (section 7).
- 123. Throughout sections 3, 4 & 6 of the cable corridor the cable installation method will be mainly open-cut trenching with small sections of trenchless techniques for main watercourse, road, and sensitive habitat crossings.
- 124. The choice of crossing methodology throughout this section was the result of a site selection process, considering environmental and technical constraints. The site selection process is described in **Chapter 4: Site Selection and Assessment of Alternatives**.

5.6.2 Onshore Export Cable Infrastructure

125. **Table 5.3** shows the main parameters for the Onshore Export Cable corridor and its construction. The standard temporary working width of the Onshore Export Cable Corridor will typically be 30m and comprises the trench or trenches, storage of excavated material (split into segregated subsoil and topsoil) and a haul road. At specific locations along the Onshore Export Cable Corridor, the working width may require widening to accommodate access at crossings or specific specialist equipment associated with trenchless techniques or micro-tunnelling or indeed decreasing at pinch points to around 12m. The typical cross section through the construction strip, based on two cable circuits, is shown in **Appendix 5.D** *Figure 21.*



| Onshore cable corridor | Minimum | Maximum |
|------------------------------------|----------------------------------|--------------|
| Electrical connection | High Voltage Alternating Current | |
| Number of cable circuits / | 1 | 2 |
| trenches | | |
| Cable construction width (onshore | 12 | 60 |
| corridor) (m) | | |
| Cable construction width at | 7 | 15 |
| trenchless crossings (m) | | |
| Cable route length (km) | N/A | 5.5 |
| Cable trench width (m) | 0.89 | 4 |
| Cable trench depth (m) | 1.6 | 1.9 |
| Depth to top of buried | 1.2 | 1.5 |
| infrastructure (ducts) (m) | | |
| Running track width (m) | N/A | 4 |
| Typical jointing bay frequency (m) | 600 | 1,000 |
| No. of jointing bay | 15 | 30 |
| Jointing bay dimensions (length x | N/A | 12 x 4 x 1.5 |
| width x height) (m) | | |
| Depth to top of jointing bay (m) | 1.2 | 1.5 |
| Link box frequency | 600 | 1,000 |
| No. of link box | 15 | 30 |
| Link box (height) (m) | 1 | 2 |
| Link box (length x width) (m) | 2 x 2 | 3 x 3 |
| Haul road width (m) | 5 | 8 |
| Haul road length (km) | N/A | 6.5 |
| Main construction compound area | N/A | 3,500 |
| (m2) | | |
| Mobilisation areas (m2) | N/A | 30,000 |

Table 5.3 Onshore cable parameters

126. The onshore underground cable system will be installed in one or two trenches consisting of one 132kv or two 66kv cables and one fibre optical cable per trench. The trench holding the circuit may be up to 4m wide, but typically would be less than 1m wide at the base. If two 66kV circuits are chosen for the export cable then there will be a separation distance of 5m (centre to centre) between the two circuits (see **Plate 5.5** below). A running track up to 4m wide would provide a safe working area construction plant and vehicle alongside the cable trench. The topsoil and subsoil will be bunded and stored separately.






Plate 5.5 Typical trench detail

127. Jointing bays will be used to pull the cable into the ducts and/or to join the cable lengths to each other. Link boxes are used for earthing cables and will be installed inside a protective concrete chamber. The jointing bays are subsurface structures, while the link boxes will require access (for inspections) from the surface during operations and will therefore be located at ground level. At each jointing location there will be one link box for the circuit. The frequency of jointing bays and link boxes will occur every 600 m - 1,000 m, with one jointing bay and link box per cable circuit. Where possible the link boxes will be located within, or at close proximity to the joint bays.

5.6.3 Construction

- 128. The Onshore Export Cable duct will be installed in sections of up to 1km at a time, with a typical construction presence of up to four weeks along each 1km section.
- 129. A description of the activities undertaken as part of the construction of the onshore export cable is presented in the following sections.

5.6.3.1 Pre-construction works

130. Following the granting of planning permission but in advance of the main construction there will be a number of activities undertaken along the onshore export cable corridor. Some works will be required as part of the detailed design of the onshore export cable route, and some works will be undertaken as part of the mitigations identified within this environmental statement. These activities include ground investigations, ground penetrating radar, topographical, Unexploded Ordnance (UXO), ecological, and archaeological surveys, soil surveys, utility, and private supplies surveys. With the exception of archaeological investigations, ground investigations and in the event a UXO is identified - where targeted excavations would be conducted, works are generally non-intrusive. These are conducted to highlight specific areas of interest along the proposed White Cross onshore cable corridor and at the onshore substation well in advance of the construction activities.



5.6.3.1.1 Site Investigation / Ground Investigation

- 131. An initial programme of site and ground investigation works will be undertaken in autumn 2023 to provide information on the ground conditions across the onshore export cable corridor as part of the Preliminary Design. Proposed locations for the boreholes, trial pits, resistivity testing and geophysical survey are shown in **Appendix 5.D** *Figures 11 to 15.*
- 132. A further programme of works may be required in order to provide information as part of the Detailed Design Phase of the onshore export cable route. These will include a combination of methods and techniques including boreholes, window samples and trial holes.
- 133. Boreholes will be sited at appropriate locations throughout the route and particularly at major crossing points. They may be performed using a bipod light cable percussive boring rig. Further and deeper survey involving rotary rigs may also be necessary to investigate some areas of the route, particularly where deeper trenchless crossings are being considered.
- 134. Trial holes will also be excavated, by hand (or using a small tracked excavator), during the Detailed Design Phase to prove the location, depth, size, material and condition of existing services and plant, both in-field and at roadsides. This will ensure that the crossing methods envisaged are appropriate. A Trial Hole (Service) Report will be produced to record the location, depth, size, material and condition of existing services and plant.
- 135. Trial holes will be excavated every 100-500m during the preparation of the right of way (Section 5.6.3.2.1 below) to prove ground conditions in each section to ensure that the trenching and crossing methods envisaged are appropriate. A Trial Hole (Geology) Report will be produced which records the location, depth, size, strata, water ingress, and stability.

5.6.3.1.2 Archaeological Investigations

- 136. Archaeological investigations will be undertaken along the White Cross onshore cable corridor at predetermined locations to ascertain if any archaeological items of interest are present.
- 137. The initial programme of archaeological excavations was undertaken in June 2023 with a second phase planned for September 2023. These works required the excavation of a number of archaeological trial trenches at predetermined locations along the onshore export cable route.



- 138. The aim of the archaeological investigations is to examine a representative sample of the remains affected by development in order to generate accurate information on the heritage assets actually present. This stage generally consists of small-scale, selective, and sample based trial work, whilst still being sufficient to quantify, characterise and date the full range of archaeological remains potentially affected by the development works.
- 139. A range of archaeological techniques may be employed, including archaeological trenches, boreholes, and non-intrusive geophysical investigations. Archaeological investigations in the early stages may also rely upon watching briefs from suitably qualified personnel.
- 140. Early archaeological field testing may potentially lead to further, more extensive archaeological investigation. This may include full or sample archaeological excavation, further general and targeted investigations.

5.6.3.1.3 Soil Surveys

- 141. Prior to the commencement of works, the contractor will need to document information on the existing soil/land conditions and agricultural management. To successfully carry out this action, soil condition surveys and intrusive soil survey trial pits may be required to identify and describe the physical and nutrient characteristics of the existing soil profiles. The trial pits would typically be dug by hand along the White Cross onshore cable corridor at approximately 100 m intervals.
- 142. Further associated preparation activities (non-intrusive) may include: surveys of existing crop regimes, condition of existing access arrangements, position and condition of field boundaries, review of the type of agriculture taking place, establishment of location of private water supplies, quality of grazing land, assessments of yield of crops, and existing weed burden.

5.6.3.2 Site preparation and enabling works

- 143. Immediately in advance of the main works to construct the Onshore Export Cable a number of site preparation and enabling works will be undertaken. These works include survey and investigation works and will, where possible be computerised to aid the production of the construction and as built drawings.
- 144. Some of these are required in order to prepare the site before other works can commence.

5.6.3.2.1 Right of Way Preparation

145. Before the site is fully established many of the early and enabling works will take their access to the cable corridor by using existing gateways, tracks, or from the



public highway. Therefore, the first task will be to survey, set out and prepare the right of way in advance of the other enabling works. A number of activities will be completed, with different work crews following in sequence.

146. Generally, the working width design allows for adequate working space, although, around certain crossings and dependent upon the crossing methodology, subject to topography and ground conditions, it may be necessary to re-engineer the fence lines. This will also be the case where the working width design shows boxes at crossings of overhead lines, or where the spread runs parallel to overhead lines, or existing underground services. Working width drawings will detail with dimensions the required site land take. Security patrols will also be present on site.

5.6.3.2.1.1 Route Survey, Setting Out & Record of Condition

- 147. Prior to erecting the temporary fencing, the perimeter of the right of way will be defined, marked and checked for services using CAT and Genny, by the surveying teams.
- 148. Information will be digitised and used to generate the construction issue Plan and Profile long sections/strip maps.
- 149. Photographic records will be carried out during route survey and setting out of the works. Detailed records of the condition of the roads in the vicinity of the route will also be taken. Photographic records will also be taken of any features that are likely to be affected by the Onshore Project.
- 150. Excavations will also be undertaken along the route in order to locate any buried services that have previously been identified through desk-top studies, and to mark out their locations/erect warning notices. Any excavations within the vicinity of buried services will be undertaken under a permit to dig.

5.6.3.2.1.2 Temporary Fencing

- 151. Fence posts will be distributed along the marked lines and driven into the ground, generally with an excavator bucket. Fencing for stock accesses will be installed at this time and topsoil strip will be carried out across them. Gates at road crossings, stock and other accesses, together with any required signs, will also be installed. The fencing crew foreman shall ensure that all service protection fencing, and matting is in place when they pass through. The fencing will be suitably earthed with rods beneath overhead electric lines if it is required.
- 152. Where identified on the working width drawings, specific fencing will be installed, with demarcation fencing in arable areas, stock fencing in cattle areas, post and rain fencing in horse areas, and Heras fencing/hoarding in urban/security risk areas.



5.6.3.2.1.3 Hedgerow and Vegetation Removal

- 153. Where hedgerows and vegetation occur within the working area, they will be removed ahead of each working section. The width of hedgerow removed will be limited wherever possible to minimise the impact on local ecology. All crossings are listed within a crossing schedule provided as **Appendix 5.G** to this chapter.
- 154. Prior to the commencement of any works to a hedgerow, an Ecological Clerk of Works will be present on site to ensure that the specified protection and mitigation measures are appropriately implemented, including any measures set out within the Arboricultural Method Statement (see **Appendix 16.R**).
- 155. At the completion of the project hedgerows will be reinstated in accordance with the Landscape and Ecology Mitigation Plan.

5.6.3.2.2 Topsoil Strip

- 156. Where topsoil stripping takes place, every care will be taken to prevent topsoil and subsoil mixing and the work will be continuously monitored to ensure this is the case. Topsoil will be stripped to its full depth and records will be kept of the depths stripped in every parcel of land.
- 157. Track mounted 360-degree slew backhoe excavators will (where appropriate) be used to pull the topsoil away from the left-hand temporary fence far enough to allow a tracked dozer to push and strip towards the right hand fence where it is stacked. Banksmen will be in position to make sure that material does not get pushed outside the easement or damage the temporary fence. To ensure that the heap is weatherproof and not impeding the working spread more than required, it will be built neatly, left tidy and be well-shaped. Where topsoil is removed from the banks of watercourses or ditches it will be stacked separately. Gaps will be left in the topsoil heap to permit the maintenance of public rights of way, water management and beneath all overhead cables. Stripping will not take place above underground services. When working in a flood plain is unavoidable, special measures will be agreed with the Environment Agency, this may include weather monitoring, topsoil wrapping fuel storage constraints and emergency procedures. If required, side slope benching will be carried out to give a level running track and working platform along the side of the trench.

5.6.3.2.3 Haul Road

158. The haul road would provide safe access for construction vehicles along the Onshore Export Cable Corridor, between construction compounds and the work fronts. As set out in the project strategy for access (Chapter 19: Traffic & Transport, and Appendix 19.A: Transport Assessments) all HGVs will be required to use the



haul road for deliveries with no HGVs from the project accessing the Onshore Export Cable Corridor via the narrow local roads. The haul road would be up to 5m wide (and up to 8m wide at passing bay locations). Speed limits on the haul road are expected to be limited to 20mph.

- 159. Following an initial topsoil strip, the haul road would be installed in stages as each work front progresses. Typically, it would be excavated to a depth of 400mm with a sub base and MOT Type 1 stone running course on top of a layer of protective matting. Protection to existing underground services will be provided by means bogmat protection above, and quarantine hi-vis netlon fencing to limit crossing of the service to the temporary haul road.
- 160. In some areas dependant on the ground conditions, for example in areas that are very wet, an alternative method may be employed for the construction of the haul road. This could include laying of bogmats directly on to the ground surface, or through the use of a 'floating road', a technique developed for installing haul roads across peat in Scotland. For both alternative techniques the road is lain directly on the ground surface without the need for any topsoil stripping.
- 161. When all works are completed the haul road would be removed and the ground reinstated using the stored topsoil.

5.6.3.2.4 Highways Access

162. Three new temporary and one permanent access will be created by the Onshore Project to provide access to and along the Onshore Export Cable Corridor and haul road. The temporary access will be removed and reinstated following the completion of the Onshore Project, and the permanent access will become the permanent access for the new White Cross Onshore Substation. The proposed access routes are shown on **Appendix 19.A** *Figure 1*.

5.6.3.2.4.1 Access 003

- 163. Access 003 is a proposed new temporary priority access junction from the B3231 Saunton Road. The proposed junction is located west of the Broad Lane / Blind Acres staggered crossroads.
- 164. To the north of this access the hedgerow will be coppiced to reduce the height to approx. 200mm above ground level for an area 2.4m by 90m to provide visibility of drivers emerging from the access to other road users. The access at the junction will be widened to accommodate the largest anticipated construction vehicles, i.e. a 16.5m maximum legal length articulated HGV.



- 165. A bellmouth or turning area will be created at the access junction comprising geotextile membrane or similar lain directly on top of the subsoil which will have stone spread over the top of it to a depth of approximately 350mm.
- 166. This access will be removed and reinstated following the completion of the Onshore Project with the coppiced hedgerow grown back and if required planting to fill in any gaps.

5.6.3.2.4.2 Access 008

- 167. Access 008 comprises of two priority junctions to the east and west of Sandy Lane to create a haul road crossing.
- 168. These accesses would allow HGV traffic to access from access 003 to the north and travel via the temporary haul road and cross over Sandy Lane towards the River Taw (thus avoiding the need for HGVs to travel via Sandy Lane). Access for LVs at access 008 would however be permitted from Sandy Lane.
- 169. The junctions have been designed to minimise impact on surrounding vegetation whilst allowing a 16.5m maximum legal length articulated HGV to manoeuvre from east to west and vice versa. To the north of this access the hedgerow will be coppiced to reduce the height to approx. 200mm above ground level for an area 2.4m by 40m to provide visibility of drivers emerging from the access to other road users.
- 170. Traffic management controls will be imposed on the haul road approaches to the junction to ensure shuttle working across Sandy Lane. No traffic management would be proposed for Sandy Lane.
- 171. A bellmouth or turning area will be created at the on either side of the access junction comprising geotextile membrane or similar lain directly on top of the subsoil which will have stone spread over the top of it to a depth of approximately 350mm.
- 172. This access will be removed and reinstated following the completion of the project with the coppiced hedgerow grown back and if required planting to fill in any gaps.

5.6.3.2.4.3 Access 015

173. Access 015 comprises of the construction access for the proposed White Cross Onshore Substation, this will be used to provide access to the Onshore Export Cable Corridor and haul road for all construction traffic in Section 6. This access will also become the permanent access to the White Cross Onshore Substation (see Section 5.8 below).



174. The access would connect onto an existing private access road running south to the public highway at the B3233 West Yelland. It is not proposed to alter the existing priority junction between the B3233 West Yelland and the private access road, which already accommodates HGVs.

5.6.3.2.4.4 Access 016

- 175. Access 016 would provide a haul road crossing of the Tarka Trail long distance footpath and cycleway only. The crossing would utilise existing field gates on either side of the Tarka Trail and would be subject to traffic management by banksmen to ensure the safety of pedestrians and cyclists.
- 176. Some works, including vegetation removal, may be required to widen the access to accommodate the largest anticipated construction vehicles, i.e. a 16.5m maximum legal length articulated HGV.
- 177. This access will be removed and reinstated following the completion of the project with any removed vegetation replanted or replaced.

5.6.3.2.5 Watercourse crossings

- 178. Along the Onshore Export Cable Corridor, the haul road will traverse a number of ditches, drains and other watercourses. Access for the haul road needs to be maintained through the onshore cable corridor, therefore crossings will be required of all features for the haul road.
- 179. Where the cable corridor crosses minor watercourses such as an open ditch or drain an appropriately sized culvert will be installed within the ditch and the haul road would be installed over the top of the culvert (see **Plate 5.6**). The culvert would be installed in the channel bed to avoid upstream impoundment and would be sized to accommodate realistic worst-case water volumes and flows. These culverts will remain in place for the duration of the cable duct installation and subsequent cable pull.





Plate 5.6 Typical culvert crossing for minor watercourse

180. At larger crossings, including the crossing for the haul road of Sir Arthur's Pill (Main River) and Boundary Drain (Ordinary Watercourse) or those managed by the Internal Drainage Board (IDB), temporary bridges (e.g. Bailey bridges or similar) may be employed to allow continuation of the haul road while mitigating impacts to the watercourse (see **Plate 5.7** and **Plate 5.8** below).





Plate 5.7 Typical beam bridge crossing for larger watercourse



Plate 5.8 Bailey bridge crossing for major watercourse

181. Following the completion of all works the culverts, bridges and or any other infrastructure installed for the haul road crossings will be removed and the watercourse reinstated in accordance with the Landscape and Ecology Mitigation Plan.



5.6.3.2.6 Drainage and Dewatering

- 182. A number of existing field drains and water management systems have been identified across the onshore export cable corridor, and it is therefore possible that as part of the constriction works some of these systems may be severed, and/or that works will be undertaken within the vicinity of the drainage ditches or channels.
- 183. Therefore, a detailed drainage strategy will be developed post-consent by a specialist drainage engineer, taking into account existing land drainage and will include details of header drains, outfall locations and cross-easement interconnections (if applicable).
- 184. This strategy will be prepared in consultation with the landowners and the Braunton Marsh Drainage Board (if within the IDB area).
- 185. This strategy will include measures to be installed pre-construction, dewatering measures to manage the water during construction, and the measures for the reinstatement and reconnection of drainage following completion of construction.

5.6.3.2.6.1 Pre-construction Drainage

- 186. Pre-construction drainage will be installed by a specialist sub-contractor in accordance with the design developed by the drainage engineer. Following the erection of fences, this work will be carried out as soon as practically possible.
- 187. Pre-construction drainage is installed to the "High" side of the construction corridor, using a drainage trenching machine. This is in order to provide a cut off or header drain which will divert the drained water from the existing drainage system which may be damaged during trenching operations prior to pipe installation. This prevents the cable trench from being inundated with water when evacuated, and ensures the construction works do not increase the risk of flooding to surrounding land.





Plate 5.9 Pre-construction drainage being installed using drainage trenching machine

- 188. Additional drainage channels will be installed to intercept water from the cable trench. This will be discharged at a controlled rate into local ditches or drains via temporary interceptor drains. Depending upon the precise location, water from the channels will be infiltrated or discharged into the existing drainage network.
- 189. A soakaway drainage pit / outfall may be required if no suitable outfall to a nearby watercourse is possible.
- 190. Drainage for the main site compound, mobilisation areas and off easement accesses will be installed by a specialist sub-contractor in accordance with the design developed by the drainage engineer. This work will be carried out as soon as is practically possible, to prevent deterioration of the working areas.
- 191. Generally, existing drainage will be repaired where necessary and cleaned out where required. In the event that further drainage is required to provide a drained working area, then this will be installed using either a 360 ° Backhoe or a Drainage trencher, depending upon the size of the area to be drained.

5.6.3.2.6.2 Dewatering

192. To ensure safe working conditions, certain areas along the cable route may require point dewatering depending upon ground conditions and water levels. Pipes will be sunk to a depth dictated by the ground conditions and water pumped out in advance of the works to temporarily lower the surrounding groundwater level. The groundwater produced will be pumped to an adjacent watercourse downstream of



the works and outline pipes will be installed to prevent scouring and disturbance of the watercourse bed. The watercourse will be monitored for sediment disturbance and rate of flow with additional mitigation measures being put in place if required.

- 193. For the removal of water in the trench or localised ponding on the right of way, the Foreman will be notified of the land are agreed as suitable to pump the water on to. Where any further locations are required as the work continues, these will be directed through the Agricultural Liaison Officer and agreed with the landowners and IDB (if on the Braunton Marshes).
- 194. Where surrounding land is not available for discharging water, then excess water will pass through a filtration system, such as temporary settlement lagoons, with straw bales and silt netting filtration and then into a watercourse.
- 195. A water management scheme may also be installed which is formed from a number of lined lagoons with interconnecting spill ways in order to manage any ground water encountered during the dewatering or run off. This water would need testing for contaminants prior to discharge into any adjacent watercourses, if a permit is obtainable from the relevant authorities.

5.6.3.2.6.3 Drainage Reconnections

- 196. The reconnection of land drains cut by the cable trench, that are not being replaced by an easement or header drain will be carried out as part of the backfill operation. After the installation of the cable the backfill will be compacted in layers up to the underside of the severed drains which are to be permanently reinstated by cross connection. The replacement drain will extend into the virgin/undisturbed ground on each side of the trench width for a minimum of 1m measured at right angles to the trench. The undisturbed ground will be excavated by hand and a good connection formed to the existing drain. The cable trench backfill will then be compacted up to the subsoil surface level.
- 197. All drainage reconnections across the trench will be carried out in accordance with the requirements of the land drainage specification.
- 198. Post-construction agricultural drainage will be reinstated including the replacement of any drains that were damaged during the construction process.

5.6.3.2.7 Temporary construction compounds and mobilisation areas

199. There will be one temporary construction compound for the works to install the Onshore Export Cable, this will up to 3,500m² and will be located adjacent to Access 003. This will house portable offices, welfare facilities, and stores. The construction compound would be constructed by laying a geotextile membrane or similar directly



on top of the subsoil which will have stone spread over the top of it to a depth of approximately 350mm.

- 200. Across the route there will also be up to 10 mobilisation areas, these will be used for the localised stores, as well as acting as staging posts for localised secure storage for equipment and component deliveries. This area will also provide additional works space for the stringing out and welding of the ducting to be used for the trenchless crossings of the Golf Course and Taw Estuary. The total area for the mobilisation areas across the Onshore Development Area will be approximately 30,000m².
- 201. In addition, the trenchless crossings and White Cross Onshore Substation works would have their own dedicated construction compounds. The compound for the substation works would also provide the welfare facilities for the works to install the Onshore Export Cable south of the River Taw (Section 5).



Plate 5.10 Typical construction compound welfare cabins and offices

5.6.3.1 Open-cut excavation

202. The Onshore Export Cables in sections 3, 4, and 5 will be mainly laid in open cut trenches following the methodology outlined below.

5.6.3.1.1 Soil management

203. Stripped topsoil and excavated subsoil will be stored separately within the Onshore Export Cable Corridor. The area to be used for storing the topsoil would be cleared



of vegetation and any waste arising from the development (e.g. building rubble and fill materials). Topsoil would also be stripped from any land to be used for storing subsoil.

204. Effective stockpiles would be created by:

- Removing vegetation and waste materials from the area before forming stockpiles
- Storing topsoil and subsoil layers separately
- Locating stockpiles away from trees, hedgerows, drains, watercourses, or excavations
- Managing the site so that soil storage periods are kept as short as possible
- Stockpiling soils in the driest condition possible
- Using tracked equipment wherever possible to reduce compaction
- Protecting stockpiles from erosion by seeding or covering them.

5.6.3.1 Duct installation

- 205. The Onshore Export Cable will be installed in pre-laid ducts, the HDPE ducting will be laid to the floor of the trench on a minimum of 150mm thick bed of cement bound sand (CBS). There will be three ducts per circuit arranged in a trefoil formation with zip-ties used to hold the three ducts together.
- 206. Where the ducts require jointing, this work will be undertaken topside of the trench to avoid working in an unsupported trench where possible. The trench will be kept free of water during duct installation and checks will be made for duct damage once the duct is lifted and prior to being lowered into the trench. In the event any defects are discovered, they will be repaired using an approved quick setting repair compound. Two methods will be used for the laying of the ducts.

5.6.3.1.1 Hand laying method

- 207. Ducts would be palletised and manoeuvred along the easement using a telehandler (or equivalent). Operatives in the trench would lay zip-ties in the base of the trench following the profile of the trench base and sides at predetermined intervals ahead of the ducts being laid.
- 208. This method would be chosen were there are short strings of 3-4 ducts, the jointed strings will be laid out alongside the trench, then excavators will lift the strings into the trench. When the duct is lowered off in the trench an engineer will check that the required cover has been achieved. Joint bays and link boxes will also be installed at this time (see below).



5.6.3.1.2 Ducting trailer method

209. For longer sections of ducting, a ducting trailer or trenching machine may be used. This enables the ducts to be joined on the trailer platform and lowered directly into the trench as the tractor moves the trailer forward. The ducts are zip-tied into the correct formation prior to leaving the working platform. The use of the duct trailer or duct machine minimises the need for personnel to work in the trench and is a quicker method for installing longer sections of ducting.

5.6.3.1.3 Duct surround and backfill

- 210. The duct would be buried to a minimum depth of 1.2m (from top of duct to surface). Depending on the thermal resistivity of the soil and the height of the water table, it is likely that a stabilised backfill such as CBS will be required to encase the ducting. This is commonly used to ensure that the thermal conductivity of the material around the cables is of a known consistent value for the length of the installation.
- 211. The CBS has a low thermal resistance to conduct the heat produced during electricity transmission away from the HV cables. Additionally, as CBS tends to consist of a weak sand to cement ratio (typically 14:1), it is relatively easy to remove if maintenance or removal of cables is required.
- 212. Once the ducts are encased in CBS (typically covering depth of 75mm above the ducts) a compaction plate would be used until the required level of compaction is achieved. The trench would then be backfilled in stages using the subsoil stored at the side of the trench and compacted using suitable compaction plant. Following construction, the stored topsoil would then be replaced on top of the backfilled subsoil to reinstate the trench to pre-construction condition, so far as reasonably possible.

5.6.3.2 Joint bays

- 213. Joint bays would be required along the route of the Onshore Export Cables to connect sections of cable, these are typically concrete lined pits (approximately 12m by 4m) that provide a clean and dry environment for jointing sections of cable together.
- 214. Joint bays are likely to be required every 600 to 1000 m along the export cable for each circuit. The number and placement of the joint bays would be determined as part of the detailed design but indicative locations have been provided in **Appendix 5.D** *Figures 1 to 5.* Joint bays would be installed at least 1.2m below ground and would be of a similar design to the TJB described for the Landfall (**Section 5.4.3.3**). The joint bays would be formed on completion of the duct installation before the cables are installed.



5.6.3.3 Link boxes

- 215. Each jointing bay associated with a single circuit will require a smaller concrete enclosure known as a link box, to provide connections between cable sheaths essential for the efficient operation of the cable and for fault testing. The link boxes will be a maximum of 3m by 3m, with a height of up to 2m.
- 216. Link boxes are required to be in proximity of the jointing bay locations and where possible the link boxes will be located within, or at close proximity to the joint bays. The number and placement of the link boxes would be determined as part of the detailed design. But as a worst-case for the assessment is has been assumed there will be one link box located at the same location at the joint bays.
- 217. The link boxes need to be accessible during the operation and maintenance phase of the project to allow periodic access by technicians for inspection and testing of the cables. They would be buried to ground level with above ground marker posts to locate them and will include a secured access panel.

5.6.3.4 Cable pull

- 218. Cables would be pulled through the pre-installed ducts later in the construction programme. Trenches would not need to be reopened, and the cable pull would take place from the jointing bays located approximately every 600m to 1,000m along the cable corridor.
- 219. During the cable pull and jointing works, cable drums would be delivered by HGV low loader to the open joint bay locations using the haul road. The cable would then be winched off the drum from one joint pit to another, through the buried ducts. Cable jointing would be conducted once both lengths of cable have been installed within each joint bay.
- 220. The cable pulling and jointing process would take approximately eight weeks per 1000m length of cable. However, any one joint bay could be open for up to 16 weeks to allow its neighbouring joint bay to be opened and the cables pulled from one pit to the next, dependent on the level of parallel work being conducted.
- 221. Once the cables are joined together the jointing bays would be backfilled following a similar methodology to set out about in **Section 5.6.3.1.3** for duct surround and backfill.

5.6.3.5 Crossing methods

222. All crossings are listed within a crossing schedule provided as **Appendix 5.F** to this chapter.



223. During detailed design, contact will be made with all the relevant local and statutory authorities, private companies and agencies to obtain all consents, permits, licences and authorisation necessary to carry out the crossings.

5.6.3.5.1 Major watercourse crossings (trenchless)

- 224. Where Onshore Export Cable Corridor crosses major watercourses, including Environment Agency Main Rivers or IDB maintained watercourses, trenchless crossing techniques such as a HDD micro rig, will be employed. The crossing of the Taw Estuary is discussed in **Section 5.7** below.
- 225. The trenchless process involves drilling underneath the feature being avoided. The process uses a drilling head to drill a pilot hole along a predetermined profile based on an analysis of the ground conditions and cable installation requirements. This pilot hole is then widened using larger drilling heads until the hole is wide enough to fit the cable ducts. Bentonite is pumped to the drilling head during the drilling process to remove drill cuttings and to stabilise the hole and ensure that it does not collapse. Once the trenchless drilling has taken place the ducts are pulled through the drilled hole.
- 226. A detailed method statement will be produced for each crossing, this will include any specific control or mitigation measures such as setback distances from Main Rivers, that are deemed required to mitigate any potential effects from the works.
- 227. When crossing Main Rivers or IDB maintained watercourses, the cable entry and exit pits will be at least 9m from the banks of the watercourse (18m where they are tidal), and the ducts will be installed at least 2m below the channel bed.

5.6.3.5.2 Minor watercourse crossings (open cut)

- 228. Where minor watercourses such as open ditches or drains, are to be crossed, the approach will be open cut trenching combined with temporary damming and diverting of the watercourse. The suitability of this method would be agreed at detailed design.
- 229. The watercourse would be dammed at either side of the cable crossing point, typically using sandbags, straw bales and ditching clay, and the water within the watercourse would be pumped or piped across the dammed section to effectively maintain flow across the dammed section. The cable trenches would then be excavated within the dammed section but ensuring that watercourse bed materials are stored separately to subsoils. Ducts would typically be installed to 2m below the channel bed to avoid impacts to the active channel bed.



- 230. Reinstatement of the trench would be conducted to the pre-construction depth of the watercourse, taking care to reinstate the channel bed material and subsoils in the order that they were removed.
- 231. The dams would then be removed. Temporary dam and divert would only be required for the duration of time that duct installation takes place in that location (typically no more than 1-2 weeks for a minor watercourse crossing).

5.6.3.5.3 Road, tracks, public right of way, and service crossings

- 232. Where the Onshore Export Cable Corridor crosses roads, tracks, public rights of way and services, including Sandy Lane and the Tarka Trail, trenchless techniques such as a HDD micro rig will be used in order to maintain access for the users or mitigate any disruption of or impact to the services.
- 233. The methodology used for the HDD micro rig is similar to that outlined for the major watercourse crossings in **Section 5.6.3.5.1** above. The ducts will be installed at a suitable depth depending on the type of crossing, but typically will be 2m below the bottom of the constraint.
- 234. The approach for each crossing would be agreed with the relevant authority prior to works beginning. No temporary closures or diversions would be required, the works in the vicinity of the crossings would be managed to allow safe operation.

5.6.3.5.4 Minor watercourse crossings

- 235. Where minor watercourses such as open ditches or drains, are to be crossed, the approach will be open cut trenching combined with temporary damming and diverting of the watercourse. The suitability of this method would be agreed at detailed design.
- 236. The watercourse would be dammed at either side of the cable crossing point, typically using sandbags, straw bales and ditching clay, and the water within the watercourse would be pumped or piped across the dammed section to effectively maintain flow across the dammed section. The cable trenches would then be excavated within the dammed section but ensuring that watercourse bed materials are stored separately to subsoils. Ducts would typically be installed to 2m below the channel bed to avoid impacts to the active channel bed.
- 237. Reinstatement of the trench would be conducted to the pre-construction depth of the watercourse, taking care to reinstate the channel bed material and subsoils in the order that they were removed.



238. The dams would then be removed. Temporary dam and divert would only be required for the duration of time that duct installation takes place in that location (typically no more than 1-2 weeks for a minor watercourse crossing).

5.7 Taw Estuary Trenchless Crossing (Section 5)

5.7.1.1 Background

- 239. The installation of the Onshore Export Cable beneath the River Taw Estuary will be undertaken using a trenchless technique likely to be a HDD.
- 240. The use of a trenchless technique will avoid any direct impacts on the River Taw and Taw-Torridge Estuary SSSI.
- 241. The choice of a trenchless crossing of the River Taw was the result of a site selection process, considering environmental and technical constraints. The site selection process is described in **Chapter 4: Site Selection and Assessment of Alternatives**.

5.7.1.2 Construction

5.7.1.2.1 Site setup and establishment

- 242. A temporary compound will be required at each end of the trenchless crossing, at the drilling end to accommodate the drilling rig, materials and welfare facilities and would be up to 50m long by 50m wide (**Appendix 5.D** *Figure 20*). The trenchless exit compound will be located to the west of the river Taw, with the trenchless crossing entry compound located to the east of the river Taw.
- 243. When the works associated with the Taw Estuary crossing are completed the area will be reinstated to minimise disruption.
- 244. Access to the compound on the south side will be from the new haul road connecting to the existing private road and then to the highway at the West Yelland Road (B3233), Access 015 on **Appendix 19.A** *Figure 1*. From there access will be along the Onshore Export Cable Corridor, utilising the temporary crossing of the Tarka Trail (Access 016).
- 245. To gain access to the compound on the north side all traffic will use the haul road within the Onshore Export Cable Corridor in accordance with the onshore access strategy (see **Section 5.3.3.9**).
- 246. The working hours for the Taw Estuary crossing are the standard working hours for the Onshore Project, Monday to Friday 07.00-19.00, Saturday 07.00-13.00; however



some 24 hour working we be required. A maximum of 14 days of 24 hour working for each drill has been assessed.

5.7.1.2.2 Cable installation

- 247. Cable installation methodology at the Taw Estuary crossing will be trenchless technique, namely either HDD or direct pipe and will be selected based on a comparative assessment of environmental, commercial, and technical factors.
- 248. The trenchless technique is drilled from a temporary construction compound located on the south side of the Taw Estuary outside of the Taw-Torridge Estuary SSSI. It will exit at a second temporary construction compound to on the north side of the Taw Estuary, west of the Crow Beach House (the White House). This compound will be outside of the Braunton Burrows SAC, Braunton Burrows SSSI, and the Taw-Torridge Estuary SSSI.
- 249. The length of the trenchless technique will be approximately 1300 m from the entry point to the exit point. The stringing out of the HDPE ducting to be used for trenchless crossing will undertaken on the north side of the Taw Estuary.
- 250. Further details of method used for cable instillation at the Golf Course crossing are presented within the Appendix 5.A: Braunton Burrows and Taw Estuary Crossing Method Statement. A preliminary profile design for this Taw Estuary crossing is included Appendix 5.D Figure 18.

5.7.1.2.3 Joint Bay (JB) and Link Boxes (LB)

- 251. There will be a maximum of two joint bays and link boxes installed at each end of the trenchless crossing, one for each cable circuit. Each joint bay would comprise an excavated area of 12m x 4m with a reinforced concrete floor to allow winching during cable pulling and a stable surface to allow jointing.
- 252. Following cable pulling and joining activities, the joints would be buried to a depth of up to 1.5m using stabilised backfill, pre-excavated material or a concrete box. The remainder of the joint bay will be backfilled with the pre-excavated material and returned to the pre-construction condition, so far as is reasonably possible.
- 253. The top of the joint bay would sit flush with the existing ground level, the link boxes will include an access hatch at ground level to provide access during the operations and maintenance phase of the Onshore Project.

5.7.1.3 Taw Estuary crossing parameters

254. **Table 5.4** shows the main construction parameters for the crossing of the Taw Estuary. **Figure 5.6** shows the location of the Taw Estuary crossing.



| Landfall | Minimum | Maximum |
|--|---|---------|
| Saunton Golf Club crossing installation method | Trenchless technique such as HDD or Direct Pipe | |
| Number of Joint Bays | 2 | 4 |
| Number of drills | 1 | 2 |
| Number of days for 24 hour working | n/a | 14 |
| Joint Bay dimensions (length x width) (m) | n/a | 12 x 4 |
| Joint Bay dimensions depth (m) | n/a | 1.5 |
| Crossing construction compound area (length x width) (m) | n/a | 50 x 50 |
| No. crossing construction compounds | n/a | 2 |
| Trenchless technique horizontal length (m) | n/a | 1,200 |

Table 5.4 Taw Estuary crossing construction parameters

5.8 Onshore Substation and Grid Connection Point (Section 7)

5.8.1 Background

- 255. A new Onshore Substation will be required for the Onshore Project to transform the windfarm export voltage to the National Grid Electricity Distribution (NGED) 132kV distribution voltage. The White Cross Onshore Substation will be connected to the existing NGED East Yelland substation via a single 132kV export cable where the Grid Point of Connection is located.
- 256. The White Cross Onshore Substation will be located in agricultural land and a brownfield site to the east of the NGED East Yelland substation (see **Appendix 5.E Figure 9**). The site is located approximately 250m south of the Taw Estuary and approximately 1km from Yelland.
- 257. The choice of the location for the White Cross Onshore Substation was the result of a site selection process, considering environmental and technical constraints. The site selection process is described in **Chapter 4: Site Selection and Assessment of Alternatives**.



5.8.2 Onshore substation infrastructure

- 258. The design of the White Cross Onshore Substation, including the equipment to be installed, will partly depend on the detailed design of the offshore components of the Project. But will also depend on the choice of substation supplier, as much of the technology and equipment for a substation is proprietary. Therefore a series of indicative designs have been developed in line with the principles of the Rochdale Envelope approach (for further information see **Chapter 6: EIA Methodology**).
- 259. The following components and equipment will be located within the operational footprint for the White Cross Onshore Substation:
 - Control building housing the main switchgear, auxiliary service transformer, and offices
 - Substation building housing the main equipment including:
 - Shunt reactors
 - Static Synchronous Compensators, Static Var Compensator or equivalent
 - Transformers
 - Harmonic filters
 - Associated connections between equipment via busbar and cabling, including buried earthing system
 - Access road
 - Ancillary infrastructure such as a car park and storage areas for other plant/equipment
 - Security fence, internal drainage and lighting
- 260. The White Cross Onshore Substation will either utilise an Air Insulated Switchgear (AIS), which uses air for insulation, or a Gas Insulated Switchgear (GIS), which uses sulphur hexafluoride gas for insulation. Installations for a GIS substation are generally smaller than their AIS counterparts, although a GIS substation will typically have higher upfront cost.
- 261. Typically an AIS substation will be open to the air (i.e. the equipment will not be contained within a building), while a GIS substation requires that all of the equipment is contained within a building. However the decision has been made to include a building for both of the AIS and GIS options due to the location of the Onshore Substation close to the Taw Estuary in order to provide some protection to the equipment from adverse weather and corrosion from salt air.
- 262. Based on the above three options have been defined for the White Cross Onshore Substation:



- Option A: Indicative Enclosed Gas Insulated Switchgear Substation
- Option B: Indicative Enclosed Air Insulated Switchgear Substation
- Option C: Indicative Enclosed Air Insulated Switchgear Substation with Additional Equipment Space
- 263. The indicative designs for the three options are presented in **Appendix 5.E.**
- 264. Additional land will be required adjacent to the Onshore Substation to accommodate the infrastructure required in order to mitigate the potentially significant effects from the operation phase of the Onshore Project. This includes areas for landscape screening to mitigate landscape and visual impact, see **Chapter 20: Onshore Landscape and Visual Amenity**, and to mitigate flood risk and drainage impacts, see **Chapter 14: Water Resources and Flood Risk**.
- 265. The total area of additional land required will not be known until the detailed design of the Onshore Substation is completed, and until the mitigation measures are agreed with relevant stakeholders. For the assessments within this ES the mitigation requirements are based on the worst-case design of indicative option, Option C.
- 266. **Table 5.5** describes the main onshore substation construction parameters, where there is a range the minimum is based on the indicative design for the Option A Onshore Substation, and the maximum is drawn from the indicative design for the Option C Onshore Substation.

| Onshore Substation Parameters* | Minimum (Option A) | Maximum (Option C) |
|--|--------------------|--------------------|
| Construction compound dimensions (length x width) (m) | N/A | 100 x 50 |
| Construction compound area (temporary works) (m ²) | N/A | 5,000 |
| Substation access road (temporary and permanent) dimensions (length x width) (m) | N/A | 250 x 7.5 |
| Substation operational footprint dimensions (length x width) (m) | 95 x 50 | 106 x 50 |
| Substation operational footprint area (m ²) | 4,750 | 5,300 |
| Substation building dimensions (length x width) (m) | 59 x 23 | 71 x 24 |
| Substation building height (m) | N/A | 10 |
| Substation building area (m ²) | 1,357 | 1,704 |

Table 5.5 Onshore Substation construction parameters



| Onshore Substation Parameters* | Minimum (Option A) | Maximum (Option C) |
|--|--------------------|--------------------|
| Control building dimensions (length x width) (m) | N/A | 35 x 9 |
| Control building height (m) | N/A | 8 |
| Control building area (m ²) | N/A | 315 |
| External equipment height (m) | N/A | 10 |
| Finished Floor Level (m AOD) | N/A | 6.73 |
| Building platform area (m ²) | N/A | 7,700 |

267. **Table 5.6** describes the construction parameters for the export cable from the Onshore Substation to the Grid Point of Connection in the existing East Yelland substation.

Table 5.6 Grid Point of Connection construction parameters

| Grid Point of Connection Parameters | Minimum | Maximum |
|--|--|---------|
| Electrical connection | High Voltage Alternating Current 132kV | |
| Number of cable circuits / trenches | N/A | 1 |
| Total cable route length (m) | N/A | 300m |
| Cable route length within East Yelland substation (m) | N/A | 130m |

5.8.3 White Cross Onshore substation construction method

5.8.3.1 Site setup and establishment

- 268. At the start of the works the area will be fenced and the site would be stripped, and the ground levels graded as required by the final design. Stripped material would be reused on site where possible, potentially as part of any identified bunding or screening identified through the impact assessment process.
- 269. A temporary materials storage area, incorporating a construction compound will be established to the south of the proposed substation location. This will be the main compound for all works south of the River Taw and so will also accommodate staff, materials and equipment required for the construction of the Onshore Export Cable in Section 6.
- 270. Access will be from a new haul road connecting to the existing private road and then to the highway at the West Yelland Road (B3233). This access will also then become the permanent access route to the White Cross Onshore Substation. A short (230m) section of wooden pole mounted overhead power line runs along the route



of the proposed temporary and permanent access, this will be relocated through agreement with the owner and operator, NGED.

5.8.3.2 Civils build

- 271. In order to mitigate the risk from tidal flooding to the White Cross Onshore Substation the Finished Floor Level (FFL) for the Onshore Substation needs to be raised to a minimum of 300mm above the water level for the 1 in 200 year event for 2075 (assuming a maximum operational lifetime for the Onshore Substation of 50 years). This would result in a FFL of 6.73mAOD, which based on existing ground levels would require the platform for the Onshore Substation to be approximately 1.33m to 1.73m above the existing ground levels. Further details and information on the flood risk and the design of the FFL can be found in **Chapter 14: Water Resources and Flood Risk, Appendix 14.C: Flood Risk Assessment** of this ES.
- 272. Deeper soils would be excavated from areas where the ground profile needs to be lowered (cut) and moved into the areas where the ground level needs to be raised (fill). The thickness of each fill layer would need to be determined in accordance with the specification of the material and the design of the substation platform. Where the specification of the existing soils is not up to the required load bearing standard additional material may need to be imported to the site. Any excess material would be disposed of at a licenced disposal site.
- 273. After grading of the site is complete to provide the required FFL, a stoned platform will be constructed, and excavations would then proceed associated with the laying of foundations, trenches and drainage. At this stage it is not known whether the foundations would be ground bearing or piled. This will be determined by geotechnical ground investigation post consent that will inform the detailed design. However, for the purposes of the assessment piled foundations are assumed to be required at the substation.
- 274. Following completion of the enabling works, installation of drainage and foundations, the substation platform will need to be finished with a layer of imported stone fill combined with a concrete pour. The thickness of this concrete platform would be determined during detailed design based on the geotechnical ground investigation.

5.8.3.3 Building construction

275. To further mitigate the flood risk the exterior of the White Cross Onshore Substation building has been designed using flood resistant materials, to limit flood water



ingress into the building and to provide protection to the electrical equipment and infrastructure contained within it. Therefore the buildings will be constructed on a brick or concrete base lined or coated with a suitable watertight material up to 600mm above the FFL. Access and egress into the buildings will be from steps or ramps in order that the threshold will also be raised.

- 276. The upper structure of the buildings would likely be constructed from a steel frame with cladding panels. The steel frame would be fabricated off site and then erected at the substation location with the use of cranes. The cladding would be fitted once the framework is in place.
- 277. The final design of the substation and control buildings, including the choice of building materials, form, colour, and finish will be completed as part of the detailed design for the project.
- 278. A **Substation Design Code** (**Design and Access Statement: Appendix B**) has been prepared to provide further details on the design and appearance of the Onshore Substation, including its architectural form, orientation, façade design, materials, and colours. The Design Code seeks to minimise potentially adverse impacts, as well as creating development which is sympathetic to its local context.

5.8.3.4 Mechanical and electrical build

- 279. Once the civil and buildings works are completed the substation electrical equipment would then be delivered to site and installed. Due to the size and weight of assets such as the transformers, specialist delivery methods would be employed, and assets would be offloaded at site with the use of a mobile gantry crane.
- 280. The electrical build process is set out methodically, building each part of the structure piece by piece, including cable connections to the automatic control and protection equipment.
- 281. All other equipment and plant required for the operation of the Onshore Substation, such as control room equipment, lighting, and heating, ventilation and air conditioning (HVAC) system will be installed.

5.8.3.5 Commissioning

- 282. Following installation commissioning will be undertaken to test the equipment to ensure that it is connected correctly. This includes both hot and cold commissioning.
- 283. Some of the commissioning works will need to be undertake simultaneously and retrospectively with the offshore commissioning of the WTGs, and Offshore



Substation (if required). Therefore, the final commissioning will need to align with the programme for the offshore works.

5.8.3.6 Reinstatement

- 284. Following the construction much of the area will become part of the permanent area for the Onshore Substation. This includes the operational footprint of the Onshore Substation, and the associated infrastructure such as the access road, landscaping areas and drainage.
- 285. Those areas not required for either the operational footprint of the associated infrastructure will be reinstated in accordance with the Landscape and Ecology Mitigation Plan to be produced as part of the detailed design.

5.8.4 Lighting, heating, ventilation and air conditioning

286. The final requirements for lighting, heating, ventilation and air conditioning for the Onshore Substation will not be known until the detailed design of the substation is completed. But an indicative design with worst case parameter, based on final design for other similar sized substations for offshore windfarms is provided below and assessed within this ES.

5.8.4.1 Lighting

- 287. The final design of the lighting for the White Cross Onshore Substation will be completed as part of the detailed design for the substation, and will follow all appropriate guidance. The final design of all exterior lighting will be completed in accordance with the Institution of Lighting Professionals Guidance Note 01/21: The Reduction of Obtrusive Light, and will incorporate appropriate measures to mitigate lighting impacts.
- 288. Internal lighting will be designed to allow safe movement of personnel and safe operation of equipment, where practicable all of the lights will be LED type with the lighting levels in accordance with British Standard EN12464-1:2021. They will be operated by wall switches positioned adjacent to doorways, including outside at the entrance to rooms and/or at more than one doorway if appropriate, and will incorporate a 4-hour timer manual override switch. All emergency lighting will be designed in accordance with British Standard EN5266-1:2016.
- 289. Exterior lighting, including perimeter and site lighting, will be required to allow safe access and emergency egress for personnel (including from buildings) and safe operation of equipment during the winter months. A lower level of lighting will also be required to remain overnight for security purposes.



- Maintained average illuminance 6.0 lux at ground level
- Minimum maintained point illuminance 2.5 lux at ground level.
- 290. For the perimeter lighting the luminaires shall, where practicable, be LED type with directable light output to minimise light pollution. Exterior site lighting to buildings shall incorporate IP65 wall mounted LED luminaires which will be controlled via integral PIR motion detectors.

5.8.4.2 Heating, ventilation and air conditioning

- 291. A HVAC system may be required for the substation building in order to dissipate the heat produced by transformers and other equipment, and to allow drying after particularly wet or humid periods.
- 292. The design of this system will be determined in part by the selection of the type of switchgear cooling used for the White Cross Onshore Substation. The indicative design shows, as a worst case scenario, a maximum of 15 vents around the substation building which would be required if a forced air cooling system using fans or blowers was employed.
- 293. The substation control building may also require a HVAC system in the form of a small commercial air conditioning unit. Modern units, such as those typically employed for small commercial or industrial buildings such as the White Cross Onshore Substation control building, are now all-in-one with no need for external units.
- 294. The final design of the HVAC system for the substation and control buildings will be designed in order to minimise and mitigate the noise impacts.

5.8.5 Drainage

- 295. A surface water drainage system will be required for the operational Onshore Substation and would be designed to meet the technical requirements set out in the National Planning Policy Framework. An Outline Drainage Strategy Report has been prepared (**Appendix 5.C**) which provides an outline drainage strategy and design, the final design of the drainage system will be completed as part of the detailed design for the White Cross Onshore Substation and agreed with Devon County Council as the Lead Local Flood Authority.
- 296. Surface water from across the substation site will be collected and routed via a treatment system to an attenuation pond located to the south of the substation building. The water will then channelled to an existing drainage ditch located to the northwest of the White Cross Onshore Substation. A hydrobrake flow control system



at the downstream end of the attenuation pond will ensure that the water is discharged at the greenfield run-off rate of 3.87l/s.

- 297. The combination of the attenuation pond and controlled discharge will ensure that there will be no increase in flood risk from the Onshore Substation to the surrounding area.
- 298. The White Cross Onshore Substation will not be manned and the design does not incorporate any toilet or welfare facilities. Therefore, there is no requirement for a foul drainage connection.

5.8.6 Landscape Screening

- 299. The site selected for the White Cross Onshore Substation already benefits from existing landscape screening from the north and northwest. But in order to mitigation the potentially significant visual effects from the west and south (see **Chapter 20: Onshore Landscape and Visual Amenity**) further planting will be undertaken to provide additional landscape screening.
- 300. The proposed woodland would be located around the Onshore Substation enclosing the infrastructure apart from the access and cable ingress points. Native hedgerows and scrub vegetation would be located along the Onshore Export Cable Corridor around the White Cross Onshore Substation to increase connectivity between the woodland blocks and to the existing woodland and hedgerows.
- 301. The indicative mitigation woodland planting would be designed to comprise a mix of faster growing 'nurse' species and slower growing 'core' species. Nurse species, such as alder and pine would grow quicker so that after 15 years they would be approximately 7.5m in height. They would provide shelter to bring on core, canopy species, such as oak. Whilst the nurse species would be sufficiently fast growing to provide substantial screening of the onshore substation after 15 years, the core species would outlive the nurse species and provide a preferred native woodland with a more robust structure closer in character to other nearby woodlands.
- 302. The location of the screening is set out in the Outline Landscape & Ecology Mitigation Plan (OLEMP), see Figure 20.13 within Chapter 20: Onshore Landscape and Visual Amenity. The OLEMP will be further developed as part of the detailed design with the measures agreed with relevant stakeholders and consultees as appropriate.



5.8.7 Onshore substation to grid point of connection

- 303. The 132kV interconnecting cable from the White Cross Onshore Substation to the Grid Point of Connection will be installed within ducts using a combination of opencut and trenchless techniques similar to those outlined in **Section 5.6**. A trenchless technique will be used for the crossing of the Tarka Trail in order to ensure there is no closure of the Traka Trail.
- 304. The final 130m of the interconnecting cable will be within the perimeter of the East Yelland substation, it is expected that this will be installed within or adjacent to the existing internal road within the substation. The final routing within the East Yelland substation will be agreed NGED.
- 305. Construction works within the East Yelland substation will be undertaken by NGED and will include the instillation of sealing end compounds, and circuit breakers for the grid connection. It is not anticipated that any changes or extension to the existing substation boundary or buildings will be required to accommodate the grid connection. Should they be required it will be the responsibility of NGED to secure all of the required permissions and consents.

5.9 Operations and Maintenance

- 306. The operational life of the Offshore Project is 25 years based on the proposed Agreement for Lease (AfL) with The Crown Estate (TCE). Therefore the operational lifetime for the Onshore Project is expected to also be 25 years. However, for some assessments a longer operational lifetime of 50 years has been used for the assessment as the decommissioning policy for the Project is not yet known (see **Section 5.10** below).
- 307. The overall Operations and Maintenance strategy will be finalised once the detailed design of the whole project is completed, including electrical export option and final project layout.
- 308. Maintenance activities can be categorised into two levels: preventative and corrective maintenance. Preventative maintenance is according to scheduled services whereas corrective maintenance covers unexpected repairs, component replacements, retrofit campaigns and breakdowns.

5.9.1 Onshore Export Cables

309. There is expected to be minimal maintenance of the Onshore Export Cables during the operational phase, with any operation and maintenance requirements largely



corrective with infrequent on-site inspections of the onshore transmission infrastructure undertaken through the operational lifetime.

310. Typically, every two to five years, there will be periodic testing of the cable which involves access to the link boxes along the entire onshore route. With regards to equipment, access can be achieved using lightweight vehicles and existing highways or farm access tracks.

5.9.2 White Cross Onshore Substation

- 311. The White Cross Onshore Substation would not be manned; however, access would be required for routine maintenance activities, estimated at an average of one visit per week during normal daytime working hours. There would likely also be annual maintenance and servicing of equipment, with more major servicing activities undertaken every four years. These works would take up to a week and would normally be undertaken in the summer to coincide with low wind speeds.
- 312. The normal operating conditions would not require lighting at the Onshore Substation, although low level movement detecting security lighting may be utilised for health and safety purposes. Temporary lighting during working hours will be provided during maintenance activities where those activities are undertaken during the winter months.

5.10 Decommissioning

313. No decision has been made regarding the final decommissioning policy for the Onshore Project, as it is recognised that industry best practice, rules and legislation change over time. The decommissioning methodology would need to be finalised nearer to the end of the lifetime of the Offshore Project so as to be in line with current guidance, policy and legalisation at that point. Any such methodology would be agreed with the relevant authorities and statutory consultees. The decommissioning could be subject to a separate consenting approach.

5.10.1 Onshore Export Cables

- 314. Onshore there are two main options with regards to decommissioning of the Onshore Export Cable Corridor. The cables can be left buried in-situ with the cable ends cut, sealed and securely buried. Alternatively, the cables can be removed by pulling them through the ducts. It is likely that the cables would be pulled through the ducts and removed, with the ducts themselves left in situ.
- 315. The TJB, jointing bay and link boxes would also likely be capped and left in-situ. If removal is required the method would be the reverse of construction with the



infrastructure excavated and all materials taken off site for recycling or disposal in accordance with the legislative requirements at the time.

5.10.2 Onshore Substation

316. The White Cross Onshore Substation site may be kept operational and upgraded accordingly for other potential electrical use or fully decommissioned (performed in the reverse of the construction works utilising similar types of equipment). To decommission the White Cross Onshore Substation, all electric plant is removed from their foundations and transported to a facility for processing for reuse, recycling, or disposal. The foundations may be pulled out and disposed of and any holes refilled with earth, if required. The substation and control building can be demolished, and all materials disposed of.



White Cross Offshore Windfarm Environmental Statement

Appendix 5.A: Taw Estuary and Braunton Burrows Crossing Method Statement





| Document Code: | FLO-WHI-REP-0016-05 | | | | |
|--------------------------------|--------------------------------|----------------------|--|--|--|
| Contractor Document Number: | PC2978-RHD-ZZ-XX- RP-Z-0384 | | | | |
| Version Number: | 00 | | | | |
| Date: | Issue Date 15/08/2023 | | | | |
| Prepared by: | ТМ | Electronic Signature | | | |
| Checked by: | СВ | Electronic Signature | | | |
| Owned by: | РТ | Electronic Signature | | | |
| Approved by Client : | OG | Electronic Signature | | | |

| Version Number | Reason for Issue / Major Changes | Date of Change | |
|-------------------|-------------------------------------|----------------|--|
| 00 | For issue | 15/08/2023 | |



Table of Contents

| 1. | Intr | oduc | tion | 1 |
|----|-------|-------|--|---|
| 1 | .1 | Ove | rview | 1 |
| 1 | .2 | Site | Description | 3 |
| | 1.2. | 1 | Braunton Burrows Crossing | 3 |
| | 1.2. | 2 | Taw Estuary Crossing | 6 |
| 1 | .3 | Rati | onale | 8 |
| | 1.3. | 1 | Rationale for the Use of Trenchless Crossing underneath the Taw Estuary | 8 |
| | 1.3. | 2 | Rationale for the Use of Trenchless Crossing underneath the Braunton Burrows | 9 |
| 1 | .4 | Con | sultation1 | 0 |
| 2. | Geo | techr | nical Investigation1 | 1 |
| 2 | .1 | Hyd | rofracture Assessment1 | 3 |
| | 2.1. | 1 | Analysis Methodology1 | 3 |
| | 2.1. | 2 | Assessment Results1 | 4 |
| 2 | .2 | Brau | Inton Burrows Historical Borehole Analysis1 | 4 |
| 2 | .3 | Taw | Estuary Crossing Historical Borehole Analysis1 | 6 |
| 3. | Des | ign | | 6 |
| 3 | .1 | Brau | Inton Burrows Crossing design parameters2 | 2 |
| | 3.1. | 1 | Landfall Crossing2 | 2 |
| | 3.1. | 2 | Saunton Golf Course Crossing2 | 3 |
| 3 | .2 | Taw | Estuary Crossing design parameters2 | 5 |
| 4. | Drill | ing N | 1ethodology2 | 7 |
| 4 | .1 | Site | Set Up2 | 7 |
| | 4.1. | 1 | General Set Up2 | 7 |
| | 4. | 1.1.1 | Braunton Burrows Crossing (Landfall and Saunton Golf Course Crossings)2 | 7 |
| | 4. | 1.1.2 | Taw Estuary Crossing2 | 9 |
| | 4.1. | 2 | Construction Environmental Controls | 2 |
| | 4. | 1.2.1 | Noise and Vibration3 | 2 |
| | 4. | 1.2.2 | Terrestrial Ecology3 | 2 |
| | 4. | 1.2.3 | Terrestrial Archaeology and Cultural Heritage3 | 3 |
| | 4. | 1.2.4 | Wastewater Discharges3 | 3 |
| | 4. | 1.2.5 | Oils, Fuels and Chemicals | 3 |
| | 4. | 1.2.6 | Waste Management and Circular Economy3 | 4 |



| | 4. | 1.2.7 | Traffic Management |
|-----|-------|--------|--|
| | 4. | 1.2.8 | Surface Water Management |
| | 4. | 1.2.9 | Water Abstraction |
| | 4. | 1.2.1 | D Emissions to the Air |
| | 4. | 1.2.1 | |
| | 4. | 1.2.12 | |
| 4.2 | 2 | HDD | |
| | 4.2. | | Drill Rig Set Up |
| | 4.2.2 | | Pilot Hole |
| | 4.2. | _ | Reaming |
| | 4.2.4 | - | Pull Back |
| | 4.2. | - | Demobilisation |
| 4.3 | | - | ct Pipe |
| | 4.3. | | Pipe Thruster and Tunnel Boring Machine Set Up |
| | 4.3. | | Pipe String Preparation |
| | 4.3. | | Pipe Thrust and Insertion |
| | 4.3.4 | | Demobilisation |
| 4.4 | | - | king Hours |
| | | | luid Management |
| 5. | | - | ose of Drilling Fluid |
| 5.2 | | - | eral Management Approach43 |
| 5.3 | | | sures to Prevent Drilling Fluid Breakout |
| 5.4 | - | | ng Fluid Breakout Response Planning45 |
| • | 5.4. | | Breakout on Land |
| | 5.4. | | Breakout under Water |
| | - | | es |

Table of Figures

| Figure 1.1 Braunton Burrows Crossing Location | 5 |
|---|----|
| Figure 1.2 Taw Estuary Crossing Location | 7 |
| Figure 2.1 BGS Historic Ground Investigation Locations | 12 |
| Figure 3.1 River Taw Outline HDD Plan and Profile | 19 |
| Figure 3.2 Cable Landfall Outline HDD Plan and Profile | 20 |
| Figure 3.3 Saunton Golf Club Outline HDD Plan and Profile | 21 |
| Figure 4.1 HDD Site Compound Layout (Landfall / Golf Course Crossing) | 28 |



Table of Tables

| Table 2.1 Braunton Burrows Landfall Crossing Conceptual Ground Model Stratum Depths | 15 |
|--|----|
| Table 2.2 Braunton Burrows Golf Course Crossing Conceptual Ground Model Stratum Depths | 15 |
| Table 2.3 Taw Estuary Crossing Conceptual Ground Model | 16 |
| Table 3.1 Trenchless Crossing Technique Comparisons | 17 |



Glossary of Acronyms

| | Definition |
|---------|---|
| Acronym | Definition |
| AOD | Above Ordnance Datum |
| BGL | Below Ground Level |
| BGS | British Geological Survey |
| CEFAS | Centre for Environment, Fisheries and Aquaculture Science |
| CEMP | Construction Environmental Management Plans |
| COSHH | Control of Substances Hazardous to Health |
| СТМР | Construction Traffic Management Plan |
| EIA | Environmental Impact Assessment |
| EMP | Environmental Management Plan |
| ES | Environmental Statement |
| FEED | Front-End Engineering Design |
| HDD | Horizontal Directional Drilling |
| HDPE | High Density Polyethylene |
| IAQM | Institute of Air Quality Management |
| IDB | Internal Drainage Board |
| kV | Kilovolt |
| km | Kilometre |
| MCAA | Maritime and Coastguard Agency Act |
| MHWS | Mean High Water Springs |
| MLWS | Mean Low Water Springs |
| mm | Millimetre |
| MW | Megawatt |
| NE | Natural England |
| NGC | National Grid |
| OFTO | Offshore Transmission Owner |
| OSP | Offshore Substation Platform |
| OWL | Offshore Wind Ltd |
| PLONAR | Pose Little or No Risk to the Environment |
| SAC | Special Area of Conservation |
| SHW | Specification For Highway Works |
| SSSI | Site of Special Scientific Interest |
| SUDS | Sustainable Urban Drainage Schemes |
| ТВМ | Tunnel Boring Machine |
| ТСРА | Town and Country Planning Act |
| ТЈВ | Transition Joint Bay |
| ТМСо | Traffic Management Coordinator |
| UXO | Unexploded Ordnance |
| | |



| Acronym | Definition |
|---------|---------------------------------|
| WSI | Written Scheme of Investigation |
| WTG | Wind Turbine Generators |



Glossary of Terminology

| Defined Term | Description |
|--|--|
| Applicant | Offshore Wind Limited |
| Environmental Impact Assessment (EIA) | Assessment of the potential impact of the proposed Project on the physical, biological and human environment during construction, operation and decommissioning. |
| Generation Assets | The infrastructure of the Project related to the generation of electricity within the windfarm site, including wind turbine generators, substructures, mooring lines, seabed anchors and inter-array cables |
| Mitigation | Mitigation measures have been proposed where the assessment identifies that an aspect of the development is likely to give rise to significant environmental effects, and discussed with the relevant authorities and stakeholders in order to avoid, prevent or reduce impacts to acceptable levels. For the purposes of the EIA, two types of mitigation are defined: Embedded mitigation: consisting of mitigation measures that are identified and adopted as part of the evolution of the project design, and form part of the project design that is assessed in the EIA Additional mitigation: consisting of mitigation measures that are identified during the EIA process specifically to reduce or eliminate any predicted significant effects. Additional mitigation is therefore subsequently adopted by OWL as the EIA process progresses. |
| Offshore Wind Limited | Offshore Wind Ltd (OWL) is a joint venture between Cobra Instalaciones Servicios, S.A., and Flotation Energy Ltd |
| the Project | the Project is a proposed floating offshore windfarm called White Cross located in the Celtic Sea with a capacity of up to 100MW. It encompasses the project as a whole i.e. all onshore and offshore infrastructure and activities associated with the Project |
| White Cross Offshore Windfarm | Up to 100MW capacity offshore windfarm including associated onshore and offshore infrastructure |
| Wind Turbine Generators (WTG) | The wind turbine generators convert wind energy into electrical power. Key components include the rotor blades, nacelle (housing for electrical generator and other electrical and control equipment) and tower. The final selection of project wind turbine model will be made post-consent application |
| Windfarm Site | The area within which the wind turbines, Offshore Substation Platform and inter-array cables will be present |



Appendix 5.A: Taw Estuary and Braunton Burrows Crossing Method Statement

1. Introduction

1.1 Overview

- 1. White Cross Offshore Windfarm is a proposed floating offshore windfarm located in the Celtic Sea with a capacity of up to 100MW (hereafter referred to as 'the Project'. The Project is split into 'the Offshore Project' and 'the Onshore Project'.
- 2. The Offshore Project requires Section 36 consent and Marine Licences for all components seaward of Mean High Water Springs (MHWS). This includes the infrastructure within the Windfarm Site (e.g., wind turbine generators, substructures, mooring lines, seabed anchors, inter-array cables and Offshore Substation Platform (as applicable)) and all infrastructure associated with the offshore export cable, Landfall (up to MHWS) and the crossing underneath the Taw Estuary (between MHWS on the northern edge to MHWS on the southern edge).
- 3. The Onshore Project is a separate Town and Country Planning Act 1990 (TCPA) application to the Offshore Project components. The Onshore Project includes the infrastructure associated with the Landfall at Saunton Sands (to MLWS) where the onshore components connect to the Offshore Project infrastructure, Onshore Export Cable (including joint bays and link boxes), Taw Estuary Crossing, a new White Cross Onshore Substation, and an Interconnecting Cable to the Grid Connection Point at the existing East Yelland Substation.
- An overview of the Project infrastructure is illustrated in Plate 1.1. A full project description of the Offshore Project can be found in Chapter 5: Project Description of the Offshore Environmental Statement (ES), and a full project description of the Onshore Project can be found in Chapter 5: Project Description of the Onshore ES.






Plate 1.1 The Project Infrastructure

- 5. The set of consents/permission required in order for the Project as a whole to proceed are outlined below:
 - Consent under the Section 36 of the Electricity Act 1989 and a Marine Licence under the Marine and Coastal Access Act 2009 (MCAA 2009) are required for the following generation assets (within the Windfarm Site):
 - Wind Turbine Generators
 - Semi-submersible floating platforms
 - Subsea catenary mooring lines
 - Anchoring solutions (drag embedment anchors, suction anchor or pin piles)
 - Inter-array cables and associated protection
 - Other associated offshore infrastructure, such as navigational markers.
 - A second Marine Licence is required to enable the option for an Offshore Transmission Owner (OFTO) to be appointed under The Electricity (Competitive Tenders for Offshore Transmission Licences) Regulations 2015 for the following transmission assets:
 - OSP Platform (OSP)
 - Offshore export cable (to Mean High Water Springs (MHWS) at Landfall)
 - Other associated offshore infrastructure, such as navigational markers
 - Taw Estuary Crossing (between MHWS on the northern edge to MHWS on the southern edge).
 - A separate planning permission under the Town and Country Planning Act 1990 (TCPA 1990) is required for the Onshore (landward of Mean Low Water Springs (MLWS)) transmission assets:
 - Onshore export cables
 - White Cross Onshore Substation
 - Onshore export cables (66kV from Landfall to onshore substation and 132kV from the White Cross Onshore Substation to NGC Grid Connection Point)
 - Temporary main construction compound and temporary construction compounds



- Transition Joint Bay (TJB), jointing bays, link boxes, access roads and haul roads.
- 6. Further detail on the consenting regime and relevant legislation is presented in Chapter 3: Policy and Legislative Context of the Offshore ES for the Offshore Project and in Chapter 3: Policy and Legislative Context of the Onshore ES for the Onshore Project.
- 7. This Braunton Burrow and Taw Estuary Crossing Method Statement (hereafter referred to as 'the Method Statement') presents information related to the two crossings (Landfall and Saunton Golf Course) crossings at Braunton Burrows (hereafter referred to as 'the Braunton Burrows Crossings') and Taw Estuary (MHWS north of the estuary to MHWS south of the estuary) (hereafter referred to as 'the Taw Estuary Crossing') by the onshore export cables and its associated construction activities and requirements.


1.2 Site Description

1.2.1 Braunton Burrows Crossing

- 8. The Braunton Burrows Crossing is proposed within two different sections, one is intertidal at landfall (to MLWS) and the other crossing the Saunton Golf Club. The Braunton Burrows Crossing at landfall (to MLWS), is from the Transition Joint Bay (TJB) at Saunton Sands car park out to offshore. The Braunton Burrows Crossing at Saunton Golf Club is from Saunton Sands car park to the east side of Saunton Golf Club. The location of the Braunton Burrow Crossings is shown in **Figure 1.1**.
- 9. This site was determined based on an appraisal of constraints and engineering feasibility from both offshore and onshore perspectives. A full discussion of the process undertaken to identify the Offshore and Onshore Export Cable Corridors for the Offshore Project is laid out in **Chapter 4: Site Selection and Assessment of Alternatives** of the ES.
- 10. The techniques that have been proposed for the Braunton Burrows Crossing at landfall (to MLWS) are either open-trenching or a trenchless technique. Or a combination of the two. Following consultation, Natural England (NE) recognise that trenchless techniques are generally a 'preferred method' as it is considered the impact to the intertidal is significantly reduced if trenching is not required (i.e. trenchless technique is used). The potential options include:
 - Option 1 Piperam duct (trenchless) and open cut in intertidal zone. This option consists of a combination of a trenchless technique to cross the dunes at the edge of the Saunton Sands carpark, with open cut used across the beach and into the intertidal zone




- Option 2 HDD duct with intertidal exit. This option will utilise Horizontal Directional Drilling (HDD) to install a maximum of two ducts from the carpark to the intertidal zone at a depth of 0m Above Ordnance Datum (A.O.D)
- Option 3 HDD duct with offshore exit. This option will utilise Horizontal Directional Drilling (HDD) to install a maximum of two ducts from the carpark to exit offshore at a depth of -5m A.O.D.
- 11. Whichever option is selected for the landfall (to MLWS) a section of open cut trench will be required to connect the TJB to the exit point for the trenchless crossing of the Saunton Golf Club. This will be located entirely within the carpark and will have a maximum length of 200m.
- 12. The technique proposed for the cable installation for the Braunton Burrows Crossing at Saunton Golf Club is a trenchless technique, either Horizontal Directional Drilling (HDD) or Direct Pipe. Both options will utilise the same location for the entry and exit points and involve a drill length of approximately 1.3km.
- 13. The crossing site runs through the Braunton Burrows SSSI and Special Area of Conservation (SAC), however both launch pits and the reception pit for the golf course crossing are located outside of the SSSI and SAC boundary. Braunton Burrows is characterised by an extensive system of coastal sand dunes and variably flooded slacks, grassland and scrub. The estuary is also designated as a shellfish water protected area under the Water Environment (Water Framework Directive) (England and Wales) Regulations 2017 (as amended) and a coastal sensitive area (eutrophic).





1.2.2 Taw Estuary Crossing

- 14. The Taw Estuary Crossing is proposed between an entry point on the south bank and an exit point on the north bank of the River Taw. The entry and exit compounds and pit locations will be set a minimum of 16m from the River Taw. The crossing site is located at a natural narrowing of the River Taw.
- 15. This site was determined based on an appraisal of constraints and engineering feasibility from both offshore and onshore perspectives. The location of the Taw Estuary Crossing is shown in Figure 1.2. A full discussion of the process undertaken to identify the Offshore Export Cable Corridor for the Offshore Project is laid out in Chapter 4: Site Selection and Assessment of Alternatives of the Offshore ES. A full discussion of the process undertaken to identify the Corridor for the Onshore Project is laid out in Chapter 4: Site Selection and Assessment of Alternatives of the Offshore ES. A full discussion of the process undertaken to identify the Site Selection and Assessment of Alternatives of the Onshore Export Cable Corridor for the Onshore Project is laid out in Chapter 4: Site Selection and Assessment of Alternatives of the Onshore ES.





- 16. Trenchless crossing techniques have been proposed for the Taw Estuary Crossing, with two options being considered, namely Horizontal Directional Drilling (HDD) and Direct Pipe. Both options will utilise the same location for the entry and exit points and involve a drill length of approximately 1.3km below the River Taw. Cable installation works will be undertaken from south to north, with temporary compound area and access requirements for the entry and exit points.
- 17. The area surrounding the crossing site and the River Taw form part of the Taw-Torridge Estuary Site of Special Scientific Interest (SSSI), which is of major importance for its overwintering and migratory populations of wading birds and rare plants that grow along the shores of the river.
- 18. In addition, the crossing site is also located in the vicinity of Braunton Burrows SSSI and Special Area of Conservation (SAC). Braunton Burrows is characterised by an extensive system of coastal sand dunes and variably flooded slacks, grassland and scrub. The estuary is also designated as a shellfish water protected area under the Water Environment (Water Framework Directive) (England and Wales) Regulations 2017 (as amended) and a coastal sensitive area (eutrophic).
- 19. The Taw Estuary Crossing lies within the Taw/Torridge operational catchment. At this location, the estuary channel has an asymmetrical cross-section at low tide. A geomorphology baseline survey (**Appendix 14.A: Geomorphology Baseline Survey**) was undertaken on 29th April 2022 and 17th August 2022 for the Onshore Project. The recorded channel width was around 1,000m, a wetted channel width at low water at around 250m and tidal range between 4m immediately downstream of Barnstaple and 8m at the estuary mouth. The channel bed substrates were characterised as sandy in the main channel and as finer silts in lower energy areas. The entry and exit points will be located on the adjacent floodplains of the Taw Estuary (Sir Arthur's Pill catchment) and coastal catchment (Braunton Burrows).

1.3 Rationale

1.3.1 Rationale for the Use of Trenchless Crossing underneath the Taw Estuary

20. OWL's commitment to the use of trenchless crossing techniques at the Taw Estuary Crossing ensures that potential impacts on designated sites and the wider estuarine and riverine environment are avoided as part of the Offshore and Onshore Project's embedded mitigation. All commitments laid out within the Onshore and Offshore ESs are set out in **Appendix 6.B: Mitigation Register** of the Onshore ES. This commitment is anticipated to:



- Avoid direct physical disturbance to the natural environment and non-statutory and statutory designated sites of ecological importance, including the Taw-Torridge Estuary SSSI and Braunton Burrows SSSI and SAC (which are considered further in Chapter 16: Onshore Ecology and Ornithology of the ES for the Onshore Project)
- Mitigate disturbance or harm to species such as waterfowl and migratory salmon and potential destruction, damage or disturbance to priority habitats such as coastal grazing marsh and mudflats
- Avoid direct disturbance to the River Taw's sediment transport pathways
- Avoid direct disturbance of the Taw/Torridge surface water catchment and the potential to alter the geomorphology and hydrology of the watercourse
- Mitigate increased sediment supply to the Taw/Torridge surface water catchment
- Mitigate the risk of contaminants supply to the Taw/Torridge surface water catchment and the River Taw and North Devon Streams groundwater catchment
- Avoid direct disturbance to surface drainage patterns and surface flows of the Taw/Torridge surface water catchment and therefore its associated flood risk
- Avoid the need for cable protection measures across the river bed.

1.3.2 Rationale for the Use of Trenchless Crossing underneath the Braunton Burrows

- 21. OWL's commitment to the use of trenchless crossing techniques at the Braunton Burrows Crossing ensures that potential impacts on designated sites and the wider environment are avoided as part of the Onshore and Offshore Project's embedded mitigation. All commitments laid out within the Onshore and Offshore ESs are set out in **Appendix 6.B: Mitigation Register** of the Onshore ES. This commitment is anticipated to:
 - Avoid direct physical disturbance to the natural environment and non-statutory and statutory designated sites of ecological importance, including the Braunton Burrows SSSI and SAC (which are considered further in **Chapter 16: Onshore Ecology and Ornithology** of the ES for the Onshore Project)
 - Mitigate disturbance or harm to species such as whitethroat and skylark and potential destruction, damage or disturbance to priority habitats such as shifting and fixed coastal dunes
 - Avoid direct physical disturbance of Saunton Golf Club
 - Avoid direct disturbance to surface drainage patterns and surface flows of the surface water catchment and therefore its associated flood risk
 - Avoid the need for cable protection measures across the Braunton Burrows.




1.4 Consultation

- 22. OWL notes the interests of Natural England (NE) and other stakeholders regarding the Taw Estuary Crossing and Braunton Burrows Crossing and its associated construction activities. This Method Statement has been prepared to demonstrate how the Offshore and aspects of the Onshore Project will avoid, minimise or mitigate environmental effects associated with the export cables crossing the Braunton Burrows and between the north and south bank of the River Taw.
- 23. OWL will consult these stakeholders and seek agreement on the design and methodology set out in this document prior to the commencement of construction works at the Taw Estuary and Braunton Burrows Crossing. Where conflict arises between environmental constraints or obligations, OWL will liaise with the relevant stakeholders to determine the optimal, acceptable solution for the crossing and would not proceed where reasonable concern from stakeholders was not being addressed.



2. Geotechnical Investigation

- 24. Key to ensuring that the design is appropriate for the location and that it can be constructed safely is understanding the ground and river conditions on-site. Detailed geotechnical investigations will be conducted to characterise ground conditions, establish the chemical and mechanical properties of the ground, map water depths and topography of the river bed and identify the hydrology and hydrogeology of the Taw Estuary Crossing and Braunton Burrows Crossing site. It is proposed that full geotechnical investigations and production of a subsequent report should be a post-consent planning condition that must be adhered to prior to any trenchless crossing works commencing.
- 25. Geotechnical investigations will be undertaken for the Taw Estuary and Braunton Burrows Crossing, this will include boreholes as a minimum and other surveys where deemed necessary.
- 26. Geological desk-based studies have been undertaken as part of an Onshore Export Cable Corridor feasibility assessment. Analysis of a total of 11 historic boreholes identified within the vicinity of Onshore Export Cable Corridor were identified and are shown in **Figure 2.1**.



| Provide and the second | | | | | | | | | | |
|---|--------------------|-------|--------|----------|----------------------|-------------|--|--|--|--|
| | dfall Cro | ossin | g | | | | | | | |
| | eholes Il holes | | | | | | | | | |
| _ 110 | | | | | | | | | | |
| | | | | | | | | | | |
| | | | | | | | | | | |
| | | | | | | | | | | |
| | | | | | | | | | | |
| | | | | | | | | | | |
| | | | | | | | | | | |
| | | | | | | | | | | |
| | | | | | | | | | | |
| | | | | | | | | | | |
| ent: | | | | Project: | | | | | | |
| Offs | hore Wi | nd Li | td. | | 'hite Cro ore Win | | | | | |
| | | | | Ulish | | ulann | | | | |
| e: | | | | | | | | | | |
| BGS Historic Ground Investigation Locations | | | | | | | | | | |
| | | | | | | | | | | |
| ^{ure:} 2.1 ^{Drawing No:} PC2978-RHD-ZZ-XX-DR-Z-0542 | | | | | | | | | | |
| vision: | Date: | | Drawn: | Checked: | Size: | Scale: | | | | |
| P03 | 18/08/20 | 023 | AB | ТМ | A3 | 1:30,000 | | | | |
| P02 23/06/2023 AB | | ТМ | A3 | 1:30,000 | | | | | | |
| ordinate system: British National Grid | | | | | | | | | | |
| | | | | | | | | | | |
| X | WHITE | CR | OSS | Ha | skonin | WHITE CROSS | | | | |



2.1 Hydrofracture Assessment

- 27. The preliminary hydrofracture assessment has been undertaken to determine the risk of drill fluid breakout to the surface at the Taw Estuary and Braunton Burrows trenchless crossings (Waterman Infrastructure & Environment Ltd, 2023). Hydrofracture occurs if during the drilling process the drilling fluid pressure in the borehole exceeds the resistance of the overburden soils resulting in a breakout at the surface.
- 28. Hydrofracture was one of Natural England's (NE) specific concerns raised about the project having dealt with similar projects where HDD in fluvial systems where silty sediments and air pockets exist has failed, including hydrofracture.
- 29. NE highlighted that the Taw Estuary trenchless crossing goes beneath the Taw-Torridge Estuary SSSI which is designated due to its overwintering and migratory populations of wading bords and in addition rare plants grow along the shores within wide areas of saltmarsh, mudflats and sandbanks. The Estuary also supports typical estuarine species such as mullet, flat fish, bass, pollack, migratory salmon, sea trout and eels along with many invertebrates.
- 30. Therefore, a hydrofracture assessment has been undertaken to determine the risk of drill fluid breakout to the surface at the Taw Estuary and Braunton Burrows Crossings.

2.1.1 Analysis Methodology

- 31. The preliminary hydrofracture assessment has been undertaken prior to the Geotechnical Investigation. Therefore, the assessment relies on a conservative assumption that the ground conditions are made up of granular materials (rather than firm to stiff clays or competent rock). The geotechnical analysis parameters are shown in **Annex 1: Hydrofracture Assessment**.
- 32. The groundwater level has been conservatively assumed as commensurate with the ground surface throughout the analysis. The groundwater level assumption is likely to be relaxed following the completion of ground investigation with associated groundwater monitoring.
- 33. The bore diameters are yet to be confirmed. It is anticipated that there will be a TJB between the onshore and offshore cables within Saunton Sands Car Park. The landfall calculations therefore assume an offshore cable specification within the golf course crossing and the Taw Estuary Crossing assumes an onshore cable specification (with a consequent reduction in likely cable and duct diameter).



2.1.2 Assessment Results

- 34. At each of the assessed trenchless crossings (Taw Estuary, Golf Course and Landfall), the assessment demonstrates that there is no significant risk of hydrofracture along the bore profiles with the exception of the final stages of the bore where the profiles begin to rise resulting in loss of cover. This is unavoidable but can easily be controlled by site measures such as sandbagging and casing in line with general working methodologies. Hydrofracture calculations and further information is set out within **Annex 1: Hydrofracture Assessment**.
- 35. The design will incorporate measures to address hydrofracture, ensuring sufficient depth of cover for the bore path. This approach minimises the hydrofracture risk through increased overburden pressure.
- 36. The risk of drilling fluid breakout is considered to be very low based on analysis of historical borehole and desk-based assessment of the geology present in the area. However, this cannot be fully assessed beforehand. Substantial decreases in the volume of returning drilling fluid to the entry pit will trigger the need for site personnel to assess the situation and respond accordingly. Therefore, a close watching brief during drilling fluid breakout is contained, bunded and pumped back to the entry pit with minimum disturbance to the surrounding environment.

2.2 Braunton Burrows Historical Borehole Analysis

- 37. A programme of geotechnical works are being undertaken for the offshore components of the Project, and this includes a Phase 2: Reconnaissance Geotechnical Investigation. The desk-based analysis undertaken as part of these works were reviewed to inform the preliminary design for the Landfall Crossing.
- 38. This indicated that within the nearshore area of the offshore export cable route (i.e. at landfall), the top of the Pilton Shales Formation, consists of Devonian and Carboniferous rocks of mudstone, sandstone, and limestone nature. The only layer observed below this unit was bedrock. Overlying this horizon, a continuous layer of sediments (Unit E) mainly composed of fine sand, is prominent.
- 39. Unit E has a thickness of around 7m at the landfall approach. Then, approximately 1 km away from the shoreline, the Unit thickness decreases rapidly to 2-3 m. From there, an unconformity within the seabed and underlying R1 is recognizable. During the following four kilometres, the thickness ranges from 2 to 5 m on the average.
- 40. It is recommended that further site investigation is undertaken to determine the Marine sediments present at the HDD Exit points, and that a Seismic/Mag survey



should be undertaken to provide sediment depth/depth to rockhead data across the intertidal area. But from this analysis **Table 2.1** suggests that a trenchless crossing is not precluded by the geology present, the cables can be installed, and the chosen methodology is relatively low risk.

| Location | Stratum | Depth (m bgl) | Thickness (m) |
|-------------|--------------------------------|---------------|---------------|
| Entry Point | Blown Sand | 0.00 | 0.00 to 10 |
| | Marine Beach Deposits (Unit E) | 10.00 | 7.00 |
| | Rock (Pilton Shales Formation) | 17 | - |
| Exit Point | Blown Sand | - | - |
| (Option 2 | Marine Beach Deposits (Unit E) | 0.00 | 2.00 |
| 1850m) | Rock (Pilton Shales Formation) | 2.00 | - |

Table 2.1 Braunton Burrows Landfall Crossing Conceptual Ground Model Stratum Depths

- 41. The analysis of historical borehole located onshore indicates within Braunton Burrows Blown Sands are likely to be present, overlying Holocene Estuarine Alluvium and Marine Beach Deposits and or Pleistocene/Fluvial Sands and Gravels. Superficial deposits and bedrock beneath the Saunton Golf Club Crossing are expected to be encountered up to 15m bgl at the eastern side of the golf course and 5m bgl at Saunton Sands carpark.
- 42. A conceptual ground model was developed as part of the feasibility assessment to provide information on the composition and depths likely to be encountered at the crossings of the Braunton Burrow. It is assumed that the entry point is underlain by a layer of Blown Sand and Marine Beach Deposits, overlaying rock. This strata composition continues to the exit point. It is noted that at this location, the Blown Sands are vegetated suggesting a more mature state and likely of increased density/cohesion, however, this would require confirmation via ground investigation. Table 2.2 suggests that a trenchless crossing is not precluded by the geology present, the cables can be installed, and the chosen methodology is relatively low risk. Similarly, to in Section 2.3, this will be confirmed prior to commencement of drilling activity via appropriate and agreed geotechnical investigations.

| Location | Stratum | Depth (m bgl) | Thickness (m) |
|--------------------|-----------------------|---------------|---------------|
| Entry Point | Blown Sand | 0.00 | 0.00 to 10 |
| | Marine Beach Deposits | 10.00 | 5.00 |
| | Rock | 15 | - |
| Exit Point | Blown Sand | - | - |

Table 2.2 Braunton Burrows Golf Course Crossing Conceptual Ground Model StratumDepths



| Location | Stratum | Depth (m bgl) | Thickness (m) |
|----------|-----------------------|---------------|---------------|
| | Marine Beach Deposits | 0.00 | 5.00 |
| | Rock | 5.00 | - |

2.3 Taw Estuary Crossing Historical Borehole Analysis

- 43. The historical borehole analysis indicates that the drift geology of the site is predominantly underlain by Marine or Estuarine Alluvium, Blown Sand and Tidal Flat Deposits, while its solid geology is predominantly underlain by Ashton Mudstone Member and Crackington Formation (Undifferentiated) and is typically presented as Mudstone and Siltstone.
- 44. It was noted that bedrock may be visible at the surface on the south bank of the River Taw but is expected to deepen substantially within the area to the north. However, ground investigation is required to confirm this observation. A borehole (SS43SE/25) drilled in 1963 was also noted east of the proposed entry point, where groundwater was encountered at a depth of 8.53m below ground level (bgl).
- 45. In addition, a conceptual ground model was developed as part of the feasibility assessment to provide information on the composition and depths likely to be encountered at the crossing site. This was informed by the geological desk-based studies and aerial images and topographic/bathymetric data (Appendix 8.B: Geophysical Survey Results of the Offshore ES) collected for the Offshore Project. The model shown in Table 2.3 suggests that a trenchless crossing is not precluded by the geology present, the cables can be installed, and the chosen methodology is relatively low risk. This will be confirmed prior to commencement of drilling activity via appropriate and agreed geotechnical investigations.

| Location | Stratum | Depth (m bgl) | Thickness (m) | | | | |
|-----------------------|--|---------------|---------------|--|--|--|--|
| Entry Point | Drift (Tidal Flats Deposit) | 0.00 | 0.00 to 6.40 | | | | |
| | Rock | 6.40 | - | | | | |
| River Crossing | Drift (Tidal Flats Deposit) | 0.00 | 3.50 | | | | |
| | Marine or Estuarine Alluvial Deposits | 3.50 | - | | | | |
| Exit Point | Drift (Tidal Flats Deposit) | 0.00 | 3.30 | | | | |
| | Marine or Estuarine Alluvial Deposits | 3.30 | 13.00 | | | | |
| | Rock | 16.30 | - | | | | |

| Table 2.3 Taw Es | stuary Crossing | Conceptual | Ground Model |
|------------------|-----------------|------------|--------------|
|------------------|-----------------|------------|--------------|

3. Design

46. The crossing design will be refined and finalised post-consent and will rely on inputs from onshore and offshore pre-construction site investigations, as well as



information from the detailed cable system design. Awaiting these pre-construction site investigations will ensure that the most appropriate design is selected in order to minimise impact to the surrounding environment. Site characterisation data of the entry and exit points and potential drill paths will inform the detailed design of the selected crossing technique.

- 47. Sufficient flexibility exists in the capabilities of modern trenchless technologies such as the capacity of drill rigs and range of drill heads available, to ensure a suitable solution can be delivered at the site within the parameters assessed within the ES.
- 48. The two trenchless crossing techniques being investigated for the Braunton Burrows: Saunton Golf Course Crossing (if a trenchless technique is applicable) and Taw Estuary Crossing to minimise disturbances to the physical and natural environment are:
 - Option 1 HDD: a construction technique whereby a tunnel is drilled below ground to avoid obstacles such as waterways and designated sites, and a pipeline, cable or other conduit is pulled through the drilled tunnel
 - Option 2 Direct Pipe: a construction technique that combines HDD and microtunnelling whereby the drilling of the underground tunnel and the installation of the pipeline, cable or other conduit occurs simultaneously in a one-pass operation.
- 49. Indicative drawings of the two options are shown in **Figure 3.1** and **Figure 3.2**. respectively. Key advantages and disadvantages associated with HDD and Direct Pipe are compared in **Table 3.1**.

| Trenchless Crossing Technique Option | Advantages | Disadvantages |
|---|---|---|
| HDD | Relatively economical trenchless option Fast mobilisation and site setup No requirement for large entry or exit pits. | Borehole only supported by bentonite, potential for collapse Not suitable for non- supporting ground due to a high risk of tool snapping or loss of control during push reaming Potential to lose tools downhole. |

Table 3.1 Trenchless Crossing Technique Comparisons



| Trenchless Crossing Technique Option | Advantages | Disadvantages |
|---|--|--|
| Direct Pipe | Able to retract the assembly to the entry pit and change cutting tools if required Relatively low pressure used at the cutting face, enabling shallower drill depths Suitable for superficial geology such as fluvial and alluvial Borehole permanently supported, very low risk of collapse. | Longer mobilisation and site setup time than HDD More expensive than HDD. |

- 50. Three techniques being investigated for the Braunton Burrows: Landfall Crossing:
 - Option 1 Piperam duct (trenchless) and open cut in intertidal zone: combination of a trenchless technique to cross the dunes at the edge of the Saunton Sands carpark (approx. 60m), with open cut used across the beach and into the intertidal zone using a cable plough (approx. 700m)
 - Option 2 HDD duct with intertidal exit: HDD will be used to install ducts from the carpark to the intertidal zone at a depth of 0m A.O.D., with a length for the drill of approximately 650m to MLWS
 - Option 3 HDD duct with offshore exit: HDD will be used to install ducts from the carpark to exit offshore at a depth of -5m A.O.D., with a length for the drill of approximately 1850m.
- 51. Only Options 2 and 3 for Landfall Crossing are discussed further in this document as they are the major trenchless techniques similar in design and methodology to the HDD option being considered for the crossings of the Golf Course and Taw Estuary.
- 52. A full description of Option 1 is provided in **Chapter 5: Project Description**.



| | 損 <u>12.80%</u> | | | TIDE NOT INDIO WELL BELOW E | CONOMICAL TIDE LOWEST ASTRONO CATED GIVEN LEVE BATHYMETRIC RIVE SSUMED DRY AT LC | IS R BED W TIDE | METRIC SURVEY DA | | WATER LEVEL THUS PREFER | Y WAS LIKELY PIO LAT THE TIME OF RENCE GIVEN TO C DATA AT RIVER | SURVEY | ì | | | | | | | | | | INDICA | ED ON BATH | EP CHANNEL N HYMETRIC SU AWN AS 5m D | URVEY | | | | |
|---------------------|---|---|---|----------------------------------|--|---|---|--|--|--|--------------------------------------|---|---|--|--|--|-------------------------------|---|---|---|--|---|-----------------------------------|--|--|--|-----------------------------------|--|--|
| Level | | | | | | | | | | | | | -0.57% | | | | | | | | | | | 8 | | | 6.55% | | |
| | -15 - -20 - -25 | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| Chainage | 0.000 10.000 30.000 30.000 40.000 | 60.000 70.000 80.000 90.000 100.000 | 110.000 120.000 130.000 140.000 | 160.000 170.000 180.000 | 200.000 210.000 220.000 230.000 240.000 | 260.000 270.000 280.000 290.000 | 310.000 320.000 330.000 350.000 350.000 | 360.000 370.000 380.000 390.000 | 400.000 410.000 420.000 430.000 | 450.000 450.000 460.000 470.000 | 490.000 500.000 510.000 | 520.000 530.000 550.000 550.000 | 560.000 570.000 580.000 590.000 600.000 | 610.000 620.000 630.000 640.000 | 650.000 660.000 670.000 680.000 | 690.000 700.000 710.000 720.000 | 730.000 740.000 750.000 | 760.000 770.000 780.000 790.000 800.000 | 810.000 820.000 830.000 840.000 850.000 | 860.000 870.000 880.000 890.000 | 910.000 920.000 930.000 940.000 | 960.000 970.000 980.000 | 1000.000 1010.000 1020.000 | 1030.000 1040.000 1050.000 1050.000 | 1070.000 1080.000 1090.000 1100.000 | 1110.000 1120.000 1130.000 1140.000 | 1160.000 1170.000 1180.000 | 1200.000 1210.000 1220.000 1230.000 | 1240.000 1250.000 1260.000 1270.000 |
| | | | | | | | | | | | | | | | | | 1 1 | | | | | | + 1 1 | | | | + | | |
| Existing Levels | 0.033 0.081 0.123 0.165 0.186 | | 0.094 0.025 0.000 0.013 | 0.150 0.219 0.288 0.356 | 0.425 0.493 0.507 0.516 0.516 0.516 | 0.535 0.530 0.535 0.535 0.539 | 0.549 0.553 0.558 0.558 0.563 | 0.572 0.577 0.581 0.586 | 0.590 0.595 0.598 0.579 | 0.560 0.541 0.521 0.502 0.833 | 0.403 0.464 0.445 0.426 | 0.406 0.387 0.368 0.368 0.349 | 0.330 0.318 0.305 0.292 0.279 | 0.266 0.253 0.240 0.227 | 0.215 0.202 0.189 0.177 | 0.167 0.156 0.149 0.138 | 0.134 0.123 0.102 | 0.086 0.088 0.090 0.093 | 0.097 0.100 0.102 0.102 0.107 | 0.109 0.111 0.114 0.116 0.116 | 0.121 0.123 0.125 0.128 | 0.132 0.135 0.135 0.137 0.137 | | 0.148 0.151 0.153 0.155 | 0.153 0.158 0.160 0.165 0.165 | 0.167 0.169 0.172 0.174 | 0.179 0.181 0.183 0.183 | 0.188 0.190 0.193 0.195 | 0.197 0.199 0.202 0.204 |
| | | | | | | | | | | | | | | | | | 1 1 | | | | | | | | | | | | |
| Level Difference | 1.202 2.508 2.960 7.960 | 7.331 9.231 9.764 8.697 | 8.496 8.594 8.661 8.721 8.721 | 8.912 8.984 8.984 9.018 | 9.068 9.139 9.191 9.328 9.328 | 9.419 9.459 9.528 9.595 6715 | 9.739 9.762 9.832 9.880 9.980 | 10.020 10.081 10.151 | 10.244 10.328 10.374 10.443 | 10.511 10.551 10.615 10.650 | 10.715 10.765 10.823 10.867 | 10.946 10.955 11.034 11.099 | 11.193 11.212 11.296 11.323 | 11.444 11.519 11.560 11.629 | 11.688 11.758 11.805 11.866 | 11.889 11.948 12.037 12.088 | 12.152 12.190 12.271 | 12.299 12.354 12.425 12.488 12.497 | 12.550 12.689 12.673 12.781 12.840 | 12.815 12.940 12.690 13.015 | 12.862 12.920 12.977 13.035 | 13.150 13.207 13.264 13.322 | 13.380 13.437 13.494 | 13.547 13.502 13.323 13.012 | 13.012 12.567 11.988 11.334 10.680 | 10.025 9.371 8.716 8.176 7.906 | 8.286 8.286 10.371 8.801 | 5.996 3.972 3.677 2.811 | 2.031 1.680 0.844 0.090 |
| Horizontal Geometry | , | | | | | I | | | | | I | I | | L =1271. | .719 | | I | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| Vertical Geometry | G =-12.799% L =26.583 | R =750.000 K =7.500 L =91.681 | | | | | | | | | | | <u>G</u> =-0.574% L =909.051 | | | | | | | | | | | R =750.0 K =7.50 L =53.39 | 00 | | G =6.545% L =190.892 | | |
| | | | I | | | | | | | | | | | | | | | | | | | | | | Γ | | | | |

RIVER CROSSING - LONGSECTION SCALE: H 1:2000,V 1:2000. DATUM: -25.000

This drawing should not be scaled. Dimensions to be verified on site. Any discrepancies should be referred to the Engineer prior to work being put in hand. This drawing is the property of Waterman Infrastructure & Environment Limited, and the drawing is issued on the condition that it is not copied reproduced, retained or disclosed to any unauthorised person, either wholly or in part without the consent in writing of Waterman Lengthere the product limited. Waterman Infrastructure & Environment Limited Pickfords Wharf, Clink Street, London SE1 9DG t 020 7928 7888 f 03333 444 501

GENERAL NOTES

- 1. THIS DRAWING IS TO BE READ IN CONJUNCTION WITH ALL ENGINEER'S, ARCHITECT'S OR OTHER RELEVANT DRAWINGS AND SPECIFICATIONS.
- 2. ALL DIMENSIONS AND LEVELS ARE TO BE CHECKED ON SITE BY THE CONTRACTOR PRIOR TO PREPARING ANY WORKING DRAWINGS OR COMMENCING ON SITE.
- THE CONTRACTOR MUST ENSURE AND WILL BE HELD RESPONSIBLE FOR THE OVERALL STABILITY OF THE BUILDING/STRUCTURE/EXCAVATION AT ALL STAGES OF THE WORK.
- 4. ALL WORK BY THE CONTRACTOR MUST BE CARRIED OUT IN SUCH A WAY THAT ALL REQUIREMENTS UNDER THE HEALTH AND SAFETY AT WORK ACT ARE SATISFIED.
- 5. ALL WORK IS TO BE CARRIED OUT IN COMPLIANCE WITH THE REQUIREMENTS OF THE RELEVANT STATUTORY AUTHORITIES AND REGULATIONS.

SITE COMPOUND LAYOUT KEY: 1. 50 KVA GENERATOR 2M X 2M

- 2. TOILET BLOCK 6M X 2M
- 3. DRY/CHANGE ROOM 6M X 2M 4. CANTEEN 6M X 2M
- 5. OFFICE 6M X 2M
- 6. OFFICE 6M X 2M 7. 21 TON TRACKED 360 EXCAVATOR
- 8. DRILL PIPE STORAGE 10M X 2M
- 9. HDD DRILL RIG 16M X 2M 10. POWER PACK 6M X 2M
- 11. CONTROL CABIN 6M X 2M
- 12. MUD LAB 3M X 2M
- 13. MUD ENTRY PIT 3M X 4M 14. HIGH PRESSURE MUD PUMP 6M X 2M
- 15. MUD MIXING TANK 7M X 2M
- 16. 350 KVA GENERATOR 5M X 2M
- 17. RECYCLING UNIT 6M X 2M 18. WATER STORAGE TANK 6M X 2M
- 19. DRY DRILLING FLUID STORAGE 4M X 10M
- 20. WORKSHOP 6M X 2M 21. STORES 6M X 2M

| II FRACOMBE T | DE GAUGE SITE | | | | | | | | |
|---------------------------|------------------------------|--|--|--|--|--|--|--|--|
| TIDE LEVELS | ORDNANCE DATUM NEWLYN (mAOD) | | | | | | | | |
| HIGHEST ASTRONOMICAL TIDE | 5.46 | | | | | | | | |
| MEAN HIGH WATER SPRINGS | 4.47 | | | | | | | | |
| MEAN HIGH WATER NEAPS | 2.19 | | | | | | | | |
| MEAN LOW WATER NEAPS | -1.69 | | | | | | | | |
| MEAN LOW WATER SPRINGS | -3.94 | | | | | | | | |
| LOWEST ASTRONOMICAL TIDE | -4.89 | | | | | | | | |

| GEOLOGY |
|-----------|
| BLOWN SA |
| DRIFT DEF |
| ESTUARIN |
| ROCK |
| |

| GEOLOGY KEY | |
|--------------------------|--|
| BLOWN SANDS (SAND DUNES) | |
| DRIFT DEPOSITS | |
| ESTUARINE DEPOSITS | |
| BOCK | |

1:2000 0 20m 40m 60m 80m 100m 120m 140m 160m 180m 200m

1:1 0 10 20 30 40 50 60 70 80 90 100

| RIVER | RIVER TAW OUTLINE HDD PLAN AND PROFILE | | | | | | | | | | | | |
|--|---|-----------------|-------------|--------------|------------|--|--|--|--|--|--|--|--|
| | | | | | | | | | | | | | |
| W waterman | | | | | | | | | | | | | |
| STOCKTON | | | | | | | | | | | | | |
| Broxden House Broxden Business Park Lamberkine Drive Perth PH1 1RA t: 01738 449 801 mail@watermangroup.com www.watermangroup.com | | | | | | | | | | | | | |
| Suitability | OR F | PLANNIN | IG SUB | MISSION | | | | | | | | | |
| Designed By | LP | Director | CG | Waterman Ref | E12731-135 | | | | | | | | |
| Drawn By | LP | Date | 20.05.22 | Scales @ A0 | AS NOTED | | | | | | | | |
| Stockton Checker | | Stockton Approv | er | Date | | | | | | | | | |
| Project - Origir | nator - | Volume - Level | - Type - Ro | e - Number | Revision | | | | | | | | |
| 12731-1 | 35-W | ′IF-77-X | X-M3-C | -91003 | P03 | | | | | | | | |

P0311.08.23SITE COMPOUND LAYOUTS REMOVED. RE-ISSUED FOR
INFORMATION AS PART OF PLANNING SUBMISSIONP0210.03.23TITLE UPDATED & DRAFT BANNER REMOVED

2 DRAFT ISSUE FOR INFORMATION ONLY

Amendments

WHITE CROSS FLOATING WINDFARM

A01 A1





| EL (m AOD) | 20 15 10 5 -17.58% -17.58% -17.58% 10 -17.58% -17.58% -17.58% -17.58% -17.58% -17.58% -17.58% -10 -17.58% -10 -10 -10 -10 -10 -10 -10 -10 | | | | | | _ | · | | | | | | | | | | | | | | | |
|---|---|--|--|--|---|---|---|---|--|---|----------------------|---|----------------------------------|---|--------------------------------|--|------------------------|-----------------------------------|--|---|-------------------------------------|--|-------------------------------------|
| | 25 — 30 — 35 — 40 — 45 — | | | | | | | | | | | | | | | | | | | | | -0.11% | |
| CHAINAGE (m) | 0+000 0+010 - 0+020 - 0+030 - 0+040 - | 0+060 | 0+110 | 0+150 0+160 - 0+170 - 0+180 - | 0+200 0+210 - 0+220 - 0+230 - 0+240 - | 0+250 0+260 0+270 0+280 0+290 | 0+300 0+310 - 0+320 - 0+330 - 0+340 - | 0+350 - 0+380 - 0+380 - 0+380 - 0+380 - 0+380 - 0+390 | 0+400 0+410 0+420 0+420 | 0+440 | 0+490 - 0+500 | 0+510 0+520 0+530 0+540 0+550 | 0+560 0+570 0+580 | 0+590 - 0+600 0+610 - 0+620 - 0+630 - | 0+640 - 0+650 0+660 - | 0+670 - 0+680 - 0+690 - 0+700 | 0+710 0+720 | 0+740 | - 06/+0 - 08/+0 | 0+800 0+810 - 0+820 - 0+840 - 0+840 - | - 078+0 - 078+0 - 088+0 | 0+890 0+900 0+910 0+910 | 0+920 |
| ONSHORE EXISTING LEVELS (m AOD) | 12.966 13.080 - 13.181 - 13.580 - 14.118 - 14.147 | 14.147 13.984 - 13.739 - 13.452 - 13.362 - 13.277 | 13.223 - 13.372 - 16.245 - 15.014 - | 12.462 8.021 - 7.558 - 5.960 - | 4.717 4.298 - 3.972 - 3.662 - 3.393 - | 3.174 | | | | | | | | | | | | | | | | | |
| OFFSHORE EXISTING LEVELS (m AOD) | | | | | | | | | | -4.792 - -4.746 - -4.718 - | -4.739 - | -4.780 - -4.800 - -4.800 - -4.800 - -4.800 - | -4.800 - -4.800 - -4.800 - | -4.800 - -4.749 -4.681 - -4.612 - | -4.476 - -4.407 -4.339 - | -4.270 - -4.202 - -4.134 - -4.065 | -4.003 - -3.992 - | -3.959 | -3.949 - -3.940 - -3.957 - -3.973 - | -3.989 -4.011 -4.070 -4.100 -4.100 | -4.146 - -4.146 - -4.215 - | -4.210 -4.287 -4.359 -4.431 | -4.503 -4.575 -4.627 |
| BORE PROFILE LEVEL (m AOD) (TOP OF PIPE) | 12.966 11.208 - 9.450 - 7.692 - 5.935 - 4.177 | 4.1// 2.419 – 0.661 – -1.061 – -2.717 – -4.306 | -5.829 - -7.284 - -8.674 - -9.996 - | -11.252 -12.441 - -13.563 - -14.619 - | -16.531 -17.387 - -18.176 - -18.898 - -19.554 - | -20.143 -20.666 - -21.122 - -21.511 - -21.833 - | -22.089 -22.278 - -22.401 - -22.456 - -22.468 - | -22.491 - -22.502 - -22.513 - -22.524 - | -22.535 -22.546 - -22.557 - -22.568 - | -22.579 - -22.590 -22.601 - -22.612 - -22.624 - | -22.635 - -22.646 | -22.657 - -22.668 - -22.679 - -22.690 - -22.701 | -22.712 -22.723 -22.734 | -22.745 - -22.756 -22.768 - -22.779 - -22.790 - | | -22.834 - -22.845 - -22.856 - -22.867 | -22.878 - -22.889 - | -22.900 - -22.912 - -22.923 | -22.934 - -22.945 - -22.956 - -22.967 - | -22.978 -22.989 - -23.000 - -23.011 - -23.022 - | -23.056 - -23.056 - -23.057 - | -23.067 - -23.078 - -23.089 -23.100 - | -23.111 - -23.122 - -23.133 - |
| BORE VERTICAL GEOMETRY | G=-17.577% L=69.709m- | | | | =1500.000m < =15.000 =262.001m | | | 1 | | | | | | | 1 | | | | | | | <u> </u> | |

INFERRED EXISTING GROUND PROFILE BETWEEN LIDAR AND BATHYMETRIC SURVEY DATA. LIDAR SURVEY DATA EXTENTS OFFSHORE BUT HAS BEEN CLIPPED AS APPEARS TO BE PICKING UP WATER LEVEL AT TIME OF SURVEY

20 —









This drawing should not be scaled. Dimensions to be verified on site. Any discrepancies should be referred to the Engineer prior to work being put in hand. This drawing is the property of Waterman Infrastructure & Environment Limited, and the drawing is issued on the condition that it is not copied reproduced, retained or disclosed any unauthorised person, either wholly or in part without the consent in writing of Waterman Infrastructure & Environment Limited Pickfords Wharf, Clink Street, London SE1 9DG t 020 7928 7888 f 03333 444 501 GENERAL NOTES OFFSHORE . THIS DRAWING IS TO BE READ IN CONJUNCTION WITH ALL ENGINEER'S, ARCHITECT'S OR OTHER RELEVANT DRAWINGS -----AND SPECIFICATIONS. 2. ALL DIMENSIONS AND LEVELS ARE TO BE CHECKED ON SITE BY THE CONTRACTOR PRIOR TO PREPARING ANY WORKING DRAWINGS OR COMMENCING ON SITE. 3. THE CONTRACTOR MUST ENSURE AND WILL BE HELD RESPONSIBLE FOR THE OVERALL STABILITY OF THE BUILDING/STRUCTURE/EXCAVATION AT ALL STAGES OF THE 4. ALL WORK BY THE CONTRACTOR MUST BE CARRIED OUT IN SUCH A WAY THAT ALL REQUIREMENTS UNDER THE HEALTH AND SAFETY AT WORK ACT ARE SATISFIED. 5. ALL WORK IS TO BE CARRIED OUT IN COMPLIANCE WITH THE REQUIREMENTS OF THE RELEVANT STATUTORY AUTHORITIES AND REGULATIONS. _____ 705% T R =5000.000m G =7.049% K =50.000 L =357.991m L =20.231m

WIF12731-1

A0-Wat-SDL-S

FLOTATION ENERGY LTD

FOR PLANNING SUBMISSION

110-099-DRG-

FLO-WHI-LAY-0017



| | Гe | 25 - 20 - 15 - 10 - | | |) | | | | | |
|------------------|-------|--|---------|----------|---------|-----------------|--------------|---------|----------|----------------------|
| | Level | 0-1 -5-1 -10-1 -15-1 -20-1 | | | | | | | | |
| Chainage | | - ² 000.0 | 10.000 | 20.000 | 30.000 | 40.000 | 60.000 | 70.000 | 80.000 | 90.000 |
| Existing Levels | | 8.743 | 8.569 - | 10.513 - | 9.745 — | 8.543 10.018 | 11.081 - | 10.848 | 10.998 — | 12.770 — 12.756 — |
| Level Difference |) | -0.014 | 0.614 - | 3.360 | 3.394 — | 2.994 5.271 | 7.136 - | 7.706 - | 8.657 — | 11.233 – 12.020 |
| Horizontal Geon | netry | 1 | | | | | | | | |
| Vertical Geomet | ry | | | | | 3 = 8 L =10 | .022 3.74 | % | | |

GOLF COURSE CROSSING - LONGSECTION SCALE: H 1:2000,V 1:2000. DATUM: -25.000

| | 0.58% | | | | | | | | | | | | | | 8.71 | % | | | | | | | | | | | | | | |
|----------------------|---|--------------------------------|-------------------------------|--|----------------------------------|-------------------------------|--|---|--|---------------------|--|---|--------------------------|----------------------------------|----------------------|---------------------------------------|---|--------------------------------------|---------|--|--|-------------------------------|----------------------------------|--|--------------------------------|----------------------------------|--|---|--|----------------------------------|
| | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 90.000 - 100.000 | 120.000 130.000 140.000 140.000 120.0000 120.00000 120.0000000000 | 160.000 170.000 | 180.000 190.000 200.000 | 210.000 220.000 230.000 240.000 | 260.000 270.000 280.000 | 290.000 300.000 310.000 | 320.000 330.000 340.000 350.000 | 360.000 370.000 380.000 390.000 390.000 | 410.000 430.000 440.000 140.000 | 450.000 - 460.000 - | 470.000 480.000 490.000 500.000 | 510.000 520.000 530.000 540.000 550.000 | 560.000 - | 580.000 590.000 600.000 | 610.000 - 620.000 - | 630.000 - 650.000 - 650.000 - 650.000 | 660.000 670.000 680.000 680.000 700.000 | 710.000 | 750.000 | 770.000 780.000 800.000 800.000 | 810.000 820.000 830.000 840.000 | 850.000 860.000 870.000 | 880.000 900.000 1 | 910.000 920.000 930.000 940.000 | 950.000 960.000 970.000 | 980.000 990.000 1000.000 | 1010.000 - 1020.000 - 1030.000 - 1040.000 - | 1060.000 1070.000 1080.000 1090.000 11090.000 | 1110.000 - 1120.000 - 1130.000 - 1140.000 - | 1150.000 1160.000 1178.928 |
| 12.770 – 12.756 – | 12.944 13.763 14.512 13.723 | 13.739 13.453 - 13.887 - | 12.436 - 8.995 - 7.997 | 7.882 | 8.198 8.138 8.022 | 8.258 8.405 8.761 | 10.486 11.898 12.385 15.458 | 15.163 13.924 15.365 12.590 | 12.220 – 12.362 – 12.430 – 12.577 – | 13.165 13.695 - | 14.033 14.138 14.137 14.269 | 14.310 14.392 13.997 13.935 13.460 | 13.519 | 13.073 – 14.098 – 13.629 – | 13.735 - 13.853 - | 14.248 – 14.366 – 14.493 | 14.647 14.796 14.929 14.877 16.152 | 18.458 | 17.068 | 18.433 16.645 15.299 15.299 | 15.206 | 14.491 | 14.672 – 14.318 – 14.550 – | 16.951 | 18.812 21.090 – 21.760 – | 20.882 - 18.539 - 16.761 - | 16.551 | 13.817 | 13.961 | 13.097 12.951 12.796 |
| 11.233 – 12.020 | 12.984 14.455 15.723 15.619 | 15.30/ 15.421 - 15.842 - | 14.333 – 14.335 – 9.779 | 9.606 9.641 9.516 9.616 | 9.633 9.633 9.516 9.343 | 9.520 9.610 9.909 | 11.576 12.931 13.359 16.375 | 16.022 14.725 16.108 13.276 | 12.790 | 13.505 | 14.258 14.305 14.320 14.320 | 14.304 14.329 13.876 13.255 13.255 | 13.225 | 12.663 – 13.631 – 13.104 | 13.152 - 13.212 - | 13.550 - 13.610 - 13.680 - | 13.776 13.867 13.943 13.833 15.050 | 17.299 15.862 14.538 14.538 | 15.678 | 16.928 – 15.082 – 13.621 – 13.621 | 13.469 13.612 13.731 13.794 | 12.394 | 12.532 - 12.121 - 12.295 | 14.638 - 16.361 - 16.181 - 14.365 - | 16.269 18.489 19.101 | 18.166 – 15.765 – 13.930 | 13.662 13.389 13.158 12.923 11.205 | 10.303 9.393 8.857 8.437 7.750 | 7.081 | 2.735 2.735 1.718 0.698 |
| L =1176.745 | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| | R =750.000 K =7.500 L =64.488 L =869.295 | | | | | | | | | | | | G =8.7 L <i>=</i> 78. | 07% 827 | | | | | | | | | | | | | | | | |

his drawing should not be scaled. Dimensions to be verified on site. Any discrepancies should be referred to the Engineer prior to work being put in hand. This drawing is the property of Waterman Infrastructure & Environment Limited, and the drawing is issued on the condition that it is not copied reproduced, retained or disclosed to any unauthorised person, either wholly or in part without the consent in writing of Waterman Infrastructure & Environment Limited Pickfords Wharf, Clink Street, London SE1 9DG t 020 7928 7888 f 03333 444 501

GENERAL NOTES

- 1. THIS DRAWING IS TO BE READ IN CONJUNCTION WITH ALL ENGINEER'S, ARCHITECT'S OR OTHER RELEVANT DRAWINGS AND SPECIFICATIONS.
- ALL DIMENSIONS AND LEVELS ARE TO BE CHECKED ON SITE BY THE CONTRACTOR PRIOR TO PREPARING ANY WORKING DRAWINGS OR COMMENCING ON SITE.
- THE CONTRACTOR MUST ENSURE AND WILL BE HELD RESPONSIBLE FOR THE OVERALL STABILITY OF THE BUILDING/STRUCTURE/EXCAVATION AT ALL STAGES OF THE WORK.
- ALL WORK BY THE CONTRACTOR MUST BE CARRIED OUT IN SUCH A WAY THAT ALL REQUIREMENTS UNDER THE HEALTH AND SAFETY AT WORK ACT ARE SATISFIED.
- ALL WORK IS TO BE CARRIED OUT IN COMPLIANCE WITH THE REQUIREMENTS OF THE RELEVANT STATUTORY AUTHORITIES AND REGULATIONS.

SITE COMPOUND LAYOUT KEY: 1. 50 KVA GENERATOR 2M X 2M

- 2. TOILET BLOCK 6M X 2M
- 3. DRY/CHANGE ROOM 6M X 2M 4. CANTEEN 6M X 2M
- 5. OFFICE 6M X 2M
- 6. OFFICE 6M X 2M 7. 21 TON TRACKED 360 EXCAVATOR
- 8. DRILL PIPE STORAGE 10M X 2M
- 9. HDD DRILL RIG 16M X 2M 10. POWER PACK 6M X 2M
- 11. CONTROL CABIN 6M X 2M
- 12. MUD LAB 3M X 2M
- 13. MUD ENTRY PIT 3M X 4M
- 14. HIGH PRESSURE MUD PUMP 6M X 2M 15. MUD MIXING TANK 7M X 2M
- 16. 350 KVA GENERATOR 5M X 2M
- 17. RECYCLING UNIT 6M X 2M
- 18. WATER STORAGE TANK 6M X 2M 19. DRY DRILLING FLUID STORAGE 4M X 10M
- 20. WORKSHOP 6M X 2M
- 21. STORES 6M X 2M

| P03 | 11.08.23 | SITE COMPOUND LAYOUTS REMOVED. RE-ISSUED FOR INFORMATION AS PART OF PLANNING SUBMISSION | LP | CG | | | | | | |
|------------|----------|--|----|-----|--|--|--|--|--|--|
| P02 | 10.03.23 | TITLE UPDATED AND DRAFT BANNER REMOVED | LP | CG | | | | | | |
| P01 | 20.05.22 | DRAFT ISSUE FOR INFORMATION ONLY | LP | CG | | | | | | |
| Rev | Date | Description | Ву | Chk | | | | | | |
| Amendments | | | | | | | | | | |

WHITE CROSS FLOATING WINDFARM

SAUNTON GOLF CLUB OUTLINE HDD PLAN AND PROFILE

FLOTATION ENERGY LTD



Stockton Approver

110-099-DRG-021

FLO-WHI-LAY-0018

Project - Originator - Volume - Level - Type - Role - Number Revision

12731-135-WIE-ZZ-XX-M3-C-91006 P03

Stockton Checker

GEOLOGY KEY BLOWN SANDS (SAND DUNES) DRIFT DEPOSITS ROCK

1:2000 0 20m 40m 60m 80m 100m 120m 140m 160m 180m 200m

1:1 0 10 20 30 40 50 60 70 80 90 100

A01 A1



3.1 Braunton Burrows Crossing design parameters

3.1.1 Landfall Crossing

- 53. Preliminary engineering appraisal was undertaken regarding the Landfall constructability. The following parameters are indicated for HDD components of Options 2 and 3, it should be noted these parameters will be refined, as a preferred trenchless crossing technique is determined for the final design:
- 54. The proposed cable landing is located in Saunton Sands car park, which is approximately 1km to the west of Saunton village.
- 55. It is assumed that offshore cable with a maximum outside diameter of 294mm will be required for the landfall crossing, this will typically require a duct with a minimum diameter of 458mm, or 1.56 times the cable diameter.
- 56. Due to available duct sections it is assumed a 560mm HDPE SDR 11 pipe diameter duct will be required. This size ducting requires a minimum diameter 914mm reamed borehole to install it. The initial trenchless pilot hole would therefore be reamed out to circa 312mm diameter prior to the 250mm duct being pulled through the bore.
- 57. Where two ducts are to be installed a minimum 10m separation will be required between the ducts.
- 58. As the HDD approaches the exit point, a reception pit will be excavated to clear the exit zone of beach/marine sediments, in order to prevent debris ingress into the bore.
- 59. It is proposed to install the ducts from offshore to onshore. This will require remote fabrication of the HDD ducts, either offsite at a local port or at the onshore compound. Marine support to install the ducts, such as floating on barges to the exit point, will also be required.
- 60. The proposed entry compound will be located within the Saunton Sands car park, and it is anticipated that this should be sufficient for the compound setup without any earthworks required.
- 61. Construction works at this location are to be completed during the off season between September and April. Movements to site for plant and materials should be optimised in order to minimise project traffic movements wherever possible. Due to the proximity of dwellings to the proposed construction compound, due consideration should be given to minimising noise, emissions, and light pollution wherever possible.



- 62. Access the HDD compound will be via the B3231 (Saunton road) and via the Car park access road. Due to the seasonal constraints and proximity to a public car park, and dwellings, it is proposed to install the landfall HDD from the west side of the HDD compound, and when complete, reposition the HDD rig to the east side of the HDD compound, in readiness for the HDD installation of the Golf course crossing to the east.
- 63. A Transition Joint Bay (TJB) will be required where the offshore cable is connected to the onshore cable. Typically a TJB will consist of precast reinforced concrete units to create an approximate 20m x 8m x 2m concrete box, infilled with a sand / gravel surround. These can be installed at depth such that they are trafficable with incorporation of vehicle rated covers.

3.1.2 Saunton Golf Course Crossing

- 64. Preliminary engineering appraisal undertaken as part of the Onshore Export Cable Corridor feasibility assessment indicates the following parameters. However, it should be noted these parameters will be refined, as a preferred trenchless crossing technique is determined for the final design:
- 65. The crossing is located from Saunton Sands car park to the east of Saunton Golf Club, with an approximate crossing length of 1.2 km.
- 66. At the Saunton Golf Course Crossing, it has been assumed that an onshore cable with a maximum outside diameter of 165mm will be required, which will typically require a duct with a minimum diameter of 225mm, or 1.5 times the cable diameter.
- 67. Due to available duct sections, and assuming HDPE SDR 21, a nominal 250mm diameter duct will be required. The initial trenchless pilot hole would therefore be reamed out to circa 312mm diameter prior to the 250mm duct being pulled through the bore.
- 68. The proposed entry compound will be located within the Saunton Sands car park, and it is anticipated that this should be sufficient for the compound setup without any earthworks required.
- 69. For a typical trenchless application, an ideal compound size of 50m x 50m will typically be required with level and stable terrain. The compound is required to site a variety of containers which contain welfare, offices, storage, mud labs, mud mixing, mud recycling units and workshops.
- 70. An entry pit should be formed for the containment of drill fluids and may require temporary support. Given that the overburden at site consists of Blown Sand



deposits and groundwater is considered likely to be shallow, there may be issues with leakage of the drill fluid which should be overcome through lining the pit with an impermeable barrier such as visqueen sheeting, so as to form a sump.

- 71. The exit compound is located within an area of arable farmland to the east of Saunton Golf Club. In typical HDD applications a minimum area of 100m length by 20m width behind the exit pit is used to facilitate stringing out the product pipe with the support of stilts and rollers. In this instance if HDD is the selected method of installation, it is anticipated that the product pipe will be pulled from the exit compound to the entry compound.
- 72. The Exit Compound will typically be required with level and stable terrain which will require minor earthworks on site. It is not anticipated that earthworks will require substantial excavation of solid deposits, the drilling contractor should be consulted during this aspect of the design.
- 73. A 3.5m to 4.0m wide temporary access track suitable for the equipment to be employed will need to be formed through the fields from the access off the Burrows Lane to the exit compound. This will require the placing of a suitable depth of imported clean angular stone, such as SHW Type A to Clause 801, placed on top of a geotextile separation membrane. Alternatively, temporary metal roadway could be used.
- 74. Depending on the location of the TJB a short section of onshore cable, installed in an open cut trench, may be required to connect the cable for the Golf Course Crossing to the TJB and the Landfall Crossing.
- 75. Joint bays will be required at either end of the trenchless crossing. Joint bays typically consist of precast reinforced concrete units, which create a box of approximately 12m by 4m by 1.5m infilled with a sand/gravel surround. The joint bays within the Saunton Sands car park will also incorporate vehicle rated covers.
- 76. The final design will be included within the final Method Statement to be produced pre-construction and will identify the following:
 - Entry pit and exit pit locations and their surrounding compounds. When crossing Internal Drainage Board (IDB) maintained watercourses, the entry and exit pits will be located at least 16m from the banks of the watercourse
 - Drill paths between the entry and exit pit locations, with the separation between drill lines being dictated by parameters from the cable design
 - Drill profiles based on an analysis of the site conditions and cable installation requirements.



- 77. Output from the design phase will provide recommendations on the drilling methodology to be adopted to best suit the selected crossing technique and the site conditions.
- 78. No ongoing requirement for regular maintenance of the onshore export cables following installation is anticipated. However, access would be required to conduct emergency repairs, if necessary.
- 79. No decision has been made regarding the final decommissioning policy for the onshore export cables, as it is recognised that industry best practice, rules and legislation change over time. It is likely the cables would be removed from the ducts and recycled, with the joint bays and ducts capped, sealed and left in situ.

3.2 Taw Estuary Crossing design parameters

- 80. Preliminary engineering appraisal undertaken as part of the Onshore Export Cable Corridor feasibility assessment indicates the following parameters. However, it should be noted these parameters will be refined, as a preferred trenchless crossing technique is determined for the final design.
- 81. At the Taw Estuary Crossing, it has been assumed that an onshore cable with a maximum outside diameter of 165mm will be required, which will typically require a duct with a minimum diameter of 255mm, or 1.5 times the cable diameter.
- 82. Due to the available duct sections and assuming HDPE SDR 21, a nominal 250mm diameter duct is assumed. This will require an initial pilot hole to be reamed out to 312mm diameter prior to the pull back operation for the HDD option. For the Direct Pipe option, the duct would be installed within the Direct Pipe Casing prior to the annulus being grouted up, which will likely require a Direct Pipe diameter of 1,422mm, subject to ground investigation.
- 83. Both options will likely require a drill length of 1.3km and will use the same entry and exit point locations.
- 84. Joint bays will be required at either end of the trenchless crossing. Joint bays typically consist of precast reinforced concrete units, which create a box of approximately 12m by 4m by 1.5m infilled with a sand/gravel surround.
- 85. The final design will be included within the final Taw Estuary Crossing Method Statement to be produced pre-construction and will identify the following:
 - Entry pit and exit pit locations and their surrounding compounds. When crossing main rivers or IDB maintained watercourses, the entry and exit pits will be located at least 16m from the banks of the watercourse



- Drill paths between the entry and exit pit locations, with the separation between drill lines being dictated by parameters from the cable design. The depth of the drill path below the channel bed at the Taw Estuary Crossing will be confirmed following completion of hydrofracture (the inadvertent loss of drilling fluid from the borehole annulus to the surrounding soil due to excess fluid pressure) calculations and geotechnical investigations
- Drill profiles based on an analysis of the site conditions and cable installation requirements.
- 86. Output from the design phase will provide recommendations on the drilling methodology to be adopted to best suit the selected trenchless crossing technique and the site conditions.
- 87. No ongoing requirement for regular maintenance of the onshore export cables following installation is anticipated. However, access would be required to conduct emergency repairs, if necessary.
- 88. No decision has been made regarding the final decommissioning policy for the onshore export cables, as it is recognised that industry best practice, rules and legislation change over time. It is likely the cables would be removed from the ducts and recycled, with the joint bays and ducts capped, sealed and left in situ.



4. Drilling Methodology


4.1 Site Set Up

4.1.1 General Set Up

- 89. Prior to commencement of construction works at the Crossings, the general site area will be prepared to a suitable level to ensure construction safety and good operating conditions for drilling works.
- 90. Access will be required to allow the establishment of temporary compounds around the entry and exit points. The entry point compounds will also include a control cabin and welfare facilities for site personnel, including connection of utilities such as water, power, lighting and telecommunications services. Other plant and equipment anticipated within the compound include storage containers, power packs, mud labs, recycling units, mud mixing units, mud pumps, hydraulic excavators, power generators and other construction vehicles and machinery.
- 91. Temporary site lighting will also be installed and assessed for effectiveness ahead of starting construction activities. The compounds will be enclosed in temporary Heras fencing, and 24-hour security will be present until site reinstatement and demobilisation is complete. Information on existing underground utilities will also be obtained, and their location will be located and marked to ensure adequate separation distances. Any utilities that conflict with the proposed drill paths or site operations will be exposed to confirm their exact location, and appropriate measures will be taken to protect them from damage and ensure construction safety.

4.1.1.1 Braunton Burrows Crossing (Landfall and Saunton Golf Course Crossings)

92. A single temporary onshore compound will be required for the entry point for both the landfall and Saunton golf course crossings, which will be set within the car park at Saunton Sands. This would be up to 100m long by 50m wide for the landfall (Stage 1 Figure 4.1), reduced to 50m long by 50m wide (Stage 2 Figure 4.1) for the crossing of the golf course. This location is outside of the Braunton Burrows SAC.





- 93. Access to the entry point compound will be from Saunton Road (B3231) using the existing car park access road. It is not anticipated that any major works will be needed to improve this access for the Onshore Project.
- 94. The initial site setup and establishment will be undertaken outside of the peak summer holiday season, defined as July August in order to mitigate any impacts on either the local highways or the users of the car park. Movement to site for plant and materials will be optimised in order to minimise traffic movements from the Onshore Project wherever possible.
- 95. When the works associated with the crossings are completed the area will be reinstated and the areas with the carpark returned to the operator.
- 96. The temporary exit compound for the Saunton golf course crossing will be located within the fields to east, outside of the Braunton Burrows SAC. There will be no exit compound for the landfall crossing as the exit location will be below MLWS.
- 97. Access to the exit point compound for the Saunton golf course crossing will be through the Onshore Export Cable Corridor using the temporary main access from Saunton Road (B3231) and the Onshore Project haul road.
- 98. For the landfall crossing the ducts would be fabricated onshore, either at a local port or at the onshore compound, and then floated out to the exit point on barges to be installed from offshore to onshore. The stringing and welding of the ducts for the Saunton golf course crossing will be undertaken in the fields to the east of the golf course within the Onshore Export Cable Corridor, therefore the ducts would be pulled from the exit to the entry compound.

4.1.1.2 Taw Estuary Crossing

- 99. The entry compound will be located within an area of farmland adjacent to the East Yelland substation on the south bank of the River Taw. Minor earthworks will be required to level the working area, which typically involve stripping and storing the topsoil, installing geotextile membranes to the sub-surface and laying and compacting suitable hard material to form a firm working platform, although substantial excavation of solid deposits is not anticipated.
- 100. Preliminary engineering appraisal indicates that a compound area of 50x50m is considered ideal for a typical trenchless application. In addition, for the HDD option, a cast in-situ reinforced concrete anchor block would be installed adjacent to the entry point as an anchor for the HDD rig. For the Direct Pipe option, a sheet pile launch pit would be required.



- 101. Access to the entry compound on the south bank will be from the new haul road connecting to the existing private road and then to the highway at the West Yelland Road (B3233).
- 102. The entry compound would be located outside of the Taw-Torridge Estuary SSSI.





- 103. The exit compound will be located within an area of farmland adjacent to the Crow Point Carpark. The stringing-out and welding of the HDPE ducts (for the HDD option) would be undertaken on the north side of the Taw Estuary within the Onshore Export Cable Corridor, therefore the ducts would be pulled from the exit to the entry compound. Similar minor earthworks are anticipated for the exit compound.
- 104. Access to the exit point compound for the Taw Estuary crossing will be through the Onshore Export Cable Corridor using the temporary main access from Saunton Road (B3231) and the Onshore Project haul road.
- 105. The exit compound would be located outside of the Braunton Burrows SAC, Braunton Burrows SSSI, and the Taw-Torridge Estuary SSSI.

4.1.2 Construction Environmental Controls

- 106. All construction activities at the Taw Estuary and Braunton Burrows Crossing will observe the best practice measures and conditions documented in **Appendix 5.C: Outline Construction Environmental Management Plan** and other relevant management plans submitted in support of the Offshore and Onshore Project's consenting and planning permission applications. Works will also be carried out in accordance with the contractor's own site management plan, risk assessments and method statements.
- 107. Prior to the commencement of construction works at the Taw Estuary and Brunton Burrows Crossings, OWL will consult NE and other stakeholders and seek agreement on the design and methodology set out in this document.
- 108. Within **Sections 4.1.2.1** to **4.1.2.12**, relevant construction environmental controls are laid out.

4.1.2.1 Noise and Vibration

- 109. Construction environmental controls relevant to noise and vibration anticipated for the site include but are not limited to:
 - Adequate control measures to minimise noise and vibration impacts will include temporary screening and traffic management measures specified the Construction Traffic Management Plan (CTMP).

4.1.2.2 Terrestrial Ecology

110. Construction environmental controls relevant to terrestrial ecology anticipated for the site include but are not limited to:



- Adequate control measures to avoid and minimise impacts on flora and fauna and any protected species
- Consents/licences may also be required in relation to protected species and habitats
- Specific measures to mitigate impacts on wintering birds (including high tide roosts), such as screening, minimising the movement of personnel and timing of the works.

4.1.2.3 Terrestrial Archaeology and Cultural Heritage

- 111. Construction environmental controls relevant to terrestrial archaeology and cultural heritage anticipated for the site include but are not limited to:
 - Sites of archaeological importance will be identified in the Written Scheme of Investigation (WSI) and appropriate environmental control measures such as the establishment of exclusion and buffer zones will be implemented where required.

4.1.2.4 Wastewater Discharges

- 112. Construction environmental controls relevant to wastewater discharges anticipated for the site include but are not limited to:
 - Relevant permits will be obtained by the principal contractor from the regulator associated with the use of septic tanks for other effluent/washout water treatment facilities
 - Wastewater management through the use of septic tanks or other effluent/washout water treatment facilities. In addition, monitoring and recording specified volumetric, quality or reference conditions to demonstrate compliance will be undertaken
 - Waste sludge from septic tanks and effluents from cesspits and sewage holding tanks must be removed by a suitably licenced and registered waste carrier in accordance with Duty of Care requirements
 - Monitoring records in relation to the disposal of grey water, foul water, bilge water or ballast water during the construction phase must be retained.

4.1.2.5 Oils, Fuels and Chemicals

- 113. Construction environmental controls relevant to oils, fuels and chemicals anticipated for the site include but are not limited to:
 - Ensure adequate controls for the delivery, storage and use of fuels, oils and chemicals on site



- Oils and chemicals must be clearly labelled and a up-to-date hazardous substance register must be retained
- The principal contractor will wherever possible use drilling fluids that are on the PLONAR (Poses Little Or No Risk), the list is controlled and maintained by The Centre for Environment, Fisheries and Aquaculture Science (CEFAS)
- Activities involving the handling of large quantities of hazardous materials, such as deliveries and refuelling, should have detailed method statements and be undertaken by designated and trained personnel
- Oil and fuel storage must be robust and provide adequate secondary containment and be located in designated areas taking into account security, the location of sensitive receptors and pathways such as drains and watercourses, and safe access for plant and manual handling
- Spill response materials should be provided nearby an be readily accessible, with project personnel trained in spill response
- All materials ordered or brought to site listed as hazardous under the Control of Substances Hazardous to Health (COSHH) Regulations are accompanied with hazardous information sheet.

4.1.2.6 Waste Management and Circular Economy

- 114. Construction environmental controls relevant to waste management and circular economy anticipated for the site include but are not limited to:
 - The waste reduction hierarchy (Avoid, Reuse, Recycle or Recover) should be considered where practical and economically feasible prior to considering disposal
 - The principal contractor is required to prepare a Waste Management Plan to record the following information, as a minimum:
 - The types and quantities of waste generated
 - The management approach for each waste type (Reuse, Recycle, Recover, Dispose) including any treatment
 - The storage arrangements for each waste type
 - The site waste monitoring and reporting arrangements.
 - Waste carrier details and waste management/disposal facilities.
 - Duty of care requirements in relation to the storage, transfer and disposal of waste must be complied with
 - Circular economy principles should be considered, where practical and economically feasible, specifically the priority area of circular construction and adopting circular economy interventions such as:



- adopting circular design principles and construction processes, particularly the opportunity to create a physical and virtual resource recovery and material exchange hub to make better use of material wasted in construction
- supporting the growth of regional specialist circular products and services in the construction industry.

4.1.2.7 Traffic Management

- 115. Construction environmental controls relevant to traffic management anticipated for the site include but are not limited to:
 - Appointment of a Traffic Management Coordinator (TMCo)
 - Obtain technical approval for construction of accesses and crossings
 - Implement direction signing
 - Establish monitoring systems
 - Agree scope of and undertake pre-commencement highway condition surveys
 - Agree and implement measures for each access to control the deposition of detritus on the public highway
 - Inspect the highway for detritus and request regular cleansing as required
 - Monitoring of CTMP measures
 - Produce monthly monitoring reports
 - Update condition surveys and agree any remedial works.

4.1.2.8 Surface Water Management

- 116. Construction environmental controls relevant to surface water management anticipated for the site include but are not limited to:
 - A detailed surface water management design/drainage plan for the site included in the CEMP. The plan should detail the surface water management measures to be implemented during the works. The detailed design should be supported by the rationale for selecting the chosen mitigation measures, together with associated calculations and methodologies for sizing. Where appropriate, the principles of Sustainable Urban Drainage Schemes (SUDS) should be applied
 - Mitigation measures must be maintained and monitored on a regular basis. A record of inspections of mitigation measures and any required maintenance carried out must be maintained.

4.1.2.9 Water Abstraction

117. Construction environmental controls relevant to water abstraction anticipated for the site include but are not limited to:



- Abstraction of water may be required for potable supply or for use during site activities, such as concrete batching or washing. Where this is required, any permits for the use of abstracted water during the construction related activities must be obtained
- Monitoring and recording associated abstraction rates or other licence requirements to demonstrate compliance.

4.1.2.10 Emissions to the Air

- 118. Construction environmental controls relevant to emissions to the air anticipated for the site include but are not limited to:
 - Measures recommended by the Institute of Air Quality Management (IAQM)
 - Appropriate mitigation measures to suppress dust and minimise emissions to the air during the construction works.

4.1.2.11 UXO Risk

- 119. Construction environmental controls relevant to UXO risk anticipated for the site include but are not limited to:
 - Surveys and assessments of the construction site, identifying potential UXO presence or historical activities should be undertaken by the Principal Contractor. In the event of any suspected or confirmed UXO findings, Principal Contractor will be required to implement appropriate measures, such as notifying relevant authorities, establishing exclusion zones, and engaging specialised personnel for safe removal and disposal.

4.1.2.12 Project Programme and Working Hours

- 120. Construction environmental controls relevant to project programme and working hours anticipated for the site include but are not limited to:
 - Working times will be restricted to 12-hour shifts, except for circumstances in which longer periods are required due to the nature of works, to avoid night time working. However, in exceptional circumstances longer periods may be required due to the nature of works. These will be agreed in advance with the relevant authorities.

4.2 HDD

121. The description provided within this appendix is an indicative description applicable to all of the crossings.



4.2.1 Drill Rig Set Up

- 122. For the HDD options, a 1.5m deep entry pit would be excavated adjacent to the entry point, measuring approximately 4m by 4m. This pit would be surrounded by the excavated subsoil and enclosed using barrier fencing to prevent access by unauthorised personnel and provide a safe working environment. Given that the overburden around the entry point location consists of Tidal Flat deposits and groundwater is considered likely to be shallow, the entry pit may require temporary support and would be lined with an impermeable membrane such as plastic sheeting to form a sump and containment of drilling fluids. Excavated topsoil will be stored in a designated area and kept separate from the subsoil to prevent contamination.
- 123. The HDD rig, control cabin, power packs, mud labs, recycling units, mud mixing units, mud pumps, hydraulic excavators and other equipment will be delivered to the site via heavy goods vehicles, offloaded and assembled on the working platform. A slurry pump will be installed adjacent to the excavated entry pit to pump the drilling fluid-laden cuttings to the recycling units.
- 124. A steel casing pipe will be installed by an excavator as a guide pipe at the entry point. The HDD rig and ancillary equipment will be positioned at their working positions, and all necessary connections and checks will be made. The rig will be anchored to the concrete anchor block and adjusted vertically to the correct ground entry angle in accordance with the HDD design.
- 125. An indicative layout for the HDD rig set up will be presented at a later stage to reflect the final design and the nature of equipment and machinery to be used onsite.

4.2.2 Pilot Hole

126. Following all site preparation works, the pilot hole will be drilled through the ground following the predetermined profile trajectory to the exit point on the other side of the river bank. The HDD rig uses a drill string, which comprises of a drill bit connected to a gyroscope and magnetic steering system and a series of drill pipes. Drilling fluid is jetted through the centre of the drill string and out through nozzles within the drill bit to provide hydraulic power to a steerable mud motor. The drilling fluid-laden cuttings are transported back through the drilled hole to the surface and into the entry pit where the mixture is constantly pumped through the mud separation and recycling system and reused as drilling fluid, with the addition of new water and bentonite clay as needed.



- 127. Directional guidance is achieved via a signal transmitted from the gyroscope and magnetic steering system in the first drill pipe to the drilling control unit in the control room. The guidance engineer uses the directional data and records of the length of the drill pipe to calculate the progress and position of the drill bit. Such calculations will be performed at regular intervals, typically at every point the drill advances one drill pipe length, and steering corrections will be made when necessary.
- 128. The pilot hole will stop a short distance from exiting the bedrock at the exit point location, also known as the stop short point, to contain the drilling fluid within the bore during the reaming phase. The drill string will then be retracted back through the hole to the entry point by the HDD rig.

4.2.3 Reaming

- 129. After the pilot drill string has been withdrawn from the bore, an opener reamer will be assembled onto the drill string at the entry point in order to increase the pilot hole diameter. A bull nose and stabilisers attached to the front and back of the reamer respectively will help centralise the reamer within the pilot hole. The reamer is rotated and advanced along the pilot hole whilst pumping drilling fluid through the reamer nozzles. As with the pilot hole drilling, drilling fluid-laden cuttings are transported to the entry point to be recycled.
- 130. Upon reaching the stop short point, the drill string will be retracted, and the nextsized reamer will be assembled onto the string and re-deployed to continue widening the hole. This process will continue until the hole is large enough to accommodate the size of the cable duct assembly.
- 131. A final jetting and steering assembly are then installed to the drill string at the entry point and advanced through the reamed bore to punch out at pre-determined exit point. The final assembly will be removed from the drill string and replaced with a pull back assembly to facilitate the cable duct installation.

4.2.4 Pull Back

132. The cable duct to be installed will be positioned at the exit compound. The drill string with the pull back assembly will be attached to the cable duct at the swivel, and the HDD rig will then pull the drill string along with the cable duct through the reamed bore through to the entry point, at which point the installation process is complete.



4.2.5 Demobilisation

133. Once quality and safety checks have been performed and the HDD operations have fully concluded, the contents of the entry pit along with all drilled cuttings, drilling fluid, buffer tank mixture and other construction waste will be disposed of via a registered waste carrier to a licenced facility. All geotextile membranes will be removed, and the entry pit will be backfilled with its original soil. The HDD rig will be de-rigged, and all ancillary equipment and structures will be disassembled on the working platform and transported back, allowing the site to be cleared.

4.3 Direct Pipe

134. The description provided within this appendix is an indicative description applicable to all of the crossings.

4.3.1 Pipe Thruster and Tunnel Boring Machine Set Up

- 135. For the Direct Pipe option, an entry pit would be excavated adjacent to the entry point in line with the approved temporary compound design. Calculations will be undertaken as part of the design to ensure that the entry pit and the required anchoring system are capable of withstanding the horizontal and vertical thrust forces generated by the Pipe Thruster within acceptable safety margins.
- 136. The Pipe Thruster, control cabin, and ancillary equipment and structures will be delivered to the site via heavy goods vehicles, offloaded and assembled on the working platform. After securing the launch cradle to the underlying geology where the entry pit is excavated, the base frame of the Pipe Thruster, which comprise two separate parts, will be lifted into place at the base of the pit and securely fixed to the launch cradle. Hydraulic thrust cylinders will then be positioned in the pit and securely fixed to the thruster base at the correct ground entry angle.
- 137. Securing ports on each side of the base frame parts will be used to secure the thruster base to the launch cradle, providing both horizontal and vertical mechanical anchoring. Once the anchoring system is installed, the Pipe Thruster can then be lowered into position and secured. A launch seal will also be mechanically secured to the entry pit headwall to prevent the ingress of groundwater, cuttings and drilling fluid returns into the pit.
- 138. In general, the minimum width of the entry pit is determined by the width of the base frame, the maximum width of the opened clamping unit and a minimum of 1 m clearance on each side for safety purposes. The minimum length of the entry pit is determined by the maximum length of the Pipe Thruster unit and the minimum distance of the unit from the front face of the entry pit, which is dependent upon



the ground entry angle and the size of the Pipe Thruster. The typical entry pit size is 6.3m width by 20m length. The depth of the entry pit is determined by the minimum required cover over the launch seal. A minimum of 1.5 times the outer diameter of the tunnel boring machine (TBM) is recommended for cover above the launch seal.

139. The TBM and its associated components will be lifted into position centred on the launch seal, at the correct ground entry angle and parallel to the thrust cylinders of the Pipe Thruster. An antiroll unit will be secured to the launch cradle and Pipe Thruster to prevent the potential rotating of the clamping unit and subsequently the TBM assembly and the attached pipeline. The TBM assembly contains the cutting head at the front, power packs, feed and slurry lines for drilling fluid transport and a conical interface ring at the rear.

4.3.2 Pipe String Preparation

- 140. The pipeline may be strung out and welded onto the TBM assembly as a single continuous pipe string, sufficient to complete the installation from the entry to the exit pit in a single operation. Alternatively, should the site have working space limitations, it is possible to weld the pipeline and perform the installation in sections. Typically, the pipe string will be welded with a set back from the rear of the entry pit and subsequently placed on rollers to allow the pipe string to travel linearly into the borehole. Roller cradles and a ramp may also be needed at the rear of the entry pit to align with the ground entry angle of the TBM assembly and account for the difference in elevation.
- 141. In addition, supply lines will also be installed externally and/or internally to the pipe string, connecting into the control cabin and the mud separation and recycling system. These supply lines include electric and data cables, slurry and discharge hoses and drilling fluid hoses. Slurry pumps and feed line coolers will also be inserted into pipe string. In order to reduce the required length of the feed and slurry lines, it is recommended that the mud separation and recycling plant and drilling fluid injection pump are located close to the midpoint of the pipe string.
- 142. Once the welding, testing and coating operations are completed on the pipe string and all ancillary equipment has been installed, the front of the pipe string will be secured to a weld-on adaptor, which is then connected to the rear of the TBM assembly at the conical interface ring. All supply lines inside the pipe string will also be connected to the corresponding inlets inside the TBM assembly.
- 143. The clamping unit of the Pipe Thruster will then be opened to a sufficient width and positioned above the pipe string using a mobile lifting appliance. Once the clamping



unit is lowered into the entry pit and seated over the pipe string, the clamp will be closed, and the clamping plates will be hydraulically extended until the clamp is securely holding the pipe string. Hydraulic thrust cylinders on the Pipe Thruster will then be extended to the clamping unit and connected mechanically to finalise the site setup.

4.3.3 Pipe Thrust and Insertion

- 144. Prior to tunnelling works, the hydraulic, electric and pneumatic systems of the entire assembly will be activated and tested to confirm correct functionality. Once a functional test is complete, the TBM assembly is then inserted through the launch seal at the front of the entry pit. The cutting head on the TBM will then continue to drill forward along the predetermined profile trajectory to the exit point on the other side of the river bank. The pipe string, which is connected to the TBM assembly, will also be thrusted into the borehole and transported along the drill path, allowing the pipeline to be installed simultaneously with the drilling operations.
- 145. If required, the pipe string may also be installed in multiple sections. After the TBM assembly and initial pipe string is inserted into the borehole, a new pipe string can be lowered into the entry pit and welded to the rear end of the already inserted pipe string. The process is then repeated until the full length of the pipeline is achieved.

4.3.4 Demobilisation

- 146. Once the TBM assembly reaches the exit point on the other side of the river bank, the components of the assembly will be disconnected either individually or together in one piece. The dimensions of the exit pit would need to provide sufficient length for the disassembly. The supply lines, slurry pumps and feed line coolers within the installed pipe string will also be disassembled by retracting the wheeled carrier racks. Supply lines are then disconnected, cleaned and inspected for damage prior to storage.
- 147. Once quality and safety checks have been performed and all Direct Pipe operations have fully concluded, the contents of the entry pit along with all drilled cuttings, drilling fluid, buffer tank mixture and other construction waste will be disposed of via a registered waste carrier to a licenced facility. All geotextile membranes will be removed, and the entry pit will be backfilled with its original soil. The Pipe Thruster and anchoring system will be de-rigged, and all ancillary equipment and structures will be disassembled on the working platform and transported back, allowing the site to be cleared.



4.4 Working Hours

148. The typical working hours expected at the Braunton Burrows and Taw Estuary Crossing are 07:00 to 19:00 Monday to Friday, Saturday 07:00 – 13:00; however some 24 hour working we be required for the drilling associated with the trenchless cable installation methods. A maximum of 14 days of 24 hour working for each drill has been assessed. Continuous periods of construction may be required depending on the nature of works and where these are required they will be agreed in advance with the relevant authorities. Supervision will not be reduced when night shifts are undertaken. All site housekeeping checks and refuelling will be scheduled during daylight hours.



5. Drilling Fluid Management

5.1 Purpose of Drilling Fluid

- 149. Trenchless crossing techniques are undertaken with the aid of a viscous drilling fluid, typically a mixture of water, polymers and ground and refined bentonite clay (a non-toxic clay commonly used in agricultural practices). Bentonite clay is typically delivered to site as a dried and finely ground powder, which is then rehydrated in a mix tank with water. Bentonite clay is included on the OSPAR Commission's List of Substances Used and Discharged Offshore which are Considered to Pose Little or No Risk to the Environment (PLONOR) (OSPAR Commission, 2021).
- 150. Drilling fluid serves many purposes such as providing hydraulic cutting action to any alluvial geology, providing hydraulic power to the downhole mud motor, transporting cuttings out of the bore, keeping cuttings in suspension when drilling operations are halted and cooling and lubricating the drill string and product pipe. It also gives support to the borehole and equalises pressure differences between the borehole and the geological formation by building a filter cake (a thin layer of drilling fluid that lines and seals the borehole to prevent fluids from permeating to the surrounding soil).
- 151. The general approach to drilling fluid management and preventive and corrective measures to drilling fluid breakout, as outlined below, are applicable to both the HDD and Direct Pipe option.

5.2 General Management Approach

- 152. Drilling fluid will be recycled as far as practicable by separating out the solid drill cuttings, which the fluid recovers from the cutting head or drill bit and transports to the surface via the borehole. The recycling system conveys the dirty drilling fluid upon return through a loop, which is capable of removing large solid particles such as gravel and finer particles such as sand through a variety of mechanical techniques. The cleaned drilling fluid is then pumped to the drill rig for reuse after adding new water and bentonite clay to maintain the right consistency and volume. This reduces raw material consumption, in particular water and bentonite clay, the time taken for the drilling process to be completed and the amount of waste produced.
- 153. The spoil from the drilling and recycling process will be collected, stored and disposed of in line with the approved Site Waste Management Plan (as part of a CEMP) at the end of operations. Likewise, excess drilling fluid will be stored in tanks to manage the expected volumes and removed from site when necessary.



5.3 Measures to Prevent Drilling Fluid Breakout

- 154. Trenchless crossing techniques carry a potential risk of drilling fluid breakout. This may occur when the fluid is forced through highly fissured ground at pressure or where there are large, interconnected fissures in the ground or other man-made features such as old boreholes. However, drilling fluid breakouts are rare, given that bentonite clay is a thixotropic fluid of high viscosity, which enters and seals fissures within the borehole. Under these circumstances, it is only likely that the drilling fluid would reach ground level where there is a continuous path available to the surface. Section 2.1 details the hydrofracture assessment and identifies the level of risk of drilling fluid breakout for the Project.
- 155. The geotechnical investigations undertaken on-site prior to drilling operations will help establish site conditions along the drill profile, allowing a suitable trenchless crossing design to be developed. Findings from these investigations will provide critical information such as the equipment to be used, the entry and exit points, drill profile, drill depth below ground, drilling fluid viscosity and borehole diameter, all of which will minimise the risk of drilling fluid breakout during drilling operations. The review of historical borehole data suggests that the overall risk of drilling activity is low and that the probability of drilling fluid breakout during drilling operations is unlikely. This will be confirmed prior to commencing activity through targeted geotechnical investigations and through agreement with the relevant authorities.
- 156. During drilling, site monitoring will be carried out by dedicated personnel, which will include monitoring of the annular pressure and the drilling fluid levels. The site to be monitored will include an area of 100m in front or behind the drill head and 25m on either side of the centre line of the drill path. The site will be divided into separate areas which will be monitored regularly, and inspection records shall be maintained. In addition, a down hole annular pressure sensor will be installed to the drill string. The maximum allowable annular pressure according to the design calculations will be plotted on screen for the guidance engineer in the control cabin, with an alarm sounding when 90% of the allowable limit is reached. In this event, drilling operations will be immediately halted, and the drill string will be retracted until an all clear has been given to resume drilling.
- 157. A key component of preventing drilling fluid breakout is the effective removal of drill cuttings from the borehole (see **Section 5.2** for details of the drill cuttings removal process). If cuttings are not removed, they may form cutting beds at the base of the borehole, which decreases the hole's cross-sectional area and increases the annular pressure. Cutting beds may also lead to increased drilling forces, which can eventually cause equipment to be lost or stuck downhole.



- 158. It is anticipated that the following equipment (or equivalent alternatives) will be available on-site at all times to respond to drilling fluid breakout:
 - Silt fencing
 - Mobile suction pumps
 - Seal pups (large cylinder-shaped containment and absorption pads)
 - Straw bales
 - Timber stakes
 - Sand bags
 - Tools for erecting temporary bunds.
- 159. The risk of drilling fluid breakout is considered to be very low based on analysis of historical borehole and desk-based assessment of the geology present in the area. Refer to **Section 2.1** for further information.

5.4 Drilling Fluid Breakout Response Planning

- 160. Contingency measures to be adopted at the Braunton Burrows and Taw Estuary Crossing will be agreed before drilling operations commence. Possible containment and clean-up steps are provided below. These measures will form part of the CEMP and/or a specific EMP for the crossings.
- 161. This is additional mitigation included in the unlikely event that a breakout occurs.

5.4.1 Breakout on Land

- Report immediately to the control cabin using the site two-way radio
- Stop drilling immediately
- Contain the drilling fluid by constructing a bund with sandbags
- Recover the drilling fluid from the bund by using 4in pump sets and 4in hoses
- Discharge the drilling fluid into the recycling pit for recycling
- Watch the area closely to check if breakout channel has sealed when pumping
- Pump lost circulation material or cement grout into the borehole and allow to swell in the fracture
- Continue pumping drilling fluid after waiting for lost circulation material to set according to the manufacturer's recommendations. If the fracture cannot be sealed, continue to recover drilling fluid from the bunded area using 4in pumps
- For containment of breakouts on land, sandbags will be stored where they can be easily and quickly brought to the breakout point. Personnel monitoring the site will be equipped with radios for instant communication with the driller.



5.4.2 Breakout under Water

- Any loss of drilling fluid in the entry pit is reported immediately to the driller
- Stop drilling immediately
- Pump lost circulation material to seal the fissure
- Wait for the lost circulation material to swell in the fracture
- Pump a mixture of 'Pure Bore' to see if circulation can be maintained
- If not, repeat the process with lost circulation material
- If the fracture cannot be sealed, either a cement grout will be pumped to the end of the bore, or the drill string will be withdrawn by an appropriate distance and a new profile drilled to avoid the problem area. This is dependent upon the rate of fluid loss and the geology encountered.
- 162. Fast and essential reporting is an essential component of the contingency plan. Emergency telephone numbers will be available to all the appropriate parties. Contact details of the relevant authority and Statutory Nature Conservation Body will also be provided for ease of reference.
- 163. In the unlikely event of drilling fluid breakout, an investigation will be conducted by the designated personnel, and the trenchless crossing design parameters will be reviewed to determine whether any modifications to the design or Method Statement are needed to reduce the risk of further breakouts.



6. References

British Geological Survey. GeoIndex Onshore. [Online]. [Accessed 30 January 2023]. Available from: http://mapapps2.bgs.ac.uk/.

Electricity Act 1989. (c. 29). [Online]. London: The Stationary Office. [Accessed 27 January 2023]. Available from: https://www.legislation.gov.uk/.

Marine and Coastal Access Act 2009. (c. 23). [Online]. London: The Stationary Office. [Accessed 27 January 2023]. Available from: https://www.legislation.gov.uk/.

Natural England. Designated Sites View. [Online]. [Accessed 30 January 2023]. Available from: https://designatedsites.naturalengland.org.uk/.

OSPAR Commission. (2021) The OSPAR List of Substances Used and Discharged Offshore which are Considered to Pose Little or No Risk to the Environment (PLONOR) – Update 2021. [Online]. [Accessed 7 February 2023]. Available from: https://www.ospar.org/.

Town and Country Planning Act 1990. (c. 8). [Online]. London: The Stationary Office. [Accessed 27 January 2023]. Available from: https://www.legislation.gov.uk/.

The Water Environment (Water Framework Directive) (England and Wales) Regulations 2017 (as amended). SI 2017/407. [Online]. London: The Stationary Office. [Accessed 27 January 2023]. Available from: <u>https://www.legislation.gov.uk/</u>.

Waterman Infrastructure & Environment Ltd (2023). White Cross Wind Farm: Export Cable Landfall and Onshore Crossings HDD Hydrofracture Assessment – Feasibility Stage.



Annex 1 HDD Hydrofracture Assessment

Export Cable Landfall and Onshore Crossings (Feasibility Stage)



| Document Code: | FLO-WHI-TEC-0013 | |
|-----------------------------|---|---------|
| Contractor Document Number: | 110-099-TIN-004 | |
| Version Number: | 00 | |
| Date: | 14-08-2023 | |
| Prepared by: | Waterman Infrastructure & Environment Ltd | |
| Checked by: | Mark Gardner | M.B.G.t |
| Approved by Client: | Oliver Gardner | |

| Version Number | Reason for Issue / Major Changes | Date of Change |
|-------------------|----------------------------------|----------------|
| A1 | Issued for Client Review | 28-07-2023 |
| 00 | Issued for Use | 14-08-2023 |



| CLIENT | Flotation Energy |
|---------------|-------------------------------|
| PROJECT TITLE | White Cross Offshore Windfarm |
| CONTRACT NO. | 110-099 |

This document remains the property of Stockton Drilling Limited and is issued on loan to 'the holder' on the understanding that it shall remain in the safe custody of the holder and be returned to the Project Manager on termination of the contract or the holder's employment (as applicable). The holder shall be responsible for complying with the instructions that accompany any revisions.

The Project Manager, or his nominee, shall only issue revisions of this document.

DOCUMENT NUMBER

110-099-TIN-004

DOCUMENT TITLE

HDD Hydrofracture Assessment – Export Cable Landfall and Onshore Crossings (Feasibility Stage)

| SIGNA | TURE: | | Waterman Infrastructure & Environment | M.B.G. | Sm Stephens | | | | | |
|-------|----------|-------------------|---|----------------------------------|--|--|--|--|--|--|
| | | | | | | | | | | |
| A02 | 14.08.23 | Issued for Use | Waterman Infrastructure & Environment | M Gardner Engineering Manager | S Stephens Specialist Project Director | | | | | |
| A01 | 28.07.23 | Issued for Review | Waterman Infrastructure & Environment | M Gardner Engineering Manager | S Stephens Specialist Project Director | | | | | |
| REV | DATE | ISSUE STATUS | PREPARED | REVIEWED | APPROVED | | | | | |



Waterman Infrastructure & Environment Limited

Broxden House, Broxden Business Park, Lamberkine Drive, Perth, PH1 1RA www.watermangroup.com

White Cross Wind Farm: Export Cable Landfall and Onshore Crossings

HDD Hydrofracture Assessment – Feasibility Stage

| Date: | | 11 th August 2023 | | | | | | | |
|--|------------|---|--------------------------|--|--|--|--|--|--|
| Client Name: | | Stockton Drilling Ltd (on behalf of Flotation Energy Ltd) | | | | | | | |
| Document Referen | ce: | WIE12731-153-TN-2-2-3 | | | | | | | |
| This document has been pre Waterman Group's IMS (BS | | ecked in accordance with 2015, BS EN ISO 14001: 2015 a | nd BS EN ISO 45001:2018) | | | | | | |
| Issue Prepared | | by | Checked & Approved by | | | | | | |
| | Lewis Phin | | Chris Gell | | | | | | |
| 2-1-3 | Engineer | | Technical Director | | | | | | |
| 2-1-0 | L Phin. | | 07 | | | | | | |
| | Lewis Phin | | Chris Gell | | | | | | |
| 2-2-3 | Engineer | | Technical Director | | | | | | |
| | LPL | | 07 | | | | | | |

1. Background

Waterman Infrastructure & Environment Ltd ('WIE') have been appointed by Stockton Drilling Limited ('SDL') to provide support of the onshore cable route Front-End Engineering Design (FEED) for the proposed White Cross Offshore Wind Farm, located approximately 50km off the Devon Coast. The 8 No. Wind Turbine Generators will comprise innovative floating substructure technology that is anchored to the seabed. The maximum capacity of the completed windfarm will be 100MW. Power will be exported by means of a subsea cable(s) that will make landfall on the Devon coast at Saunton Sands before running generally south to either a new or the existing substation at East Yelland.

As part of the cable route, 3 No. trenchless drills, by Horizontal Directional Drilling (HDD) methodology, are required for passing constraints. These drills are denoted as the 'Landfall', 'Golf Course Crossing' and 'River Taw Crossing'.

Within the HDD process, there can be a risk of drill fluid breakout to the surface, which is a phenomenon known as Hydrofracture, commonly termed 'frac-out'. In support of the FEED design, WIE have completed a preliminary assessment of the likelihood of hydrofracture based on the feasibility stage crossing profiles developed. The assessment should be revised on completion of ground investigation and finalisation of design profiles.



This Technical Note presents the results of the hydrofracture assessment. The crossing profile drawings and hydrofracture calculations are appended.

1.1 Limitations

A number of assumptions have been made to undertake these calculations including but not limited to, ground conditions, bore dimensions and bore profiles. Whilst WIE have endeavoured to make assumptions conservatively and realistically, we can accept no liability for any inaccuracies. The calculations should be treated as preliminary until such time the variables become more defined whereby the calculations should be revised accordingly.



2. Analysis Methodology

2.1 General

Hydrofracture occurs if during the drilling process the drilling fluid pressure in the borehole exceeds the resistance of the overburden soils resulting in a breakout at the surface. In this instance, there is a potential risk that this could occur within the intertidal zone, on the golf course, or within the River Taw leading to a potential pollution incident.

The HDD designer typically accounts for hydrofracture by ensuring that there is adequate cover depth of the bore path, which in turn provides a larger overburden pressure, and best mitigates hydrofracture. In granular soils, casing is typically used over the initial length of the bore to assist with mitigating the risk.

There are several possible methodologies for assessing the likelihood of hydrofracture, but this analysis has been based upon the widely used 'Dutch' method which was developed by Luger & Hergarden (1988) assuming a cavity expansion.

2.2 Geotechnical Parameters

The geology beneath the site is to be confirmed following a campaign of ground investigation, but expected to consist of superficial deposits, in the form of blown sand or marine beach deposits, overlying Mudstone, Slate or Shale bedrock.

It is anticipated that the bores would be cased through loose superficial deposits into more competent clays / weathered rock.

Due to the lack of Ground Investigation data, this preliminary hydrofracture assessment conservatively assumes granular materials (i.e. rather than firm to stiff clays or competent rock). The geotechnical parameters considered in all analysis are presented in Table 1.

| Table 1: Analysis Parameters | | | | | |
|--|---------------|--|--|--|--|
| Parameter | Assumed Value | | | | |
| Gravity (m/s/s) | 9.81 | | | | |
| Density of Water (kg/m ³) | 1000 | | | | |
| Density of Drilling Mud (kg/m ³) | 1300 | | | | |
| Soil Density (kg/m³) | 1950 | | | | |
| Cohesion (kN/m ²) | 2 | | | | |
| Friction Angle (°) | 25 | | | | |
| Poission's Ratio | 0.3 | | | | |
| Elasticity Modulus (kPa) | 40000 | | | | |
| Allowable Plastic Radius Factor | 0.50 | | | | |
| | | | | | |



2.3 Groundwater

The groundwater level has been conservatively assumed as commensurate with the ground surface throughout the analysis. It is likely that this assumption could be relaxed after completion of ground investigation with associated groundwater monitoring.

2.4 Bore Diameters

The bore diameters for the HDD crossings are to be confirmed as part of detailed design once all cable specifications are confirmed and ground conditions proven. It is anticipated that there will be a transition joint bay between the offshore and onshore cable(s) within the vicinity of the Staunton Sands beach car park. The landfall calculations therefore assume an offshore cable specification, with the Golf Course and River Taw calculations assuming an onshore cable specification (with a consequent reduction in likely cable and duct diameter).

The diameters assumed within the preliminary calculations, based on the feasibility stage designs, are summarised in Table 2.

| Table 2: Bore Diameters | 3 | |
|--------------------------------------|-------------------------|--------------------------|
| Cable Specification | Pilot Hole Diameter (m) | Reamed Hole Diameter (m) |
| Onshore (River Taw / Golf Course) | 0.305 (12") | 0.610 (24") |
| Offshore (Landfall) | 0.305 (12") | 1.118 (44") |

3. Assessment Results

3.1 River Taw Crossing

Under WIE's original appointment for the Pre-FEED Study of the onshore cable route a bore profile for crossing the River Taw was developed. This profile is presented on drawing 12731-135-WIE-ZZ-XX-M3-C-91003 included in Appendix A and is discussed within the Onshore Cable Route Feasibility Assessment (WIE12731-135-R-1-2-4, June 2022). Considering the profile developed in terms of hydrofracture, results in estimates as presented in Figure 1.

Calculations are presented in Appendix B.






Figure 1: River Taw Crossing - Hydrofracture and Annular Pressure Estimates

The variation in pressures along the borehole are shown in Figure 1, where it can be seen the permissible boreholes pressures P_{emax} and P_{max} graphs initially vary due to cover depth changes where the topography rises before trending downwards into the river channel. The deepened channel that is indicatively drawn on the profile drawing (not picked up by bathymetric survey) results in a loss of cover depth and thus a drop in permissible pressure and then the point where the profile passes back of the river channel creates some variation in the cover and hence an erratic permissible pressure.

Another feature to note on this graph is that the permissible pressures are significantly larger than the overburden pressure and this is due to the nature of the assumptions in the 'Dutch' model. The difference between P_{emax} and P_{max} arises from consideration of the water table level and the added confinement pressure due to its hydrostatic effect.

The most significant line on Figure 1 is the Annular Pressure which is the pressure in the borehole due to the drill fluid return flow. This pressure varies as the borehole progresses and is the sum of the static head and friction (flow) head. For most of the distance the annular pressure is well below P_{emax} and thus hydrofracture is not considered a concern. In the final stages of the bore profile the calculations show hydrofracture is likely as the profile begins to lose cover depth shortly before punch-out at CH1250. This is unavoidable but the effects can be easily controlled / mitigated onshore by putting appropriate site measures in place such as sandbagging and/or casing, to reduce and contain any hydrofracture. All drill fluids used should also be self-flocculating, environmentally inert and CEFAS approved.

3.2 Golf Course Crossing

Under WIE's original appointment for the Pre-FEED Study of the onshore cable route a bore profile for crossing the Golf Course was developed. This profile is presented on drawing 12731-135-WIE-ZZ-XX-M3-C-91006 included in Appendix A and is discussed within the Onshore Cable Route Feasibility Assessment (WIE12731-135-R-1-2-4, June 2022). Considering the profile developed in terms of hydrofracture, results in estimates as presented in Figure 2.

Calculations are presented in Appendix B.






Figure 2: Golf Course Crossing - Hydrofracture and Annular Pressure Estimates

The variation in pressures along the borehole are shown in Figure 2, where it can be seen the permissible boreholes pressures P_{emax} and P_{max} graphs vary due to topography changes across the golf course causing cover depth alterations.

Another feature to note on this graph is that the permissible pressures are significantly larger than the overburden pressure and this is due to the nature of the assumptions in the 'Dutch' model. The difference between P_{emax} and P_{max} arises from consideration of the water table level and the added confinement pressure due to its hydrostatic effect.

The most significant line on Figure 2 is the Annular Pressure which is the pressure in the borehole due to the drill fluid return flow. This pressure varies as the borehole progresses and is the sum of the static head and friction (flow) head. For most of the distance the annular pressure is well below P_{emax} and thus hydrofracture is not considered a concern. In the final stages of the bore profile the calculations show hydrofracture is likely as the profile begins to lose cover depth shortly before punch-out at CH1130. As with the River Taw crossing, this is unavoidable but the effects can be easily controlled / mitigated onshore by putting appropriate site measures in place such as sandbagging and/or casing, to reduce and contain any hydrofracture. All drill fluids used should also be self-flocculating, environmentally inert and CEFAS approved.



3.3 Landfall

In support of the cable route FEED study, WIE have developed an indicative profile for the cable landfall in order to demonstrate that an HDD methodology is feasible and to form the basis of preliminary hydrofracture calculations.

The preliminary profile design is presented on Drawing 12731-153-WIE-LF-XX-M3-C-91001 included in Appendix A. This indicative concept design has considered an entry point within the Saunton Sands beach car park extending out to a minimum water depth of -5m LAT, which is considered a likely minimum water depth for the follow-on cable installation works. This results in a bore length of circa 1860m.

Owing to the length of bore, and required ream size, at this stage it is considered likely that an intercept HDD methodology would be required with an onshore and offshore spread drilling pilot holes to 'intercept' at a point approximately mid-way along the bore. The bore would then be reamed by push-pull reaming from the onshore and offshore spreads. The offshore spread would require a Jack-Up Barge (JUB).

On this basis, considering a hydrofracture calculation requires consideration of the pressure head at both the onshore end, denoted by the entry hole level, and also the level of the jack-up barge sitting offshore. This would be determined by the HDD contractor at detailed design stage, thus, for the purpose of these calculations an arbitrary level of 8m AOD has been assumed based on a typical JUB deck height and allowing for wave clearance.

1800 Overburden 1600 HDD Intercept Point Pemax Pmax 1400 Annular Pressure 1200 Pressure (kPa) 1000 800 600 400 200 0 -700 500 -500 -300 -100 100 300 700 900 -900 Distance from Intercept (m) - y-axis represents intercept

Calculations are presented in Appendix B.

Figure 3: Landfall - Hydrofracture and Annular Pressure Estimates

Page 7 of 8 White Cross Wind Farm: Export Cable Landfall and Onshore Crossings WIE12731-153-TN-2-2-3 WIE12731-153



The variation in pressures along the borehole are shown in Figure 3, where it can be seen the permissible boreholes pressures P_{emax} and P_{max} initially vary due to cover depth changes within the sand dunes before trending gently downwards as per the seabed profile and subsequent cover depth.

Another feature to note on this graph is that the permissible pressures are significantly larger than the overburden pressure and this is due to the nature of the assumptions in the 'Dutch' model. The difference between P_{emax} and P_{max} arises from consideration of the water table level and the added confinement pressure due to its hydrostatic effect.

The most significant line on Figure 3 is the Annular Pressure which is the pressure in the borehole due to the drill fluid return flow. This pressure varies as the borehole progresses and is the sum of the static head and friction (flow) head. For most of the distance the annular pressure is well below P_{emax} and thus hydrofracture is not considered a concern. In the final stages of the bore profile the calculations show hydrofracture is likely as the profile begins to lose cover depth shortly before punch-out at CH1860. This is unavoidable, but would be mitigated through use of casing which will be required in any case to support the bore between the JUB deck and the seabed. All drill fluids used should also be self-flocculating, environmentally inert and CEFAS approved.

4. Conclusions & Recommendations

This preliminary hydrofracture assessment demonstrates that there is no significant risk of frac-out along the bore profiles with the exception of the final stages of the bore where the profile begins to rise resulting in loss of cover. This is unavoidable, but can be easily controlled onshore by site measures such as sandbagging and casing, in line with general HDD working methodologies. For the landfall, and assuming an intercept methodology, the risk will be controlled by the use of casing extending from the JUB deck down to the seabed (which is required regardless, to support the bore over this length).

These preliminary calculations should be updated as the design process develops and the variables become more known, such as bore diameters, ground conditions and groundwater levels. This will increase the accuracy of the assessment and inform any required design amendments, such as deepening of bore profiles, to mitigate risk should such be identified.



A. Design Drawings

Appendices White Cross Wind Farm: Export Cable Landfall and Onshore Crossings WIE12731-153-TN-2-2-3 WIE12731-153



| | 損 <u>12.80%</u> | | | TIDE NOT INDIO WELL BELOW E | CONOMICAL TIDE LOWEST ASTRONO CATED GIVEN LEVE BATHYMETRIC RIVE SSUMED DRY AT LC | IS R BED W TIDE | METRIC SURVEY DA | | WATER LEVEL THUS PREFER | Y WAS LIKELY PIO LAT THE TIME OF RENCE GIVEN TO C DATA AT RIVER | SURVEY | ì | | | | | | | | | | INDICA | ED ON BATH | EP CHANNEL N HYMETRIC SU AWN AS 5m D | URVEY | | | | |
|---------------------|---|---|---|----------------------------------|--|---|---|--|--|--|--------------------------------------|---|---|--|--|--|-------------------------------|---|---|---|--|---|-----------------------------------|--|--|--|-----------------------------------|--|--|
| Level | | | | | | | | | | | | | -0.57% | | | | | | | | | | | 8 | | | 6.55% | | |
| | -15 - -20 - -25 | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| Chainage | 0.000 10.000 30.000 30.000 40.000 | 60.000 70.000 80.000 90.000 100.000 | 110.000 120.000 130.000 140.000 | 160.000 170.000 180.000 | 200.000 210.000 220.000 230.000 240.000 | 260.000 270.000 280.000 290.000 | 310.000 320.000 330.000 350.000 350.000 | 360.000 370.000 380.000 390.000 | 400.000 410.000 420.000 430.000 | 450.000 450.000 460.000 470.000 | 490.000 500.000 510.000 | 520.000 530.000 550.000 550.000 | 560.000 570.000 580.000 590.000 600.000 | 610.000 620.000 630.000 640.000 | 650.000 660.000 670.000 680.000 | 690.000 700.000 710.000 720.000 | 730.000 740.000 750.000 | 760.000 770.000 780.000 790.000 800.000 | 810.000 820.000 830.000 840.000 850.000 | 860.000 870.000 880.000 890.000 | 910.000 920.000 930.000 940.000 | 960.000 970.000 980.000 | 1000.000 1010.000 1020.000 | 1030.000 1040.000 1050.000 1050.000 | 1070.000 1080.000 1090.000 1100.000 | 1110.000 1120.000 1130.000 1140.000 | 1160.000 1170.000 1180.000 | 1200.000 1210.000 1220.000 1230.000 | 1240.000 1250.000 1260.000 1270.000 |
| | | | | | | | | | | | | | | | | | 1 1 | | | | | | + 1 1 | | | | + | | |
| Existing Levels | 0.033 0.081 0.123 0.165 0.186 | | 0.094 0.025 0.000 0.013 | 0.150 0.219 0.288 0.356 | 0.425 0.493 0.507 0.516 0.516 0.516 | 0.535 0.530 0.535 0.535 0.539 | 0.549 0.553 0.558 0.558 0.563 | 0.572 0.577 0.581 0.586 | 0.590 0.595 0.598 0.579 | 0.560 0.541 0.521 0.502 0.833 | 0.403 0.464 0.445 0.426 | 0.406 0.387 0.368 0.368 0.349 | 0.330 0.318 0.305 0.292 0.279 | 0.266 0.253 0.240 0.227 | 0.215 0.202 0.189 0.177 | 0.167 0.156 0.149 0.138 | 0.134 0.123 0.102 | 0.086 0.088 0.090 0.093 | 0.097 0.100 0.102 0.102 0.107 | 0.109 0.111 0.114 0.116 0.116 | 0.121 0.123 0.125 0.128 | 0.132 0.135 0.135 0.137 0.137 | | 0.148 0.151 0.153 0.155 | 0.153 0.158 0.160 0.165 0.165 | 0.167 0.169 0.172 0.174 | 0.179 0.181 0.183 0.183 | 0.188 0.190 0.193 0.195 | 0.197 0.199 0.202 0.204 |
| | | | | | | | | | | | | | | | | | 1 1 | | | | | | | | | | | | |
| Level Difference | 1.202 2.508 2.960 7.960 | 7.331 9.231 9.764 8.697 | 8.496 8.594 8.661 8.721 8.721 | 8.912 8.984 8.984 9.018 | 9.068 9.139 9.191 9.328 9.328 | 9.419 9.459 9.528 9.595 6715 | 9.739 9.762 9.832 9.880 9.980 | 10.020 10.081 10.151 | 10.244 10.328 10.374 10.443 | 10.511 10.551 10.615 10.650 | 10.715 10.765 10.823 10.867 | 10.946 10.955 11.034 11.099 | 11.193 11.212 11.296 11.323 | 11.444 11.519 11.560 11.629 | 11.688 11.758 11.805 11.866 | 11.889 11.948 12.037 12.088 | 12.152 12.190 12.271 | 12.299 12.354 12.425 12.488 12.497 | 12.550 12.689 12.673 12.781 12.840 | 12.815 12.940 12.690 13.015 | 12.862 12.920 12.977 13.035 | 13.150 13.207 13.264 13.322 | 13.380 13.437 13.494 | 13.547 13.502 13.323 13.012 | 13.012 12.567 11.988 11.334 10.680 | 10.025 9.371 8.716 8.176 7.906 | 8.286 8.286 10.371 8.801 | 5.996 3.972 3.677 2.811 | 2.031 1.680 0.844 0.090 |
| Horizontal Geometry | , | | | | | I | | | | | I | I | | L =1271. | .719 | | I | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| Vertical Geometry | G =-12.799% L =26.583 | R =750.000 K =7.500 L =91.681 | | | | | | | | | | | <u>G</u> =-0.574% L =909.051 | | | | | | | | | | | R =750.0 K =7.50 L =53.39 | 00 | | G =6.545% L =190.892 | | |
| | | | I | | | | | | | | | | | | | | | | | | | | | | Γ | | | | |

RIVER CROSSING - LONGSECTION SCALE: H 1:2000,V 1:2000. DATUM: -25.000

This drawing should not be scaled. Dimensions to be verified on site. Any discrepancies should be referred to the Engineer prior to work being put in hand. This drawing is the property of Waterman Infrastructure & Environment Limited, and the drawing is issued on the condition that it is not copied reproduced, retained or disclosed to any unauthorised person, either wholly or in part without the consent in writing of Waterman Lengthere the product limited. Waterman Infrastructure & Environment Limited Pickfords Wharf, Clink Street, London SE1 9DG t 020 7928 7888 f 03333 444 501

GENERAL NOTES

- 1. THIS DRAWING IS TO BE READ IN CONJUNCTION WITH ALL ENGINEER'S, ARCHITECT'S OR OTHER RELEVANT DRAWINGS AND SPECIFICATIONS.
- 2. ALL DIMENSIONS AND LEVELS ARE TO BE CHECKED ON SITE BY THE CONTRACTOR PRIOR TO PREPARING ANY WORKING DRAWINGS OR COMMENCING ON SITE.
- THE CONTRACTOR MUST ENSURE AND WILL BE HELD RESPONSIBLE FOR THE OVERALL STABILITY OF THE BUILDING/STRUCTURE/EXCAVATION AT ALL STAGES OF THE WORK.
- 4. ALL WORK BY THE CONTRACTOR MUST BE CARRIED OUT IN SUCH A WAY THAT ALL REQUIREMENTS UNDER THE HEALTH AND SAFETY AT WORK ACT ARE SATISFIED.
- 5. ALL WORK IS TO BE CARRIED OUT IN COMPLIANCE WITH THE REQUIREMENTS OF THE RELEVANT STATUTORY AUTHORITIES AND REGULATIONS.

SITE COMPOUND LAYOUT KEY: 1. 50 KVA GENERATOR 2M X 2M

- 2. TOILET BLOCK 6M X 2M
- 3. DRY/CHANGE ROOM 6M X 2M 4. CANTEEN 6M X 2M
- 5. OFFICE 6M X 2M
- 6. OFFICE 6M X 2M 7. 21 TON TRACKED 360 EXCAVATOR
- 8. DRILL PIPE STORAGE 10M X 2M
- 9. HDD DRILL RIG 16M X 2M 10. POWER PACK 6M X 2M
- 11. CONTROL CABIN 6M X 2M
- 12. MUD LAB 3M X 2M
- 13. MUD ENTRY PIT 3M X 4M 14. HIGH PRESSURE MUD PUMP 6M X 2M
- 15. MUD MIXING TANK 7M X 2M
- 16. 350 KVA GENERATOR 5M X 2M
- 17. RECYCLING UNIT 6M X 2M 18. WATER STORAGE TANK 6M X 2M
- 19. DRY DRILLING FLUID STORAGE 4M X 10M
- 20. WORKSHOP 6M X 2M 21. STORES 6M X 2M

| II FRACOMBE T | DE GAUGE SITE |
|---------------------------|------------------------------|
| TIDE LEVELS | ORDNANCE DATUM NEWLYN (mAOD) |
| HIGHEST ASTRONOMICAL TIDE | 5.46 |
| MEAN HIGH WATER SPRINGS | 4.47 |
| MEAN HIGH WATER NEAPS | 2.19 |
| MEAN LOW WATER NEAPS | -1.69 |
| MEAN LOW WATER SPRINGS | -3.94 |
| LOWEST ASTRONOMICAL TIDE | -4.89 |

| GEOLOGY |
|-----------|
| BLOWN SA |
| DRIFT DEF |
| ESTUARIN |
| ROCK |
| |

| GEOLOGY KEY | |
|--------------------------|--|
| BLOWN SANDS (SAND DUNES) | |
| DRIFT DEPOSITS | |
| ESTUARINE DEPOSITS | |
| BOCK | |

1:2000 0 20m 40m 60m 80m 100m 120m 140m 160m 180m 200m

1:1 0 10 20 30 40 50 60 70 80 90 100

| RIVER TAW OUTLINE HDD PLAN AND PROFILE | | | | | | | | | |
|--|---------|-----------------|-------------|--------------|------------|--|--|--|--|
| Client | FLC | DTATION | ENERG | Y LTD | | | | | |
| W waterman | | | | | | | | | |
| 5 | | | K 1 | | N | | | | |
| Broxden House Broxden Business Park Lamberkine Drive Perth PH1 1RA t: 01738 449 801 mail@watermangroup.com www.watermangroup.com | | | | | | | | | |
| SUITABILITY FOR PLANNING SUBMISSION | | | | | | | | | |
| Designed By | LP | Director | CG | Waterman Ref | E12731-135 | | | | |
| Drawn By | LP | Date | 20.05.22 | Scales @ A0 | AS NOTED | | | | |
| Stockton Checker | | Stockton Approv | er | Date | | | | | |
| Project - Origir | nator - | Volume - Level | - Type - Ro | e - Number | Revision | | | | |
| 12731-1 | 35-W | ′IF-77-X | X-M3-C | -91003 | P03 | | | | |

P0311.08.23SITE COMPOUND LAYOUTS REMOVED. RE-ISSUED FOR
INFORMATION AS PART OF PLANNING SUBMISSIONP0210.03.23TITLE UPDATED & DRAFT BANNER REMOVED

2 DRAFT ISSUE FOR INFORMATION ONLY

Amendments

WHITE CROSS FLOATING WINDFARM

A01 A1



| | Гe | 25 - 20 - 15 - 10 - | | | · | -8.(| 2% | | | |
|------------------|-------|--|---------|----------|---------|-----------------|--------------|----------|----------|----------------------|
| | Level | 0-1 -5-1 -10-1 -15-1 -20-1 | | | | | | | | |
| Chainage | | - ² 000.0 | 10.000 | 20.000 | 30.000 | 40.000 | 60.000 | 70.000 | 80.000 | 90.000 |
| Existing Levels | | 8.743 | 8.569 - | 10.513 - | 9.745 — | 8.543 10.018 | 11.081 - | 10.848 — | 10.998 — | 12.770 — 12.756 — |
| Level Difference |) | -0.014 | 0.614 - | 3.360 | 3.394 — | 2.994 5.271 | 7.136 - | 7.706 | 8.657 - | 11.233 – 12.020 |
| Horizontal Geon | netry | 1 | | | | | | | | |
| Vertical Geomet | ry | | | | | 3 = 8 L =10 | .022 3.74 | % 2 | | |

GOLF COURSE CROSSING - LONGSECTION SCALE: H 1:2000,V 1:2000. DATUM: -25.000

| | | | 2 | | | | | | | | | | | 0.5 | 58% | | | | | | | | | | | | S 2 - S - S | | 8.71 | % |
|----------------------|---|--------------------------------|-------------------------------|--|----------------------------------|-----------------------|--|---|--|---------------------|--|---|-----------|----------------------------------|------------------------|---------------------------------------|---|---|----------------------------------|----------------------|--|----------------------|--|--|----------------------------------|--------------------|--|--|----------------------------------|--------------------------------------|
| 11 | | | | | | | | | | | | | | | 11. | | | | | | | | 1 | | | 11 | | | | 11 11 |
| 90.000 - 100.000 - | 120.000 130.000 140.000 140.000 120.0000 120.00000 120.0000000000 | 160.000 170.000 | 180.000 190.000 200.000 | 210.000 220.000 230.000 240.000 | 260.000 270.000 280.000 | 300.000 | 320.000 330.000 340.000 350.000 | 360.000 370.000 380.000 390.000 390.000 | 410.000 420.000 430.000 440.000 | 450.000 - 460.000 - | 470.000 480.000 490.000 500.000 | 510.000 520.000 530.000 540.000 560.000 | 560.000 - | 580.000 590.000 600.000 | 610.000 - 620.000 - | 630.000 - 650.000 - 650.000 - 650.000 | 660.000 670.000 680.000 680.000 700.000 | 710.000 720.000 730.000 730.000 | - 000.067 - 000.077 | 790.000 | 810.000 820.000 830.000 840.000 850.000 | 860.000 - 870.000 - | 880.000 900.000 900.000 900.000 900.000 900.000 900.000 900.000 900.000 900.000 900.000 900.000 900.000 900.000 900.000 900.000 | 920.000 920.000 940.000 940.000 | 960.000 970.000 980.000 | 990.000 | 1010.000 1020.000 1030.000 1040.000 | 1060.000 1070.000 1080.000 1090.000 | 1110.000 1120.000 1130.000 | 1150.000 1160.000 1178.928 |
| 12.770 – 12.756 – | 12.944 13.763 14.512 13.723 | 13.739 13.453 - 13.887 - | 12.436 – 8.995 – 7.997 | 7.882 | 8.198 8.138 8.022 | 8.761 - 8.761 - 8.761 | 10.486 11.898 15.458 | 15.163 13.924 15.365 12.590 | 12.220 – 12.362 – 12.430 – 12.577 – | 13.165 13.695 — | 14.033 14.138 14.137 14.269 | 14.310 14.392 13.997 13.935 | 13.519 | 13.073 – 14.098 – 13.629 – | 13.735 - 13.853 - | 14.248 – 14.366 – 14.493 | 14.647 | 18.458 17.079 15.813 1 <u>5</u> .873 | 17.302 - 18.433 - 16.645 - | 15.133 15.299 | 15.206 15.406 15.583 15.103 14.361 | 14.491 | 14.672 14.318 14.550 | 10.931 18.731 18.609 16.851 16.851 | 21.090 - 21.760 - 20.882 - | 18.539 16.761 | 16.551 - 16.336 - 16.163 - 15.989 - 14.429 - | 13.817 | 13.961 | 13.097 13.097 12.951 12.796 |
| 11.233 – 12.020 | 12.984 14.455 15.723 15.619 | 15.30/ 15.421 - 15.842 - | 14.333 – 14.335 – 9.779 | 9.606 9.641 9.516 9.616 | 9.633 9.633 9.516 9.343 | 9.909 9.909 | 11.576 12.931 13.359 16.375 | 16.022 14.725 16.108 13.276 | 12.790 | 13.505 | 14.258 14.305 14.326 14.320 | 14.304 14.329 13.876 13.256 | 13.225 - | 12.663 – 13.631 – 13.104 | 13.152 | 13.550 | 13.776 | 17.299 15.862 14.538 14.540 | 15.854 | 13.512 - 13.621 - | 13.469 13.612 13.731 13.794 12.394 | 12.467 – 12.359 – | 12.532 | 16.361 | 18.489 | 15.765 - 13.930 | 13.662 | 10.303 9.393 8.857 8.437 7.750 | 7.081 | 2.735 2.735 1.718 0.698 |
| | | | | | | | | | | | | | L | =1176.74 | 45 | | | | | | | | | | | | | | | |
| | R =750.00 K =7.500 L =64.48 | 0 | | | | | | | | | | | | | <u>.577%</u> 59.295 | | | | | | | | | | | | k | R =750.000 K =7.500 L =60.976 | G =8.7 L <i>=</i> 78. | 0 7% .827 |

his drawing should not be scaled. Dimensions to be verified on site. Any discrepancies should be referred to the Engineer prior to work being put in hand. This drawing is the property of Waterman Infrastructure & Environment Limited, and the drawing is issued on the condition that it is not copied reproduced, retained or disclosed to any unauthorised person, either wholly or in part without the consent in writing of Waterman Infrastructure & Environment Limited Pickfords Wharf, Clink Street, London SE1 9DG t 020 7928 7888 f 03333 444 501

GENERAL NOTES

- 1. THIS DRAWING IS TO BE READ IN CONJUNCTION WITH ALL ENGINEER'S, ARCHITECT'S OR OTHER RELEVANT DRAWINGS AND SPECIFICATIONS.
- ALL DIMENSIONS AND LEVELS ARE TO BE CHECKED ON SITE BY THE CONTRACTOR PRIOR TO PREPARING ANY WORKING DRAWINGS OR COMMENCING ON SITE.
- THE CONTRACTOR MUST ENSURE AND WILL BE HELD RESPONSIBLE FOR THE OVERALL STABILITY OF THE BUILDING/STRUCTURE/EXCAVATION AT ALL STAGES OF THE WORK.
- ALL WORK BY THE CONTRACTOR MUST BE CARRIED OUT IN SUCH A WAY THAT ALL REQUIREMENTS UNDER THE HEALTH AND SAFETY AT WORK ACT ARE SATISFIED.
- ALL WORK IS TO BE CARRIED OUT IN COMPLIANCE WITH THE REQUIREMENTS OF THE RELEVANT STATUTORY AUTHORITIES AND REGULATIONS.

SITE COMPOUND LAYOUT KEY: 1. 50 KVA GENERATOR 2M X 2M

- 2. TOILET BLOCK 6M X 2M
- 3. DRY/CHANGE ROOM 6M X 2M 4. CANTEEN 6M X 2M
- 5. OFFICE 6M X 2M
- 6. OFFICE 6M X 2M 7. 21 TON TRACKED 360 EXCAVATOR
- 8. DRILL PIPE STORAGE 10M X 2M
- 9. HDD DRILL RIG 16M X 2M 10. POWER PACK 6M X 2M
- 11. CONTROL CABIN 6M X 2M
- 12. MUD LAB 3M X 2M
- 13. MUD ENTRY PIT 3M X 4M
- 14. HIGH PRESSURE MUD PUMP 6M X 2M 15. MUD MIXING TANK 7M X 2M
- 16. 350 KVA GENERATOR 5M X 2M
- 17. RECYCLING UNIT 6M X 2M
- 18. WATER STORAGE TANK 6M X 2M 19. DRY DRILLING FLUID STORAGE 4M X 10M
- 20. WORKSHOP 6M X 2M
- 21. STORES 6M X 2M

| P03 | 11.08.23 | SITE COMPOUND LAYOUTS REMOVED. RE-ISSUED FOR INFORMATION AS PART OF PLANNING SUBMISSION | LP | CG |
|-----|----------|--|----|-----|
| P02 | 10.03.23 | TITLE UPDATED AND DRAFT BANNER REMOVED | LP | CG |
| P01 | 20.05.22 | DRAFT ISSUE FOR INFORMATION ONLY | LP | CG |
| Rev | Date | Description | Ву | Chk |
| | | Amendments | | |

WHITE CROSS FLOATING WINDFARM

SAUNTON GOLF CLUB OUTLINE HDD PLAN AND PROFILE

FLOTATION ENERGY LTD



Stockton Approver

110-099-DRG-021

FLO-WHI-LAY-0018

Project - Originator - Volume - Level - Type - Role - Number Revision

12731-135-WIE-ZZ-XX-M3-C-91006 P03

Stockton Checker

GEOLOGY KEY BLOWN SANDS (SAND DUNES) DRIFT DEPOSITS ROCK

1:2000 0 20m 40m 60m 80m 100m 120m 140m 160m 180m 200m

1:1 0 10 20 30 40 50 60 70 80 90 100

A01 A1





| EL (m AOD) | 20 15 10 5 -17.58% -17.58% -17.58% 10 -17.58% -17.58% -17.58% -17.58% -17.58% -17.58% -17.58% -10 -17.58% -10 -10 -10 -10 -10 -10 -10 -10 | | | | | | _ | · | | | | | | | | | | | | | | | |
|---|---|--|--|--|---|---|---|---|--|---|----------------------|---|----------------------------------|---|--------------------------------|--|------------------------|-----------------------------------|--|---|-------------------------------------|--|-------------------------------------|
| | 25 — 30 — 35 — 40 — 45 — | | | | | | | | | | | | | | | | | | | | | -0.11% | |
| CHAINAGE (m) | 0+000 0+010 - 0+020 - 0+030 - 0+040 - | 0+060 | 0+110 | 0+150 0+160 - 0+170 - 0+180 - | 0+200 0+210 - 0+220 - 0+230 - 0+240 - | 0+250 0+260 0+270 0+280 0+290 | 0+300 0+310 - 0+320 - 0+330 - 0+340 - | 0+350 - 0+380 - 0+380 - 0+380 - 0+380 - 0+380 - 0+390 - 0+300 | 0+400 0+410 0+420 0+420 | 0+440 | 0+490 - 0+500 | 0+510 0+520 0+530 0+540 0+550 | 0+560 0+570 0+580 | 0+590 - 0+600 0+610 - 0+620 - 0+630 - | 0+640 - 0+650 0+660 - | 0+670 - 0+680 - 0+690 - 0+700 | 0+710 0+720 | 0+740 | - 06/+0 - 08/+0 | 0+800 0+810 - 0+820 - 0+840 - 0+840 - | - 078+0 - 078+0 - 088+0 | 0+890 0+900 0+910 0+910 | 0+920 |
| ONSHORE EXISTING LEVELS (m AOD) | 12.966 13.080 - 13.181 - 13.580 - 14.118 - 14.147 | 14.147 13.984 - 13.739 - 13.452 - 13.362 - 13.277 | 13.223 - 13.372 - 16.245 - 15.014 - | 12.462 8.021 - 7.558 - 5.960 - | 4.717 4.298 - 3.972 - 3.662 - 3.393 - | 3.174 | | | | | | | | | | | | | | | | | |
| OFFSHORE EXISTING LEVELS (m AOD) | | | | | | | | | | -4.792 - -4.746 - -4.718 - | -4.739 - | -4.780 - -4.800 - -4.800 - -4.800 - -4.800 - | -4.800 - -4.800 - -4.800 - | -4.800 - -4.749 -4.681 - -4.612 - | -4.476 - -4.407 -4.339 - | -4.270 - -4.202 - -4.134 - -4.065 | -4.003 - -3.992 - | -3.959 | -3.949 - -3.940 - -3.957 - -3.973 - | -3.989 -4.011 -4.070 -4.100 -4.100 | -4.146 - -4.146 - -4.215 - | -4.210 -4.287 -4.359 -4.431 | -4.503 -4.575 -4.627 |
| BORE PROFILE LEVEL (m AOD) (TOP OF PIPE) | 12.966 11.208 - 9.450 - 7.692 - 5.935 - 4.177 | 4.1// 2.419 – 0.661 – -1.061 – -2.717 – -4.306 | -5.829 - -7.284 - -8.674 - -9.996 - | -11.252 -12.441 - -13.563 - -14.619 - | -16.531 -17.387 - -18.176 - -18.898 - -19.554 - | -20.143 -20.666 - -21.122 - -21.511 - -21.833 - | -22.089 -22.278 - -22.401 - -22.456 - -22.468 - | -22.491 - -22.502 - -22.513 - -22.524 - | -22.535 -22.546 - -22.557 - -22.568 - | -22.579 - -22.590 -22.601 - -22.612 - -22.624 - | -22.635 - -22.646 | -22.657 - -22.668 - -22.679 - -22.690 - -22.701 | -22.712 -22.723 -22.734 | -22.745 - -22.756 -22.768 - -22.779 - -22.790 - | | -22.834 - -22.845 - -22.856 - -22.867 | -22.878 - -22.889 - | -22.900 - -22.912 - -22.923 | -22.934 - -22.945 - -22.956 - -22.967 - | -22.978 -22.989 - -23.000 - -23.011 - -23.022 - | -23.056 - -23.056 - -23.057 - | -23.067 - -23.078 - -23.089 -23.100 - | -23.111 - -23.122 - -23.133 - |
| BORE VERTICAL GEOMETRY | G=-17.577% L=69.709m- | | | | =1500.000m < =15.000 =262.001m | | | 1 | | | | | | | 1 | | | | | | | <u> </u> | |

INFERRED EXISTING GROUND PROFILE BETWEEN LIDAR AND BATHYMETRIC SURVEY DATA. LIDAR SURVEY DATA EXTENTS OFFSHORE BUT HAS BEEN CLIPPED AS APPEARS TO BE PICKING UP WATER LEVEL AT TIME OF SURVEY

20 —









This drawing should not be scaled. Dimensions to be verified on site. Any discrepancies should be referred to the Engineer prior to work being put in hand. This drawing is the property of Waterman Infrastructure & Environment Limited, and the drawing is issued on the condition that it is not copied reproduced, retained or disclosed any unauthorised person, either wholly or in part without the consent in writing of Waterman Infrastructure & Environment Limited Pickfords Wharf, Clink Street, London SE1 9DG t 020 7928 7888 f 03333 444 501 GENERAL NOTES OFFSHORE . THIS DRAWING IS TO BE READ IN CONJUNCTION WITH ALL ENGINEER'S, ARCHITECT'S OR OTHER RELEVANT DRAWINGS -----AND SPECIFICATIONS. 2. ALL DIMENSIONS AND LEVELS ARE TO BE CHECKED ON SITE BY THE CONTRACTOR PRIOR TO PREPARING ANY WORKING DRAWINGS OR COMMENCING ON SITE. 3. THE CONTRACTOR MUST ENSURE AND WILL BE HELD RESPONSIBLE FOR THE OVERALL STABILITY OF THE BUILDING/STRUCTURE/EXCAVATION AT ALL STAGES OF THE 4. ALL WORK BY THE CONTRACTOR MUST BE CARRIED OUT IN SUCH A WAY THAT ALL REQUIREMENTS UNDER THE HEALTH AND SAFETY AT WORK ACT ARE SATISFIED. 5. ALL WORK IS TO BE CARRIED OUT IN COMPLIANCE WITH THE REQUIREMENTS OF THE RELEVANT STATUTORY AUTHORITIES AND REGULATIONS. _____ 705% T R =5000.000m G =7.049% K =50.000 L =357.991m L =20.231m

WIF12731-1

A0-Wat-SDL-S

FLOTATION ENERGY LTD

FOR PLANNING SUBMISSION

110-099-DRG-

FLO-WHI-LAY-0017




B. Hydrofracture Calculations

Appendices White Cross Wind Farm: Export Cable Landfall and Onshore Crossings WIE12731-153-TN-2-2-3 WIE12731-153

| | | Spreadsh | eet Calcpad | | Pro | oject |
|--|---|--|-------------------|---|---|---|
| | (Macros mus | t be enabled | I. Ctrl+Alt+F9 re | calculates.) | WIE12 | 731-153 |
| 11) waterman | | | | | Prepared | Date |
| | | | Vhite Cross Ph | | LP | 18-Jul-23 |
| | | | Hydrofracture | | Checked | Date |
| | | | | | CG | 19-Jul-23 |
| $Pmax = Pem$ $Pemax = (P$ $Q = \frac{(\sigma o.sin)}{2}$ | symetry around the c elastic deformation. It plastic zone. This giv ax + U $f + c. cot \emptyset$). {($\frac{0+c.cos\emptyset}{G}$ $+ sin\emptyset$) + c. co | $\left(\frac{Ro}{Rpmax}\right)^2$ | | | shown Eqn(1) Eqn(2) Eqn(3) Eqn(4) Eqn(5) | |
| Pmax U Pemax σ _o φ c Ro Rpmax G E N | maximum allowak initial in-situ pore maximum allowak initial effective str internal angle of f cohesion internal radius of maximum allowak shear modulus elasticity modulus Poisson's ratio | pressure ole effective ress riction borehole ole radius o | e mud pressure | | | |
| Density of wate Density of drilling mu Soil densi Cohesio Friction ar Poissi Elasticity modu | d (kg/m3): γm ty (kg/m ³): γs n (kN/m ²): Coh ngle (deg): Φ on's ratio : ν | 9.81 1000 1300 1950 2 25 0.3 40000 15385 | Radians Φr = | 0.4363 | are all as | |
| Product pip Drill bit diame Drill pipe (Initial radius of bor Allowable plastic rad | ter (inch): DD (inch): | 24.00 inc 12.00 inc 0.305 0.50 | h Di | 0.610 m 0.305 m ^f drill bit diameter | feasibility Rpmax u between | usually assumed 1/2 and 2/3 depth d 1/2 as worst case |
| Consider lateral soil Passive coeffi | pressure: No cient ko = IF(Y_N = ' = IF(= "Yes = 0 | "Yes", 1 - Sll | | select Y/N | | ative to not Iateral soil S |

| Annular pressure calculations | | | | | |
|--|--------------------------------|---|--------------------------|--|-----------------|
| Darcy Weisbach equation for flow in an ann diameter, V the flow velocity, L flow pipe len- circular pipes Dh = Do - Di. The exact drillin some estimated values have been applied - the static head. | gth and ig opera | l f is a friction fac ational paramete | tor. In the ors, such as | case of co-centere flow rate are unkn | ed Iown, but |
| Assumed flow velocity (m/s): | V | 0.50 | | | |
| Assumed friction coefficient: | f | 1.00 | | | |
| | | | | | |
| The calculations at each chainage location a Summary Figures | are perf | ormed in the frac | c-out table | | |
| | | ormed in the frac 4.11 mOD | c-out table | | |
| Summary Figures |)D = | | c-out table Diff = | <i>0.67</i> m | |
| Summary Figures Elevation of entrance hole mC |)D =)D = | 4.11 mOD | | <i>0.67</i> m | |
| Summary Figures Elevation of entrance hole mC Elevation of exit hole mC |)D =)D = ble = | 4.11 mOD 3.44 mOD | | 0.67 m 1.0 Bar | |
| Summary Figures Elevation of entrance hole mC Elevation of exit hole mC Maximum cover to HDD boreho |)D =)D = ble = ire = | 4.11 mOD 3.44 mOD 10.4 m | | | |



Expressions used in hydrofracture calculations

In the tabulation below the following functions are applied

Saturated Layer **Sat'd**: IF (WTL<=HDD, Elevn-HDD, Max(Elevn-WTL, 0))

Bouyant Layer **Bou't**: IF (WTL<=HDD, 0, Min(WTL-HDD, Elevn-HDD))

 $\sigma v = (\gamma s^*Satd+(\gamma s-\gamma w)^*Bout)^*g/1000$

 $\sigma o = SQRT((\gamma s*Satd+(\gamma s-\gamma w)*Bout)^2 + (ko * (\gamma s*Satd + (\gamma s-\gamma w)*Bout))^2))$

- $\mathbf{Q} = (\sigma o^* SIN(\Phi r) + Coh^* COS(\Phi r)) / Gmod$
- **Pf** = $(\sigma o^* (1+SIN(\Phi r))) + (Coh^* COS(\Phi r))$

LAT


Pemax = (Pf + Coh*COT(Φ r)) * (((Ro/Rpmax)^2 + Q)^(-SIN(Φ r)/(1+SIN(Φ r)))) - Coh*COT(Φ r)

 $\label{eq:Pelim} \textbf{Pelim} = (Pf + Coh^*COT(\Phi r)) \ * \ (\ Q^{(-SIN(\Phi r)/(1+SIN(\Phi r)))}) - Coh^*COT(\Phi r)$

| WTc | ontrols: | 0 | -4.89 | | | | | | | |
|--------|----------|-------|-------|--------|--------|-------|-------|-------|-------|-------|
| Dist | Elev'n | Loc'n | WTL | C-Line | Soffit | Cover | Sat'd | Bou't | U | Hs |
| (m) | (mOD) | 20011 | (mOD) | (mOD) | (mOD) | (m) | (m) | (m) | kN/m2 | kN/m3 |
| 0.00 | 4.11 | | 4.11 | 4.11 | 4.41 | 0.00 | 0.00 | 0.00 | 0 | 0 |
| 10.00 | 4.03 | | 4.03 | 2.83 | 3.13 | 0.90 | 0.00 | 0.90 | 9 | 12 |
| 20.00 | 4.06 | | 4.06 | 1.55 | 1.85 | 2.21 | 0.00 | 2.21 | 22 | 29 |
| 30.00 | 3.24 | | 3.24 | 0.28 | 0.58 | 2.66 | 0.00 | 2.66 | 26 | 45 |
| 40.00 | 3.94 | | 3.94 | -0.89 | -0.59 | 4.53 | 0.00 | 4.53 | 44 | 60 |
| 50.00 | 4.04 | | 4.04 | -1.93 | -1.63 | 5.67 | 0.00 | 5.67 | 56 | 73 |
| 60.00 | 4.50 | | 4.50 | -2.83 | -2.53 | 7.03 | 0.00 | 7.03 | 69 | 85 |
| 70.00 | 5.64 | | 5.64 | -3.59 | -3.29 | 8.93 | 0.00 | 8.93 | 88 | 94 |
| 80.00 | 6.52 | | 6.52 | -4.23 | -3.93 | 10.45 | 0.00 | 10.45 | 102 | 102 |
| 90.00 | 5.03 | | 5.03 | -4.73 | -4.43 | 9.46 | 0.00 | 9.46 | 93 | 109 |
| 100.00 | 3.60 | | 3.60 | -5.10 | -4.80 | 8.39 | 0.00 | 8.39 | 82 | 114 |
| 110.00 | 3.16 | | 3.16 | -5.33 | -5.03 | 8.19 | 0.00 | 8.19 | 80 | 117 |
| 120.00 | 1.58 | | 1.58 | -5.43 | -5.13 | 6.71 | 0.00 | 6.71 | 66 | 118 |
| 130.00 | 0.00 | | 0.00 | -5.49 | -5.19 | 5.19 | 0.00 | 5.19 | 51 | 119 |
| 140.00 | 0.01 | | 0.01 | -5.55 | -5.25 | 5.26 | 0.00 | 5.26 | 52 | 119 |
| 150.00 | 0.08 | | 0.08 | -5.61 | -5.31 | 5.39 | 0.00 | 5.39 | 53 | 120 |
| 160.00 | 0.15 | | 0.15 | -5.66 | -5.36 | 5.51 | 0.00 | 5.51 | 54 | 121 |
| 170.00 | 0.22 | | 0.22 | -5.72 | -5.42 | 5.63 | 0.00 | 5.63 | 55 | 121 |
| 180.00 | 0.29 | | 0.29 | -5.78 | -5.48 | 5.76 | 0.00 | 5.76 | 57 | 122 |
| 190.00 | 0.36 | | 0.36 | -5.84 | -5.54 | 5.89 | 0.00 | 5.89 | 58 | 123 |
| 200.00 | 0.43 | | 0.43 | -5.89 | -5.59 | 6.01 | 0.00 | 6.01 | 59 | 124 |
| 210.00 | 0.49 | | 0.49 | -5.95 | -5.65 | 6.14 | 0.00 | 6.14 | 60 | 124 |
| 220.00 | 0.51 | | 0.51 | -6.01 | -5.71 | 6.21 | 0.00 | 6.21 | 61 | 125 |
| 230.00 | 0.51 | | 0.51 | -6.07 | -5.77 | 6.28 | 0.00 | 6.28 | 62 | 126 |
| 240.00 | 0.52 | | 0.52 | -6.12 | -5.82 | 6.33 | 0.00 | 6.33 | 62 | 127 |
| 250.00 | 0.52 | | 0.52 | -6.18 | -5.88 | 6.40 | 0.00 | 6.40 | 63 | 127 |
| 260.00 | 0.53 | | 0.53 | -6.24 | -5.94 | 6.46 | 0.00 | 6.46 | 63 | 128 |
| 270.00 | 0.53 | | 0.53 | -6.30 | -6.00 | 6.53 | 0.00 | 6.53 | 64 | 129 |
| 280.00 | 0.54 | | 0.54 | -6.35 | -6.05 | 6.58 | 0.00 | 6.58 | 65 | 130 |
| 290.00 | 0.54 | | 0.54 | -6.41 | -6.11 | 6.64 | 0.00 | 6.64 | 65 | 130 |
| 300.00 | 0.54 | | 0.54 | -6.47 | -6.17 | 6.71 | 0.00 | 6.71 | 66 | 131 |
| 310.00 | 0.55 | | 0.55 | -6.53 | -6.23 | 6.77 | 0.00 | 6.77 | 66 | 132 |
| 320.00 | 0.55 | | 0.55 | -6.58 | -6.28 | 6.83 | 0.00 | 6.83 | 67 | 132 |
| 330.00 | 0.56 | | 0.56 | -6.64 | -6.34 | 6.89 | 0.00 | 6.89 | 68 | 133 |
| 340.00 | 0.56 | | 0.56 | -6.70 | -6.40 | 6.96 | 0.00 | 6.96 | 68 | 134 |
| 350.00 | 0.57 | | 0.57 | -6.76 | -6.46 | 7.02 | 0.00 | 7.02 | 69 | 135 |
| 360.00 | 0.57 | | 0.57 | -6.81 | -6.51 | 7.08 | 0.00 | 7.08 | 69 | 135 |
| 370.00 | 0.58 | | 0.58 | -6.87 | -6.57 | 7.14 | 0.00 | 7.14 | 70 | 136 |
| 380.00 | 0.58 | | 0.58 | -6.93 | -6.63 | 7.21 | 0.00 | 7.21 | 71 | 137 |
| 390.00 | 0.59 | | 0.59 | -6.99 | -6.69 | 7.27 | 0.00 | 7.27 | 71 | 138 |
| 400.00 | 0.59 | | 0.59 | -7.04 | -6.74 | 7.33 | 0.00 | 7.33 | 72 | 138 |
| 410.00 | 0.60 | | 0.60 | -7.10 | -6.80 | 7.39 | 0.00 | 7.39 | 72 | 139 |
| 420.00 | 0.60 | | 0.60 | -7.16 | -6.86 | 7.45 | 0.00 | 7.45 | 73 | 140 |
| 430.00 | 0.58 | | 0.58 | -7.22 | -6.92 | 7.49 | 0.00 | 7.49 | 74 | 141 |
| 440.00 | 0.56 | | 0.56 | -7.27 | -6.97 | 7.53 | 0.00 | 7.53 | 74 | 141 |
| 450.00 | 0.54 | | 0.54 | -7.33 | -7.03 | 7.57 | 0.00 | 7.57 | 74 | 142 |
| 460.00 | 0.52 | | 0.52 | -7.39 | -7.09 | 7.61 | 0.00 | 7.61 | 75 | 143 |
| 470.00 | 0.50 | | 0.50 | -7.44 | -7.14 | 7.64 | 0.00 | 7.64 | 75 | 143 |
| 480.00 | 0.48 | | 0.48 | -7.50 | -7.20 | 7.68 | 0.00 | 7.68 | 75 | 144 |
| 490.00 | 0.46 | | 0.46 | -7.56 | -7.26 | 7.72 | 0.00 | 7.72 | 76 | 145 |
| 500.00 | 0.45 | | 0.45 | -7.62 | -7.32 | 7.76 | 0.00 | 7.76 | 76 | 146 |
| 510.00 | 0.43 | | 0.43 | -7.67 | -7.37 | 7.79 | 0.00 | 7.79 | 76 | 146 |
| 520.00 | 0.41 | | 0.41 | -7.73 | -7.43 | 7.83 | 0.00 | 7.83 | 77 | 147 |

| 530.00 | 0.39 | 0.39 | -7.79 | -7.49 | 7.87 | 0.00 | 7.87 | 77 | 148 |
|---------|-------|-------|----------------|--------|-------|------|-------|----------|-----|
| 540.00 | 0.37 | 0.37 | -7.85 | -7.55 | 7.91 | 0.00 | 7.91 | 78 | 149 |
| 550.00 | 0.35 | 0.35 | -7.90 | -7.60 | 7.94 | 0.00 | 7.94 | 78 | 149 |
| | 0.33 | 0.33 | -7.96 | | 7.99 | 0.00 | 7.99 | 78 | 150 |
| 560.00 | | | | -7.66 | | | | | |
| 570.00 | 0.32 | 0.32 | -8.02 | -7.72 | 8.03 | 0.00 | 8.03 | 79 | 151 |
| 580.00 | 0.31 | 0.31 | -8.08 | -7.78 | 8.08 | 0.00 | 8.08 | 79 | 152 |
| 590.00 | 0.29 | 0.29 | -8.13 | -7.83 | 8.12 | 0.00 | 8.12 | 80 | 152 |
| 600.00 | 0.28 | 0.28 | -8.19 | -7.89 | 8.16 | 0.00 | 8.16 | 80 | 153 |
| 610.00 | 0.27 | 0.27 | -8.25 | -7.95 | 8.21 | 0.00 | 8.21 | 81 | 154 |
| 620.00 | 0.25 | 0.25 | -8.31 | -8.01 | 8.26 | 0.00 | 8.26 | 81 | 155 |
| 630.00 | 0.24 | 0.24 | -8.36 | -8.06 | 8.30 | 0.00 | 8.30 | 81 | 155 |
| 640.00 | 0.23 | 0.23 | -8.42 | -8.12 | 8.34 | 0.00 | 8.34 | 82 | 156 |
| | | | | | | | | | |
| 650.00 | 0.22 | 0.22 | -8.48 | -8.18 | 8.39 | 0.00 | 8.39 | 82 | 157 |
| 660.00 | 0.20 | 0.20 | -8.54 | -8.24 | 8.44 | 0.00 | 8.44 | 83 | 157 |
| 670.00 | 0.19 | 0.19 | -8.59 | -8.29 | 8.47 | 0.00 | 8.47 | 83 | 158 |
| 680.00 | 0.18 | 0.18 | -8.65 | -8.35 | 8.52 | 0.00 | 8.52 | 84 | 159 |
| 690.00 | 0.17 | 0.17 | -8.71 | -8.41 | 8.57 | 0.00 | 8.57 | 84 | 160 |
| 700.00 | 0.16 | 0.16 | -8.77 | -8.47 | 8.62 | 0.00 | 8.62 | 85 | 160 |
| 710.00 | 0.15 | 0.15 | -8.82 | -8.52 | 8.66 | 0.00 | 8.66 | 85 | 161 |
| 720.00 | 0.14 | 0.14 | -8.88 | -8.58 | 8.71 | 0.00 | 8.71 | 85 | 162 |
| 730.00 | 0.13 | 0.13 | -8.94 | -8.64 | 8.77 | 0.00 | 8.77 | 86 | 163 |
| 740.00 | 0.12 | 0.12 | -9.00 | -8.70 | 8.82 | 0.00 | 8.82 | 87 | 163 |
| | | | | | | | | 87 87 | 164 |
| 750.00 | 0.10 | 0.10 | -9.05 | -8.75 | 8.85 | 0.00 | 8.85 | | |
| 760.00 | 0.09 | 0.09 | -9.11 | -8.81 | 8.89 | 0.00 | 8.89 | 87 | 165 |
| 770.00 | 0.09 | 0.09 | -9.17 | -8.87 | 8.95 | 0.00 | 8.95 | 88 | 165 |
| 780.00 | 0.09 | 0.09 | -9.23 | -8.93 | 9.02 | 0.00 | 9.02 | 88 | 166 |
| 790.00 | 0.09 | 0.09 | -9.28 | -8.98 | 9.07 | 0.00 | 9.07 | 89 | 167 |
| 800.00 | 0.10 | 0.10 | -9.34 | -9.04 | 9.13 | 0.00 | 9.13 | 90 | 168 |
| 810.00 | 0.10 | 0.10 | -9.40 | -9.10 | 9.19 | 0.00 | 9.19 | 90 | 168 |
| 820.00 | 0.10 | 0.10 | -9.46 | -9.16 | 9.26 | 0.00 | 9.26 | 91 | 169 |
| 830.00 | 0.10 | 0.10 | -9.51 | -9.21 | 9.31 | 0.00 | 9.31 | 91 | 170 |
| 840.00 | 0.10 | 0.10 | -9.57 | -9.27 | 9.37 | 0.00 | 9.37 | 92 | 171 |
| 850.00 | 0.10 | 0.10 | -9.63 | -9.33 | 9.43 | 0.00 | 9.43 | 93 | 171 |
| | | | | | | | | | |
| 860.00 | 0.11 | 0.11 | -9.69 | -9.39 | 9.49 | 0.00 | 9.49 | 93 | 172 |
| 870.00 | 0.11 | 0.11 | -9.74 | -9.44 | 9.55 | 0.00 | 9.55 | 94 | 173 |
| 880.00 | 0.11 | 0.11 | -9.80 | -9.50 | 9.61 | 0.00 | 9.61 | 94 | 174 |
| 890.00 | 0.12 | 0.12 | -9.86 | -9.56 | 9.67 | 0.00 | 9.67 | 95 | 174 |
| 900.00 | 0.12 | 0.12 | -9.91 | -9.61 | 9.72 | 0.00 | 9.72 | 95 | 175 |
| 910.00 | 0.12 | 0.12 | -9.97 | -9.67 | 9.79 | 0.00 | 9.79 | 96 | 176 |
| 920.00 | 0.12 | 0.12 | -10.03 | -9.73 | 9.85 | 0.00 | 9.85 | 97 | 176 |
| 930.00 | 0.13 | 0.13 | -10.09 | -9.79 | 9.91 | 0.00 | 9.91 | 97 | 177 |
| 940.00 | 0.13 | 0.13 | -10.14 | -9.84 | 9.96 | 0.00 | 9.96 | 98 | 178 |
| 950.00 | 0.13 | 0.13 | -10.20 | -9.90 | 10.03 | 0.00 | 10.03 | 98 | 179 |
| 960.00 | 0.13 | 0.13 | -10.26 | -9.96 | | 0.00 | 10.09 | 99 | 179 |
| | | | | | 10.09 | | | | |
| 970.00 | 0.14 | 0.14 | -10.32 | -10.02 | 10.15 | 0.00 | 10.15 | 100 | 180 |
| 980.00 | 0.14 | 0.14 | -10.37 | -10.07 | 10.20 | 0.00 | 10.20 | 100 | 181 |
| 990.00 | -4.86 | -4.86 | -10.43 | -10.13 | 5.27 | 0.00 | 5.27 | 52 | 182 |
| 1000.00 | -4.86 | -4.86 | -10.49 | -10.19 | 5.33 | 0.00 | 5.33 | 52 | 182 |
| 1010.00 | -4.86 | -4.86 | -10.55 | -10.25 | 5.39 | 0.00 | 5.39 | 53 | 183 |
| 1020.00 | -4.85 | -4.85 | -10.60 | -10.30 | 5.45 | 0.00 | 5.45 | 53 | 184 |
| 1030.00 | -4.85 | -4.85 | -10.66 | -10.36 | 5.51 | 0.00 | 5.51 | 54 | 184 |
| 1040.00 | -4.85 | -4.85 | -10.61 | -10.31 | 5.46 | 0.00 | 5.46 | 54 | 184 |
| 1050.00 | -4.85 | -4.85 | -10.43 | -10.13 | 5.28 | 0.00 | 5.28 | 52 | 182 |
| 1060.00 | 0.16 | 0.16 | -10.12 | -9.82 | 9.97 | 0.00 | 9.97 | 98 | 178 |
| 1070.00 | 0.16 | 0.16 | -9.68 | -9.38 | 9.53 | 0.00 | 9.53 | 94 | 172 |
| | | | | | | | | | 165 |
| 1080.00 | 0.16 | 0.16 | -9.10 | -8.80 | 8.96 | 0.00 | 8.96 | 88 | |
| 1090.00 | 0.16 | 0.16 | -8.44 | -8.14 | 8.30 | 0.00 | 8.30 | 81 | 156 |
| 1100.00 | 0.17 | 0.17 | -7.79 | -7.49 | 7.65 | 0.00 | 7.65 | 75 | 148 |
| 1110.00 | 0.17 | 0.17 | -7.14 | -6.84 | 7.00 | 0.00 | 7.00 | 69 | 140 |
| 1120.00 | 0.17 | 0.17 | -6.48 | -6.18 | 6.34 | 0.00 | 6.34 | 62 | 131 |
| 1130.00 | 0.17 | 0.17 | -5.83 | -5.53 | 5.70 | 0.00 | 5.70 | 56 | 123 |
| 1140.00 | 0.17 | 0.17 | -5.17 | -4.87 | 5.04 | 0.00 | 5.04 | 49 | 114 |
| 1150.00 | 2.13 | 2.13 | -4.52 | -4.22 | 6.35 | 0.00 | 6.35 | 62 | 106 |
| 1160.00 | 4.42 | 4.42 | -3.86 | -3.56 | 7.98 | 0.00 | 7.98 | 78 | 98 |
| 1170.00 | 6.94 | 6.94 | -3.21 | -2.91 | 9.85 | 0.00 | 9.85 | 97 | 89 |
| 1180.00 | 7.82 | 7.82 | -2.55 | -2.25 | 10.06 | 0.00 | 10.06 | 99 | 81 |
| 1190.00 | 6.90 | 6.90 | -2.55 -1.90 | | | 0.00 | 8.50 | | 73 |
| 1190.00 | 0.90 | 0.90 | -1.90 | -1.60 | 8.50 | 0.00 | 0.00 | 83 | 15 |

| 1200.00 | 4.75 | 4.75 | -1.24 | -0.94 | 5.69 | 0.00 | 5.69 | 56 | 64 |
|---------|------|------|-------|-------|------|------|------|----|----|
| 1210.00 | 3.38 | 3.38 | -0.59 | -0.29 | 3.67 | 0.00 | 3.67 | 36 | 56 |
| 1220.00 | 3.74 | 3.74 | 0.06 | 0.36 | 3.38 | 0.00 | 3.38 | 33 | 48 |
| 1230.00 | 3.53 | 3.53 | 0.72 | 1.02 | 2.51 | 0.00 | 2.51 | 25 | 39 |
| 1240.00 | 3.47 | 3.47 | 1.37 | 1.67 | 1.79 | 0.00 | 1.79 | 18 | 31 |
| 1250.00 | 3.71 | 3.71 | 2.03 | 2.33 | 1.37 | 0.00 | 1.37 | 13 | 23 |
| 1260.00 | 3.53 | 3.53 | 2.68 | 2.98 | 0.54 | 0.00 | 0.54 | 5 | 14 |
| 1270.00 | 3.43 | 3.43 | 3.34 | 3.64 | 0.00 | 0.00 | 0.00 | 0 | 6 |
| 1272.00 | 3.44 | 3.44 | 3.44 | 3.74 | 0.00 | 0.00 | 0.00 | 0 | 5 |
| - | | | | | | | | | |




| Dist | σν | σh | σο | Pf | Q | Rpmax | Pemax | Pmax | Hf | H | The pressure calculations |
|----------------|--------------|------------|--------------|----------------|--------------------|------------|------------|------------|----------|----------------------|---|
| (m) | (kN/m²) | (kN/m²) | (kN/m²) | (kN/m²) | | (m) | (kN/m²) | (kN/m²) | • | (kN/m ²) | are set out in this table. Note that Rpmax varies |
| 0.0 | 0.0 | 0.0 | 0.0 | 1.8 | 0.00012 | 0.3 | 2 | 2 | 0 | 0 | as it is set to be a |
| 10.0 | 8.3 | 0.0 | 8.3 | 13.7 | 0.00035 | 0.4 | 18 | 27 | 0 | 13 | proportion of the cover |
| 20.0 | 20.6 | 0.0 | 20.6 | 31.0 | 0.00068 | 1.1 | 71 | 93 | 1 | 30 | depth. |
| 30.0 | 24.7 | 0.0 | 24.7 | 37.0 | 0.00080 | 1.3 | 94 | 120 | 1 | 46 | |
| 40.0 | 42.2 | 0.0 | 42.2 | 61.8 | 0.00128 | 2.3 | 209 | 253 | 2 | 62 | Hf is a rough estimate of |
| 50.0 | 52.8 | 0.0 | 52.8 | 77.0 | 0.00157 | 2.8 | 290 | 346 | 2 | 75 | the drilling mud pressure in |
| 60.0 | 65.5 | 0.0 | 65.5 | 95.0 | 0.00192 | 3.5 | 392 | 461 | 3 | 87 | the return annular flow. |
| 70.0 | 83.2 | 0.0 | 83.2 | 120.1 | 0.00240 | 4.5 | 538 | 625 | 3 | 97 | The total head H is the |
| 80.0 | 97.3 | 0.0 | 97.3 | 140.3 | 0.00279 | 5.2 | 650 | 753 | 3 | 106 | static head Hs (table |
| 90.0 | 88.1 | 0.0 | 88.1 | 127.2 | 0.00254 | 4.7 | 577 | 670 | 4 | 113 | above) and Hf . |
| 100.0 | 78.2 | 0.0 | 78.2 | 113.1 | 0.00227 | 4.2 | 497 | 579 | 4 | 118 | |
| 110.0 | 76.3 | 0.0 | 76.3 | 110.4 | 0.00221 | 4.1 | 481 | 562 | 5 | 121 | |
| 120.0 | 62.5 | 0.0 | 62.5 | 90.7 | 0.00183 | 3.4 | 368 | 434 | 5 | 123 | |
| 130.0 | 48.3 | 0.0 | 48.3 | 70.6 | 0.00145 | 2.6 | 255 | 306 | 5 | 124 | |
| 140.0 | 49.0 | 0.0 | 49.0 | 71.5 | 0.00146 | 2.6 | 260 | 312 | 6 | 125 | |
| 150.0 | 40.0 50.2 | 0.0 | 50.2 | 73.2 | 0.00150 | 2.0 | 200 | 322 | 6 | 126 | |
| 160.0 | 51.3 | 0.0 | 51.3 | 74.8 | 0.00153 | 2.8 | 270 | 332 | 7 | 127 | |
| 170.0 | 52.5 | 0.0 | 52.5 | 74.0 | 0.00156 | 2.8 | 288 | 343 | 7 | 129 | |
| 180.0 | 53.7 | 0.0 | 53.7 | 78.2 | 0.00159 | 2.9 | 200 | 354 | 8 | 130 | |
| 190.0 | 54.9 | 0.0 | 54.9 | 79.9 | 0.00163 | 2.9 | 306 | 364 | 8 | 131 | |
| 210.0 | 57.2 | 0.0 | 57.2 | 83.2 | 0.00169 | 3.1 | 325 | 385 | 9 | 133 | |
| 220.0 | 57.9 | 0.0 | 57.9 | 84.2 | 0.00171 | 3.1 | 330 | 391 | 9 | 134 | |
| 230.0 | 58.5 | 0.0 | 58.5 | 85.0 | 0.00172 | 3.1 | 335 | 397 | 10 | 136 | |
| 240.0 | 59.0 | 0.0 | 59.0 | 85.8 | 0.00174 | 3.2 | 339 | 402 | 10 | 137 | |
| 250.0 | 59.6 | 0.0 | 59.6 | 86.6 | 0.00176 | 3.2 | 344 | 407 | 10 | 138 | |
| 260.0 | 60.2 | 0.0 | 60.2 | 87.5 | 0.00177 | 3.2 | 349 | 413 | 11 | 139 | |
| 270.0 | 60.8 | 0.0 | 60.8 | 88.3 | 0.00179 | 3.3 | 354 | 418 | 11 | 140 | |
| 280.0 | 61.3 | 0.0 | 61.3 | 89.1 | 0.00180 | 3.3 | 358 | 423 | 12 | 141 | |
| 290.0 | 61.9 | 0.0 | 61.9 | 89.9 | 0.00182 | 3.3 | 363 | 428 | 12 | 142 | |
| 300.0 | 62.5 | 0.0 | 62.5 | 90.8 | 0.00184 | 3.4 | 368 | 434 | 13 | 144 | |
| 310.0 320.0 | 63.1 63.6 | 0.0 0.0 | 63.1 63.6 | 91.6 92.3 | 0.00185 0.00187 | 3.4 3.4 | 373 377 | 439 444 | 13 13 | 145 146 | |
| 330.0 | 64.2 | 0.0 | 64.2 | 92.3 93.2 | 0.00187 | 3.4 3.4 | 382 | 450 | 13 | 140 | |
| 340.0 | 64.8 | 0.0 | 64.8 | 94.1 | 0.00100 | 3.5 | 387 | 455 | 14 | 148 | |
| 350.0 | 65.4 | 0.0 | 65.4 | 94.9 | 0.00192 | 3.5 | 392 | 461 | 15 | 149 | |
| 360.0 | 66.0 | 0.0 | 66.0 | 95.6 | 0.00193 | 3.5 | 396 | 466 | 15 | 150 | |
| 370.0 | 66.6 | 0.0 | 66.6 | 96.5 | 0.00195 | 3.6 | 401 | 471 | 15 | 152 | |
| 380.0 | 67.2 | 0.0 | 67.2 | 97.4 | 0.00196 | 3.6 | 406 | 477 | 16 | 153 | |
| 390.0 | 67.8 | 0.0 | 67.8 | 98.2 | 0.00198 | 3.6 | 411 | 482 | 16 | 154 | |
| 400.0 | 68.3 | 0.0 | 68.3 | 98.9 | 0.00199 | 3.7 | 415 | 487 | 17 | 155 | |
| 410.0 | 68.9 | 0.0 | 68.9 | 99.8 | 0.00201 | 3.7 | 420 | 493 | 17 | 156 | |
| 420.0 | 69.5 | 0.0 | 69.5 | 100.6 | 0.00203 | 3.7 | 425 | 498 | 18 | 157 | |
| 430.0 | 69.8 | 0.0 | 69.8 | 101.2 | 0.00204 | 3.7 | 428 | 502 | 18 | 159 | |
| 440.0 | 70.1 | 0.0 | 70.1 | 101.6 | 0.00204 | 3.8 | 431 | 504 | 18 | 160 | |
| 450.0 | 70.5 | 0.0 | 70.5 | 102.1 | 0.00205 | 3.8 | 434 | 508 | 19 10 | 161 | |
| 460.0 470.0 | 70.9 71.2 | 0.0 0.0 | 70.9 71.2 | 102.7 103.1 | 0.00207 | 3.8 | 437 439 | 511 514 | 19 20 | 162 163 | |
| 470.0 480.0 | 71.2 71.6 | 0.0 | 71.2 71.6 | 103.1 | 0.00207 | 3.8 3.8 | 439 442 | 514 518 | 20 20 | 163 164 | |
| 480.0 | 71.0 | 0.0 | 71.0 | 103.0 | 0.00208 | 3.8 3.9 | 442 | 521 | 20 | 165 | |
| 490.0 500.0 | 72.3 | 0.0 | 72.3 | 104.2 | 0.00209 | 3.9 | 443 | 525 | 20 | 167 | |
| 510.0 | 72.6 | 0.0 | 72.6 | 105.1 | 0.00211 | 3.9 | 451 | 527 | 21 | 168 | |
| 520.0 | 73.0 | 0.0 | 73.0 | 105.6 | | 3.9 | 454 | 531 | 22 | 169 | |
| | - | - | | | | - | | | | | |

| 530.0 | 73.4 | 0.0 | 73.4 | 106.2 | 0.00213 | 3.9 | 457 | 534 | 22 | 170 |
|--|--|--|--|--|--|---|--|--|--|---|
| | | | | | | | | | 23 | |
| 540.0 | 73.7 | 0.0 | 73.7 | 106.7 | 0.00214 | 4.0 | 460 | 538 | | 171 |
| 550.0 | 74.0 | 0.0 | 74.0 | 107.1 | 0.00215 | 4.0 | 463 | 541 | 23 | 172 |
| 560.0 | 74.4 | 0.0 | 74.4 | 107.7 | 0.00216 | 4.0 | 466 | 544 | 23 | 173 |
| 570.0 | 74.9 | 0.0 | 74.9 | 108.3 | 0.00217 | 4.0 | 469 | 548 | 24 | 175 |
| | | | | | | | | | | |
| 580.0 | 75.3 | 0.0 | 75.3 | 108.9 | 0.00219 | 4.0 | 473 | 552 | 24 | 176 |
| 590.0 | 75.6 | 0.0 | 75.6 | 109.4 | 0.00220 | 4.1 | 476 | 556 | 25 | 177 |
| 600.0 | 76.1 | 0.0 | 76.1 | 110.1 | 0.00221 | 4.1 | 480 | 560 | 25 | 178 |
| | | | | | | | | | | |
| 610.0 | 76.5 | 0.0 | 76.5 | 110.7 | 0.00222 | 4.1 | 483 | 564 | 26 | 179 |
| 620.0 | 77.0 | 0.0 | 77.0 | 111.3 | 0.00223 | 4.1 | 487 | 568 | 26 | 180 |
| 630.0 | 77.3 | 0.0 | 77.3 | 111.8 | 0.00224 | 4.1 | 490 | 571 | 26 | 181 |
| | | | | | | | | | | |
| 640.0 | 77.7 | 0.0 | 77.7 | 112.4 | 0.00225 | 4.2 | 493 | 575 | 27 | 183 |
| 650.0 | 78.2 | 0.0 | 78.2 | 113.1 | 0.00227 | 4.2 | 497 | 579 | 27 | 184 |
| 660.0 | 78.6 | 0.0 | 78.6 | 113.7 | 0.00228 | 4.2 | 500 | 583 | 28 | 185 |
| 670.0 | 79.0 | 0.0 | 79.0 | 114.2 | 0.00229 | 4.2 | 503 | 586 | 28 | 186 |
| | | | | | | | | | | |
| 680.0 | 79.4 | 0.0 | 79.4 | 114.8 | 0.00230 | 4.3 | 507 | 591 | 28 | 187 |
| 690.0 | 79.9 | 0.0 | 79.9 | 115.5 | 0.00231 | 4.3 | 511 | 595 | 29 | 188 |
| 700.0 | 80.3 | 0.0 | 80.3 | 116.1 | 0.00232 | 4.3 | 514 | 599 | 29 | 190 |
| | | | | | | | | | | |
| 710.0 | 80.7 | 0.0 | 80.7 | 116.7 | 0.00234 | 4.3 | 518 | 603 | 30 | 191 |
| 720.0 | 81.2 | 0.0 | 81.2 | 117.3 | 0.00235 | 4.4 | 521 | 607 | 30 | 192 |
| 730.0 | 81.7 | 0.0 | 81.7 | 118.1 | 0.00236 | 4.4 | 526 | 612 | 31 | 193 |
| 740.0 | 82.2 | 0.0 | 82.2 | 118.7 | 0.00238 | 4.4 | 529 | 616 | 31 | 194 |
| | | | | | | | | | | |
| 750.0 | 82.5 | 0.0 | 82.5 | 119.1 | 0.00238 | 4.4 | 532 | 618 | 31 | 195 |
| 760.0 | 82.9 | 0.0 | 82.9 | 119.7 | 0.00239 | 4.4 | 535 | 622 | 32 | 196 |
| 770.0 | 83.4 | 0.0 | 83.4 | 120.5 | 0.00241 | 4.5 | 540 | 627 | 32 | 198 |
| | | | | | | | | | | |
| 780.0 | 84.0 | 0.0 | 84.0 | 121.3 | 0.00243 | 4.5 | 544 | 633 | 33 | 199 |
| 790.0 | 84.5 | 0.0 | 84.5 | 122.0 | 0.00244 | 4.5 | 548 | 637 | 33 | 200 |
| 800.0 | 85.1 | 0.0 | 85.1 | 122.9 | 0.00246 | 4.6 | 553 | 643 | 33 | 201 |
| | | | | | | | | | | |
| 810.0 | 85.7 | 0.0 | 85.7 | 123.7 | 0.00247 | 4.6 | 558 | 648 | 34 | 202 |
| 820.0 | 86.3 | 0.0 | 86.3 | 124.5 | 0.00249 | 4.6 | 562 | 653 | 34 | 203 |
| 830.0 | 86.7 | 0.0 | 86.7 | 125.2 | 0.00250 | 4.7 | 566 | 658 | 35 | 205 |
| | 87.3 | | | | | 4.7 | | | | |
| 840.0 | | 0.0 | 87.3 | 126.0 | 0.00252 | | 571 | 663 | 35 | 206 |
| 850.0 | 87.9 | 0.0 | 87.9 | 126.9 | 0.00253 | 4.7 | 576 | 668 | 36 | 207 |
| 860.0 | 88.5 | 0.0 | 88.5 | 127.7 | 0.00255 | 4.7 | 580 | 673 | 36 | 208 |
| 870.0 | 89.0 | 0.0 | 89.0 | 128.4 | 0.00256 | 4.8 | 584 | 678 | 36 | 209 |
| | | | | | | | | | | |
| 880.0 | 89.6 | 0.0 | 89.6 | 129.2 | 0.00258 | 4.8 | 589 | 683 | 37 | 210 |
| 890.0 | 90.1 | 0.0 | 90.1 | 130.0 | 0.00259 | 4.8 | 594 | 688 | 37 | 211 |
| 900.0 | 90.6 | 0.0 | 90.6 | 130.7 | 0.00261 | 4.9 | 597 | 693 | 38 | 213 |
| | | | | | | | | | | |
| 910.0 | 91.2 | 0.0 | 91.2 | 131.6 | 0.00262 | 4.9 | 602 | 698 | 38 | 214 |
| 920.0 | 91.8 | 0.0 | 91.8 | 132.4 | 0.00264 | 4.9 | 607 | 703 | 38 | 215 |
| 930.0 | 92.4 | 0.0 | 92.4 | 133.2 | 0.00265 | 5.0 | 611 | 708 | 39 | 216 |
| | | | | | | | | | | |
| 940.0 | 92.9 | 0.0 | 92.9 | 133.9 | 0.00267 | 5.0 | 615 | 713 | 39 | 217 |
| 950.0 | 93.4 | 0.0 | 93.4 | 134.7 | 0.00268 | 5.0 | 620 | 718 | 40 | 218 |
| 960.0 | 94.0 | 0.0 | 94.0 | 135.5 | 0.00270 | 5.0 | 624 | 723 | 40 | 220 |
| | | | | | | | | 728 | 41 | 221 |
| 970.0 | 94.6 | 0.0 | 94.6 | 136.4 | 0.00272 | 5.1 | 629 | | | |
| 980.0 | 95.1 | 0.0 | 95.1 | 137.1 | 0.00273 | 5.1 | 633 | 733 | 41 | 222 |
| 990.0 | 49.1 | 0.0 | 49.1 | 71.6 | 0.00147 | 2.6 | 261 | 312 | 41 | 223 |
| 1000.0 | 49.6 | 0.0 | 49.6 | 72.4 | 0.00148 | 2.7 | 265 | 317 | 42 | 224 |
| | | | | | | | | | | |
| 1010.0 | 50.2 | 0.0 | 50.2 | 73.2 | 0.00150 | 2.7 | 269 | 322 | 42 | 225 |
| 1020.0 | 50.7 | 0.0 | 50.7 | 74.0 | 0.00151 | 2.7 | 274 | 327 | 43 | 226 |
| 1030.0 | 51.3 | 0.0 | 51.3 | 74.8 | 0.00153 | 2.8 | 278 | 332 | 43 | 228 |
| 1040.0 | 50.8 | 0.0 | 50.8 | 74.1 | 0.00151 | 2.7 | 274 | 328 | 43 | 227 |
| | | | | | | | | | | |
| 1050.0 | 49.2 | 0.0 | 49.2 | 71.8 | 0.00147 | 2.6 | 261 | 313 | 44 | 225 |
| 1060.0 | 92.9 | 0.0 | 92.9 | 134.0 | 0.00267 | 5.0 | 616 | 713 | 44 | 222 |
| 1070.0 | 88.8 | 0.0 | 88.8 | 128.2 | 0.00256 | 4.8 | 583 | 677 | 45 | 217 |
| | | | | | | | | | | |
| 1080.0 | 83.5 | 0.0 | 83.5 | 120.5 | 0.00241 | 4.5 | 540 | 628 | 45 | 210 |
| 1090.0 | 77.3 | 0.0 | 77.3 | 111.8 | 0.00224 | 4.1 | 490 | 571 | 46 | 202 |
| | 11.0 | 0.0 | | | | | 430 | | - | 194 |
| 1100 0 | | | 713 | 103.2 | 0 00208 | 38 | | 515 | 46 | |
| 1100.0 | 71.3 | 0.0 | 71.3 | 103.2 | 0.00208 | 3.8 | 440 | 515 450 | 46 | |
| 1110.0 | 71.3 65.3 | 0.0 0.0 | 65.3 | 94.6 | 0.00191 | 3.5 | 440 390 | 459 | 46 | 186 |
| | 71.3 | 0.0 | | | | | 440 | | | |
| 1110.0 1120.0 | 71.3 65.3 59.1 | 0.0 0.0 0.0 | 65.3 59.1 | 94.6 85.9 | 0.00191 0.00174 | 3.5 3.2 | 440 390 340 | 459 403 | 46 47 | 186 178 |
| 1110.0 1120.0 1130.0 | 71.3 65.3 59.1 53.1 | 0.0 0.0 0.0 0.0 | 65.3 59.1 53.1 | 94.6 85.9 77.3 | 0.00191 0.00174 0.00158 | 3.5 3.2 2.8 | 440 390 340 292 | 459 403 348 | 46 47 47 | 186 178 170 |
| 1110.0 1120.0 1130.0 1140.0 | 71.3 65.3 59.1 53.1 47.0 | 0.0 0.0 0.0 0.0 0.0 | 65.3 59.1 53.1 47.0 | 94.6 85.9 77.3 68.6 | 0.00191 0.00174 0.00158 0.00141 | 3.5 3.2 2.8 2.5 | 440 390 340 292 245 | 459 403 348 294 | 46 47 47 48 | 186 178 170 162 |
| 1110.0 1120.0 1130.0 | 71.3 65.3 59.1 53.1 | 0.0 0.0 0.0 0.0 | 65.3 59.1 53.1 | 94.6 85.9 77.3 | 0.00191 0.00174 0.00158 | 3.5 3.2 2.8 | 440 390 340 292 | 459 403 348 | 46 47 47 | 186 178 170 |
| 1110.0 1120.0 1130.0 1140.0 | 71.3 65.3 59.1 53.1 47.0 | 0.0 0.0 0.0 0.0 0.0 | 65.3 59.1 53.1 47.0 | 94.6 85.9 77.3 68.6 | 0.00191 0.00174 0.00158 0.00141 | 3.5 3.2 2.8 2.5 | 440 390 340 292 245 | 459 403 348 294 | 46 47 47 48 | 186 178 170 162 |
| 1110.0 1120.0 1130.0 1140.0 1150.0 1160.0 | 71.3 65.3 59.1 53.1 47.0 59.1 74.4 | 0.0 0.0 0.0 0.0 0.0 0.0 0.0 | 65.3 59.1 53.1 47.0 59.1 74.4 | 94.6 85.9 77.3 68.6 85.9 107.6 | 0.00191 0.00174 0.00158 0.00141 0.00174 0.00216 | 3.5 3.2 2.8 2.5 3.2 4.0 | 440 390 340 292 245 340 465 | 459 403 348 294 403 544 | 46 47 47 48 48 48 | 186 178 170 162 154 146 |
| 1110.0 1120.0 1130.0 1140.0 1150.0 1160.0 1170.0 | 71.3 65.3 59.1 53.1 47.0 59.1 74.4 91.8 | 0.0 0.0 0.0 0.0 0.0 0.0 0.0 0.0 | 65.3 59.1 53.1 47.0 59.1 74.4 91.8 | 94.6 85.9 77.3 68.6 85.9 107.6 132.4 | 0.00191 0.00174 0.00158 0.00141 0.00174 0.00216 0.00264 | 3.5 3.2 2.8 2.5 3.2 4.0 4.9 | 440 390 340 292 245 340 465 607 | 459 403 348 294 403 544 703 | 46 47 47 48 48 48 48 49 | 186 178 170 162 154 146 138 |
| 1110.0 1120.0 1130.0 1140.0 1150.0 1160.0 1170.0 1180.0 | 71.3 65.3 59.1 53.1 47.0 59.1 74.4 91.8 93.8 | 0.0 0.0 0.0 0.0 0.0 0.0 0.0 0.0 0.0 | 65.3 59.1 53.1 47.0 59.1 74.4 91.8 93.8 | 94.6 85.9 77.3 68.6 85.9 107.6 132.4 135.2 | 0.00191 0.00174 0.00158 0.00141 0.00174 0.00216 0.00264 0.00269 | 3.5 3.2 2.8 2.5 3.2 4.0 4.9 5.0 | 440 390 340 292 245 340 465 607 622 | 459 403 348 294 403 544 703 721 | 46 47 47 48 48 48 49 49 49 | 186 178 170 162 154 146 138 130 |
| 1110.0 1120.0 1130.0 1140.0 1150.0 1160.0 1170.0 | 71.3 65.3 59.1 53.1 47.0 59.1 74.4 91.8 93.8 79.2 | 0.0 0.0 0.0 0.0 0.0 0.0 0.0 0.0 | 65.3 59.1 53.1 47.0 59.1 74.4 91.8 | 94.6 85.9 77.3 68.6 85.9 107.6 132.4 | 0.00191 0.00174 0.00158 0.00141 0.00174 0.00216 0.00264 | 3.5 3.2 2.8 2.5 3.2 4.0 4.9 | 440 390 340 292 245 340 465 607 | 459 403 348 294 403 544 703 | 46 47 47 48 48 48 48 49 | 186 178 170 162 154 146 138 |
| 1110.0 1120.0 1130.0 1140.0 1150.0 1160.0 1170.0 1180.0 1190.0 | 71.3 65.3 59.1 53.1 47.0 59.1 74.4 91.8 93.8 79.2 | 0.0 0.0 0.0 0.0 0.0 0.0 0.0 0.0 0.0 0.0 | 65.3 59.1 53.1 47.0 59.1 74.4 91.8 93.8 79.2 | 94.6 85.9 77.3 68.6 85.9 107.6 132.4 135.2 114.5 | 0.00191 0.00174 0.00158 0.00141 0.00174 0.00216 0.00269 0.00229 | 3.5 3.2 2.8 2.5 3.2 4.0 4.9 5.0 4.2 | 440 390 340 292 245 340 465 607 622 505 | 459 403 348 294 403 544 703 721 588 | 46 47 48 48 48 48 49 49 50 | 186 178 170 162 154 146 138 130 123 |
| 1110.0 1120.0 1130.0 1140.0 1150.0 1160.0 1170.0 1180.0 1190.0 1200.0 | 71.3 65.3 59.1 53.1 47.0 59.1 74.4 91.8 93.8 79.2 53.0 | 0.0 0.0 0.0 0.0 0.0 0.0 0.0 0.0 0.0 0.0 | 65.3 59.1 53.1 47.0 59.1 74.4 91.8 93.8 79.2 53.0 | 94.6 85.9 77.3 68.6 85.9 107.6 132.4 135.2 114.5 77.2 | 0.00191 0.00174 0.00158 0.00141 0.00174 0.00216 0.00264 0.00269 0.00229 0.00157 | 3.5 3.2 2.8 2.5 3.2 4.0 4.9 5.0 4.2 2.8 | 440 390 340 292 245 340 465 607 622 505 291 | 459 403 348 294 403 544 703 721 588 347 | 46 47 48 48 48 49 49 50 50 | 186 178 170 162 154 146 138 130 123 115 |
| 1110.0 1120.0 1130.0 1140.0 1150.0 1160.0 1170.0 1180.0 1190.0 1200.0 1210.0 | 71.3 65.3 59.1 53.1 47.0 59.1 74.4 91.8 93.8 79.2 53.0 34.2 | 0.0 0.0 0.0 0.0 0.0 0.0 0.0 0.0 0.0 0.0 | 65.3 59.1 53.1 47.0 59.1 74.4 91.8 93.8 79.2 53.0 34.2 | 94.6 85.9 77.3 68.6 85.9 107.6 132.4 135.2 114.5 77.2 50.4 | 0.00191 0.00174 0.00158 0.00141 0.00216 0.00264 0.00269 0.00229 0.00157 0.00106 | 3.5 3.2 2.8 2.5 3.2 4.0 4.9 5.0 4.2 2.8 1.8 | 440 390 340 292 245 340 465 607 622 505 291 153 | 459 403 348 294 403 544 703 721 588 347 189 | 46 47 48 48 48 49 49 50 50 50 | 186 178 170 162 154 146 138 130 123 115 107 |
| 1110.0 1120.0 1130.0 1140.0 1150.0 1160.0 1170.0 1180.0 1190.0 1200.0 1210.0 1220.0 | 71.3 65.3 59.1 53.1 47.0 59.1 74.4 91.8 93.8 79.2 53.0 | 0.0 0.0 0.0 0.0 0.0 0.0 0.0 0.0 0.0 0.0 | 65.3 59.1 53.1 47.0 59.1 74.4 91.8 93.8 79.2 53.0 34.2 31.5 | 94.6 85.9 77.3 68.6 85.9 107.6 132.4 135.2 114.5 77.2 50.4 46.6 | 0.00191 0.00174 0.00158 0.00141 0.00174 0.00216 0.00264 0.00269 0.00229 0.00157 | 3.5 3.2 2.8 2.5 3.2 4.0 4.9 5.0 4.2 2.8 1.8 1.7 | 440 390 340 292 245 340 465 607 622 505 291 153 135 | 459 403 348 294 403 544 703 721 588 347 189 168 | 46 47 48 48 48 49 50 50 51 51 | 186 178 170 162 154 146 138 130 123 115 107 99 |
| 1110.0 1120.0 1130.0 1140.0 1150.0 1160.0 1170.0 1180.0 1190.0 1200.0 1210.0 1220.0 | 71.3 65.3 59.1 53.1 47.0 59.1 74.4 91.8 93.8 79.2 53.0 34.2 | 0.0 0.0 0.0 0.0 0.0 0.0 0.0 0.0 0.0 0.0 | 65.3 59.1 53.1 47.0 59.1 74.4 91.8 93.8 79.2 53.0 34.2 31.5 | 94.6 85.9 77.3 68.6 85.9 107.6 132.4 135.2 114.5 77.2 50.4 46.6 | 0.00191 0.00174 0.00158 0.00141 0.00216 0.00264 0.00269 0.00229 0.00157 0.00106 | 3.5 3.2 2.8 2.5 3.2 4.0 4.9 5.0 4.2 2.8 1.8 1.7 | 440 390 340 292 245 340 465 607 622 505 291 153 135 | 459 403 348 294 403 544 703 721 588 347 189 | 46 47 48 48 48 49 50 50 51 51 | 186 178 170 162 154 146 138 130 123 115 107 99 |
| 1110.0 1120.0 1130.0 1140.0 1150.0 1160.0 1170.0 1180.0 1190.0 1200.0 1210.0 1220.0 1230.0 | 71.3 65.3 59.1 53.1 47.0 59.1 74.4 91.8 93.8 79.2 53.0 34.2 31.5 23.3 | 0.0 0.0 0.0 0.0 0.0 0.0 0.0 0.0 0.0 0.0 | 65.3 59.1 53.1 47.0 59.1 74.4 91.8 93.8 79.2 53.0 34.2 31.5 23.3 | 94.6 85.9 77.3 68.6 85.9 107.6 132.4 135.2 114.5 77.2 50.4 46.6 35.0 | 0.00191 0.00174 0.00158 0.00141 0.00216 0.00264 0.00269 0.00229 0.00157 0.00106 0.00098 0.00076 | 3.5 3.2 2.8 2.5 3.2 4.0 4.9 5.0 4.2 2.8 1.8 1.7 1.3 | 440 390 340 292 245 340 465 607 622 505 291 153 135 86 | 459 403 348 294 403 544 703 721 588 347 189 168 111 | 46 47 48 48 49 49 50 50 51 51 51 | 186 178 170 162 154 146 138 130 123 115 107 99 91 |
| 1110.0 1120.0 1130.0 1140.0 1150.0 1160.0 1170.0 1180.0 1190.0 1200.0 1210.0 1220.0 1220.0 1230.0 1240.0 | 71.3 65.3 59.1 53.1 47.0 59.1 74.4 91.8 93.8 79.2 53.0 34.2 31.5 23.3 16.7 | 0.0 0.0 0.0 0.0 0.0 0.0 0.0 0.0 0.0 0.0 | 65.3 59.1 53.1 47.0 59.1 74.4 91.8 93.8 79.2 53.0 34.2 31.5 23.3 16.7 | 94.6 85.9 77.3 68.6 85.9 107.6 132.4 135.2 114.5 77.2 50.4 46.6 35.0 25.5 | 0.00191 0.00174 0.00158 0.00141 0.00216 0.00264 0.00269 0.00229 0.00157 0.00106 0.00098 0.00076 0.00058 | 3.5 3.2 2.8 2.5 3.2 4.0 4.9 5.0 4.2 2.8 1.8 1.7 1.3 0.9 | 440 390 340 292 245 340 465 607 622 505 291 153 135 86 52 | 459 403 348 294 403 544 703 721 588 347 189 168 111 70 | 46 47 48 48 49 49 50 50 51 51 51 52 | 186 178 170 162 154 146 138 130 123 115 107 99 91 83 |
| 1110.0 1120.0 1130.0 1140.0 1150.0 1160.0 1170.0 1180.0 1190.0 1200.0 1210.0 1220.0 1220.0 1230.0 1240.0 1250.0 | 71.3 65.3 59.1 53.1 47.0 59.1 74.4 91.8 93.8 79.2 53.0 34.2 31.5 23.3 16.7 12.8 | 0.0 0.0 0.0 0.0 0.0 0.0 0.0 0.0 0.0 0.0 | 65.3 59.1 53.1 47.0 59.1 74.4 91.8 93.8 79.2 53.0 34.2 31.5 23.3 16.7 12.8 | 94.6 85.9 77.3 68.6 85.9 107.6 132.4 135.2 114.5 77.2 50.4 46.6 35.0 25.5 20.0 | 0.00191 0.00174 0.00158 0.00141 0.00216 0.00264 0.00269 0.00229 0.00157 0.00106 0.00098 0.00076 0.00058 0.00047 | 3.5 3.2 2.8 2.5 3.2 4.0 4.9 5.0 4.2 2.8 1.8 1.7 1.3 0.9 0.7 | 440 390 340 292 245 340 465 607 622 505 291 153 135 86 52 35 | 459 403 348 294 403 544 703 721 588 347 189 168 111 70 49 | 46 47 48 48 49 49 50 50 51 51 51 52 52 | 186 178 170 162 154 146 138 130 123 115 107 99 91 83 75 |
| 1110.0 1120.0 1130.0 1140.0 1150.0 1160.0 1170.0 1180.0 1190.0 1200.0 1210.0 1220.0 1220.0 1230.0 1240.0 | 71.3 65.3 59.1 53.1 47.0 59.1 74.4 91.8 93.8 79.2 53.0 34.2 31.5 23.3 16.7 | 0.0 0.0 0.0 0.0 0.0 0.0 0.0 0.0 0.0 0.0 | 65.3 59.1 53.1 47.0 59.1 74.4 91.8 93.8 79.2 53.0 34.2 31.5 23.3 16.7 | 94.6 85.9 77.3 68.6 85.9 107.6 132.4 135.2 114.5 77.2 50.4 46.6 35.0 25.5 | 0.00191 0.00174 0.00158 0.00141 0.00216 0.00264 0.00269 0.00229 0.00157 0.00106 0.00098 0.00076 0.00058 | 3.5 3.2 2.8 2.5 3.2 4.0 4.9 5.0 4.2 2.8 1.8 1.7 1.3 0.9 | 440 390 340 292 245 340 465 607 622 505 291 153 135 86 52 | 459 403 348 294 403 544 703 721 588 347 189 168 111 70 | 46 47 48 48 49 49 50 50 51 51 51 52 | 186 178 170 162 154 146 138 130 123 115 107 99 91 83 |
| 1110.0 1120.0 1130.0 1140.0 1150.0 1160.0 1170.0 1180.0 1190.0 1200.0 1210.0 1220.0 1220.0 1230.0 1240.0 1250.0 1260.0 | 71.3 65.3 59.1 53.1 47.0 59.1 74.4 91.8 93.8 79.2 53.0 34.2 31.5 23.3 16.7 12.8 5.1 | 0.0 0.0 0.0 0.0 0.0 0.0 0.0 0.0 0.0 0.0 | 65.3 59.1 53.1 47.0 59.1 74.4 91.8 93.8 79.2 53.0 34.2 31.5 23.3 16.7 12.8 5.1 | 94.6 85.9 77.3 68.6 85.9 107.6 132.4 135.2 114.5 77.2 50.4 46.6 35.0 25.5 20.0 9.0 | 0.00191 0.00174 0.00158 0.00141 0.00216 0.00264 0.00269 0.00229 0.00157 0.00106 0.00098 0.00076 0.00058 0.00047 0.00026 | 3.5 3.2 2.8 2.5 3.2 4.0 4.9 5.0 4.2 2.8 1.8 1.7 1.3 0.9 0.7 0.3 | 440 390 340 292 245 340 465 607 622 505 291 153 135 86 52 35 88 | 459 403 348 294 403 544 703 721 588 347 189 168 111 70 49 13 | 46 47 48 48 49 50 50 51 51 51 51 52 52 53 | 186 178 170 162 154 146 138 130 123 115 107 99 91 83 75 67 |
| 1110.0 1120.0 1130.0 1140.0 1150.0 1160.0 1170.0 1180.0 1190.0 1200.0 1210.0 1220.0 1220.0 1230.0 1240.0 1250.0 1260.0 1270.0 | 71.3 65.3 59.1 53.1 47.0 59.1 74.4 91.8 93.8 79.2 53.0 34.2 31.5 23.3 16.7 12.8 5.1 0.0 | 0.0 0.0 0.0 0.0 0.0 0.0 0.0 0.0 0.0 0.0 | 65.3 59.1 53.1 47.0 59.1 74.4 91.8 93.8 79.2 53.0 34.2 31.5 23.3 16.7 12.8 5.1 0.0 | 94.6 85.9 77.3 68.6 85.9 107.6 132.4 135.2 114.5 77.2 50.4 46.6 35.0 25.5 20.0 9.0 1.8 | 0.00191 0.00174 0.00158 0.00141 0.00216 0.00264 0.00269 0.00229 0.00157 0.00106 0.00098 0.00076 0.00058 0.00047 0.00026 0.00012 | 3.5 3.2 2.8 2.5 3.2 4.0 4.9 5.0 4.2 2.8 1.8 1.7 1.3 0.9 0.7 0.3 0.3 | 440 390 340 292 245 340 465 607 622 505 291 153 135 86 52 35 88 2 | 459 403 348 294 403 544 703 721 588 347 189 168 111 70 49 13 2 | 46 47 48 48 49 50 50 51 51 51 51 52 52 53 53 | 186 178 170 162 154 146 138 130 123 115 107 99 91 83 75 67 59 |
| 1110.0 1120.0 1130.0 1140.0 1150.0 1160.0 1170.0 1180.0 1190.0 1200.0 1210.0 1220.0 1220.0 1230.0 1240.0 1250.0 1260.0 | 71.3 65.3 59.1 53.1 47.0 59.1 74.4 91.8 93.8 79.2 53.0 34.2 31.5 23.3 16.7 12.8 5.1 | 0.0 0.0 0.0 0.0 0.0 0.0 0.0 0.0 0.0 0.0 | 65.3 59.1 53.1 47.0 59.1 74.4 91.8 93.8 79.2 53.0 34.2 31.5 23.3 16.7 12.8 5.1 | 94.6 85.9 77.3 68.6 85.9 107.6 132.4 135.2 114.5 77.2 50.4 46.6 35.0 25.5 20.0 9.0 | 0.00191 0.00174 0.00158 0.00141 0.00216 0.00264 0.00269 0.00229 0.00157 0.00106 0.00098 0.00076 0.00058 0.00047 0.00026 | 3.5 3.2 2.8 2.5 3.2 4.0 4.9 5.0 4.2 2.8 1.8 1.7 1.3 0.9 0.7 0.3 | 440 390 340 292 245 340 465 607 622 505 291 153 135 86 52 35 88 | 459 403 348 294 403 544 703 721 588 347 189 168 111 70 49 13 | 46 47 48 48 49 50 50 51 51 51 51 52 52 53 | 186 178 170 162 154 146 138 130 123 115 107 99 91 83 75 67 |

| | | Spreadsheet Calcpad | | Pro | ject |
|--|---|---|---------------------------------------|--|--|
| | (Macros mus | t be enabled. Ctrl+Alt+F9 recald | culates.) | | . 731-153 |
| | | | , | Prepared | Date |
| W waterman | WIE12 | 731-153_White Cross Phase | 2 | LP | 18-Jul-23 |
| | | DD Option - Hydrofracture Ca | | Checked | Date |
| | | | | CG | 19-Jul-23 |
| $Q = \frac{(\sigma o.s)}{\sigma}$ | $max + U$ $(Pf + c. cot\emptyset).$ $\frac{sin\emptyset + c.cos\emptyset}{G}$ $1 + sin\emptyset) + c.$ | $\left(\frac{Ro}{Rpmax}\right)^{2} + Q \begin{cases} \frac{-\sin\theta}{1+\sin\theta} \\ -\cos\theta \end{cases}$ | c.cotØ | Eqn(1) Eqn(2) Eqn(3) Eqn(4) Eqn(5) | |
| U Pemax σ _o φ c Ro Rpmax G E N | initial effective st internal angle of f cohesion internal radius of | ole effective mud pressure ess riction borehole ole radius of plastic zone | | | |
| Density of wa Density of drilling n Soil der Cohes Friction Pois Elasticity mo | hud (kg/m3): γm hsity (kg/m ³): γs hsion (kN/m ²): Coh angle (deg): Φ hsion's ratio : ν | 9.81 1000 1300 1950 2 25 Radians Φr = 0. 0.3 40000 15385 | 4363 | are all as | |
| Drill bit dian Drill pipe Initial radius of b | e OD (inch): | 12.00 inch Di (|).610 m).305 m Il bit diameter | feasibility Rpmax u between | rs assumed at / stage. Isually assumed 1/2 and 2/3 depth I 1/2 as worst case |
| Consider lateral s Passive coe | fficient ko = IF(Y_N = | Use drop-down to sel 'Yes", 1 - SIN(Φr), 0) ", 1 - SIN(0.43633), 0) | ect Y/N | | ative to not lateral soil s |

| Annular pressure calculations | | | | |
|---|--|--------------------------|------------------------|-----------------------------------|
| Darcy Weisbach equation for flow in an annulus is diameter, V the flow velocity, L flow pipe length an circular pipes Dh = Do - Di. The exact drilling oper some estimated values have been applied - but re the static head. | d f is a friction fac rational paramete | tor. In the ors, such as | case of c flow rate | co-centered e are unknown, but |
| Assumed flow velocity (m/s): V | 0.50 | | | |
| Assumed friction coefficient: f | 1.00 | | | |
| Summary Figures | | | | |
| Elevation of entrance hole mOD = | 8.74 mOD | | | |
| Elevation of exit hole mOD = | 12.74 mOD | Diff = | -4.00 | m |
| Maximum cover to HDD borehole = | 18.8 m | | | |
| Maximum overburden pressure = | 175.2 kN/m ² | | 1.8 | Bar |
| Maximum safe effective stress Pemax = | 1164 kN/m ² | | 11.6 | Bar |
| Maximum safe stress Pmax = | 1348 kN/m ³ | | 13.5 | Bar |
| | | | | |



2

Expressions used in hydrofracture calculations

In the tabulation below the following functions are applied

Saturated Layer **Sat'd**: IF (WTL<=HDD, Elevn-HDD, Max(Elevn-WTL, 0))

Bouyant Layer **Bou't**: IF (WTL<=HDD, 0, Min(WTL-HDD, Elevn-HDD))

 $\sigma v = (\gamma s^*Satd + (\gamma s - \gamma w)^*Bout)^*g/1000$

 $\sigma o = SQRT((\gamma s*Satd+(\gamma s-\gamma w)*Bout)^2 + (ko * (\gamma s*Satd + (\gamma s-\gamma w)*Bout))^2))$

 $\mathbf{Q} = (\sigma o^* SIN(\Phi r) + Coh^* COS(\Phi r)) / Gmod$

Pf = $(\sigma o^* (1+SIN(\Phi r))) + (Coh^* COS(\Phi r))$


LAT

Pemax = (Pf + Coh*COT(Φ r)) * (((Ro/Rpmax)^2 + Q)^(-SIN(Φ r)/(1+SIN(Φ r)))) - Coh*COT(Φ r)

 $\label{eq:Pelim} \textbf{Pelim} = (Pf + Coh^*COT(\Phi r)) \ * \ (\ Q^{(-SIN(\Phi r)/(1+SIN(\Phi r)))}) - Coh^*COT(\Phi r)$

| WT d | controls: | 0 | -4.89 | | | | | | | |
|--------|-----------|-------|-------|--------|--------|-------|-------|-------|-------|-------|
| Dist | Elev'n | Loc'n | WTL | C-Line | Soffit | Cover | Sat'd | Bou't | U | Hs |
| (m) | (mOD) | LOCI | (mOD) | (mOD) | (mOD) | (m) | (m) | (m) | kN/m2 | kN/m3 |
| 0.00 | 8.74 | | 8.74 | 8.76 | 9.06 | 0.00 | 0.00 | 0.00 | 0 | 0 |
| 10.00 | 8.57 | | 8.57 | 7.96 | 8.26 | 0.31 | 0.00 | 0.31 | 3 | 6 |
| 20.00 | 10.51 | | 10.51 | 7.15 | 7.46 | 3.06 | 0.00 | 3.06 | 30 | 16 |
| 30.00 | 9.75 | | 9.75 | 6.35 | 6.66 | 3.09 | 0.00 | 3.09 | 30 | 27 |
| 40.00 | 8.54 | | 8.54 | 5.55 | 5.85 | 2.69 | 0.00 | 2.69 | 26 | 37 |
| 50.00 | 10.02 | | 10.02 | 4.75 | 5.05 | 4.97 | 0.00 | 4.97 | 49 | 47 |
| 60.00 | 11.08 | | 11.08 | 3.94 | 4.25 | 6.83 | 0.00 | 6.83 | 67 | 57 |
| 70.00 | 10.85 | | 10.85 | 3.14 | 3.45 | 7.40 | 0.00 | 7.40 | 73 | 68 |
| 80.00 | 11.00 | | 11.00 | 2.34 | 2.64 | 8.35 | 0.00 | 8.35 | 82 | 78 |
| 90.00 | 12.77 | | 12.77 | 1.54 | 1.84 | 10.93 | 0.00 | 10.93 | 107 | 88 |
| 100.00 | 12.76 | | 12.76 | 0.74 | 1.04 | 11.72 | 0.00 | 11.72 | 115 | 98 |
| 110.00 | 12.94 | | 12.94 | -0.04 | 0.26 | 12.68 | 0.00 | 12.68 | 124 | 108 |
| 120.00 | 13.76 | | 13.76 | -0.69 | -0.39 | 14.15 | 0.00 | 14.15 | 139 | 116 |
| 130.00 | 14.51 | | 14.51 | -1.21 | -0.91 | 15.42 | 0.00 | 15.42 | 151 | 123 |
| 140.00 | 14.02 | | 14.02 | -1.60 | -1.29 | 15.32 | 0.00 | 15.32 | 150 | 128 |
| 150.00 | 13.74 | | 13.74 | -1.85 | -1.54 | 15.28 | 0.00 | 15.28 | 150 | 131 |
| 160.00 | 13.45 | | 13.45 | -1.97 | -1.66 | 15.12 | 0.00 | 15.12 | 148 | 133 |
| 170.00 | 13.89 | | 13.89 | -1.96 | -1.65 | 15.54 | 0.00 | 15.54 | 152 | 133 |
| 180.00 | 12.44 | | 12.44 | -1.90 | -1.59 | 14.03 | 0.00 | 14.03 | 138 | 132 |
| 190.00 | 9.00 | | 9.00 | -1.84 | -1.53 | 10.53 | 0.00 | 10.53 | 103 | 131 |
| 200.00 | 8.00 | | 8.00 | -1.78 | -1.48 | 9.47 | 0.00 | 9.47 | 93 | 130 |
| 210.00 | 7.88 | | 7.88 | -1.72 | -1.42 | 9.30 | 0.00 | 9.30 | 91 | 130 |
| 220.00 | 7.98 | | 7.98 | -1.67 | -1.36 | 9.34 | 0.00 | 9.34 | 92 | 129 |
| 230.00 | 7.91 | | 7.91 | -1.61 | -1.30 | 9.21 | 0.00 | 9.21 | 90 | 128 |
| 240.00 | 8.07 | | 8.07 | -1.55 | -1.25 | 9.31 | 0.00 | 9.31 | 91 | 127 |
| 250.00 | 8.26 | | 8.26 | -1.49 | -1.19 | 9.45 | 0.00 | 9.45 | 93 | 127 |
| 260.00 | 8.20 | | 8.20 | -1.44 | -1.13 | 9.33 | 0.00 | 9.33 | 92 | 126 |
| 270.00 | 8.14 | | 8.14 | -1.38 | -1.07 | 9.21 | 0.00 | 9.21 | 90 | 125 |
| 280.00 | 8.02 | | 8.02 | -1.32 | -1.02 | 9.04 | 0.00 | 9.04 | 89 | 124 |
| 290.00 | 8.26 | | 8.26 | -1.26 | -0.96 | 9.22 | 0.00 | 9.22 | 90 | 124 |
| 300.00 | 8.41 | | 8.41 | -1.21 | -0.90 | 9.31 | 0.00 | 9.31 | 91 | 123 |
| 310.00 | 8.76 | | 8.76 | -1.15 | -0.84 | 9.60 | 0.00 | 9.60 | 94 | 122 |
| 320.00 | 10.49 | | 10.49 | -1.09 | -0.79 | 11.27 | 0.00 | 11.27 | 111 | 122 |
| 330.00 | 11.90 | | 11.90 | -1.03 | -0.73 | 12.63 | 0.00 | 12.63 | 124 | 121 |
| 340.00 | 12.39 | | 12.39 | -0.97 | -0.67 | 13.05 | 0.00 | 13.05 | 128 | 120 |
| 350.00 | 15.46 | | 15.46 | -0.92 | -0.61 | 16.07 | 0.00 | 16.07 | 158 | 119 |
| 360.00 | 15.16 | | 15.16 | -0.86 | -0.55 | 15.72 | 0.00 | 15.72 | 154 | 119 |
| 370.00 | 13.92 | | 13.92 | -0.80 | -0.50 | 14.42 | 0.00 | 14.42 | 141 | 118 |
| 380.00 | 15.37 | | 15.37 | -0.74 | -0.44 | 15.80 | 0.00 | 15.80 | 155 | 117 |
| 390.00 | 12.59 | | 12.59 | -0.69 | -0.38 | 12.97 | 0.00 | 12.97 | 127 | 116 |
| 400.00 | 12.26 | | 12.26 | -0.63 | -0.32 | 12.58 | 0.00 | 12.58 | 123 | 116 |
| 410.00 | 12.22 | | 12.22 | -0.57 | -0.27 | 12.49 | 0.00 | 12.49 | 122 | 115 |
| 420.00 | 12.36 | | 12.36 | -0.51 | -0.21 | 12.57 | 0.00 | 12.57 | 123 | 114 |
| 430.00 | 12.43 | | 12.43 | -0.46 | -0.15 | 12.58 | 0.00 | 12.58 | 123 | 113 |
| 440.00 | 12.58 | | 12.58 | -0.40 | -0.09 | 12.67 | 0.00 | 12.67 | 124 | 113 |
| 450.00 | 13.17 | | 13.17 | -0.34 | -0.04 | 13.20 | 0.00 | 13.20 | 129 | 112 |
| 460.00 | 13.70 | | 13.70 | -0.28 | 0.02 | 13.67 | 0.00 | 13.67 | 134 | 111 |
| 470.00 | 14.03 | | 14.03 | -0.23 | 0.08 | 13.95 | 0.00 | 13.95 | 137 | 110 |
| 480.00 | 14.14 | | 14.14 | -0.17 | 0.14 | 14.00 | 0.00 | 14.00 | 137 | 110 |
| 490.00 | 14.14 | | 14.14 | -0.11 | 0.20 | 13.94 | 0.00 | 13.94 | 137 | 109 |
| 500.00 | 14.27 | | 14.27 | -0.05 | 0.25 | 14.02 | 0.00 | 14.02 | 137 | 108 |
| 510.00 | 14.31 | | 14.31 | 0.01 | 0.31 | 14.00 | 0.00 | 14.00 | 137 | 108 |
| 520.00 | 14.39 | | 14.39 | 0.06 | 0.37 | 14.02 | 0.00 | 14.02 | 138 | 107 |

| 530.00 | 14.00 | 14.00 | 0.12 | 0.43 | 13.57 | 0.00 | 13.57 | 133 | 106 |
|---------|-------|-------|-------|-------|-------|------|-------|-----|-----------|
| 540.00 | 13.94 | 13.94 | 0.18 | 0.48 | 13.45 | 0.00 | 13.45 | 132 | 105 |
| 550.00 | 13.46 | 13.46 | 0.24 | 0.54 | 12.92 | 0.00 | 12.92 | 127 | 105 |
| 560.00 | 13.52 | 13.52 | 0.29 | 0.60 | 12.92 | 0.00 | 12.92 | 127 | 104 |
| 570.00 | 13.05 | 13.05 | 0.35 | 0.66 | 12.39 | 0.00 | 12.39 | 122 | 103 |
| 580.00 | 13.07 | 13.07 | 0.41 | 0.71 | 12.36 | 0.00 | 12.36 | 121 | 102 |
| 590.00 | 14.10 | 14.10 | 0.47 | 0.77 | 13.33 | 0.00 | 13.33 | 131 | 102 |
| 600.00 | 13.63 | 13.63 | 0.53 | 0.83 | 12.80 | 0.00 | 12.80 | 126 | 101 |
| 610.00 | 13.74 | 13.74 | 0.85 | 1.16 | 12.58 | 0.00 | 12.58 | 123 | 97 |
| 620.00 | 13.85 | 13.85 | 0.64 | 0.94 | 12.91 | 0.00 | 12.91 | 127 | 99 |
| 630.00 | 14.25 | 14.25 | 0.70 | 1.00 | 13.25 | 0.00 | 13.25 | 130 | 99 |
| 640.00 | 14.37 | 14.37 | 0.76 | 1.06 | 13.31 | 0.00 | 13.31 | 131 | 98 |
| 650.00 | 14.49 | 14.49 | 0.81 | 1.12 | 13.38 | 0.00 | 13.38 | 131 | 97 |
| 660.00 | 14.65 | 14.65 | 0.87 | 1.18 | 13.47 | 0.00 | 13.47 | 132 | 97 |
| 670.00 | 14.80 | 14.80 | 0.93 | 1.23 | 13.56 | 0.00 | 13.56 | 133 | 96 |
| 680.00 | 14.93 | 14.93 | 0.99 | 1.29 | 13.64 | 0.00 | 13.64 | 134 | 95 |
| 690.00 | 14.88 | 14.88 | 1.04 | 1.35 | 13.53 | 0.00 | 13.53 | 133 | 94 |
| 700.00 | 16.15 | 16.15 | 1.10 | 1.41 | 14.75 | 0.00 | 14.75 | 145 | 94 |
| 710.00 | 18.46 | 18.46 | 1.16 | 1.46 | 16.99 | 0.00 | 16.99 | 167 | 93 |
| 720.00 | 17.08 | 17.08 | 1.22 | 1.52 | 15.56 | 0.00 | 15.56 | 153 | 92 |
| 730.00 | 15.81 | 15.81 | 1.28 | 1.58 | 14.23 | 0.00 | 14.23 | 140 | 91 |
| 740.00 | 15.87 | 15.87 | 1.33 | 1.64 | 14.24 | 0.00 | 14.24 | 140 | 91 |
| 750.00 | 17.07 | 17.07 | 1.39 | 1.69 | 15.37 | 0.00 | 15.37 | 151 | 90 |
| 760.00 | 17.30 | 17.30 | 1.45 | 1.75 | 15.55 | 0.00 | 15.55 | 153 | 89 |
| 770.00 | 18.43 | 18.43 | 1.51 | 1.81 | 16.62 | 0.00 | 16.62 | 163 | 88 |
| 780.00 | 16.65 | 16.65 | 1.56 | 1.87 | 14.78 | 0.00 | 14.78 | 145 | 88 |
| 790.00 | 15.13 | 15.13 | 1.62 | 1.93 | 13.21 | 0.00 | 13.21 | 130 | 87 |
| 800.00 | 15.30 | 15.30 | 1.68 | 1.98 | 13.32 | 0.00 | 13.32 | 131 | 86 |
| 810.00 | 15.21 | 15.21 | 1.74 | 2.04 | 13.17 | 0.00 | 13.17 | 129 | 85 |
| 820.00 | 15.41 | 15.41 | 1.79 | 2.10 | 13.31 | 0.00 | 13.31 | 131 | 85 |
| 830.00 | 15.58 | 15.58 | 1.85 | 2.16 | 13.43 | 0.00 | 13.43 | 132 | 84 |
| 840.00 | 15.10 | 15.10 | 1.91 | 2.21 | 12.89 | 0.00 | 12.89 | 126 | 83 |
| 850.00 | 14.36 | 14.36 | 1.97 | 2.27 | 12.09 | 0.00 | 12.09 | 119 | 83 |
| 860.00 | 14.49 | 14.49 | 2.02 | 2.33 | 12.16 | 0.00 | 12.16 | 119 | 82 |
| 870.00 | 14.44 | 14.44 | 2.08 | 2.39 | 12.05 | 0.00 | 12.05 | 118 | 81 |
| 880.00 | 14.67 | 14.67 | 2.14 | 2.44 | 12.23 | 0.00 | 12.23 | 120 | 80 |
| 890.00 | 14.32 | 14.32 | 2.20 | 2.50 | 11.82 | 0.00 | 11.82 | 116 | 80 |
| 900.00 | 14.55 | 14.55 | 2.26 | 2.56 | 11.99 | 0.00 | 11.99 | 118 | 79 |
| 910.00 | 16.95 | 16.95 | 2.31 | 2.62 | 14.33 | 0.00 | 14.33 | 141 | 78 |
| 920.00 | 18.73 | 18.73 | 2.37 | 2.67 | 16.06 | 0.00 | 16.06 | 158 | 77 |
| 930.00 | 18.61 | 18.61 | 2.43 | 2.73 | 15.88 | 0.00 | 15.88 | 156 | 77 |
| 940.00 | 16.85 | 16.85 | 2.49 | 2.79 | 14.06 | 0.00 | 14.06 | 138 | 76 |
| 950.00 | 18.81 | 18.81 | 2.54 | 2.85 | 15.96 | 0.00 | 15.96 | 157 | 75 |
| 960.00 | 21.09 | 21.09 | 2.60 | 2.91 | 18.18 | 0.00 | 18.18 | 178 | 74 |
| 970.00 | 21.76 | 21.76 | 2.66 | 2.96 | 18.80 | 0.00 | 18.80 | 184 | 74 |
| 980.00 | 20.88 | 20.88 | 2.72 | 3.02 | 17.86 | 0.00 | 17.86 | 175 | 73 |
| 990.00 | 18.54 | 18.54 | 2.77 | 3.08 | 15.46 | 0.00 | 15.46 | 152 | 72 |
| 1000.00 | 16.76 | 16.76 | 2.83 | 3.14 | 13.62 | 0.00 | 13.62 | 134 | 71 |
| 1010.00 | 16.55 | 16.55 | 2.89 | 3.19 | 13.36 | 0.00 | 13.36 | 131 | 71 |
| 1020.00 | 16.34 | 16.34 | 2.95 | 3.25 | 13.08 | 0.00 | 13.08 | 128 | 70 |
| 1030.00 | 16.16 | 16.16 | 3.01 | 3.31 | 12.85 | 0.00 | 12.85 | 126 | 69 |
| 1040.00 | 15.99 | 15.99 | 3.07 | 3.37 | 12.62 | 0.00 | 12.62 | 124 | 68 |
| 1050.00 | 14.43 | 14.43 | 3.22 | 3.53 | 10.90 | 0.00 | 10.90 | 107 | 66 |
| 1060.00 | 13.82 | 13.82 | 3.52 | 3.82 | 10.00 | 0.00 | 10.00 | 98 | 63 |
| 1070.00 | 13.33 | 13.33 | 3.94 | 4.24 | 9.09 | 0.00 | 9.09 | 89 | 57 |
| 1080.00 | 13.35 | 13.35 | 4.50 | 4.80 | 8.55 | 0.00 | 8.55 | 84 | 50 |
| 1090.00 | 13.62 | 13.62 | 5.19 | 5.49 | 8.13 | 0.00 | 8.13 | 80 | 41 |
| 1100.00 | 13.76 | 13.76 | 6.01 | 6.31 | 7.45 | 0.00 | 7.45 | 73 | 31 |
| 1110.00 | 13.96 | 13.96 | 6.88 | 7.18 | 6.78 | 0.00 | 6.78 | 66 | 20 |
| 1120.00 | 15.10 | 15.10 | 7.75 | 8.05 | 7.04 | 0.00 | 7.04 | 69 | 9 |
| 1130.00 | 14.11 | 14.11 | 8.62 | 8.93 | 5.19 | 0.00 | 5.19 | 51 | 0 |
| 1140.00 | 13.30 | 13.30 | 9.49 | 9.80 | 3.50 | 0.00 | 3.50 | 34 | 0 |
| 1150.00 | 13.10 | 13.10 | 10.36 | 10.67 | 2.43 | 0.00 | 2.43 | 24 | 0 |
| 1160.00 | 12.95 | 12.95 | 11.23 | 11.54 | 1.41 | 0.00 | 1.41 | 14 | 0 |
| 1170.00 | 12.80 | 12.80 | 12.10 | 12.41 | 0.39 | 0.00 | 0.39 | 4 | 0 |
| 1177.00 | 12.74 | 12.74 | 12.69 | 13.00 | 0.00 | 0.00 | 0.00 | 0 | 0 |



Distance from entry point (m)

| Dist | σν | σh | σο | Pf | Q | Rpmax | | Pmax | Hf | н | The pressure calculations |
|----------------|----------------|------------|----------------|----------------------|--------------------|------------|------------|--------------|----------------------|------------|---|
| (m) | (kN/m²) | (kN/m²) | (kN/m²) | (kN/m ²) | ~ | (m) | (kN/m²) | (kN/m²) | (kN/m ²) | (kN/m²) | are set out in this table. |
| 0.0 | 0.0 | 0.0 | 0.0 | 1.8 | 0.00012 | 0.3 | 2 | 2 | 0 | 0 | Note that Rpmax varies as it is set to be a |
| 10.0 | 2.9 | 0.0 | 2.9 | 5.9 | 0.00020 | 0.2 | 3 | 6 | 0 | 7 | proportion of the cover |
| 20.0 | 28.5 | 0.0 | 28.5 | 42.3 | 0.00090 | 1.5 | 116 | 146 | 1 | 17 | depth. |
| 30.0 | 28.8 | 0.0 | 28.8 | 42.8 | 0.00091 | 1.5 | 118 | 149 | 1 | 28 | , |
| 40.0 | 25.1 | 0.0 | 25.1 | 37.5 | 0.00081 | 1.3 | 96 | 122 | 2 | 39 | Hf is a rough estimate of |
| 50.0 | 46.3 | 0.0 | 46.3 | 67.7 | 0.00139 | 2.5 | 239 | 288 | 2 | 49 | the drilling mud pressure in |
| 60.0 | 63.7 | 0.0 | 63.7 | 92.4 | 0.00187 | 3.4 | 377 | 444 | 3 | 60 | the return annular flow. |
| 70.0 | 69.0 | 0.0 | 69.0 | 99.9 | 0.00201 | 3.7 | 421 | 494 | 3 | 70 | The total head H is the |
| 80.0 | 77.8 | 0.0 | 77.8 | 112.6 | 0.00226 | 4.2 | 494 | 576 | 3 | 81 | The total head H is the static head Hs (table |
| 90.0 | 101.8 | 0.0 | 101.8 | 146.7 | 0.00292 | 5.5 | 685 | 792 | 4 | 92 | above) and Hf . |
| 100.0 | 109.2 | 0.0 | 109.2 | 157.1 | 0.00312 | 5.9 | 740 | 855 | 4 | 102 | |
| 110.0 | 118.2 | 0.0 | 118.2 | 169.9 | 0.00336 | 6.3 | 805 | 930 | 5 | 113 | |
| 120.0 | 131.9 | 0.0 | 131.9 | 189.4 | 0.00374 | 7.1 | 900 | 1039 | 5 | 121 | |
| 130.0 | 143.7 | 0.0 | 143.7 | 206.2 | 0.00406 | 7.7 | 977 | 1128 | 5 | 128 | |
| 140.0 | 142.7 | 0.0 | 142.7 | 204.9 | 0.00404 | 7.7 | 970 | 1120 | 6 | 134 | |
| 150.0 | 142.4 | 0.0 | 142.4 | 204.4 | 0.00403 | 7.6 | 969 | 1118 | 6 | 137 | |
| 160.0 | 142.4 | 0.0 | 140.9 | 204.4 | 0.00399 | 7.6 | 959 | 1107 | 7 | 139 | |
| 170.0 | 144.8 | 0.0 | 144.8 | 202.2 | 0.00410 | 7.8 | 984 | 1136 | 7 | 140 | |
| 180.0 | 130.7 | 0.0 | 130.7 | 187.8 | 0.00371 | 7.0 | 892 | 1030 | 8 | 139 | |
| 190.0 | 98.1 | 0.0 | 98.1 | 141.4 | 0.00281 | 5.3 | 656 | 760 | 8 | 139 | |
| 210.0 | 86.7 | 0.0 | 86.7 | 125.1 | 0.00250 | 4.7 | 566 | 657 | 9 | 138 | |
| 220.0 | 87.0 | 0.0 | 87.0 | 125.6 | 0.00251 | 4.7 | 568 | 660 | 9 | 138 | |
| 230.0 | 85.8 | 0.0 | 85.8 | 123.9 | 0.00248 | 4.6 | 559 | 649 | 10 | 138 | |
| 240.0 | 86.8 | 0.0 | 86.8 | 125.3 | 0.00250 | 4.7 | 567 | 658 | 10 | 137 | |
| 250.0 | 88.1 | 0.0 | 88.1 | 127.1 | 0.00254 | 4.7 | 577 | 670 | 10 | 137 | |
| 260.0 | 86.9 85 9 | 0.0 | 86.9 | 125.5 123.9 | 0.00251 | 4.7 | 568 | 659 649 | 11 11 | 137 136 | |
| 270.0 280.0 | 85.8 84.2 | 0.0 0.0 | 85.8 84.2 | 123.9 | 0.00248 0.00243 | 4.6 4.5 | 559 546 | 635 | 12 | 136 | |
| 200.0 | 85.9 | 0.0 | 85.9 | 121.0 | 0.00243 | 4.6 | 559 | 650 | 12 | 136 | |
| 300.0 | 86.7 | 0.0 | 86.7 | 125.2 | 0.00250 | 4.7 | 566 | 657 | 13 | 136 | |
| 310.0 | 89.5 | 0.0 | 89.5 | 129.1 | 0.00258 | 4.8 | 588 | 683 | 13 | 135 | |
| 320.0 | 105.0 | 0.0 | 105.0 | 151.2 | 0.00300 | 5.6 | 709 | 820 | 13 | 135 | |
| 330.0 | 117.7 | 0.0 | 117.7 | 169.2 | 0.00335 | 6.3 | 802 | 926 | 14 | 135 | |
| 340.0 | 121.7 | 0.0 | 121.7 | 174.9 | 0.00346 | 6.5 | 830 | 958 | 14 | 134 | |
| 350.0 | 149.8 | 0.0 | 149.8 | 214.9 | 0.00423 | 8.0 | 1015 | 1172 | 15 | 134 | |
| 360.0 | 146.5 | 0.0 | 146.5 | 210.2 | 0.00414 | 7.9 | 994 | 1148 | 15 | 134 | |
| 370.0 380.0 | 134.4 147.3 | 0.0 0.0 | 134.4 147.3 | 193.0 211.3 | 0.00381 0.00416 | 7.2 7.9 | 916 999 | 1058 1154 | 15 16 | 133 133 | |
| | | ~ ~ | | | | 7.9 6.5 | | | | 133 | |
| 390.0 400.0 | 120.9 117.3 | 0.0 0.0 | 120.9 117.3 | 173.8 168.6 | 0.00344 | 6.3 | 825 799 | 952 922 | 16 17 | 133 | |
| 410.0 | 116.4 | 0.0 | 116.4 | 167.4 | 0.00331 | 6.2 | 792 | 915 | 17 | 132 | |
| 420.0 | 117.1 | 0.0 | 117.1 | 168.5 | 0.00334 | 6.3 | 798 | 921 | 18 | 132 | |
| 430.0 | 117.2 | 0.0 | 117.2 | 168.6 | 0.00334 | 6.3 | 799 | 922 | 18 | 131 | |
| 440.0 | 118.1 | 0.0 | 118.1 | 169.8 | 0.00336 | 6.3 | 805 | 929 | 18 | 131 | |
| 450.0 | 123.0 | 0.0 | 123.0 | 176.8 | 0.00350 | 6.6 | 839 | 969 | 19 | 131 | |
| 460.0 | 127.4 | 0.0 | 127.4 | 183.1 | 0.00362 | 6.8 | 870 | 1004 | 19 | 130 | |
| 470.0 | 130.0 | 0.0 | 130.0 | 186.8 | 0.00369 | 7.0 | 887 | 1024 | 20 | 130 | |
| 480.0 | 130.5 | 0.0 | 130.5 | 187.4 | 0.00370 | 7.0 | 890 | 1028 | 20 | 130 | |
| 490.0 | 129.9 | 0.0 | 129.9 | 186.6 | 0.00369 | 7.0 | 887 | 1023 | 20 | 129 | |
| 500.0 | 130.6 | 0.0 | 130.6 | 187.6 | 0.00371 | 7.0 | 891 | 1029 | 21 | 129 | |
| 510.0 520.0 | 130.5 130.7 | 0.0 0.0 | 130.5 130.7 | 187.4 187.7 | 0.00370 0.00371 | 7.0 7.0 | 890 892 | 1028 1029 | 21 22 | 129 129 | |
| 520.0 | 150.7 | 0.0 | 130.7 | 107.7 | 0.00071 | 1.0 | 092 | 1029 | ~~ | 123 | I |


| Comments | 1170.0 | | | | | | | | | | | | | | | 990.0 14 | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | 620.0 12 | | | | | | 550.0 12 | 540.0 12 | 530.0 12 |
|----------|-------------------------------|---------------------|--------------|---------|----------|----------------------|---------------------|----------|----------|----------|------------|----------------------|------------|----------|----------|----------|----------|----------|----------------------|-------------|----------------------|----------------------|-------------|----------|----------|----------|----------|----------|----------|----------------------|----------------------|----------------------|----------------------|------------|----------|----------|----------|----------|----------|----------------------|----------------------|----------|----------|----------|----------|----------------------|----------------------|----------|----------|----------|----------------------|----------------------|----------|----------|----------|----------|----------|
| i | 3.6 0.0 0.0 0.0 | 22.6 0.0 3.2 0.0 | 32.6 0.0 | 8.3 0.0 | 65.6 0.0 | 69.4 0.0 63.2 0.0 | 75.8 0.0 9.4 0.0 | 79.7 0.0 | 84.7 0.0 | 03.2 0.0 | 01.6 0.0 | 19.8 0.0 17.6 0.0 | 21.9 0.0 | 24.5 0.0 | 27.0 0.0 | 44.1 0.0 | 66.5 0.0 | 75.2 0.0 | 40.0 0.0 69.5 0.0 | 48.8 0.0 | 48.0 0.0 31.0 0.0 | 49.6 0.0 48.0 0.0 | 33.6 0.0 | 11.7 0.0 | 10.1 0.0 | 14.0 0.0 | 12.3 0.0 | 13.3 0.0 | 12.7 0.0 | 20.1 0.0 20.1 0.0 | 24.0 0.0 25.1 0.0 | 22.7 0.0 24.0 0.0 | 24.1 0.0 22.7 0.0 | 23.1 0.0 | 37.7 0.0 | 54.9 0.0 | 44.9 0.0 | 43.3 0.0 | 32.7 0.0 | 45.0 0.0 32.6 0.0 | 58.4 0.0 45.0 0.0 | 37.4 0.0 | 26.1 0.0 | 27.1 0.0 | 26.4 0.0 | 24.7 0.0 25.5 0.0 | 24.0 0.0 24.7 0.0 | 23.4 0.0 | 20.3 0.0 | 17.2 0.0 | 24.2 0.0 19.3 0.0 | 15.2 0.0 24.2 0.0 | 15.5 0.0 | 20.4 0.0 | 20.4 0.0 | 20.4 0.0 | 25.4 0.0 |
| | 3.6 | | | | | | | | 84.7 | | | | | | | 144.1 | | | | 131.0 | 148.0 131.0 | 149.6 148.0 | 133.6 | 111.7 | | 114.0 | 112.3 | | 112.7 | 120.1 | | 122.7 124.0 | 124.1 122.7 | 123.1 | 137.7 | 154.9 | 144.9 | 143.3 | 132.7 | 145.0 | 158.4 145.0 | 137.4 | 126.1 | 127.1 | | 124.7 | 124.0 124.7 | 123.4 | 120.3 | | 124.2 | 115.2 124.2 | 115.5 | 120.4 | 120.4 | 120.4 | 125.4 |
| | 6.9 1.8 | 34.0 20.5 | 48.2 34.0 | 70.6 | 95.2 | 91.7 | 109.6 100.5 | 115.2 | 122.3 | 134.4 | 146.3 | 172.2 169.1 | 175.3 | 178.9 | 182.4 | 206.8 | 238.6 | 251.0 | 242.9 | 213.5 | 212.3 188.2 | 214.7 212.3 | 191.8 | 160.8 | 158.5 | 163.9 | 161.6 | 163.1 | 162.1 | 172.7 | 179.8 | 176.4 178.2 | 178.4 176.4 | 176.9 | 197.7 | 222.2 | 208.0 | 205.6 | 190.6 | 208.1 190.5 | 227.1 208.1 | 197.3 | 181.2 | 182.6 | 181.6 | 179.1 | 178.2 179.1 | 177.4 | 173.0 | 168.6 | 170.5 | 165.7 178.5 | 166.1 | 173.1 | 173.1 | 180.1 | 4004 |
| | 0.00022 0.00012 | 0.00074 0.00048 | 0.00101 | 0.00145 | 0.00100 | 0.00202 | 0.00220 0.00202 | 0.00231 | 0.00244 | 0.00268 | 0.00335 | 0.00341 0.00335 | 0.00347 | 0.00354 | 0.00361 | 0.00408 | 0.00469 | 0.00493 | | 0.00372 | 0.00418 | 0.00423 0.00418 | 0.00379 | 0.00319 | 0.00314 | 0.00325 | 0.00320 | 0.00323 | 0.00321 | 0.00342 | 0.00352 | 0.00349 | 0.00353 0.00349 | 0.00350 | 0.00390 | 0.00437 | 0.00410 | 0.00405 | 0.00376 | 0.00410 | 0.00447 0.00410 | 0.00389 | 0.00358 | 0.00361 | 0.00359 | 0.00354 | 0.00352 0.00354 | 0.00351 | 0.00342 | 0.00334 | 0.00333 | 0.00328 0.00353 | 0.00329 | 0.00343 | 0.00342 | 0.00356 | |
| | 0.2 0.3 | 1.2 0.7 | 1.8 1.2 | 2.6 | 3.5 | 3.7 3.4 | 4.1 3.7 | 4.3 | 4.5 | 5.0 | 0.3 5.5 | 6.4 6.3 | 6.5 | 6.7 | 6.8 | 7.7 | 8.9 | 9.4 | 9.1 | 7.0 8.0 | 7.9 7.0 | 8.0 7.9 | 7.2 | 6.0 | 5.9 | 6.1 | 6.0 | 6.1 | 6.0 | 6.4 | 6.7 | 6.6 6.7 | 6.7 6.6 | 6.6 | 7.4 | 8.3 | 7.8 | 7.7 | 7.1 | 7.0 7.1 | 8.5 7.8 | 7.4 | 6.8 | 6.8 | 6.8 | 6.7 6.7 | 6.7 6.7 | 6.6 | 6.5 | 6.3 | 6.4 | 6.2 6.7 | 6.2 | 6.5 | 6.5 | 6.7 | ~ - |
| | 4 | 83 37 | 143 83 | 255 | 393 | 424 373 | 477 424 | 509 | 550 | 618 | 683 | 817 801 | 832 | 850 | 867 | 979 | 1114 | 1164 | 1132 | 094 1008 | 1003 894 | 1014 1003 | 911 1014 | 759 | 747 | 775 | 763 | 771 | 766 | 819 | 854 | 837 846 | 847 837 | 840 | 938 | 1046 | 984 | 974 | 905 | 965 905 | 1067 985 | 936 | 861 | 868 | 863 | 857 | 846 851 | 842 | 820 | 799 | 813 | 784 848 | 786 | 821 | 821 | 850 | 856 |
| | 8 2 | 50 | 177 106 | 306 | 462 | 497 440 | 557 497 | 593 | 639 | 716 | 923 790 | 943 925 | 960 043 | 981 | 1000 | 1131 | 1289 | 1348 | 1310 | 1032 | 1159 | 1171 1159 | 1052 | 877 | 863 | 895 | 882 | 890 | 884 | 946 | 986 | 966 977 | 978 966 | 969 078 | 1083 | 1209 | 1137 | 1125 | 1045 | 1045 | 1233 1137 | 1081 | 993 | 1001 | 996 | 982 989 | 977 982 | 972 | 947 | 922 | 939 | 905 978 | 908 | 948 | 948 | 988 | 000 |
| | 49 49 | 48 48 | 48 48 | 47 | 47 | 40 46 | 46 46 | 45 | 45 | 44 | 43 44 | 43 43 | 43 | 42 | 42 | 41 | 41 | 41 | 40 40 | 39 40 | 39 39 | 38 39 | 38 | 38 | 37 | 37 | 36 | 36 | 36 | 35 | 34 | 34 34 | 33 34 | 33 22 | 33 | 32 | 32 | 31 | 31 | 30 31 | 30 30 | 29 20 | 29 | 28 | 28 | 27 | 27 27 | 26 | 26 | 26 | 25 | 24 25 | 24 | 23 | 23 | 23 | ~~ |
| | 49 49 | 48 48 | 48 48 | 47 | 56 | 66 | 87 77 | 95 | 102 | 107 | 112 | 112 112 | 113 | 113 | 113 | 114 | 114 | 114 | 115 | 115 | 116 115 | 116 116 | 116 | 116 | 117 | 117 | 117 | 118 | 118 | 118 | 119 | 119 119 | 120 119 | 120 | 120 | 121 | 121 | 121 | 122 | 122 | 123 122 | 123 | 123 | 123 | 124 | 124 | 125 124 | 125 | 125 | 122 | 120 | 127 126 | 127 | 127 | 128 | 128 | |


Comments



| | | Spreadsheet Ca | lcpad | | Pro | ject |
|--|--|---|---|--|--|--|
| | (Macros mus | t be enabled. Ctrl+ | Alt+F9 ree | calculates.) | WIE127 | 731-131 |
| 11) waterman | | | | | Prepared | Date |
| | WIE12 | 731-153_White (| Cross Pha | ase 2 | LP | 26-Jul-23 |
| | | HDD Hydrofractu | | | Checked | Date |
| | | - | | | CG | 27-Jul-23 |
| | ······································ | | | | | - |
| ydrofracture - Longit | udinal Profile Ch | eck | | | | |
| | | | | | | |
| Dere and Dame | | | | | Eam(4) | |
| Pmax = Pem | | R_{0} $)^{2}$ | -sinø | | Eqn(1) | |
| | $f' + c. cot \emptyset$). | $\frac{10}{Rpmax}$) + Q | } - | - c.cotØ | Eqn(2) | |
| $Q = \frac{(\sigma o. \sin \alpha)}{2}$ | 0 | | | | Eqn(3) | |
| | + sinØ) + c.co | sØ | | | Eqn(4) | |
| $G=\frac{E}{2}\left(1+\right.$ | θ) | | | | Eqn(5) | |
| /here: | mavimum alla | | | | | |
| Pmax | maximum allowat | - | | | | |
| U Domax | initial in-situ pore | - | PFOOFO | | | |
| Pemax | maximum allowat | | pressure | | | |
| σο | initial effective str | | | | | |
| ϕ | internal angle of f | riction | | | | |
| С | cohesion | | | | | |
| Ro | internal radius of | | | | | |
| Rpmax | maximum allowat | ole radius of plast | ic zone | | | |
| G | shear modulus | | | | | |
| Ε | elasticity modulus | | | | | |
| Ν | Poisson's ratio | | | | | |
| nly enter data into green h rite the formula. | ighlight cells. Other c | ells may contain ca | lculations | and editing them v | vill over- | |
| eneral variables | | | | | | |
| | vity (m/s/s): g | 9.81 | | | | |
| Density of wate | al (kar/ma 2)) | 1000 | | | | |
| Density of drilling mu | | 1300 | | | | |
| 0 1 1 | ity (kg/m ³): ys | 1950 | | | | acteristic values sumed and |
| | | 2 | | | are an as | SUITED AILD |
| Cohesic | | 25 | . | 0.4000 | should h | e confirmed hv |
| Cohesic Friction a | ngle (deg): Φ | | ans Φr = | 0.4363 | should be Intrusive | e confirmed by Ground |
| Cohesic Friction a Poissi | ngle (deg): Φ ion's ratio : v | 0.3 | ans Φr = | 0.4363 | | Ground |
| Cohesic Friction a Poissi Elasticity mode | ngle (deg): Φ ion's ratio : ν ulus (kPa): Emod | 0.3 40000 | ans Φr = | 0.4363 | Intrusive | Ground |
| Cohesic Friction a Poissi | ngle (deg): Φ ion's ratio : ν ulus (kPa): Emod | 0.3 | ans Φr = | 0.4363 | Intrusive | Ground |
| Cohesic Friction a Poissi Elasticity mod Shear mod Product pip | ngle (deg): Φ ion's ratio : ν ulus (kPa): Emod ulus (kPa): Gmod = e OD (m): | 0.3 40000 | ans Φr = Do | | Intrusive Investiga | Ground tion. |
| Cohesic Friction a Poissi Elasticity mod Shear mod Product pip Drill bit diame | ngle (deg): Φ ion's ratio : ν ulus (kPa): Emod ulus (kPa): Gmod = e OD (m): | 0.3 40000 15385 | | 0.4363 1.118 m 0.305 m | Intrusive Investiga Diameter feasibility | Ground tion. 's assumed at 's stage. |
| Cohesic Friction ar Poissi Elasticity mode Shear mode Product pip Drill bit diame Drill pipe (| ngle (deg): Φ ion's ratio : ν ulus (kPa): Emod ulus (kPa): Gmod = e OD (m): eter (inch): OD (inch): | 0.3 40000 15385 44.00 inch 12.00 inch | Do Di | 1.118 ^m 0.305 ^m | Intrusive Investiga Diameter feasibility Rpmax u | Ground tion. 's assumed at 's stage. sually assumed |
| Cohesic Friction ar Poissi Elasticity mod Shear mod Product pip Drill bit diame Drill pipe d | ngle (deg): Φ ion's ratio : ν ulus (kPa): Emod ulus (kPa): Gmod = e OD (m): eter (inch): OD (inch): | 0.3 40000 15385 44.00 inch 12.00 inch | Do Di | 1.118 ^m | Intrusive Investiga Diameter feasibility Rpmax u between | Ground tion. 's assumed at 's stage. sually assumed 1/2 and 2/3 depth |
| Cohesic Friction ar Poissi Elasticity mod Shear mod Product pip Drill bit diame Drill pipe d | ngle (deg): Φ ion's ratio : ν ulus (kPa): Emod ulus (kPa): Gmod = e OD (m): Gmod = eter (inch): OD (inch): rehole (m): Ro dius factor Rpmax | 0.3 40000 15385 44.00 inch 12.00 inch 0.559 0.50 | Do Di Equal half | 1.118 ^m 0.305 ^m | Intrusive Investiga Diameter feasibility Rpmax u between assumed | Ground tion. 's assumed at 's stage. sually assumed 1/2 and 2/3 depth |
| Cohesic Friction au Poissi Elasticity modi Shear modi Product pip Drill bit diame Drill pipe o Initial radius of bou Allowable plastic ra Consider lateral soi | ngle (deg): Φ ion's ratio : ν ulus (kPa): Emod ulus (kPa): Gmod = e OD (m): Gmod = eter (inch): OD (inch): rehole (m): Ro dius factor Rpmax | 0.3 40000 15385 44.00 inch 12.00 inch 0.559 0.50 <i>Use drop</i> | Do Di Equal half -down to | 1.118 m 0.305 m drill bit diameter | Intrusive Investiga Diameter feasibility Rpmax u between assumed scenario Conserva | Ground tion. s assumed at stage. sually assumed 1/2 and 2/3 depth 1/2 as worst case |
| Cohesic Friction au Poissi Elasticity modi Shear modi Product pip Drill bit diame Drill pipe o Initial radius of bou Allowable plastic ra Consider lateral soi | ngle (deg): Φ ngle (deg): Φ ion's ratio : ν ulus (kPa): Emod ulus (kPa): Gmod = e OD (m): Gmod = eter (inch): OD (inch): orbit factor Rpmax l pressure: No cient ko = IF(Y_N = | 0.3 40000 15385 44.00 inch 12.00 inch 0.559 0.50 <i>Use drop</i> | Do Di Equal half -down to D) | 1.118 m 0.305 m drill bit diameter | Intrusive Investiga Diameter feasibility Rpmax u between assumed scenario Conserva | Ground tion. 's assumed at stage. sually assumed 1/2 and 2/3 depth 1/2 as worst case ative to not lateral soil |

| Annular pressure calculations | | | | |
|---|--|----------------------------|--|---------------|
| Darcy Weisbach equation for flow in an annulus is diameter, V the flow velocity, L flow pipe length an circular pipes Dh = Do - Di. The exact drilling oper some estimated values have been applied - but re the static head. | d f is a friction fact rational parameter | or. In the o s, such as | case of co-centered flow rate are unkno | d own, but |
| Assumed flow velocity (m/s): V | 0.50 | | | |
| Assumed friction coefficient: f | 2.50 | | | |
| The calculations at each chainage location are per Summary Figures | formed in the frac | -out table | | |
| | 44.45 45 | | | |
| Elevation of entrance hole mOD = Elevation of exit hole mOD = Maximum cover to HDD borehole = | 12.97 mOD -9.89 mOD 25.0 m | Diff = | 22.86 m | |
| Maximum overburden pressure = | 233.1 kN/m ² | | 2.3 Bar | |
| Maximum safe effective stress Pemax = | 1387 kN/m ² | | 13.9 Bar | |
| Maximum safe stress Pmax = | 1632 kN/m ³ | | 16.3 Bar | |





Expressions used in hydrofracture calculations

In the tabulation below the following functions are applied

Saturated Layer **Sat'd**: IF (WTL<=HDD, Elevn-HDD, Max(Elevn-WTL, 0))

Bouyant Layer **Bou't**: IF (WTL<=HDD, 0, Min(WTL-HDD, Elevn-HDD))

 $\sigma v = (\gamma s^*Satd + (\gamma s - \gamma w)^*Bout)^*g/1000$

 $\sigma o = SQRT((\gamma s*Satd+(\gamma s-\gamma w)*Bout)^2 + (ko * (\gamma s*Satd + (\gamma s-\gamma w)*Bout))^2))$

- $\mathbf{Q} = (\sigma o^* SIN(\Phi r) + Coh^* COS(\Phi r)) / Gmod$
- **Pf** = $(\sigma o^* (1+SIN(\Phi r))) + (Coh^* COS(\Phi r))$

LAT

Pemax = (Pf + Coh*COT(Φ r)) * (((Ro/Rpmax)^2 + Q)^(-SIN(Φ r)/(1+SIN(Φ r)))) - Coh*COT(Φ r)

 $\label{eq:Pelim} \textbf{Pelim} = (Pf + Coh^*COT(\Phi r)) \ * \ (\ Q^{(-SIN(\Phi r)/(1+SIN(\Phi r)))}) - Coh^*COT(\Phi r)$

| WT ~ | controls: | 0 | -4.89 | | | | | | | |
|------------------|-----------|-------|-------|--------|--------|----------------|-------|----------------|------------|------------|
| Dist | Elev'n | | WTL | C-Line | Soffit | Cover | Sat'd | Bou't | U | Hs |
| (m) | (mOD) | Loc'n | (mOD) | (mOD) | (mOD) | (m) | (m) | (m) | kN/m2 | kN/m3 |
| 0.00 | 12.97 | | 12.97 | | 12.97 | 0.00 | 0.00 | 0.00 | 0 | 0 |
| 10.00 | 13.08 | | 13.08 | | 11.21 | 1.87 | 0.00 | 1.87 | 18 | 22 |
| 20.00 | 13.18 | | 13.18 | | 9.45 | 3.73 | 0.00 | 3.73 | 37 | 45 |
| 30.00 | 13.58 | | 13.58 | | 7.96 | 5.62 | 0.00 | 5.62 | 55 | 64 |
| 40.00 | 14.12 | | 14.12 | | 5.94 | 8.18 | 0.00 | 8.18 | 80 | 90 |
| 50.00 | 14.15 | | 14.15 | | 4.18 | 9.97 | 0.00 | 9.97 | 98 | 112 |
| 60.00 | 13.98 | | 13.98 | | 2.15 | 11.84 | 0.00 | 11.84 | 116 | 138 |
| 70.00 | 13.74 | | 13.74 | | 0.66 | 13.08 | 0.00 | 13.08 | 128 | 157 |
| 80.00 | 13.45 | | 13.45 | | -1.06 | 14.51 | 0.00 | 14.51 | 142 | 179 |
| 90.00 | 13.36 | | 13.36 | | -2.72 | 16.08 | 0.00 | 16.08 | 158 | 200 |
| 100.00 | 13.28 | | 13.28 | | -4.31 | 17.58 | 0.00 | 17.58 | 172 | 220 |
| 110.00 | 13.22 | | 13.22 | | -5.83 | 19.05 | 0.00 | 19.05 | 187 | 240 |
| 120.00 | 13.37 | | 13.37 | | -7.28 | 20.66 | 0.00 | 20.66 | 203 | 258 |
| 120.00 | 16.25 | | 16.25 | | -7.20 | 20.00 | 0.00 | 20.00 | 203 244 | 236 |
| 140.00 | 15.01 | | 15.01 | | -10.00 | 24.92 25.01 | 0.00 | 24.92 | 244 | 293 |
| 140.00 | 12.46 | | 12.46 | | -10.00 | 23.01 | 0.00 | 23.01 | 243 | 309 |
| 160.00 | 8.02 | | 8.02 | | -11.25 | 20.46 | | | 233 201 | 309 324 |
| | | | | | | | 0.00 | 20.46 | 207 | 324 338 |
| 170.00 | 7.56 | | 7.56 | | -13.56 | 21.12 | 0.00 | 21.12 20.58 | | |
| 180.00 190.00 | 5.96 | | 5.96 | | -14.62 | 20.58 | 0.00 | | 202 | 352 |
| | 5.29 | | 5.29 | | -15.61 | 20.89 | 0.00 | 20.89 | 205 | 364 |
| 200.00 | 4.72 | | 4.72 | | -16.53 | 21.25 | 0.00 | 21.25 | 208 | 376 |
| 210.00 | 4.30 | | 4.30 | | -17.39 | 21.69 | 0.00 | 21.69 | 213 | 387 |
| 220.00 | 3.97 | | 3.97 | | -18.18 | 22.15 | 0.00 | 22.15 | 217 | 397 |
| 230.00 | 3.66 | | 3.66 | | -18.90 | 22.56 | 0.00 | 22.56 | 221 | 406 |
| 240.00 | 3.39 | | 3.39 | | -19.55 | 22.95 | 0.00 | 22.95 | 225 | 415 |
| 250.00 | 3.17 | | 3.17 | | -20.14 | 23.32 | 0.00 | 23.32 | 229 | 422 |
| 260.00 | 2.79 | | 2.79 | | -20.67 | 23.46 | 0.00 | 23.46 | 230 | 429 |
| 270.00 | 2.41 | | 2.41 | | -21.12 | 23.53 | 0.00 | 23.53 | 231 | 435 |
| 280.00 | 2.03 | | 2.03 | | -21.51 | 23.54 | 0.00 | 23.54 | 231 | 440 |
| 290.00 | 1.64 | | 1.64 | | -21.83 | 23.48 | 0.00 | 23.48 | 230 | 444 |
| 300.00 | 1.26 | | 1.26 | | -22.09 | 23.35 | 0.00 | 23.35 | 229 | 447 |
| 310.00 | 0.88 | | 0.88 | | -22.28 | 23.16 | 0.00 | 23.16 | 227 | 449 |
| 320.00 | 0.50 | | 0.50 | | -22.40 | 22.90 | 0.00 | 22.90 | 225 | 451 |
| 330.00 | 0.11 | | 0.11 | | -22.46 | 22.57 | 0.00 | 22.57 | 221 | 452 |
| 340.00 | -0.27 | | -0.27 | | -22.47 | 22.20 | 0.00 | 22.20 | 218 | 452 |
| 350.00 | -0.65 | | -0.65 | | -22.48 | 21.83 | 0.00 | 21.83 | 214 | 452 |
| 360.00 | -1.04 | | -1.04 | | -22.49 | 21.46 | 0.00 | 21.46 | 210 | 452 |
| 370.00 | -1.42 | | -1.42 | | -22.50 | 21.08 | 0.00 | 21.08 | 207 | 452 |
| 380.00 | -1.80 | | -1.80 | | -22.51 | 20.71 | 0.00 | 20.71 | 203 | 452 |
| 390.00 | -2.18 | | -2.18 | | -22.52 | 20.34 | 0.00 | 20.34 | 200 | 453 |
| 400.00 | -2.57 | | -2.57 | | -22.54 | 19.97 | 0.00 | 19.97 | 196 | 453 |
| 410.00 | -2.95 | | -2.95 | | -22.55 | 19.60 | 0.00 | 19.60 | 192 | 453 |
| 420.00 | -3.33 | | -3.33 | | -22.56 | 19.23 | 0.00 | 19.23 | 189 | 453 |
| 430.00 | -3.72 | | -3.72 | | -22.57 | 18.85 | 0.00 | 18.85 | 185 | 453 |
| 440.00 | -4.10 | | -4.10 | | -22.58 | 18.48 | 0.00 | 18.48 | 181 | 453 |
| 450.00 | -4.48 | | -4.48 | | -22.59 | 18.11 | 0.00 | 18.11 | 178 | 453 |
| 460.00 | -4.79 | | -4.79 | | -22.60 | 17.81 | 0.00 | 17.81 | 175 | 454 |
| 470.00 | -4.75 | | -4.75 | | -22.61 | 17.87 | 0.00 | 17.87 | 175 | 454 |
| 480.00 | -4.72 | | -4.72 | | -22.62 | 17.91 | 0.00 | 17.91 | 176 | 454 |
| 490.00 | -4.74 | | -4.74 | | -22.64 | 17.90 | 0.00 | 17.90 | 176 | 454 |
| 500.00 | -4.76 | | -4.76 | | -22.65 | 17.89 | 0.00 | 17.89 | 175 | 454 |
| 510.00 | -4.78 | | -4.78 | | -22.66 | 17.88 | 0.00 | 17.88 | 175 | 454 |
| 520.00 | -4.80 | | -4.80 | | -22.67 | 17.87 | 0.00 | 17.87 | 175 | 454 |
| 520.00 | 4.00 | | 4.00 | | 22.07 | 11.07 | 0.00 | 11.01 | | 707 |


3

| 530.00 | -4.80 | | -4.80 | -22.68 | 17.88 | 0.00 | 17.88 | 175 | 455 | |
|---|---|--|--|--|--|---|---|--|--|-----------|
| 540.00 | -4.80 | | -4.80 | -22.69 | 17.89 | 0.00 | 17.89 | 176 | 455 | |
| 550.00 | -4.80 | | -4.80 | -22.70 | 17.90 | 0.00 | 17.90 | 176 | 455 | |
| 560.00 | -4.80 | | -4.80 | -22.71 | 17.91 | 0.00 | 17.91 | 176 | 455 | |
| 570.00 | -4.80 | | -4.80 | -22.72 | 17.92 | 0.00 | 17.92 | 176 | 455 | |
| 580.00 | -4.80 | | -4.80 | -22.73 | 17.93 | 0.00 | 17.93 | 176 | 455 | |
| 590.00 | -4.80 | | -4.80 | -22.75 | 17.95 | 0.00 | 17.95 | 176 | 455 | |
| | | | | | | | | | | |
| 600.00 | -4.75 | | -4.75 | -22.76 | 18.01 | 0.00 | 18.01 | 177 | 456 | |
| 610.00 | -4.68 | | -4.68 | -22.77 | 18.09 | 0.00 | 18.09 | 177 | 456 | |
| 620.00 | -4.61 | | -4.61 | -22.78 | 18.17 | 0.00 | 18.17 | 178 | 456 | |
| 630.00 | -4.54 | | -4.54 | -22.79 | 18.25 | 0.00 | 18.25 | 179 | 456 | |
| 640.00 | -4.48 | | -4.48 | -22.80 | 18.33 | 0.00 | 18.33 | 180 | 456 | |
| 650.00 | -4.41 | | -4.41 | -22.81 | 18.41 | 0.00 | 18.41 | 181 | 456 | |
| 660.00 | -4.34 | | -4.34 | -22.82 | 18.48 | 0.00 | 18.48 | 181 | 456 | |
| 670.00 | -4.27 | | -4.27 | -22.83 | 18.56 | 0.00 | 18.56 | 182 | 457 | |
| 680.00 | -4.20 | | -4.20 | -22.85 | 18.64 | 0.00 | 18.64 | 183 | 457 | |
| 690.00 | -4.13 | | -4.13 | -22.86 | 18.72 | 0.00 | 18.72 | 184 | 457 | |
| 700.00 | -4.07 | | -4.07 | -22.87 | 18.80 | 0.00 | 18.80 | 184 | 457 | |
| 710.00 | -4.00 | | -4.00 | -22.88 | 18.88 | 0.00 | 18.88 | 185 | 457 | |
| 720.00 | -3.99 | | -3.99 | -22.89 | 18.90 | 0.00 | 18.90 | 185 | 457 | |
| 730.00 | -3.98 | | -3.98 | -22.90 | 18.92 | 0.00 | 18.92 | 186 | 457 | |
| 740.00 | -3.97 | | -3.97 | -22.90 | 18.94 | 0.00 | 18.94 | 186 | 458 | |
| 740.00 | -3.97 -3.96 | | -3.96 | -22.91 | 18.94 | 0.00 | 18.94 18.96 | 186 | 458 458 | |
| | | | | | | | | | | |
| 760.00 | -3.95 | | -3.95 | -22.93 | 18.99 | 0.00 | 18.99 | 186 | 458 | |
| 770.00 | -3.94 | | -3.94 | -22.95 | 19.01 | 0.00 | 19.01 | 186 | 458 | |
| 780.00 | -3.96 | | -3.96 | -22.96 | 19.00 | 0.00 | 19.00 | 186 | 458 | |
| 790.00 | -3.97 | | -3.97 | -22.97 | 18.99 | 0.00 | 18.99 | 186 | 458 | |
| 800.00 | -3.99 | | -3.99 | -22.98 | 18.99 | 0.00 | 18.99 | 186 | 458 | |
| 810.00 | -4.01 | | -4.01 | -22.99 | 18.98 | 0.00 | 18.98 | 186 | 459 | |
| 820.00 | -4.04 | | -4.04 | -23.00 | 18.96 | 0.00 | 18.96 | 186 | 459 | |
| 830.00 | -4.07 | | -4.07 | -23.01 | 18.94 | 0.00 | 18.94 | 186 | 459 | |
| 840.00 | -4.10 | | -4.10 | -23.02 | 18.92 | 0.00 | 18.92 | 186 | 459 | |
| 850.00 | -4.12 | | -4.12 | -23.03 | 18.91 | 0.00 | 18.91 | 185 | 459 | |
| 860.00 | -4.15 | | -4.15 | -23.04 | 18.90 | 0.00 | 18.90 | 185 | 459 | |
| 870.00 | -4.17 | | -4.17 | -23.06 | 18.89 | 0.00 | 18.89 | 185 | 459 | |
| 880.00 | -4.22 | | -4.22 | -23.07 | 18.85 | 0.00 | 18.85 | 185 | 460 | |
| 890.00 | -4.29 | | -4.29 | -23.08 | 18.79 | 0.00 | 18.79 | 184 | 460 | |
| 900.00 | -4.36 | | -4.36 | -23.09 | 18.73 | 0.00 | 18.73 | 184 | 460 | |
| 910.00 | -4.43 | | -4.43 | -23.10 | 18.67 | 0.00 | 18.67 | 183 | 460 | |
| 920.00 | -4.50 | | -4.50 | -23.11 | 18.61 | 0.00 | 18.61 | 183 | 460 | |
| 930.00 | -4.58 | | -4.58 | -23.12 | 18.55 | 0.00 | 18.55 | 182 | 460 | INTERCEPT |
| 940.00 | -4.63 | | -4.63 | -23.13 | 18.51 | 0.00 | 18.51 | 182 | 397 | |
| 950.00 | -4.71 | | -4.71 | -23.14 | 18.44 | 0.00 | 18.44 | 181 | 397 | |
| 960.00 | -4.79 | | -4.79 | -23.16 | 18.37 | 0.00 | 18.37 | 180 | 397 | |
| 970.00 | -4.89 | sea | -4.89 | -23.10 | 18.28 | 0.00 | 18.28 | 179 | 397 | |
| 970.00 980.00 | -4.89 -4.99 | sea | -4.89 -4.89 | -23.17 -23.18 | 18.19 | 0.00 | 18.19 | 179 | 398 | |
| 980.00 990.00 | -4.99 -5.09 | sea | -4.89 -4.89 | -23.10 -23.19 | 18.19 | 0.00 | 18.19 18.10 | 180 | 398 398 | |
| | -0.09 | | -4.09 | | 10 10 | | | 100 | | 1 |
| | | | | | | | | | | |
| 1000.00 | -5.19 | sea | -4.89 | -23.20 | 18.01 | 0.00 | 18.01 | 180 | 398 | |
| 1000.00 1010.00 | -5.19 -5.29 | sea sea | -4.89 -4.89 | -23.20 -23.21 | 18.01 17.92 | 0.00 0.00 | 18.01 17.92 | 180 180 | 398 398 | |
| 1000.00 1010.00 1020.00 | -5.19 -5.29 -5.39 | sea sea sea | -4.89 -4.89 -4.89 | -23.20 -23.21 -23.22 | 18.01 17.92 17.83 | 0.00 0.00 0.00 | 18.01 17.92 17.83 | 180 180 180 | 398 398 398 | |
| 1000.00 1010.00 1020.00 1030.00 | -5.19 -5.29 -5.39 -5.49 | sea sea sea sea | -4.89 -4.89 -4.89 -4.89 | -23.20 -23.21 -23.22 -23.23 | 18.01 17.92 17.83 17.74 | 0.00 0.00 0.00 0.00 | 18.01 17.92 17.83 17.74 | 180 180 180 180 | 398 398 398 398 | |
| 1000.00 1010.00 1020.00 1030.00 1040.00 | -5.19 -5.29 -5.39 -5.49 -5.59 | sea sea sea sea sea | -4.89 -4.89 -4.89 -4.89 -4.89 | -23.20 -23.21 -23.22 -23.23 -23.24 | 18.01 17.92 17.83 17.74 17.65 | 0.00 0.00 0.00 0.00 0.00 | 18.01 17.92 17.83 17.74 17.65 | 180 180 180 180 180 | 398 398 398 398 398 398 | |
| 1000.00 1010.00 1020.00 1030.00 1040.00 1050.00 | -5.19 -5.29 -5.39 -5.49 -5.59 -5.69 | sea sea sea sea sea | -4.89 -4.89 -4.89 -4.89 -4.89 -4.89 | -23.20 -23.21 -23.22 -23.23 -23.24 -23.26 | 18.01 17.92 17.83 17.74 17.65 17.56 | 0.00 0.00 0.00 0.00 0.00 0.00 | 18.01 17.92 17.83 17.74 17.65 17.56 | 180 180 180 180 180 180 | 398 398 398 398 398 398 399 | |
| 1000.00 1010.00 1020.00 1030.00 1040.00 1050.00 1060.00 | -5.19 -5.29 -5.39 -5.49 -5.59 -5.69 -5.78 | sea sea sea sea sea | -4.89 -4.89 -4.89 -4.89 -4.89 -4.89 -4.89 -4.89 | -23.20 -23.21 -23.22 -23.23 -23.24 -23.26 -23.27 | 18.01 17.92 17.83 17.74 17.65 17.56 17.49 | 0.00 0.00 0.00 0.00 0.00 0.00 0.00 | 18.01 17.92 17.83 17.74 17.65 17.56 17.49 | 180 180 180 180 180 180 180 | 398 398 398 398 398 398 399 399 | |
| 1000.00 1010.00 1020.00 1030.00 1040.00 1050.00 1060.00 1070.00 | -5.19 -5.29 -5.39 -5.49 -5.59 -5.69 | sea sea sea sea sea | -4.89 -4.89 -4.89 -4.89 -4.89 -4.89 -4.89 -4.89 | -23.20 -23.21 -23.22 -23.23 -23.24 -23.26 | 18.01 17.92 17.83 17.74 17.65 17.56 17.49 17.43 | 0.00 0.00 0.00 0.00 0.00 0.00 | 18.01 17.92 17.83 17.74 17.65 17.56 | 180 180 180 180 180 180 180 180 | 398 398 398 398 398 399 399 399 | |
| 1000.00 1010.00 1020.00 1030.00 1040.00 1050.00 1060.00 | -5.19 -5.29 -5.39 -5.49 -5.59 -5.69 -5.78 | sea sea sea sea sea sea sea | -4.89 -4.89 -4.89 -4.89 -4.89 -4.89 -4.89 -4.89 | -23.20 -23.21 -23.22 -23.23 -23.24 -23.26 -23.27 | 18.01 17.92 17.83 17.74 17.65 17.56 17.49 | 0.00 0.00 0.00 0.00 0.00 0.00 0.00 | 18.01 17.92 17.83 17.74 17.65 17.56 17.49 | 180 180 180 180 180 180 180 | 398 398 398 398 398 398 399 399 | |
| 1000.00 1010.00 1020.00 1030.00 1040.00 1050.00 1060.00 1070.00 | -5.19 -5.29 -5.39 -5.49 -5.59 -5.69 -5.78 -5.85 | sea sea sea sea sea sea sea | -4.89 -4.89 -4.89 -4.89 -4.89 -4.89 -4.89 -4.89 | -23.20 -23.21 -23.22 -23.23 -23.24 -23.26 -23.27 -23.28 | 18.01 17.92 17.83 17.74 17.65 17.56 17.49 17.43 | 0.00 0.00 0.00 0.00 0.00 0.00 0.00 0.0 | 18.01 17.92 17.83 17.74 17.65 17.56 17.49 17.43 | 180 180 180 180 180 180 180 180 | 398 398 398 398 398 399 399 399 | |
| 1000.00 1010.00 1020.00 1030.00 1040.00 1050.00 1060.00 1070.00 1080.00 | -5.19 -5.29 -5.39 -5.49 -5.59 -5.69 -5.78 -5.85 -5.93 | sea sea sea sea sea sea sea sea | -4.89 -4.89 -4.89 -4.89 -4.89 -4.89 -4.89 -4.89 -4.89 | -23.20 -23.21 -23.22 -23.23 -23.24 -23.26 -23.27 -23.28 -23.29 | 18.01 17.92 17.83 17.74 17.65 17.56 17.56 17.49 17.43 17.36 | 0.00 0.00 0.00 0.00 0.00 0.00 0.00 0.0 | 18.01 17.92 17.83 17.74 17.65 17.56 17.49 17.43 17.36 | 180 180 180 180 180 180 180 180 | 398 398 398 398 398 399 399 399 399 | |
| 1000.00 1010.00 1020.00 1030.00 1040.00 1050.00 1060.00 1070.00 1080.00 1090.00 | -5.19 -5.29 -5.39 -5.49 -5.59 -5.69 -5.78 -5.85 -5.93 -6.00 | sea sea sea sea sea sea sea sea sea | -4.89 -4.89 -4.89 -4.89 -4.89 -4.89 -4.89 -4.89 -4.89 -4.89 -4.89 | -23.20 -23.21 -23.22 -23.23 -23.24 -23.26 -23.27 -23.28 -23.29 -23.30 | 18.01 17.92 17.83 17.74 17.65 17.56 17.49 17.43 17.36 17.30 | 0.00 0.00 0.00 0.00 0.00 0.00 0.00 0.0 | 18.01 17.92 17.83 17.74 17.65 17.56 17.49 17.43 17.36 17.30 | 180 180 180 180 180 180 180 180 180 | 398 398 398 398 398 399 399 399 399 399 | |
| 1000.00 1010.00 1020.00 1030.00 1040.00 1050.00 1060.00 1070.00 1080.00 1090.00 1100.00 1110.00 | -5.19 -5.29 -5.39 -5.49 -5.59 -5.69 -5.78 -5.85 -5.93 -6.00 -6.08 -6.16 | sea sea sea sea sea sea sea sea sea sea | -4.89 -4.89 -4.89 -4.89 -4.89 -4.89 -4.89 -4.89 -4.89 -4.89 -4.89 -4.89 -4.89 | -23.20 -23.21 -23.22 -23.23 -23.24 -23.26 -23.27 -23.28 -23.29 -23.30 -23.31 -23.32 | 18.01 17.92 17.83 17.74 17.65 17.56 17.49 17.43 17.30 17.30 17.23 17.17 | 0.00 0.00 0.00 0.00 0.00 0.00 0.00 0.0 | 18.01 17.92 17.83 17.74 17.65 17.56 17.49 17.43 17.30 17.23 17.17 | 180 180 180 180 180 180 180 180 181 181 | 398 398 398 398 398 399 399 399 399 399 | |
| 1000.00 1010.00 1020.00 1030.00 1040.00 1050.00 1060.00 1070.00 1080.00 1090.00 1100.00 1110.00 1120.00 | -5.19 -5.29 -5.39 -5.49 -5.59 -5.69 -5.78 -5.85 -5.93 -6.00 -6.08 -6.16 -6.23 | sea sea sea sea sea sea sea sea sea sea | -4.89 -4.89 -4.89 -4.89 -4.89 -4.89 -4.89 -4.89 -4.89 -4.89 -4.89 -4.89 -4.89 -4.89 -4.89 | -23.20 -23.21 -23.22 -23.23 -23.24 -23.26 -23.27 -23.28 -23.29 -23.30 -23.31 -23.32 -23.32 -23.33 | 18.01 17.92 17.83 17.74 17.65 17.56 17.49 17.43 17.36 17.30 17.23 17.17 17.10 | 0.00 0.00 0.00 0.00 0.00 0.00 0.00 0.0 | 18.01 17.92 17.83 17.74 17.65 17.56 17.49 17.43 17.36 17.30 17.23 | 180 180 180 180 180 180 180 180 181 181 | 398 398 398 398 399 399 399 399 399 399 | |
| 1000.00 1010.00 1020.00 1030.00 1040.00 1050.00 1060.00 1070.00 1080.00 1090.00 1100.00 1110.00 1120.00 1130.00 | -5.19 -5.29 -5.39 -5.49 -5.59 -5.69 -5.78 -5.85 -5.93 -6.00 -6.08 -6.16 -6.23 -6.30 | sea sea sea sea sea sea sea sea sea sea | -4.89 -4.89 -4.89 -4.89 -4.89 -4.89 -4.89 -4.89 -4.89 -4.89 -4.89 -4.89 -4.89 -4.89 -4.89 -4.89 | -23.20 -23.21 -23.22 -23.23 -23.24 -23.26 -23.27 -23.28 -23.29 -23.30 -23.31 -23.32 -23.33 -23.33 -23.34 | 18.01 17.92 17.83 17.74 17.65 17.56 17.49 17.43 17.30 17.23 17.23 17.17 17.10 17.04 | 0.00 0.00 0.00 0.00 0.00 0.00 0.00 0.0 | 18.01 17.92 17.83 17.74 17.65 17.56 17.49 17.43 17.36 17.30 17.23 17.17 17.10 17.04 | 180 180 180 180 180 180 180 180 181 181 | 398 398 398 398 399 399 399 399 399 399 | |
| 1000.00 1010.00 1020.00 1030.00 1040.00 1050.00 1060.00 1070.00 1080.00 1090.00 1100.00 1110.00 1120.00 1130.00 1140.00 | -5.19 -5.29 -5.39 -5.49 -5.59 -5.69 -5.78 -5.85 -5.93 -6.00 -6.08 -6.16 -6.23 -6.30 -6.37 | sea sea sea sea sea sea sea sea sea sea | -4.89 -4.89 -4.89 -4.89 -4.89 -4.89 -4.89 -4.89 -4.89 -4.89 -4.89 -4.89 -4.89 -4.89 -4.89 -4.89 -4.89 -4.89 | -23.20 -23.21 -23.22 -23.23 -23.24 -23.26 -23.27 -23.28 -23.29 -23.30 -23.31 -23.32 -23.33 -23.33 -23.34 -23.36 | 18.01 17.92 17.83 17.74 17.65 17.56 17.49 17.43 17.36 17.30 17.23 17.17 17.10 17.04 16.99 | 0.00 0.00 0.00 0.00 0.00 0.00 0.00 0.0 | 18.01 17.92 17.83 17.74 17.65 17.56 17.49 17.43 17.36 17.30 17.23 17.17 17.10 17.04 16.99 | 180 180 180 180 180 180 180 180 181 181 | 398 398 398 398 399 399 399 399 399 399 | |
| 1000.00 1010.00 1020.00 1030.00 1040.00 1050.00 1060.00 1070.00 1080.00 1090.00 1100.00 1110.00 1120.00 1130.00 1140.00 1150.00 | -5.19 -5.29 -5.39 -5.59 -5.69 -5.78 -5.85 -5.93 -6.00 -6.08 -6.16 -6.23 -6.30 -6.37 -6.45 | sea sea sea sea sea sea sea sea sea sea | -4.89 -4.89 -4.89 -4.89 -4.89 -4.89 -4.89 -4.89 -4.89 -4.89 -4.89 -4.89 -4.89 -4.89 -4.89 -4.89 -4.89 -4.89 -4.89 | -23.20 -23.21 -23.22 -23.23 -23.24 -23.26 -23.27 -23.28 -23.29 -23.30 -23.31 -23.32 -23.33 -23.34 -23.36 -23.37 | 18.01 17.92 17.83 17.74 17.65 17.56 17.49 17.43 17.36 17.30 17.23 17.17 17.10 17.04 16.99 16.92 | 0.00 0.00 0.00 0.00 0.00 0.00 0.00 0.0 | 18.01 17.92 17.83 17.74 17.65 17.56 17.49 17.43 17.36 17.30 17.23 17.17 17.10 17.04 16.99 16.92 | 180 180 180 180 180 180 180 180 181 181 | 398 398 398 398 399 399 399 399 399 399 | |
| 1000.00 1010.00 1020.00 1030.00 1050.00 1060.00 1070.00 1080.00 1090.00 1100.00 1110.00 1120.00 1130.00 1140.00 1150.00 1160.00 | -5.19 -5.29 -5.39 -5.59 -5.69 -5.78 -5.85 -5.93 -6.00 -6.08 -6.23 -6.30 -6.37 -6.45 -6.50 | sea sea sea sea sea sea sea sea sea sea | -4.89 | -23.20 -23.21 -23.22 -23.23 -23.24 -23.26 -23.27 -23.28 -23.29 -23.30 -23.31 -23.32 -23.33 -23.34 -23.36 -23.37 -23.38 | 18.01 17.92 17.83 17.74 17.65 17.66 17.49 17.43 17.30 17.30 17.23 17.17 17.10 17.04 16.99 16.92 16.88 | 0.00 0.00 0.00 0.00 0.00 0.00 0.00 0.0 | 18.01 17.92 17.83 17.74 17.65 17.56 17.49 17.43 17.36 17.30 17.23 17.17 17.10 17.04 16.99 16.92 16.88 | 180 180 180 180 180 180 180 180 181 181 | 398 398 398 398 399 399 399 399 399 399 | |
| 1000.00 1010.00 1020.00 1030.00 1040.00 1050.00 1060.00 1070.00 1090.00 1100.00 1110.00 1120.00 1130.00 1140.00 1150.00 1160.00 1170.00 | -5.19 -5.29 -5.39 -5.49 -5.59 -5.69 -5.78 -5.85 -5.93 -6.00 -6.08 -6.23 -6.30 -6.37 -6.45 -6.50 -6.55 | sea sea sea sea sea sea sea sea sea sea | -4.89 | -23.20 -23.21 -23.22 -23.23 -23.24 -23.26 -23.27 -23.28 -23.29 -23.30 -23.31 -23.32 -23.33 -23.34 -23.36 -23.37 -23.38 -23.39 | 18.01 17.92 17.83 17.74 17.65 17.56 17.49 17.43 17.36 17.30 17.23 17.17 17.10 17.04 16.99 16.92 16.88 16.84 | 0.00 0.00 0.00 0.00 0.00 0.00 0.00 0.0 | 18.01 17.92 17.83 17.74 17.65 17.56 17.49 17.43 17.30 17.23 17.17 17.10 17.04 16.99 16.92 16.88 16.84 | 180 180 180 180 180 180 180 180 181 181 | 398 398 398 398 399 399 399 399 399 399 | |
| 1000.00 1010.00 1020.00 1030.00 1050.00 1060.00 1070.00 1080.00 1090.00 1100.00 1110.00 1120.00 1130.00 1140.00 1150.00 1160.00 | -5.19 -5.29 -5.39 -5.59 -5.69 -5.78 -5.85 -5.93 -6.00 -6.08 -6.23 -6.30 -6.37 -6.45 -6.50 | sea sea sea sea sea sea sea sea sea sea | -4.89 | -23.20 -23.21 -23.22 -23.23 -23.24 -23.26 -23.27 -23.28 -23.29 -23.30 -23.31 -23.32 -23.33 -23.34 -23.36 -23.37 -23.38 | 18.01 17.92 17.83 17.74 17.65 17.66 17.49 17.43 17.30 17.30 17.23 17.17 17.10 17.04 16.99 16.92 16.88 | 0.00 0.00 0.00 0.00 0.00 0.00 0.00 0.0 | 18.01 17.92 17.83 17.74 17.65 17.56 17.49 17.43 17.36 17.30 17.23 17.17 17.10 17.04 16.99 16.92 16.88 | 180 180 180 180 180 180 180 180 181 181 | 398 398 398 398 399 399 399 399 399 399 | |

| 1200.00 | -6.70 | sea | -4.89 | -23.42 | 16.73 | 0.00 | 16.73 | 182 | 401 | |
|---------|----------------|-----|----------------|-----------------|---------|------|-------|-----|-----|--|
| 1210.00 | -6.74 | sea | -4.89 | -23.43 | 16.69 | 0.00 | 16.69 | 182 | 401 | |
| 1220.00 | -6.75 | sea | -4.89 | -23.44 | 16.70 | 0.00 | 16.70 | 182 | 401 | |
| 1230.00 | -6.75 | | -4.89 | -23.45 | 16.70 | 0.00 | 16.70 | 182 | 401 | |
| | | sea | | | | | | | | |
| 1240.00 | -6.77 | sea | -4.89 | -23.47 | 16.70 | 0.00 | 16.70 | 182 | 401 | |
| 1250.00 | -6.79 | sea | -4.89 | -23.48 | 16.68 | 0.00 | 16.68 | 182 | 401 | |
| 1260.00 | -6.85 | sea | -4.89 | -23.49 | 16.64 | 0.00 | 16.64 | 182 | 402 | |
| 1270.00 | -6.92 | sea | -4.89 | -23.50 | 16.58 | 0.00 | 16.58 | 183 | 402 | |
| 1280.00 | -6.99 | sea | -4.89 | -23.51 | 16.52 | 0.00 | 16.52 | 183 | 402 | |
| 1290.00 | -7.06 | sea | -4.89 | -23.52 | 16.46 | 0.00 | 16.46 | 183 | 402 | |
| 1300.00 | | | -4.89 | -23.53 | 16.40 | 0.00 | 16.40 | 183 | 402 | |
| | -7.13 | sea | | | | | | | | |
| 1310.00 | -7.20 | sea | -4.89 | -23.54 | 16.34 | 0.00 | 16.34 | 183 | 402 | |
| 1320.00 | -7.27 | sea | -4.89 | -23.55 | 16.28 | 0.00 | 16.28 | 183 | 402 | |
| 1330.00 | -7.34 | sea | -4.89 | -23.57 | 16.23 | 0.00 | 16.23 | 183 | 403 | |
| 1340.00 | -7.41 | sea | -4.89 | -23.58 | 16.17 | 0.00 | 16.17 | 183 | 403 | |
| 1350.00 | -7.47 | sea | -4.89 | -23.59 | 16.11 | 0.00 | 16.11 | 183 | 403 | |
| 1360.00 | -7.54 | sea | -4.89 | -23.60 | 16.06 | 0.00 | 16.06 | 184 | 403 | |
| | | | | | | | | | | |
| 1370.00 | -7.61 | sea | -4.89 | -23.61 | 16.00 | 0.00 | 16.00 | 184 | 403 | |
| 1380.00 | -7.67 | sea | -4.89 | -23.62 | 15.95 | 0.00 | 15.95 | 184 | 403 | |
| 1390.00 | -7.74 | sea | -4.89 | -23.63 | 15.90 | 0.00 | 15.90 | 184 | 403 | |
| 1400.00 | -7.80 | sea | -4.89 | -23.64 | 15.84 | 0.00 | 15.84 | 184 | 404 | |
| 1410.00 | -7.85 | sea | -4.89 | -23.65 | 15.80 | 0.00 | 15.80 | 184 | 404 | |
| 1420.00 | -7.90 | sea | -4.89 | -23.67 | 15.76 | 0.00 | 15.76 | 184 | 404 | |
| 1430.00 | -7.95 | sea | -4.89 | -23.68 | 15.72 | 0.00 | 15.72 | 184 | 404 | |
| | | | | | | | | | | |
| 1440.00 | -8.00 | sea | -4.89 | -23.69 | 15.68 | 0.00 | 15.68 | 184 | 404 | |
| 1450.00 | -8.06 | sea | -4.89 | -23.70 | 15.64 | 0.00 | 15.64 | 185 | 404 | |
| 1460.00 | -8.11 | sea | -4.89 | -23.71 | 15.60 | 0.00 | 15.60 | 185 | 404 | |
| 1470.00 | -8.16 | sea | -4.89 | -23.72 | 15.56 | 0.00 | 15.56 | 185 | 405 | |
| 1480.00 | -8.21 | sea | -4.89 | -23.73 | 15.52 | 0.00 | 15.52 | 185 | 405 | |
| 1490.00 | -8.26 | sea | -4.89 | -23.73 | 15.47 | 0.00 | 15.47 | 185 | 405 | |
| 1500.00 | -8.31 | sea | -4.89 | -23.71 | 15.40 | 0.00 | 15.40 | 185 | 404 | |
| 1510.00 | -8.36 | | -4.89 | -23.67 | 15.31 | 0.00 | 15.31 | 184 | 404 | |
| | | sea | | | | | | | | |
| 1520.00 | -8.41 | sea | -4.89 | -23.61 | 15.20 | 0.00 | 15.20 | 184 | 403 | |
| 1530.00 | -8.46 | sea | -4.89 | -23.53 | 15.07 | 0.00 | 15.07 | 183 | 402 | |
| 1540.00 | -8.51 | sea | -4.89 | -23.44 | 14.92 | 0.00 | 14.92 | 182 | 401 | |
| 1550.00 | -8.56 | sea | -4.89 | -23.32 | 14.75 | 0.00 | 14.75 | 181 | 399 | |
| 1560.00 | -8.61 | sea | -4.89 | -23.18 | 14.56 | 0.00 | 14.56 | 179 | 398 | |
| 1570.00 | -8.67 | sea | -4.89 | -23.02 | 14.35 | 0.00 | 14.35 | 178 | 396 | |
| 1580.00 | -8.71 | sea | -4.89 | -22.84 | 14.12 | 0.00 | 14.12 | 176 | 393 | |
| | | | | | | | | | | |
| 1590.00 | -8.76 | sea | -4.89 | -22.64 | 13.88 | 0.00 | 13.88 | 174 | 391 | |
| 1600.00 | -8.80 | sea | -4.89 | -22.42 | 13.62 | 0.00 | 13.62 | 172 | 388 | |
| 1610.00 | -8.84 | sea | -4.89 | -22.18 | 13.34 | 0.00 | 13.34 | 170 | 385 | |
| 1620.00 | -8.88 | sea | -4.89 | -21.92 | 13.04 | 0.00 | 13.04 | 167 | 382 | |
| 1630.00 | -8.92 | sea | -4.89 | -21.64 | 12.72 | 0.00 | 12.72 | 164 | 378 | |
| 1640.00 | -8.96 | sea | -4.89 | -21.34 | 12.38 | 0.00 | 12.38 | 161 | 374 | |
| 1650.00 | -8.90 -9.00 | | -4.89 -4.89 | | 12.03 | 0.00 | | | 374 | |
| | | sea | | -21.02 | | | 12.03 | 158 | | |
| 660.00 | -9.03 | sea | -4.89 | -20.68 | 11.65 | 0.00 | 11.65 | 155 | 366 | |
| 670.00 | -9.07 | sea | -4.89 | -20.32 | 11.25 | 0.00 | 11.25 | 151 | 361 | |
| 680.00 | -9.12 | sea | -4.89 | -19.94 | 10.83 | 0.00 | 10.83 | 148 | 356 | |
| 1690.00 | -9.16 | sea | -4.89 | -19.55 | 10.39 | 0.00 | 10.39 | 144 | 351 | |
| 1700.00 | -9.20 | sea | -4.89 | -19.13 | 9.92 | 0.00 | 9.92 | 140 | 346 | |
| 1710.00 | -9.25 | sea | -4.89 | -18.69 | 9.44 | 0.00 | 9.44 | 135 | 340 | |
| 1720.00 | -9.29 | sea | -4.89 | -18.23 | 8.94 | 0.00 | 8.94 | 131 | 334 | |
| | | | | | | | | | | |
| 1730.00 | -9.34 | sea | -4.89 | -17.75 | 8.41 | 0.00 | 8.41 | 126 | 328 | |
| 1740.00 | -9.38 | sea | -4.89 | -17.25 | 7.87 | 0.00 | 7.87 | 121 | 322 | |
| 1750.00 | -9.42 | sea | -4.89 | -16.73 | 7.30 | 0.00 | 7.30 | 116 | 315 | |
| 1760.00 | -9.47 | sea | -4.89 | -16.19 | 6.72 | 0.00 | 6.72 | 111 | 308 | |
| 1770.00 | -9.51 | sea | -4.89 | -15.63 | 6.12 | 0.00 | 6.12 | 105 | 301 | |
| 1780.00 | -9.56 | sea | -4.89 | -15.05 | 5.49 | 0.00 | 5.49 | 100 | 294 | |
| | | | | | | | | | | |
| 1790.00 | -9.60 | sea | -4.89 | -14.45 | 4.85 | 0.00 | 4.85 | 94 | 286 | |
| 1800.00 | -9.64 | sea | -4.89 | -13.83 | 4.19 | 0.00 | 4.19 | 88 | 278 | |
| 1810.00 | -9.69 | sea | -4.89 | -13.19 | 3.51 | 0.00 | 3.51 | 81 | 270 | |
| 1820.00 | -9.73 | sea | -4.89 | -12.53 | 2.80 | 0.00 | 2.80 | 75 | 262 | |
| 1830.00 | -9.77 | sea | -4.89 | -11.85 | 2.08 | 0.00 | 2.08 | 68 | 253 | |
| 1840.00 | -9.82 | sea | -4.89 | -11.16 | 1.34 | 0.00 | 1.34 | 61 | 244 | |
| | -9.82 -9.86 | | -4.89 | | 0.59 | 0.00 | 0.59 | 55 | 235 | |
| 1850.00 | | sea | -4.89 -4.89 | -10.45 -9.89 | 0.59 | 0.00 | 0.59 | | | |
| 1860.00 | -9.89 | sea | | | () ()() | 0.00 | 0.00 | 49 | 228 | |

WIE12731-153_Frac-out Calcs_Landfall

8.00 8.00 0.00



| | | | | D | istance fro | om entry p | oint (m) | | | | | |
|----------------|----------------------|----------------------|----------------------|----------------|--------------------|--------------|--------------|----------------------|----------|----------------------|--|---|
| | | | | | | | | | | | | |
| Dist | σν | σh | σο | Pf | Q | Rpmax | Pemax | Pmax | Hf | H | The pressure calculation are set out in this table | |
| (m) | (kN/m ²) | (kN/m ²) | (kN/m ²) | | | (m) | | (kN/m ²) | | (kN/m ²) | Note that Rpmax varie | |
| 0.0 | 0.0 | 0.0 | 0.0 | 1.8 | 0.00012 | 0.6 | 2 | 2 | 0 | 0 | as it is set to be a | |
| 10.0 | 17.4 | 0.0 | 17.4 | 26.6 | 0.00060 | 0.9 | 38 | 56 | 0 | 23 | proportion of the cover | |
| 20.0 | 34.8 | 0.0 | 34.8 | 51.3 | 0.00107 | 1.9 | 109 | 146 | 1 | 46 | depth. | |
| 30.0 | 52.4 | 0.0 | 52.4 | 76.3 | 0.00156 | 2.8 | 204 | 259 | 1 | 65 | | |
| 40.0 | 76.3 | 0.0 | 76.3 | 110.3 | 0.00221 | 4.1 | 357 | 438 | 2 | 91 | Hf is a rough estimate | |
| 50.0 | 92.9 | 0.0 | 92.9 | 134.0 | 0.00267 | 5.0 | 475 | 573 | 2 | 114 | the drilling mud pressu | |
| 60.0 | 110.3 | 0.0 | 110.3 | 158.7 | 0.00315 | 5.9 | 601 | 717 | 2 | 140 | the return annular flow | |
| 70.0 | 121.9 | 0.0 | 121.9 | 175.2 | 0.00347 | 6.5 | 685 | 814 | 3 | 160 | The total head H is the | 2 |
| 80.0 | 135.3 | 0.0 | 135.3 | 194.2 | 0.00383 | 7.3 | 781 | 923 | 3 | 182 | static head Hs (table | • |
| 90.0 | 149.8 | 0.0 | 149.8 | 215.0 | 0.00423 | 8.0 | 882 | 1040 | 4 | 204 | above) and Hf . | |
| 100.0 | 163.9 | 0.0 | 163.9 | 234.9 | 0.00462 | 8.8 | 976 | 1149 | 4 | 224 | , | |
| 110.0 | 177.6 | 0.0 | 177.6 | 254.4 | 0.00500 | 9.5 | 1064 | 1251 | 4 | 244 | | |
| 120.0 | 192.5 | 0.0 | 192.5 | 275.7 | 0.00541 | 10.3 | 1157 | 1359 | 5 | 263 | | |
| 130.0 | 232.2 | 0.0 | 232.2 | 332.2 | 0.00650 | 12.5 | 1382 | 1627 | 5 | 281 | | |
| 140.0 | 233.1 | 0.0 | 233.1 | 333.4 | 0.00652 | 12.5 | 1387 | 1632 | 5 | 298 | | |
| 150.0 | 221.0 | 0.0 | 221.0 | 316.2 | 0.00619 | 11.9 | 1321 | 1554 | 6 | 315 | | |
| 160.0 | 190.7 | 0.0 | 190.7 | 273.1 | 0.00536 | 10.2 | 1146 | 1346 | 6 | 330 | | |
| 170.0 | 196.8 | 0.0 | 196.8 | 281.8 | 0.00552 | 10.6 | 1182 | 1390 | 7 | 345 | | |
| 180.0 | 191.8 | 0.0 | 191.8 | 274.7 | 0.00539 | 10.3 | 1152 | 1354 | 7 | 359 | | |
| 190.0 | 194.7 | 0.0 | 194.7 | 278.8 | 0.00547 | 10.4 | 1170 | 1375 | 7 | 372 | | |
| 210.0 | 202.1 | 0.0 | 202.1 | 289.3 | 0.00567 | 10.8 | 1213 | 1426 | 8 | 395 | | |
| 220.0 | 206.4 | 0.0 | 206.4 | 295.5 | 0.00579 | 11.1 | 1239 | 1456 | 9 | 406 | | |
| 230.0 | 210.2 | 0.0 | 210.2 | 300.9 | 0.00589 | 11.3 | 1261 | 1482 | 9 | 415 | | |
| 240.0 | 213.9 | 0.0 | 213.9 | 306.0 | 0.00599 | 11.5 | 1281 | 1506 | 9 | 424 | | |
| 250.0 | 217.3 | 0.0 | 217.3 | 311.0 | 0.00609 | 11.7 | 1300 | 1529 | 10 | 432 | | |
| 260.0 270.0 | 218.6 219.3 | 0.0 0.0 | 218.6 219.3 | 312.8 313.8 | 0.00612 0.00614 | 11.7 11.8 | 1308 1312 | 1538 1542 | 10 11 | 439 445 | | |
| 270.0 | 219.3 | 0.0 | 219.3 | 313.9 | 0.00614 | 11.8 | 1312 | 1542 | 11 | 445 451 | | |
| 290.0 | 218.8 | 0.0 | 218.8 | 313.1 | 0.00613 | 11.7 | 1309 | 1539 | 11 | 455 | | |
| 300.0 | 217.6 | 0.0 | 217.6 | 311.4 | 0.00610 | 11.7 | 1302 | 1531 | 12 | 459 | | |
| 310.0 | 215.8 | 0.0 | 215.8 | 308.8 | 0.00605 | 11.6 | 1292 | 1519 | 12 | 462 | | |
| 320.0 | 213.4 | 0.0 | 213.4 | 305.4 | 0.00598 | 11.4 | 1278 | 1503 | 13 | 464 | | |
| 330.0 | 210.3 | 0.0 | 210.3 | 301.0 | 0.00590 | 11.3 | 1261 | 1482 | 13 | 465 | | |
| 340.0 | 206.9 | 0.0 | 206.9 | 296.1 | 0.00580 | 11.1 | 1241 | 1459 | 13 | 465 | | |
| 350.0 | 203.4 | 0.0 | 203.4 | 291.2 | 0.00571 | 10.9 | 1221 | 1435 | 14 | 466 | | |
| 360.0 | 199.9 | 0.0 | 199.9 | 286.3 | 0.00561 | 10.7 | 1201 | 1411 | 14 | 466 | | |
| 370.0 | 196.5 | 0.0 | 196.5 | 281.3 | 0.00552 | 10.5 | 1180 | 1387 1363 | 15 | 467 | | |
| 380.0 390.0 | 193.0 189.6 | 0.0 0.0 | 193.0 189.6 | 276.4 271.5 | 0.00542 0.00532 | 10.4 10.2 | 1160 1139 | 1303 | 15 15 | 467 468 | | |
| 400.0 | 186.1 | 0.0 | 186.1 | 266.6 | 0.00523 | 10.2 | 1118 | 1313 | 16 | 468 | | |
| 410.0 | 182.6 | 0.0 | 182.6 | 261.6 | 0.00513 | 9.8 | 1096 | 1288 | 16 | 469 | | |
| 420.0 | 179.2 | 0.0 | 179.2 | 256.7 | 0.00504 | 9.6 | 1075 | 1263 | 16 | 469 | | |
| 430.0 | 175.7 | 0.0 | 175.7 | 251.8 | 0.00494 | 9.4 | 1053 | 1238 | 17 | 470 | | |
| 440.0 | 172.2 | 0.0 | 172.2 | 246.8 | 0.00485 | 9.2 | 1031 | 1212 | 17 | 471 | | |
| 450.0 | 168.8 | 0.0 | 168.8 | 241.9 | 0.00475 | 9.1 | 1008 | 1186 | 18 | 471 | | |
| 460.0 | 166.0 | 0.0 | 166.0 | 237.9 | 0.00468 | 8.9 | 990 | 1165 | 18 | 472 | | |
| 470.0 | 166.5 | 0.0 | 166.5 | 238.7 | 0.00469 | 8.9 | 994 | 1169 | 18 | 472 | | |
| 480.0 | 166.9 | 0.0 | 166.9 | 239.2 | 0.00470 | 9.0 | 996 | 1172 | 19 | 473 | | |
| 490.0 | 166.8 | 0.0 | 166.8 | 239.1 | 0.00470 | 8.9 | 995 | 1171 | 19 20 | 473 | | |
| 500.0 | 166.7 166.6 | 0.0 | 166.7 166.6 | 238.9 | 0.00470 0.00469 | 8.9 8.0 | 995 994 | 1170 1170 | 20 20 | 474 474 | | |
| 510.0 520.0 | 166.6 166.5 | 0.0 0.0 | 166.6 166.5 | 238.8 238.7 | 0.00469 | 8.9 8.9 | 994 994 | 1170 | 20 20 | 474 475 | | |
| 520.0 | 166.6 | 0.0 | 166.6 | 238.9 | 0.00469 | 8.9 8.9 | 994 994 | 1170 | 20 21 | 475 475 | | |
| 540.0 | | 0.0 | 100.0 | | 0.00409 | 0.9 | 994 | 1170 | 21 | 475 | | |

540.0 166.7

0.0

995

1171

21

476

166.7 239.0 0.00470 8.9

| | | 100.0 | | 100.0 | 000 4 | 0.00470 | ~ ~ | | 4474 | | 470 |
|---|---|---|--|---|--|---|---|--|--|--|---|
| | 550.0 | 166.8 | 0.0 | 166.8 | 239.1 | 0.00470 | 9.0 | 996 | 1171 | 22 | 476 |
| | 560.0 | 166.9 | 0.0 | 166.9 | 239.3 | 0.00470 | 9.0 | 996 | 1172 | 22 | 477 |
| | 570.0 | 167.0 | 0.0 | 167.0 | 239.4 | 0.00471 | 9.0 | 997 | 1173 | 22 | 477 |
| | | | | | | | | | | | |
| | 580.0 | 167.1 | 0.0 | 167.1 | 239.6 | 0.00471 | 9.0 | 998 | 1174 | 23 | 478 |
| | 590.0 | 167.2 | 0.0 | 167.2 | 239.7 | 0.00471 | 9.0 | 998 | 1174 | 23 | 479 |
| | 600.0 | 167.8 | 0.0 | 167.8 | 240.6 | 0.00473 | 9.0 | 1002 | 1179 | 24 | 479 |
| | | | | | | | | | | | |
| | 610.0 | 168.6 | 0.0 | 168.6 | 241.6 | 0.00475 | 9.0 | 1007 | 1184 | 24 | 480 |
| | 620.0 | 169.3 | 0.0 | 169.3 | 242.7 | 0.00477 | 9.1 | 1012 | 1190 | 24 | 480 |
| | 630.0 | 170.0 | 0.0 | 170.0 | 243.7 | 0.00479 | 9.1 | 1017 | 1196 | 25 | 481 |
| | | | | | | | | | | | |
| | 640.0 | 170.8 | 0.0 | 170.8 | 244.8 | 0.00481 | 9.2 | 1021 | 1201 | 25 | 481 |
| | 650.0 | 171.5 | 0.0 | 171.5 | 245.8 | 0.00483 | 9.2 | 1026 | 1207 | 25 | 482 |
| | 660.0 | 172.3 | 0.0 | 172.3 | 246.9 | 0.00485 | 9.2 | 1031 | 1212 | 26 | 482 |
| | | | | | | | | | | | |
| | 670.0 | 173.0 | 0.0 | 173.0 | 247.9 | 0.00487 | 9.3 | 1036 | 1218 | 26 | 483 |
| | 680.0 | 173.7 | 0.0 | 173.7 | 249.0 | 0.00489 | 9.3 | 1040 | 1223 | 27 | 483 |
| | | | | | | | 9.4 | | 1229 | 27 | 484 |
| | 690.0 | 174.5 | 0.0 | 174.5 | 250.0 | 0.00491 | | 1045 | | | |
| | 700.0 | 175.2 | 0.0 | 175.2 | 251.1 | 0.00493 | 9.4 | 1050 | 1234 | 27 | 484 |
| | 710.0 | 175.9 | 0.0 | 175.9 | 252.1 | 0.00495 | 9.4 | 1054 | 1239 | 28 | 485 |
| | | | | | | | | | | 28 | 485 |
| | 720.0 | 176.1 | 0.0 | 176.1 | 252.4 | 0.00496 | 9.4 | 1055 | 1241 | | |
| | 730.0 | 176.3 | 0.0 | 176.3 | 252.6 | 0.00496 | 9.5 | 1057 | 1242 | 29 | 486 |
| | 740.0 | 176.5 | 0.0 | 176.5 | 252.9 | 0.00497 | 9.5 | 1058 | 1244 | 29 | 487 |
| | | | | | | | | | | | |
| | 750.0 | 176.7 | 0.0 | 176.7 | 253.2 | 0.00497 | 9.5 | 1059 | 1245 | 29 | 487 |
| | 760.0 | 176.9 | 0.0 | 176.9 | 253.5 | 0.00498 | 9.5 | 1061 | 1247 | 30 | 488 |
| | 770.0 | 177.1 | 0.0 | 177.1 | 253.8 | 0.00498 | 9.5 | 1062 | 1248 | 30 | 488 |
| | | | | | | | | | | | |
| | 780.0 | 177.1 | 0.0 | 177.1 | 253.7 | 0.00498 | 9.5 | 1061 | 1248 | 31 | 489 |
| | 790.0 | 177.0 | 0.0 | 177.0 | 253.6 | 0.00498 | 9.5 | 1061 | 1247 | 31 | 489 |
| | 800.0 | 177.0 | 0.0 | 177.0 | 253.6 | 0.00498 | 9.5 | 1061 | 1247 | 31 | 490 |
| | | | | | | | | | | | |
| | 810.0 | 176.9 | 0.0 | 176.9 | 253.4 | 0.00498 | 9.5 | 1060 | 1246 | 32 | 490 |
| | 820.0 | 176.7 | 0.0 | 176.7 | 253.2 | 0.00497 | 9.5 | 1059 | 1245 | 32 | 491 |
| | 830.0 | 176.5 | 0.0 | 176.5 | 252.9 | 0.00497 | 9.5 | 1058 | 1244 | 33 | 491 |
| | | | | | | | | | | | |
| | 840.0 | 176.3 | 0.0 | 176.3 | 252.7 | 0.00496 | 9.5 | 1057 | 1242 | 33 | 492 |
| | 850.0 | 176.2 | 0.0 | 176.2 | 252.5 | 0.00496 | 9.5 | 1056 | 1242 | 33 | 492 |
| | 860.0 | 176.1 | 0.0 | 176.1 | 252.4 | 0.00496 | 9.4 | 1055 | 1241 | 34 | 493 |
| | | | | | | | | | | | |
| | 870.0 | 176.0 | 0.0 | 176.0 | 252.2 | 0.00495 | 9.4 | 1055 | 1240 | 34 | 493 |
| | 880.0 | 175.7 | 0.0 | 175.7 | 251.8 | 0.00494 | 9.4 | 1053 | 1238 | 34 | 494 |
| | 890.0 | 175.1 | 0.0 | 175.1 | 250.9 | 0.00493 | 9.4 | 1049 | 1233 | 35 | 495 |
| | | | | | | | | | | | |
| | 900.0 | 174.6 | 0.0 | 174.6 | 250.1 | 0.00491 | 9.4 | 1045 | 1229 | 35 | 495 |
| | 910.0 | 174.0 | 0.0 | 174.0 | 249.3 | 0.00490 | 9.3 | 1042 | 1225 | 36 | 496 |
| | 920.0 | 173.4 | 0.0 | 173.4 | 248.5 | 0.00488 | 9.3 | 1038 | 1221 | 36 | 496 |
| | | | | | | | | 1038 | | | 430 |
| | 930.0 | 172.8 | 0.0 | 172.8 | 247.7 | 0.00487 | 9.3 | | 1217 | 36 | |
| | | | | | | | | | | | |
| ľ | 920.0 | 176.0 | 0.0 | 176.0 | 252.2 | 0.00495 | 9.4 | 1055 | 1240 | 36 | 433 |
| | | | 0.0 | 176.0 | 252.2 | | 9.4 | 1055 | 1240 | | |
| | 910.0 | 175.7 | 0.0 0.0 | 176.0 175.7 | 252.2 251.8 | 0.00494 | 9.4 9.4 | 1055 1053 | 1240 1238 | 36 | 433 |
| | 910.0 900.0 | 175.7 175.1 | 0.0 0.0 0.0 | 176.0 175.7 175.1 | 252.2 251.8 250.9 | 0.00494 0.00493 | 9.4 9.4 9.4 | 1055 1053 1049 | 1240 1238 1233 | 36 35 | 433 433 |
| | 910.0 | 175.7 | 0.0 0.0 | 176.0 175.7 | 252.2 251.8 | 0.00494 | 9.4 9.4 | 1055 1053 | 1240 1238 | 36 | 433 |
| | 910.0 900.0 890.0 | 175.7 175.1 174.6 | 0.0 0.0 0.0 0.0 | 176.0 175.7 175.1 174.6 | 252.2 251.8 250.9 250.1 | 0.00494 0.00493 0.00491 | 9.4 9.4 9.4 9.4 | 1055 1053 1049 1045 | 1240 1238 1233 1229 | 36 35 35 | 433 433 432 |
| | 910.0 900.0 890.0 880.0 | 175.7 175.1 174.6 174.0 | 0.0 0.0 0.0 0.0 0.0 | 176.0 175.7 175.1 174.6 174.0 | 252.2 251.8 250.9 250.1 249.3 | 0.00494 0.00493 0.00491 0.00490 | 9.4 9.4 9.4 9.4 9.3 | 1055 1053 1049 1045 1042 | 1240 1238 1233 1229 1225 | 36 35 35 34 | 433 433 432 432 |
| | 910.0 900.0 890.0 880.0 870.0 | 175.7 175.1 174.6 174.0 173.4 | 0.0 0.0 0.0 0.0 0.0 0.0 | 176.0 175.7 175.1 174.6 174.0 173.4 | 252.2 251.8 250.9 250.1 249.3 248.5 | 0.00494 0.00493 0.00491 0.00490 0.00488 | 9.4 9.4 9.4 9.3 9.3 | 1055 1053 1049 1045 1042 1038 | 1240 1238 1233 1229 1225 1221 | 36 35 35 34 34 | 433 433 432 432 432 |
| | 910.0 900.0 890.0 880.0 | 175.7 175.1 174.6 174.0 | 0.0 0.0 0.0 0.0 0.0 | 176.0 175.7 175.1 174.6 174.0 | 252.2 251.8 250.9 250.1 249.3 | 0.00494 0.00493 0.00491 0.00490 | 9.4 9.4 9.4 9.4 9.3 | 1055 1053 1049 1045 1042 | 1240 1238 1233 1229 1225 | 36 35 35 34 | 433 433 432 432 |
| | 910.0 900.0 890.0 880.0 870.0 860.0 | 175.7 175.1 174.6 174.0 173.4 172.8 | 0.0 0.0 0.0 0.0 0.0 0.0 0.0 | 176.0 175.7 175.1 174.6 174.0 173.4 172.8 | 252.2 251.8 250.9 250.1 249.3 248.5 247.7 | 0.00494 0.00493 0.00491 0.00490 0.00488 0.00487 | 9.4 9.4 9.4 9.3 9.3 9.3 9.3 | 1055 1053 1049 1045 1042 1038 1035 | 1240 1238 1233 1229 1225 1221 1217 | 36 35 35 34 34 34 | 433 433 432 432 432 432 432 |
| | 910.0 900.0 890.0 880.0 870.0 860.0 850.0 | 175.7 175.1 174.6 174.0 173.4 172.8 172.5 | 0.0 0.0 0.0 0.0 0.0 0.0 0.0 0.0 | 176.0 175.7 175.1 174.6 174.0 173.4 172.8 172.5 | 252.2 251.8 250.9 250.1 249.3 248.5 247.7 247.2 | 0.00494 0.00493 0.00491 0.00490 0.00488 0.00487 0.00486 | 9.4 9.4 9.4 9.3 9.3 9.3 9.3 9.3 | 1055 1053 1049 1045 1042 1038 1035 1032 | 1240 1238 1233 1229 1225 1221 1217 1214 | 36 35 35 34 34 34 33 | 433 433 432 432 432 432 432 431 |
| | 910.0 900.0 890.0 880.0 870.0 860.0 850.0 840.0 | 175.7 175.1 174.6 174.0 173.4 172.8 172.5 171.8 | 0.0 0.0 0.0 0.0 0.0 0.0 0.0 0.0 0.0 0.0 | 176.0 175.7 175.1 174.6 174.0 173.4 172.8 172.5 171.8 | 252.2 251.8 250.9 250.1 249.3 248.5 247.7 247.2 246.3 | 0.00494 0.00493 0.00491 0.00490 0.00488 0.00487 0.00486 0.00484 | 9.4 9.4 9.4 9.3 9.3 9.3 9.3 9.3 9.2 | 1055 1053 1049 1045 1042 1038 1035 1032 1028 | 1240 1238 1233 1229 1225 1221 1217 1214 1209 | 36 35 34 34 34 33 33 | 433 433 432 432 432 432 432 431 431 |
| | 910.0 900.0 890.0 880.0 870.0 860.0 850.0 | 175.7 175.1 174.6 174.0 173.4 172.8 172.5 | 0.0 0.0 0.0 0.0 0.0 0.0 0.0 0.0 | 176.0 175.7 175.1 174.6 174.0 173.4 172.8 172.5 | 252.2 251.8 250.9 250.1 249.3 248.5 247.7 247.2 | 0.00494 0.00493 0.00491 0.00490 0.00488 0.00487 0.00486 | 9.4 9.4 9.4 9.3 9.3 9.3 9.3 9.3 | 1055 1053 1049 1045 1042 1038 1035 1032 | 1240 1238 1233 1229 1225 1221 1217 1214 | 36 35 35 34 34 34 33 | 433 433 432 432 432 432 432 431 |
| | 910.0 900.0 890.0 880.0 870.0 860.0 850.0 840.0 830.0 | 175.7 175.1 174.6 174.0 173.4 172.8 172.5 171.8 171.2 | 0.0 0.0 0.0 0.0 0.0 0.0 0.0 0.0 0.0 0.0 | 176.0 175.7 175.1 174.6 174.0 173.4 172.8 172.5 171.8 171.2 | 252.2 251.8 250.9 250.1 249.3 248.5 247.7 247.2 246.3 245.3 | 0.00494 0.00493 0.00491 0.00490 0.00488 0.00487 0.00486 0.00484 0.00482 | 9.4 9.4 9.4 9.3 9.3 9.3 9.3 9.3 9.2 9.2 | 1055 1053 1049 1045 1042 1038 1035 1032 1028 1024 | 1240 1238 1233 1229 1225 1221 1217 1214 1209 1204 | 36 35 34 34 34 33 33 33 | 433 432 432 432 432 432 431 431 431 |
| | 910.0 900.0 890.0 870.0 860.0 850.0 840.0 830.0 820.0 | 175.7 175.1 174.6 174.0 173.4 172.8 172.5 171.8 171.2 170.4 | 0.0 0.0 0.0 0.0 0.0 0.0 0.0 0.0 0.0 0.0 | 176.0 175.7 175.1 174.6 174.0 173.4 172.8 172.5 171.8 171.2 170.4 | 252.2 251.8 250.9 250.1 249.3 248.5 247.7 247.2 246.3 245.3 244.2 | 0.00494 0.00493 0.00491 0.00490 0.00488 0.00487 0.00486 0.00484 0.00482 0.00482 | 9.4 9.4 9.4 9.3 9.3 9.3 9.3 9.2 9.2 9.2 9.1 | 1055 1053 1049 1045 1042 1038 1035 1032 1028 1024 1019 | 1240 1238 1233 1229 1225 1221 1217 1214 1209 1204 1198 | 36 35 34 34 34 33 33 33 33 32 | 433 432 432 432 432 432 431 431 431 431 |
| | 910.0 900.0 890.0 870.0 860.0 850.0 840.0 830.0 820.0 810.0 | 175.7 175.1 174.6 174.0 173.4 172.8 172.5 171.8 171.2 170.4 169.5 | 0.0 0.0 0.0 0.0 0.0 0.0 0.0 0.0 0.0 0.0 | 176.0 175.7 175.1 174.6 174.0 173.4 172.8 172.5 171.8 171.2 170.4 169.5 | 252.2 251.8 250.9 250.1 249.3 248.5 247.7 247.2 246.3 245.3 244.2 243.0 | 0.00494 0.00493 0.00491 0.00490 0.00488 0.00487 0.00486 0.00484 0.00482 0.00482 0.00480 0.00477 | 9.4 9.4 9.4 9.3 9.3 9.3 9.3 9.2 9.2 9.1 9.1 | 1055 1053 1049 1045 1042 1038 1035 1032 1028 1024 1019 1013 | 1240 1238 1229 1225 1221 1217 1214 1209 1204 1198 1192 | 36 35 34 34 34 33 33 33 32 32 | 433 432 432 432 432 432 431 431 431 431 430 |
| | 910.0 900.0 890.0 870.0 860.0 850.0 840.0 830.0 820.0 | 175.7 175.1 174.6 174.0 173.4 172.8 172.5 171.8 171.2 170.4 | 0.0 0.0 0.0 0.0 0.0 0.0 0.0 0.0 0.0 0.0 | 176.0 175.7 175.1 174.6 174.0 173.4 172.8 172.5 171.8 171.2 170.4 | 252.2 251.8 250.9 250.1 249.3 248.5 247.7 247.2 246.3 245.3 244.2 | 0.00494 0.00493 0.00491 0.00490 0.00488 0.00487 0.00486 0.00484 0.00482 0.00482 0.00480 0.00477 0.00475 | 9.4 9.4 9.4 9.3 9.3 9.3 9.3 9.2 9.2 9.2 9.1 | 1055 1053 1049 1045 1042 1038 1035 1032 1028 1024 1019 | 1240 1238 1233 1229 1225 1221 1217 1214 1209 1204 1198 | 36 35 34 34 34 33 33 33 33 32 | 433 432 432 432 432 432 431 431 431 431 |
| | 910.0 900.0 890.0 870.0 860.0 850.0 840.0 830.0 820.0 810.0 800.0 | 175.7 175.1 174.6 174.0 173.4 172.8 172.5 171.8 171.2 170.4 169.5 168.7 | 0.0 0.0 0.0 0.0 0.0 0.0 0.0 0.0 0.0 0.0 | 176.0 175.7 175.1 174.6 174.0 173.4 172.8 172.5 171.8 171.2 170.4 169.5 168.7 | 252.2 251.8 250.9 250.1 249.3 248.5 247.7 247.2 246.3 245.3 244.2 243.0 241.8 | 0.00494 0.00493 0.00491 0.00490 0.00488 0.00487 0.00486 0.00484 0.00482 0.00482 0.00480 0.00477 0.00475 | 9.4 9.4 9.4 9.3 9.3 9.3 9.3 9.2 9.2 9.1 9.1 9.0 | 1055 1053 1049 1045 1042 1038 1035 1032 1028 1024 1019 1013 1008 | 1240 1238 1229 1225 1221 1217 1214 1209 1204 1198 1192 1187 | 36 35 34 34 34 33 33 33 32 32 32 31 | 433 432 432 432 432 431 431 431 431 430 430 |
| | 910.0 900.0 890.0 870.0 860.0 850.0 840.0 830.0 820.0 810.0 800.0 790.0 | 175.7 175.1 174.6 174.0 173.4 172.8 172.5 171.8 171.2 170.4 169.5 168.7 167.9 | 0.0 0.0 0.0 0.0 0.0 0.0 0.0 0.0 0.0 0.0 | 176.0 175.7 175.1 174.6 174.0 173.4 172.8 172.5 171.8 171.2 170.4 169.5 168.7 167.9 | 252.2 251.8 250.9 250.1 249.3 248.5 247.7 247.2 246.3 245.3 244.2 243.0 241.8 240.6 | 0.00494 0.00493 0.00491 0.00490 0.00488 0.00487 0.00486 0.00484 0.00482 0.00482 0.00480 0.00477 0.00475 0.00473 | 9.4 9.4 9.4 9.3 9.3 9.3 9.3 9.2 9.2 9.1 9.1 9.0 9.0 | 1055 1053 1049 1045 1042 1038 1035 1032 1028 1024 1019 1013 1008 1002 | 1240 1238 1233 1229 1225 1221 1217 1214 1209 1204 1198 1192 1187 1182 | 36 35 34 34 33 33 33 33 32 32 31 31 | 433 432 432 432 432 431 431 431 431 430 430 430 |
| | 910.0 900.0 890.0 870.0 860.0 850.0 840.0 830.0 820.0 810.0 800.0 790.0 780.0 | 175.7 175.1 174.6 174.0 173.4 172.8 172.5 171.8 171.2 170.4 169.5 168.7 167.9 167.0 | 0.0 0.0 0.0 0.0 0.0 0.0 0.0 0.0 0.0 0.0 | 176.0 175.7 175.1 174.6 174.0 173.4 172.8 172.5 171.8 171.2 170.4 169.5 168.7 167.9 167.0 | 252.2 251.8 250.9 250.1 249.3 248.5 247.7 247.2 246.3 245.3 244.2 243.0 241.8 240.6 239.4 | 0.00494 0.00493 0.00491 0.00490 0.00488 0.00487 0.00486 0.00484 0.00482 0.00482 0.00480 0.00477 0.00475 0.00473 0.00471 | 9.4 9.4 9.4 9.3 9.3 9.3 9.3 9.2 9.2 9.1 9.1 9.0 9.0 9.0 | 1055 1053 1049 1045 1042 1038 1035 1032 1028 1024 1019 1013 1008 1002 997 | 1240 1238 1233 1229 1225 1221 1217 1214 1209 1204 1198 1192 1187 1182 1177 | 36 35 34 34 33 33 33 32 32 31 31 31 | 433 433 432 432 432 431 431 431 431 430 430 430 430 430 |
| | 910.0 900.0 890.0 870.0 860.0 850.0 840.0 830.0 820.0 810.0 800.0 790.0 780.0 770.0 | 175.7 175.1 174.6 174.0 173.4 172.8 172.5 171.8 171.2 170.4 169.5 168.7 167.9 167.0 166.2 | 0.0 0.0 0.0 0.0 0.0 0.0 0.0 0.0 0.0 0.0 | 176.0 175.7 175.1 174.6 174.0 173.4 172.8 172.5 171.8 171.2 170.4 169.5 168.7 167.9 167.0 166.2 | 252.2 251.8 250.9 250.1 249.3 248.5 247.7 247.2 246.3 245.3 244.2 243.0 241.8 240.6 239.4 238.2 | 0.00494 0.00493 0.00491 0.00490 0.00488 0.00487 0.00486 0.00484 0.00482 0.00482 0.00480 0.00477 0.00475 0.00473 0.00471 0.00468 | 9.4 9.4 9.4 9.3 9.3 9.3 9.2 9.2 9.1 9.1 9.0 9.0 9.0 8.9 | 1055 1053 1049 1045 1042 1038 1035 1032 1028 1024 1019 1013 1008 1002 997 992 | 1240 1238 1233 1229 1225 1221 1217 1214 1209 1204 1198 1192 1187 1182 1177 1171 | 36 35 34 34 34 33 33 33 32 32 31 31 31 30 | 433 432 432 432 432 431 431 431 431 430 430 430 430 430 429 |
| | 910.0 900.0 890.0 870.0 860.0 850.0 840.0 830.0 820.0 810.0 800.0 790.0 780.0 | 175.7 175.1 174.6 174.0 173.4 172.8 172.5 171.8 171.2 170.4 169.5 168.7 167.9 167.0 | 0.0 0.0 0.0 0.0 0.0 0.0 0.0 0.0 0.0 0.0 | 176.0 175.7 175.1 174.6 174.0 173.4 172.8 172.5 171.8 171.2 170.4 169.5 168.7 167.9 167.0 | 252.2 251.8 250.9 250.1 249.3 248.5 247.7 247.2 246.3 245.3 244.2 243.0 241.8 240.6 239.4 | 0.00494 0.00493 0.00491 0.00490 0.00488 0.00487 0.00486 0.00484 0.00482 0.00482 0.00480 0.00477 0.00475 0.00473 0.00471 | 9.4 9.4 9.4 9.3 9.3 9.3 9.3 9.2 9.2 9.1 9.1 9.0 9.0 9.0 | 1055 1053 1049 1045 1042 1038 1035 1032 1028 1024 1019 1013 1008 1002 997 | 1240 1238 1233 1229 1225 1221 1217 1214 1209 1204 1198 1192 1187 1182 1177 | 36 35 34 34 33 33 33 32 32 31 31 31 | 433 433 432 432 432 431 431 431 431 430 430 430 430 430 |
| | 910.0 900.0 890.0 870.0 860.0 850.0 840.0 830.0 820.0 810.0 800.0 790.0 780.0 770.0 760.0 | 175.7 175.1 174.6 174.0 173.4 172.8 172.5 171.8 171.2 170.4 169.5 168.7 167.9 167.0 166.2 165.4 | 0.0 0.0 0.0 0.0 0.0 0.0 0.0 0.0 0.0 0.0 | 176.0 175.7 175.1 174.6 174.0 173.4 172.8 172.5 171.8 171.2 170.4 169.5 168.7 167.9 167.0 166.2 165.4 | 252.2 251.8 250.9 250.1 249.3 248.5 247.7 247.2 246.3 245.3 244.2 243.0 241.8 240.6 239.4 238.2 237.1 | 0.00494 0.00493 0.00491 0.00490 0.00488 0.00487 0.00486 0.00484 0.00482 0.00482 0.00480 0.00477 0.00475 0.00473 0.00471 0.00468 0.00466 | 9.4 9.4 9.4 9.3 9.3 9.3 9.2 9.2 9.1 9.1 9.0 9.0 9.0 8.9 8.9 | 1055 1053 1049 1045 1042 1038 1035 1032 1028 1024 1019 1013 1008 1002 997 992 986 | 1240 1238 1233 1229 1225 1221 1217 1214 1209 1204 1198 1192 1187 1182 1177 1171 1166 | 36 35 34 34 34 33 33 33 32 32 31 31 31 30 30 | 433 432 432 432 432 431 431 431 431 430 430 430 430 430 429 429 |
| | 910.0 900.0 890.0 870.0 860.0 850.0 840.0 830.0 820.0 810.0 800.0 790.0 780.0 770.0 760.0 750.0 | 175.7 175.1 174.6 174.0 173.4 172.8 172.5 171.8 171.2 170.4 169.5 168.7 167.9 167.0 166.2 165.4 164.5 | 0.0 0.0 0.0 0.0 0.0 0.0 0.0 0.0 0.0 0.0 | 176.0 175.7 175.1 174.6 174.0 173.4 172.8 172.5 171.8 171.2 170.4 169.5 168.7 167.9 167.0 166.2 165.4 164.5 | 252.2 251.8 250.9 250.1 249.3 248.5 247.7 247.2 246.3 244.2 243.0 241.8 240.6 239.4 238.2 237.1 235.9 | 0.00494 0.00493 0.00491 0.00490 0.00488 0.00487 0.00486 0.00484 0.00482 0.00482 0.00480 0.00477 0.00475 0.00473 0.00471 0.00468 0.00466 0.00464 | 9.4 9.4 9.4 9.3 9.3 9.3 9.2 9.2 9.1 9.1 9.0 9.0 8.9 8.8 | 1055 1053 1049 1045 1042 1038 1035 1032 1028 1024 1019 1013 1008 1002 997 992 986 981 | 1240 1238 1223 1225 1221 1217 1214 1209 1204 1198 1192 1187 1182 1177 1171 1166 1161 | 36 35 34 34 34 33 33 33 32 32 31 31 31 30 30 29 | 433 432 432 432 432 431 431 431 431 430 430 430 430 430 429 429 429 |
| | 910.0 900.0 890.0 880.0 850.0 840.0 830.0 820.0 810.0 800.0 790.0 780.0 770.0 760.0 750.0 740.0 | 175.7 175.1 174.6 174.0 173.4 172.8 172.5 171.8 171.2 170.4 169.5 168.7 167.9 167.0 166.2 165.4 164.5 163.7 | 0.0 0.0 0.0 0.0 0.0 0.0 0.0 0.0 0.0 0.0 | 176.0 175.7 175.1 174.6 174.0 173.4 172.8 172.5 171.8 171.2 170.4 169.5 168.7 167.9 167.0 166.2 165.4 164.5 163.7 | 252.2 251.8 250.9 250.1 249.3 248.5 247.7 247.2 246.3 245.3 244.2 243.0 241.8 240.6 239.4 238.2 237.1 235.9 234.7 | 0.00494 0.00493 0.00491 0.00490 0.00488 0.00487 0.00486 0.00484 0.00482 0.00482 0.00477 0.00475 0.00473 0.00471 0.00468 0.00466 0.00461 | 9.4 9.4 9.4 9.3 9.3 9.3 9.2 9.2 9.1 9.1 9.0 9.0 8.9 8.8 8.8 | 1055 1053 1049 1045 1042 1038 1035 1032 1028 1024 1019 1013 1008 1002 997 992 986 981 975 | 1240 1238 1233 1229 1225 1221 1217 1214 1209 1204 1198 1192 1187 1182 1177 1171 1166 1161 1155 | 36 35 34 34 34 33 33 33 32 32 31 31 31 30 30 29 29 | 433 432 432 432 432 431 431 431 431 430 430 430 430 430 430 429 429 429 429 |
| | 910.0 900.0 890.0 870.0 860.0 850.0 840.0 830.0 820.0 810.0 800.0 790.0 780.0 770.0 760.0 750.0 | 175.7 175.1 174.6 174.0 173.4 172.8 172.5 171.8 171.2 170.4 169.5 168.7 167.9 167.0 166.2 165.4 164.5 | 0.0 0.0 0.0 0.0 0.0 0.0 0.0 0.0 0.0 0.0 | 176.0 175.7 175.1 174.6 174.0 173.4 172.8 172.5 171.8 171.2 170.4 169.5 168.7 167.9 167.0 166.2 165.4 164.5 | 252.2 251.8 250.9 250.1 249.3 248.5 247.7 247.2 246.3 244.2 243.0 241.8 240.6 239.4 238.2 237.1 235.9 | 0.00494 0.00493 0.00491 0.00490 0.00488 0.00487 0.00486 0.00484 0.00482 0.00482 0.00480 0.00477 0.00475 0.00473 0.00471 0.00468 0.00466 0.00464 | 9.4 9.4 9.4 9.3 9.3 9.3 9.2 9.2 9.1 9.1 9.0 9.0 8.9 8.8 | 1055 1053 1049 1045 1042 1038 1035 1032 1028 1024 1019 1013 1008 1002 997 992 986 981 | 1240 1238 1223 1225 1221 1217 1214 1209 1204 1198 1192 1187 1182 1177 1171 1166 1161 | 36 35 34 34 34 33 33 33 32 32 31 31 31 30 30 29 | 433 432 432 432 432 431 431 431 431 430 430 430 430 430 429 429 429 |
| | 910.0 900.0 890.0 880.0 850.0 840.0 830.0 820.0 810.0 800.0 790.0 780.0 770.0 760.0 750.0 740.0 730.0 | 175.7 175.1 174.6 174.0 173.4 172.8 172.5 171.8 171.2 170.4 169.5 168.7 167.9 167.0 166.2 165.4 164.5 163.7 163.0 | 0.0 | 176.0 175.7 175.1 174.6 174.0 173.4 172.8 172.5 171.8 171.2 170.4 169.5 168.7 167.9 167.0 166.2 165.4 164.5 163.7 163.0 | 252.2 251.8 250.9 250.1 249.3 248.5 247.7 247.2 246.3 245.3 244.2 243.0 241.8 240.6 239.4 238.2 237.1 235.9 234.7 233.7 | 0.00494 0.00493 0.00491 0.00490 0.00488 0.00487 0.00486 0.00484 0.00482 0.00482 0.00477 0.00475 0.00473 0.00471 0.00468 0.00466 0.00461 0.00459 | 9.4 9.4 9.4 9.3 9.3 9.3 9.2 9.2 9.1 9.0 9.0 9.0 8.9 8.8 8.8 8.8 8.7 | 1055 1053 1049 1045 1042 1038 1035 1032 1028 1024 1019 1013 1008 1002 997 992 986 981 975 971 | 1240 1238 1233 1229 1225 1221 1217 1214 1209 1204 1198 1192 1187 1182 1177 1171 1166 1161 1155 1151 | 36 35 34 34 34 33 33 33 32 32 31 31 31 30 30 29 29 29 29 | 433 432 432 432 432 431 431 431 431 430 430 430 430 430 430 429 429 429 429 429 |
| | 910.0 900.0 890.0 880.0 850.0 840.0 830.0 820.0 810.0 800.0 790.0 780.0 770.0 760.0 750.0 740.0 730.0 720.0 | 175.7 175.1 174.6 174.0 173.4 172.8 172.5 171.8 171.2 170.4 169.5 168.7 167.9 167.0 166.2 165.4 164.5 163.7 163.0 162.4 | 0.0 0.0 0.0 0.0 0.0 0.0 0.0 0.0 0.0 0.0 | 176.0 175.7 175.1 174.6 174.0 173.4 172.8 172.5 171.8 171.2 170.4 169.5 168.7 167.9 167.0 166.2 165.4 164.5 163.7 163.0 162.4 | 252.2 251.8 250.9 250.1 249.3 248.5 247.7 247.2 246.3 245.3 244.2 243.0 241.8 240.6 239.4 238.2 237.1 235.9 234.7 233.7 232.8 | 0.00494 0.00493 0.00491 0.00490 0.00488 0.00487 0.00486 0.00484 0.00482 0.00482 0.00477 0.00475 0.00473 0.00471 0.00468 0.00466 0.00464 0.00461 0.00459 0.00458 | 9.4 9.4 9.4 9.3 9.3 9.3 9.2 9.2 9.1 9.1 9.0 9.0 9.0 8.9 8.8 8.8 8.8 8.7 8.7 | 1055 1053 1049 1045 1042 1038 1035 1032 1028 1024 1019 1013 1008 1002 997 992 986 981 975 971 967 | 1240 1238 1233 1229 1225 1221 1217 1214 1209 1204 1198 1192 1187 1182 1177 1171 1166 1161 1155 1151 1147 | 36 35 34 34 34 33 33 33 32 32 31 31 31 30 30 29 29 29 29 28 | 433 432 432 432 432 431 431 431 431 430 430 430 430 430 430 429 429 429 429 429 429 428 428 |
| | 910.0 900.0 890.0 880.0 850.0 840.0 830.0 820.0 810.0 800.0 790.0 780.0 770.0 760.0 750.0 740.0 730.0 720.0 710.0 | 175.7 175.1 174.6 174.0 173.4 172.8 172.5 171.8 171.2 170.4 169.5 168.7 167.9 167.0 166.2 165.4 164.5 163.7 163.0 162.4 161.8 | 0.0 | 176.0 175.7 175.1 174.6 174.0 173.4 172.8 172.5 171.8 171.2 170.4 169.5 168.7 167.9 167.0 166.2 165.4 164.5 163.7 163.0 162.4 161.8 | 252.2 251.8 250.9 250.1 249.3 248.5 247.7 247.2 246.3 245.3 244.2 243.0 241.8 240.6 239.4 238.2 237.1 235.9 234.7 233.7 232.8 232.0 | 0.00494 0.00493 0.00491 0.00490 0.00488 0.00487 0.00486 0.00484 0.00482 0.00482 0.00480 0.00477 0.00475 0.00473 0.00471 0.00468 0.00466 0.00464 0.00461 0.00459 0.00458 0.00456 | 9.4 9.4 9.4 9.3 9.3 9.3 9.2 9.2 9.1 9.1 9.0 9.0 9.0 8.9 8.8 8.8 8.8 8.7 8.7 8.7 | 1055 1053 1049 1045 1042 1038 1035 1032 1028 1024 1019 1013 1008 1002 997 992 986 981 975 971 967 963 | 1240 1238 1233 1229 1225 1221 1217 1214 1209 1204 1198 1192 1187 1182 1177 1171 1166 1161 1155 1151 1147 1143 | 36 35 34 34 33 33 33 32 32 31 31 31 30 30 29 29 29 29 28 28 28 | 433 432 432 432 432 431 431 431 431 431 430 430 430 430 430 430 429 429 429 429 429 429 428 428 428 |
| | 910.0 900.0 890.0 880.0 850.0 840.0 830.0 820.0 810.0 800.0 790.0 780.0 770.0 760.0 750.0 740.0 730.0 720.0 | 175.7 175.1 174.6 174.0 173.4 172.8 172.5 171.8 171.2 170.4 169.5 168.7 167.9 167.0 166.2 165.4 164.5 163.7 163.0 162.4 | 0.0 0.0 0.0 0.0 0.0 0.0 0.0 0.0 0.0 0.0 | 176.0 175.7 175.1 174.6 174.0 173.4 172.8 172.5 171.8 171.2 170.4 169.5 168.7 167.9 167.0 166.2 165.4 164.5 163.7 163.0 162.4 | 252.2 251.8 250.9 250.1 249.3 248.5 247.7 247.2 246.3 245.3 244.2 243.0 241.8 240.6 239.4 238.2 237.1 235.9 234.7 233.7 232.8 | 0.00494 0.00493 0.00491 0.00490 0.00488 0.00487 0.00486 0.00484 0.00482 0.00482 0.00477 0.00475 0.00473 0.00471 0.00468 0.00466 0.00464 0.00461 0.00459 0.00458 | 9.4 9.4 9.4 9.3 9.3 9.3 9.2 9.2 9.1 9.1 9.0 9.0 9.0 8.9 8.8 8.8 8.8 8.7 8.7 | 1055 1053 1049 1045 1042 1038 1035 1032 1028 1024 1019 1013 1008 1002 997 992 986 981 975 971 967 | 1240 1238 1233 1229 1225 1221 1217 1214 1209 1204 1198 1192 1187 1182 1177 1171 1166 1161 1155 1151 1147 | 36 35 34 34 34 33 33 33 32 32 31 31 31 30 30 29 29 29 29 28 | 433 432 432 432 432 431 431 431 431 430 430 430 430 430 430 429 429 429 429 429 429 428 428 |
| | 910.0 900.0 890.0 880.0 850.0 840.0 830.0 820.0 810.0 800.0 790.0 780.0 750.0 740.0 730.0 720.0 710.0 700.0 | 175.7 175.1 174.6 174.0 173.4 172.8 172.5 171.8 171.2 170.4 169.5 168.7 167.9 167.0 166.2 165.4 164.5 163.7 163.0 162.4 161.8 161.2 | 0.0 | 176.0 175.7 175.1 174.6 174.0 173.4 172.8 172.5 171.8 171.2 170.4 169.5 168.7 167.9 167.0 166.2 165.4 164.5 163.7 163.0 162.4 161.8 161.2 | 252.2 251.8 250.9 250.1 249.3 248.5 247.7 247.2 246.3 245.3 244.2 243.0 241.8 240.6 239.4 238.2 237.1 235.9 234.7 233.7 232.8 232.0 231.1 | 0.00494 0.00493 0.00491 0.00490 0.00488 0.00487 0.00486 0.00482 0.00482 0.00482 0.00477 0.00475 0.00473 0.00471 0.00468 0.00466 0.00464 0.00461 0.00459 0.00458 0.00455 | 9.4 9.4 9.4 9.3 9.3 9.3 9.2 9.2 9.1 9.0 9.0 9.0 8.9 8.8 8.8 8.8 8.7 8.7 8.7 8.6 | 1055 1053 1049 1045 1042 1038 1035 1032 1028 1024 1019 1013 1008 1002 997 992 986 981 975 971 967 963 959 | 1240 1238 1229 1225 1221 1217 1214 1209 1204 1198 1192 1187 1182 1177 1171 1166 1161 1155 1151 1147 1143 1139 | 36 35 34 34 33 33 33 32 31 31 31 30 29 29 29 29 29 28 28 28 27 | 433 432 432 432 432 431 431 431 431 431 430 430 430 430 430 430 429 429 429 429 429 429 428 428 428 428 |
| | 910.0 900.0 890.0 880.0 850.0 840.0 830.0 820.0 810.0 800.0 790.0 780.0 750.0 740.0 750.0 740.0 730.0 720.0 710.0 700.0 690.0 | 175.7 175.1 174.6 174.0 173.4 172.8 172.5 171.8 171.2 170.4 169.5 168.7 167.9 167.0 166.2 165.4 164.5 163.7 163.0 162.4 161.8 161.2 160.6 | 0.0 | 176.0 175.7 175.1 174.6 174.0 173.4 172.8 172.5 171.8 171.2 170.4 169.5 168.7 167.9 167.0 166.2 165.4 164.5 163.7 163.0 162.4 161.8 161.2 160.6 | 252.2 251.8 250.9 250.1 249.3 248.5 247.7 247.2 246.3 245.3 244.2 243.0 241.8 240.6 239.4 238.2 237.1 235.9 234.7 233.7 232.8 232.0 231.1 230.3 | 0.00494 0.00493 0.00491 0.00490 0.00488 0.00487 0.00486 0.00482 0.00482 0.00482 0.00477 0.00475 0.00473 0.00471 0.00468 0.00466 0.00464 0.00461 0.00459 0.00458 0.00455 0.00453 | 9.4 9.4 9.4 9.3 9.3 9.3 9.2 9.2 9.1 9.0 9.0 9.0 8.9 8.8 8.8 8.7 8.7 8.7 8.6 8.6 | 1055 1053 1049 1045 1042 1038 1035 1032 1028 1024 1019 1013 1008 1002 997 992 986 981 975 971 967 963 959 955 | 1240 1238 1223 1225 1221 1217 1214 1209 1204 1198 1192 1187 1182 1177 1171 1166 1161 1155 1151 1147 1143 1139 1135 | 36 35 34 34 33 33 33 32 31 31 31 30 29 29 29 29 29 29 28 28 28 27 27 | 433 432 432 432 432 431 431 431 431 431 430 430 430 430 430 430 429 429 429 429 429 429 429 428 428 428 428 428 |
| | 910.0 900.0 890.0 880.0 850.0 840.0 830.0 820.0 810.0 800.0 790.0 780.0 750.0 740.0 750.0 740.0 730.0 720.0 710.0 700.0 690.0 680.0 | 175.7 175.1 174.6 174.0 173.4 172.8 172.5 171.8 171.2 170.4 169.5 168.7 167.9 167.0 166.2 165.4 164.5 163.7 163.0 162.4 164.5 163.7 163.0 162.4 161.8 161.2 160.6 160.0 | 0.0 | 176.0 175.7 175.1 174.6 174.0 173.4 172.8 172.5 171.8 171.2 170.4 169.5 168.7 167.9 167.0 166.2 165.4 164.5 163.7 163.0 162.4 161.8 161.2 160.6 160.0 | 252.2 251.8 250.9 250.1 249.3 248.5 247.7 247.2 246.3 245.3 244.2 243.0 241.8 240.6 239.4 238.2 237.1 235.9 234.7 233.7 232.8 232.0 231.1 230.3 229.4 | 0.00494 0.00493 0.00491 0.00490 0.00488 0.00487 0.00486 0.00484 0.00482 0.00482 0.00480 0.00477 0.00475 0.00473 0.00471 0.00468 0.00466 0.00464 0.00461 0.00459 0.00458 0.00455 0.00453 0.00451 | 9.4 9.4 9.4 9.3 9.3 9.3 9.2 9.2 9.1 9.0 9.0 9.0 8.9 8.8 8.8 8.8 8.7 8.7 8.7 8.6 8.6 8.6 | 1055 1053 1049 1045 1042 1038 1035 1032 1028 1024 1019 1013 1008 1002 997 992 986 981 975 971 967 963 959 955 951 | 1240 1238 1229 1225 1221 1217 1214 1209 1204 1198 1192 1187 1182 1177 1171 1166 1161 1155 1151 1147 1143 1139 1135 1131 | 36 35 34 34 33 33 33 32 31 31 31 30 29 29 29 29 29 29 29 28 28 27 27 27 | 433 432 432 432 432 431 431 431 431 431 430 430 430 430 430 429 429 429 429 429 429 429 428 428 428 428 428 428 427 |
| | 910.0 900.0 890.0 880.0 850.0 840.0 830.0 820.0 810.0 800.0 790.0 780.0 750.0 740.0 750.0 740.0 730.0 720.0 710.0 700.0 690.0 | 175.7 175.1 174.6 174.0 173.4 172.8 172.5 171.8 171.2 170.4 169.5 168.7 167.9 167.0 166.2 165.4 164.5 163.7 163.0 162.4 161.8 161.2 160.6 | 0.0 | 176.0 175.7 175.1 174.6 174.0 173.4 172.8 172.5 171.8 171.2 170.4 169.5 168.7 167.9 167.0 166.2 165.4 164.5 163.7 163.0 162.4 161.8 161.2 160.6 | 252.2 251.8 250.9 250.1 249.3 248.5 247.7 247.2 246.3 245.3 244.2 243.0 241.8 240.6 239.4 238.2 237.1 235.9 234.7 233.7 232.8 232.0 231.1 230.3 | 0.00494 0.00493 0.00491 0.00490 0.00488 0.00487 0.00486 0.00482 0.00482 0.00482 0.00477 0.00475 0.00473 0.00471 0.00468 0.00466 0.00464 0.00461 0.00459 0.00458 0.00455 0.00453 | 9.4 9.4 9.4 9.3 9.3 9.3 9.2 9.2 9.1 9.0 9.0 9.0 8.9 8.8 8.8 8.8 8.7 8.7 8.7 8.6 8.6 8.6 8.6 | 1055 1053 1049 1045 1042 1038 1035 1032 1028 1024 1019 1013 1008 1002 997 992 986 981 975 971 967 963 955 951 947 | 1240 1238 1223 1225 1221 1217 1214 1209 1204 1198 1192 1187 1182 1177 1171 1166 1161 1155 1151 1147 1143 1139 1135 | 36 35 34 34 33 33 33 32 31 31 31 30 29 29 29 29 29 29 28 28 27 27 27 26 | 433 432 432 432 432 431 431 431 431 430 430 430 430 430 430 429 429 429 429 429 429 429 429 428 428 428 428 428 428 427 427 |
| | 910.0 900.0 890.0 880.0 850.0 840.0 830.0 820.0 810.0 800.0 790.0 780.0 750.0 740.0 750.0 740.0 730.0 720.0 710.0 700.0 690.0 680.0 | 175.7 175.1 174.6 174.0 173.4 172.8 172.5 171.8 171.2 170.4 169.5 168.7 167.9 167.0 166.2 165.4 164.5 163.7 163.0 162.4 164.5 163.7 163.0 162.4 161.8 161.2 160.6 160.0 | 0.0 | 176.0 175.7 175.1 174.6 174.0 173.4 172.8 172.5 171.8 171.2 170.4 169.5 168.7 167.9 167.0 166.2 165.4 164.5 163.7 163.0 162.4 161.8 161.2 160.6 160.0 | 252.2 251.8 250.9 250.1 249.3 248.5 247.7 247.2 246.3 245.3 244.2 243.0 241.8 240.6 239.4 238.2 237.1 235.9 234.7 233.7 232.8 232.0 231.1 230.3 229.4 | 0.00494 0.00493 0.00491 0.00490 0.00488 0.00487 0.00486 0.00484 0.00482 0.00482 0.00480 0.00477 0.00475 0.00473 0.00471 0.00468 0.00466 0.00464 0.00461 0.00459 0.00458 0.00455 0.00453 0.00451 | 9.4 9.4 9.4 9.3 9.3 9.3 9.2 9.2 9.1 9.0 9.0 9.0 8.9 8.8 8.8 8.8 8.7 8.7 8.7 8.6 8.6 8.6 8.6 | 1055 1053 1049 1045 1042 1038 1035 1032 1028 1024 1019 1013 1008 1002 997 992 986 981 975 971 967 963 959 955 951 | 1240 1238 1229 1225 1221 1217 1214 1209 1204 1198 1192 1187 1182 1177 1171 1166 1161 1155 1151 1147 1143 1139 1135 1131 | 36 35 34 34 33 33 33 32 31 31 31 30 29 29 29 29 29 29 28 28 27 27 27 26 | 433 432 432 432 432 431 431 431 431 430 430 430 430 430 430 429 429 429 429 429 429 429 429 428 428 428 428 428 428 427 427 |
| | 910.0 900.0 890.0 880.0 850.0 840.0 830.0 820.0 810.0 800.0 790.0 780.0 760.0 750.0 740.0 730.0 720.0 710.0 700.0 690.0 680.0 660.0 | 175.7 175.1 174.6 174.0 173.4 172.8 172.5 171.8 171.2 170.4 169.5 168.7 167.9 167.0 166.2 165.4 164.5 163.7 163.0 162.4 164.5 163.7 163.0 162.4 164.5 163.7 163.0 162.4 161.8 161.2 160.6 160.0 159.4 158.8 | 0.0 | 176.0 175.7 175.1 174.6 174.0 173.4 172.8 172.5 171.8 171.2 170.4 169.5 168.7 167.9 167.0 166.2 165.4 164.5 163.7 163.0 162.4 161.8 161.2 160.6 160.0 159.4 158.8 | 252.2 251.8 250.9 250.1 249.3 248.5 247.7 247.2 246.3 245.3 244.2 243.0 241.8 240.6 239.4 238.2 237.1 235.9 234.7 233.7 232.8 232.0 231.1 230.3 229.4 228.6 227.7 | 0.00494 0.00493 0.00491 0.00490 0.00488 0.00487 0.00486 0.00484 0.00482 0.00482 0.00477 0.00475 0.00473 0.00471 0.00468 0.00466 0.00464 0.00461 0.00459 0.00458 0.00455 0.00455 0.00453 0.00451 0.00450 0.00448 | 9.4 9.4 9.4 9.3 9.3 9.3 9.2 9.2 9.1 9.0 9.0 9.0 9.0 8.9 8.8 8.8 8.8 8.7 8.7 8.7 8.6 8.6 8.6 8.6 8.5 | 1055 1053 1049 1045 1042 1038 1035 1032 1028 1024 1019 1013 1008 1002 997 992 986 981 975 971 967 963 955 951 947 943 | 1240 1238 1223 1225 1221 1217 1214 1209 1204 1198 1192 1187 1182 1177 1171 1166 1161 1155 1151 1147 1143 1139 1135 1131 1128 1124 | 36 35 34 34 33 33 33 32 31 31 31 30 29 29 29 29 29 29 29 29 29 29 29 29 29 | 433 432 432 432 432 431 431 431 431 430 430 430 430 430 430 429 429 429 429 429 429 429 429 429 429 |
| | 910.0 900.0 890.0 880.0 850.0 840.0 830.0 820.0 810.0 800.0 790.0 780.0 770.0 760.0 750.0 740.0 730.0 720.0 710.0 700.0 690.0 680.0 650.0 | 175.7 175.1 174.6 174.0 173.4 172.8 172.5 171.8 171.2 170.4 169.5 168.7 167.9 167.0 166.2 165.4 164.5 163.7 163.0 162.4 164.5 163.7 163.0 162.4 164.5 163.7 163.0 162.4 164.5 163.7 163.0 162.4 164.5 163.7 163.0 162.4 164.5 163.7 163.0 162.4 163.5 163.7 163.0 162.4 163.5 163.7 163.0 165.4 163.5 163.7 163.0 165.4 165.5 165.4 165.5 165.4 165.5 165.4 165.5 165.4 165.5 165.4 165.5 165.4 165.5 165.4 165.5 165.4 165.5 165.4 165.5 165.4 165.5 175.5 175.5 175.5 175.5 177.5 177.5 177.5 177.5 167.0 166.2 165.4 165.4 165.5 165.4 165.5 165.4 165.5 165.4 165.5 165.4 165.5 165.4 165.5 165.4 165.5 165.4 165.5 165.4 165.5 165.4 165.5 165.4 165.5 165.4 165.5 | 0.0 | 176.0 175.7 175.1 174.6 174.0 173.4 172.8 172.5 171.8 171.2 170.4 169.5 168.7 167.9 167.0 166.2 165.4 164.5 163.7 163.0 162.4 164.5 163.7 163.0 162.4 161.8 161.2 160.6 160.0 159.4 158.8 158.3 | 252.2 251.8 250.9 250.1 249.3 248.5 247.7 247.2 246.3 245.3 244.2 243.0 241.8 240.6 239.4 238.2 237.1 235.9 234.7 233.7 232.8 232.0 231.1 230.3 229.4 228.6 227.7 227.0 | 0.00494 0.00493 0.00491 0.00490 0.00488 0.00487 0.00486 0.00482 0.00482 0.00482 0.00477 0.00475 0.00473 0.00471 0.00468 0.00466 0.00466 0.00464 0.00459 0.00455 0.00455 0.00455 0.00453 0.00451 0.00450 0.00448 0.00447 | 9.4 9.4 9.4 9.3 9.3 9.3 9.2 9.2 9.1 9.0 9.0 9.0 9.0 8.9 8.8 8.8 8.7 8.7 8.7 8.7 8.6 8.6 8.6 8.5 8.5 | 1055 1053 1049 1045 1042 1038 1035 1032 1028 1024 1019 1013 1008 1002 997 992 986 981 975 971 967 963 955 951 947 943 940 | 1240 1238 1229 1225 1221 1217 1214 1209 1204 1198 1192 1187 1182 1177 1171 1166 1161 1155 1151 1147 1143 1139 1135 1131 1128 1124 | 36 35 34 34 33 33 33 32 31 31 31 30 29 29 29 29 29 29 29 29 29 29 29 29 29 | 433 432 432 432 432 431 431 431 431 430 430 430 430 430 430 429 429 429 429 429 429 429 429 429 429 |
| | 910.0 900.0 890.0 880.0 850.0 840.0 830.0 820.0 810.0 800.0 790.0 780.0 770.0 760.0 750.0 740.0 750.0 740.0 730.0 720.0 710.0 700.0 690.0 680.0 650.0 640.0 | 175.7 175.1 174.6 174.0 173.4 172.8 172.5 171.8 171.2 170.4 169.5 168.7 167.9 167.0 166.2 165.4 164.5 163.7 163.0 162.4 164.5 163.7 163.0 162.4 164.5 163.7 163.0 162.4 164.5 163.7 163.0 162.4 164.5 163.7 163.0 162.4 164.5 163.7 163.0 162.4 164.5 163.7 163.0 162.4 163.5 163.7 163.0 165.4 164.5 163.7 163.0 165.4 165.5 165.4 165.5 165.4 165.5 165.4 165.5 165.4 165.5 165.4 165.5 165.4 165.5 165.4 165.5 165.7 165.4 165.5 165.4 165.5 165.4 165.5 165.4 165.5 165.4 165.5 165.4 165.5 165.4 165.5 165.4 165.5 165.4 165.5 165.4 165.5 165.4 165.5 165.4 165.5 165.4 165.5 165.4 165.5 165.4 165.5 165.4 165.5 165.4 165.5 165.4 165.5 | 0.0 | 176.0 175.7 175.1 174.6 174.0 173.4 172.8 172.5 171.8 171.2 170.4 169.5 168.7 167.9 167.0 166.2 165.4 164.5 163.7 163.0 162.4 164.5 163.7 163.0 162.4 161.8 161.2 160.6 160.0 159.4 158.8 158.3 157.6 | 252.2 251.8 250.9 250.1 249.3 248.5 247.7 247.2 246.3 245.3 244.2 243.0 241.8 240.6 239.4 238.2 237.1 235.9 234.7 233.7 232.8 232.0 231.1 230.3 229.4 228.6 227.7 227.0 226.1 | 0.00494 0.00493 0.00491 0.00490 0.00488 0.00487 0.00486 0.00482 0.00482 0.00482 0.00477 0.00475 0.00473 0.00471 0.00468 0.00466 0.00466 0.00464 0.00461 0.00459 0.00455 0.00455 0.00455 0.00453 0.00451 0.00450 0.00448 0.00447 0.00445 | 9.4 9.4 9.4 9.3 9.3 9.3 9.2 9.2 9.1 9.0 9.0 9.0 9.0 8.9 8.8 8.8 8.7 8.7 8.7 8.7 8.6 8.6 8.6 8.5 8.5 8.5 | 1055 1053 1049 1045 1042 1038 1035 1032 1028 1024 1019 1013 1008 1002 997 992 986 981 975 971 967 963 955 951 947 943 940 935 | 1240 1238 1233 1229 1225 1221 1217 1214 1209 1204 1198 1192 1187 1182 1177 1171 1166 1161 1155 1151 1147 1143 1139 1135 1131 1128 1124 1121 | 36 35 34 34 33 33 33 32 31 31 31 30 29 29 29 28 28 27 27 26 26 25 25 | 433 433 432 432 432 431 431 431 431 430 430 430 430 430 430 429 429 429 429 429 429 429 429 429 429 |
| | 910.0 900.0 890.0 880.0 850.0 840.0 830.0 820.0 810.0 800.0 790.0 780.0 770.0 760.0 750.0 740.0 750.0 740.0 730.0 720.0 710.0 700.0 690.0 680.0 650.0 640.0 | 175.7 175.1 174.6 174.0 173.4 172.8 172.5 171.8 171.2 170.4 169.5 168.7 167.9 167.0 166.2 165.4 164.5 163.7 163.0 162.4 164.5 163.7 163.0 162.4 164.5 163.7 163.0 162.4 164.5 163.7 163.0 162.4 164.5 163.7 163.0 162.4 164.5 163.7 163.0 162.4 164.5 163.7 163.0 162.4 163.5 163.7 163.0 165.4 164.5 163.7 163.0 165.4 165.5 165.4 165.5 165.4 165.5 165.4 165.5 165.4 165.5 165.4 165.5 165.4 165.5 165.4 165.5 165.7 165.4 165.5 165.4 165.5 165.4 165.5 165.4 165.5 165.4 165.5 165.4 165.5 165.4 165.5 165.4 165.5 165.4 165.5 165.4 165.5 165.4 165.5 165.4 165.5 165.4 165.5 165.4 165.5 165.4 165.5 165.4 165.5 165.4 165.5 165.4 165.5 | 0.0 | 176.0 175.7 175.1 174.6 174.0 173.4 172.8 172.5 171.8 171.2 170.4 169.5 168.7 167.9 167.0 166.2 165.4 164.5 163.7 163.0 162.4 164.5 163.7 163.0 162.4 161.8 161.2 160.6 160.0 159.4 158.8 158.3 157.6 | 252.2 251.8 250.9 250.1 249.3 248.5 247.7 247.2 246.3 245.3 244.2 243.0 241.8 240.6 239.4 238.2 237.1 235.9 234.7 233.7 232.8 232.0 231.1 230.3 229.4 228.6 227.7 227.0 226.1 | 0.00494 0.00493 0.00491 0.00490 0.00488 0.00487 0.00486 0.00482 0.00482 0.00482 0.00477 0.00475 0.00473 0.00471 0.00468 0.00466 0.00466 0.00464 0.00459 0.00455 0.00455 0.00455 0.00453 0.00451 0.00450 0.00448 0.00447 | 9.4 9.4 9.4 9.3 9.3 9.3 9.2 9.2 9.1 9.0 9.0 9.0 9.0 8.9 8.8 8.8 8.7 8.7 8.7 8.7 8.6 8.6 8.6 8.5 8.5 8.5 | 1055 1053 1049 1045 1042 1038 1035 1032 1028 1024 1019 1013 1008 1002 997 992 986 981 975 971 967 963 955 951 947 943 940 935 | 1240 1238 1229 1225 1221 1217 1214 1209 1204 1198 1192 1187 1182 1177 1171 1166 1161 1155 1151 1147 1143 1139 1135 1131 1128 1124 | 36 35 34 34 33 33 33 32 31 31 31 30 29 29 29 28 28 27 27 26 26 25 25 | 433 433 432 432 432 431 431 431 431 430 430 430 430 430 430 429 429 429 429 429 429 429 429 429 429 |
| | 910.0 900.0 890.0 880.0 850.0 840.0 830.0 820.0 810.0 800.0 790.0 780.0 770.0 760.0 750.0 740.0 750.0 740.0 730.0 720.0 710.0 700.0 690.0 680.0 650.0 640.0 630.0 | 175.7 175.1 174.6 174.0 173.4 172.8 172.5 171.8 171.2 170.4 169.5 168.7 167.9 167.0 166.2 165.4 164.5 163.7 163.0 162.4 164.5 163.7 163.0 162.4 164.5 163.7 163.0 162.4 164.5 163.7 163.0 162.4 164.5 163.7 163.0 162.4 164.5 163.7 163.0 162.4 164.5 163.7 163.0 162.4 163.5 163.7 163.0 165.4 164.5 165.4 165.5 165.4 165.5 165.4 165.5 165.4 165.5 165.7 165.5 165.7 165.5 165.7 165.5 165.7 165.5 165.7 165.5 165.7 165.5 165.7 165.5 175.5 175.5 175.5 175.5 175.5 177.5 177.5 177.5 177.5 177.5 165.7 165.7 165.4 165.5 165.4 165.5 165.4 165.5 165.4 165.5 165.4 165.5 165.4 165.5 165.4 165.5 165.4 165.5 | 0.0 | 176.0 175.7 175.1 174.6 174.0 173.4 172.8 172.5 171.8 171.2 170.4 169.5 168.7 167.9 167.0 166.2 165.4 164.5 163.7 163.0 162.4 164.5 163.7 163.0 162.4 161.8 161.2 160.6 160.0 159.4 158.8 158.3 157.6 157.3 | 252.2 251.8 250.9 250.1 249.3 248.5 247.7 247.2 246.3 245.3 244.2 243.0 241.8 240.6 239.4 238.2 237.1 235.9 234.7 233.7 232.8 232.0 231.1 230.3 229.4 228.6 227.7 227.0 226.1 225.6 | 0.00494 0.00493 0.00491 0.00490 0.00488 0.00487 0.00486 0.00482 0.00482 0.00482 0.00477 0.00475 0.00473 0.00471 0.00468 0.00466 0.00464 0.00461 0.00459 0.00455 0.00455 0.00455 0.00453 0.00451 0.00448 0.00447 0.00445 0.00444 | 9.4 9.4 9.4 9.3 9.3 9.3 9.2 9.2 9.1 9.0 9.0 9.0 9.0 8.9 8.8 8.8 8.7 8.7 8.7 8.7 8.6 8.6 8.6 8.5 8.5 8.5 8.4 | 1055 1053 1049 1045 1042 1038 1035 1032 1028 1024 1019 1013 1008 1002 997 992 986 981 975 971 967 963 955 971 967 963 955 951 947 943 940 935 933 | 1240 1238 1233 1229 1225 1221 1217 1214 1209 1204 1198 1192 1187 1182 1177 1182 1177 1171 1166 1161 1155 1151 1147 1143 1139 1135 1131 1128 1124 1121 1126 | 36 35 34 34 33 33 33 32 31 31 31 30 29 29 29 28 29 29 28 28 27 27 26 25 25 25 25 | 433 433 432 432 432 431 431 431 431 430 430 430 430 430 430 429 429 429 429 429 429 429 429 429 429 |
| | 910.0 900.0 890.0 880.0 850.0 840.0 830.0 820.0 810.0 800.0 790.0 780.0 770.0 760.0 750.0 740.0 750.0 740.0 730.0 720.0 710.0 700.0 690.0 680.0 650.0 640.0 630.0 620.0 | 175.7 175.1 174.6 174.0 173.4 172.8 172.5 171.8 171.2 170.4 169.5 168.7 167.9 167.0 166.2 165.4 164.5 163.7 163.0 162.4 164.5 163.7 163.0 162.4 164.5 163.7 163.0 162.4 164.5 163.7 163.0 159.4 158.8 158.3 157.6 157.3 156.9 | 0.0 | 176.0 175.7 175.1 174.6 174.0 173.4 172.8 172.5 171.8 171.2 170.4 169.5 168.7 167.9 167.0 166.2 165.4 164.5 163.7 163.0 162.4 164.5 163.7 163.0 162.4 161.8 161.2 160.6 160.0 159.4 158.8 158.3 157.6 157.3 156.9 | 252.2 251.8 250.9 250.1 249.3 248.5 247.7 247.2 246.3 245.3 244.2 243.0 241.8 240.6 239.4 238.2 237.1 235.9 234.7 233.7 232.8 232.0 231.1 230.3 229.4 228.6 227.7 227.0 226.1 225.6 225.1 | 0.00494 0.00493 0.00491 0.00490 0.00488 0.00487 0.00486 0.00482 0.00482 0.00482 0.00477 0.00475 0.00473 0.00471 0.00468 0.00466 0.00464 0.00461 0.00459 0.00455 0.00455 0.00455 0.00455 0.00453 0.00451 0.00451 0.00448 0.00447 0.00444 0.00443 | 9.4 9.4 9.4 9.3 9.3 9.3 9.2 9.2 9.1 9.0 9.0 9.0 9.0 8.9 8.8 8.8 8.7 8.7 8.7 8.7 8.6 8.6 8.6 8.5 8.5 8.5 8.4 8.4 | $1055 \\ 1053 \\ 1049 \\ 1045 \\ 1042 \\ 1038 \\ 1035 \\ 1032 \\ 1028 \\ 1024 \\ 1019 \\ 1013 \\ 1008 \\ 1002 \\ 997 \\ 992 \\ 986 \\ 981 \\ 975 \\ 971 \\ 967 \\ 963 \\ 959 \\ 955 \\ 951 \\ 967 \\ 963 \\ 959 \\ 955 \\ 951 \\ 947 \\ 943 \\ 940 \\ 935 \\ 933 \\ 930 \\ $ | 1240 1238 1233 1229 1225 1221 1217 1214 1209 1204 1198 1192 1187 1182 1177 1182 1177 1171 1166 1161 1155 1151 1147 1143 1139 1135 1131 1128 1124 1121 1116 1114 1112 | 36 35 34 34 33 33 33 32 31 31 31 30 29 29 29 29 29 29 29 29 29 29 29 29 29 | 433 433 432 432 432 431 431 431 431 430 430 430 430 430 430 429 429 429 429 429 429 429 429 429 429 |
| | 910.0 900.0 890.0 880.0 850.0 840.0 830.0 820.0 810.0 800.0 790.0 780.0 770.0 760.0 750.0 740.0 750.0 740.0 730.0 720.0 710.0 700.0 690.0 680.0 650.0 640.0 630.0 620.0 610.0 | 175.7 175.1 174.6 174.0 173.4 172.8 172.5 171.8 171.2 170.4 169.5 168.7 167.9 167.0 166.2 165.4 164.5 163.7 163.0 162.4 164.5 163.7 163.0 162.4 164.5 163.7 163.0 162.4 164.5 163.7 163.0 159.4 158.8 158.3 157.6 157.3 156.9 156.6 | 0.0 0.0 0.0 0.0 0.0 0.0 0.0 0.0 0.0 0.0 | 176.0 175.7 175.1 174.6 174.0 173.4 172.8 172.5 171.8 171.2 170.4 169.5 168.7 167.9 167.0 166.2 165.4 164.5 163.7 163.0 162.4 161.8 161.2 160.6 160.0 159.4 158.8 157.3 156.9 156.6 | 252.2 251.8 250.9 250.1 249.3 248.5 247.7 247.2 246.3 245.3 244.2 243.0 241.8 244.2 243.0 241.8 244.2 237.1 235.9 234.7 233.7 233.7 233.7 232.0 231.1 230.3 229.4 228.6 227.7 227.0 226.1 225.6 225.1 225.6 | 0.00494 0.00493 0.00491 0.00490 0.00488 0.00487 0.00486 0.00482 0.00482 0.00482 0.00477 0.00475 0.00473 0.00471 0.00468 0.00466 0.00464 0.00461 0.00459 0.00455 0.00455 0.00455 0.00455 0.00455 0.00453 0.00451 0.00448 0.00447 0.00444 0.00443 0.00442 | 9.4 9.4 9.4 9.3 9.3 9.3 9.2 9.2 9.1 9.0 9.0 9.0 9.0 9.0 8.9 8.8 8.8 8.7 8.7 8.7 8.6 8.6 8.6 8.5 8.5 8.4 8.4 | 1055 1053 1049 1045 1042 1038 1035 1032 1028 1024 1019 1013 1008 1002 997 992 986 981 975 971 967 963 955 951 947 943 940 935 933 930 928 | 1240 1238 1233 1229 1225 1221 1217 1214 1209 1204 1198 1192 1187 1182 1177 1171 1166 1161 1155 1151 1147 1143 1139 1135 1131 1128 1124 1121 1116 1114 1112 | 36 35 34 34 33 33 32 32 31 31 31 30 29 29 29 29 29 29 29 29 29 29 29 29 29 | 433 432 432 432 432 431 431 431 431 430 430 430 430 430 429 429 429 429 429 429 429 429 429 429 |
| | 910.0 900.0 890.0 880.0 850.0 840.0 830.0 820.0 810.0 800.0 790.0 780.0 770.0 760.0 750.0 740.0 750.0 740.0 730.0 720.0 710.0 700.0 690.0 680.0 650.0 640.0 630.0 620.0 | 175.7 175.1 174.6 174.0 173.4 172.8 172.5 171.8 171.2 170.4 169.5 168.7 167.9 167.0 166.2 165.4 164.5 163.7 163.0 162.4 164.5 163.7 163.0 162.4 164.5 163.7 163.0 162.4 164.5 163.7 163.0 159.4 158.8 158.3 157.6 157.3 156.9 156.6 | 0.0 0.0 0.0 0.0 0.0 0.0 0.0 0.0 0.0 0.0 | 176.0 175.7 175.1 174.6 174.0 173.4 172.8 172.5 171.8 171.2 170.4 169.5 168.7 167.9 167.0 166.2 165.4 164.5 163.7 163.0 162.4 161.8 161.2 160.6 160.0 159.4 158.8 157.3 156.9 156.6 | 252.2 251.8 250.9 250.1 249.3 248.5 247.7 247.2 246.3 245.3 244.2 243.0 241.8 244.2 243.0 241.8 244.2 237.1 235.9 234.7 233.7 233.7 233.7 232.0 231.1 230.3 229.4 228.6 227.7 227.0 226.1 225.6 225.1 225.6 | 0.00494 0.00493 0.00491 0.00490 0.00488 0.00487 0.00486 0.00482 0.00482 0.00482 0.00477 0.00475 0.00473 0.00471 0.00468 0.00466 0.00464 0.00461 0.00459 0.00455 0.00455 0.00455 0.00455 0.00453 0.00451 0.00451 0.00448 0.00447 0.00444 0.00443 | 9.4 9.4 9.4 9.3 9.3 9.3 9.2 9.2 9.1 9.0 9.0 9.0 9.0 9.0 8.9 8.8 8.8 8.7 8.7 8.7 8.6 8.6 8.6 8.5 8.5 8.4 8.4 | 1055 1053 1049 1045 1042 1038 1035 1032 1028 1024 1019 1013 1008 1002 997 992 986 981 975 971 967 963 955 951 947 943 940 935 933 930 928 | 1240 1238 1233 1229 1225 1221 1217 1214 1209 1204 1198 1192 1187 1182 1177 1182 1177 1171 1166 1161 1155 1151 1147 1143 1139 1135 1131 1128 1124 1121 1116 1114 1112 | 36 35 34 34 33 33 33 32 31 31 31 30 29 29 29 29 29 29 29 29 29 29 29 29 29 | 433 433 432 432 432 431 431 431 431 430 430 430 430 430 430 429 429 429 429 429 429 429 429 429 429 |
| | 910.0 900.0 890.0 880.0 870.0 860.0 850.0 840.0 830.0 820.0 810.0 790.0 780.0 770.0 760.0 750.0 740.0 750.0 740.0 730.0 720.0 710.0 700.0 690.0 680.0 650.0 640.0 630.0 620.0 610.0 600.0 | 175.7 175.1 174.6 174.0 173.4 172.8 172.5 171.8 171.2 170.4 169.5 168.7 167.9 167.0 166.2 165.4 164.5 163.7 163.0 162.4 164.5 163.7 163.0 162.4 164.5 163.7 163.0 162.4 164.5 163.7 163.0 159.4 158.8 158.3 157.6 157.3 156.9 156.6 156.2 | 0.0 | 176.0 175.7 175.1 174.6 174.0 173.4 172.8 172.5 171.8 171.2 170.4 169.5 168.7 167.9 167.0 166.2 165.4 164.5 163.7 163.0 162.4 161.8 161.2 160.6 160.0 159.4 158.8 157.3 156.9 156.6 156.2 | 252.2 251.8 250.9 250.1 249.3 248.5 247.7 247.2 246.3 245.3 244.2 243.0 241.8 244.2 243.0 241.8 244.2 237.1 235.9 234.7 233.7 233.7 233.7 232.8 232.0 231.1 230.3 229.4 228.6 227.7 227.0 226.1 225.6 225.1 225.6 225.1 224.6 | 0.00494 0.00493 0.00491 0.00490 0.00488 0.00487 0.00486 0.00482 0.00482 0.00482 0.00477 0.00475 0.00473 0.00471 0.00468 0.00464 0.00464 0.00464 0.00465 0.00455 0.00455 0.00455 0.00455 0.00455 0.00455 0.00445 0.00445 0.00444 0.00444 0.00443 0.00442 0.00441 | 9.4 9.4 9.4 9.3 9.3 9.3 9.2 9.2 9.1 9.0 9.0 9.0 9.0 9.0 8.9 8.8 8.8 8.7 8.7 8.7 8.7 8.7 8.6 8.6 8.6 8.5 8.5 8.4 8.4 8.4 8.4 | 1055 1053 1049 1045 1042 1038 1035 1032 1028 1024 1019 1013 1008 1002 997 992 986 981 975 971 967 963 955 951 947 943 940 935 933 930 928 926 | 1240 1238 1223 1225 1221 1217 1214 1209 1204 1198 1192 1187 1182 1177 1182 1177 1171 1166 1161 1155 1151 1147 1135 1131 1128 1124 1124 1121 1116 1114 1112 | 36 35 34 34 33 33 33 32 31 31 31 30 29 29 29 29 29 29 29 28 29 29 29 29 29 29 29 29 29 29 29 29 29 | 433 432 432 432 432 431 431 431 431 430 430 430 430 430 429 429 429 429 429 429 429 429 429 429 |
| | 910.0 900.0 890.0 880.0 850.0 840.0 830.0 820.0 810.0 790.0 780.0 770.0 760.0 750.0 740.0 750.0 740.0 750.0 740.0 750.0 660.0 660.0 660.0 650.0 640.0 630.0 620.0 610.0 600.0 590.0 | 175.7 175.1 174.6 174.0 173.4 172.8 172.5 171.8 171.2 170.4 169.5 168.7 167.0 166.2 165.4 164.5 163.7 163.0 162.4 164.5 163.7 163.0 162.4 164.5 163.7 163.0 162.4 164.8 161.2 160.6 160.0 159.4 158.8 158.3 157.6 157.3 156.9 156.6 156.2 155.9 | 0.0 | 176.0 175.7 175.1 174.6 174.0 173.4 172.8 172.5 171.8 171.2 170.4 169.5 168.7 167.9 167.0 166.2 165.4 164.5 163.7 163.0 162.4 161.8 161.2 160.6 160.0 159.4 158.8 157.3 156.9 156.6 156.2 155.9 | 252.2 251.8 250.9 250.1 249.3 248.5 247.7 247.2 246.3 245.3 244.2 243.0 241.8 244.2 243.0 241.8 244.2 239.4 239.4 234.7 233.7 232.8 232.7 233.7 232.8 232.1 230.3 229.4 228.6 227.7 227.0 226.1 225.6 225.1 225.6 225.1 225.6 225.1 225.6 225.1 225.6 225.1 225.6 225.1 225.6 225.1 225.6 225.1 225.6 225.1 | 0.00494 0.00493 0.00491 0.00490 0.00488 0.00487 0.00486 0.00482 0.00482 0.00482 0.00477 0.00475 0.00473 0.00471 0.00468 0.00466 0.00464 0.00461 0.00459 0.00455 0.00455 0.00455 0.00455 0.00455 0.00453 0.00451 0.00445 0.00444 0.00444 0.00444 0.00441 0.00441 0.00440 | 9.4 9.4 9.4 9.3 9.3 9.3 9.2 9.2 9.1 9.0 9.0 9.0 9.0 9.0 9.0 9.0 9.0 9.0 8.9 8.8 8.8 8.7 8.7 8.7 8.6 8.6 8.6 8.5 8.5 8.4 8.4 8.4 | 1055 1053 1049 1045 1042 1038 1035 1032 1028 1024 1019 1013 1008 1002 997 992 986 981 975 971 967 963 955 951 947 943 940 935 933 930 928 926 923 | 1240 1238 1223 1229 1225 1221 1217 1214 1209 1204 1198 1192 1187 1182 1177 1182 1177 1171 1166 1161 1155 1151 1147 1135 1131 1128 1124 1121 1116 1114 1112 1110 1107 1105 | 36 35 34 34 33 32 31 31 30 29 29 28 27 27 26 25 24 24 23 | 433 433 432 432 432 431 431 431 431 430 430 430 430 430 429 429 429 429 429 429 429 429 429 429 |
| | 910.0 900.0 890.0 880.0 870.0 860.0 850.0 840.0 830.0 820.0 810.0 790.0 780.0 770.0 760.0 750.0 740.0 750.0 740.0 750.0 740.0 750.0 660.0 660.0 650.0 640.0 650.0 640.0 650.0 630.0 730.0 730.0 730.0 740.0 740.0 750.0 740.0 750.0 740.0 750.0 740.0 750.0 750.0 740.0 750.0 740.0 750.0 750.0 740.0 750.0 | 175.7 175.1 174.6 174.0 173.4 172.8 172.5 171.8 171.2 170.4 169.5 168.7 167.0 166.2 165.4 164.5 163.7 163.0 162.4 164.5 163.7 163.0 162.4 164.5 163.7 163.0 162.4 161.8 161.2 160.6 160.0 159.4 158.8 157.6 156.9 156.6 156.2 155.9 155.5 | 0.0 | 176.0 175.7 175.1 174.6 174.0 173.4 172.8 172.5 171.8 171.2 170.4 169.5 168.7 167.9 167.0 166.2 165.4 164.5 163.7 163.0 162.4 161.8 161.2 160.6 160.0 159.4 158.8 157.3 156.9 156.6 156.2 155.9 155.5 | 252.2 251.8 250.9 250.1 249.3 248.5 247.7 247.2 246.3 245.3 244.2 243.0 241.8 244.2 243.0 241.8 244.2 239.4 239.4 239.4 235.9 234.7 233.7 232.8 232.0 231.1 230.3 229.4 228.6 227.7 227.0 226.1 225.6 225.1 225.6 225.1 225.6 225.1 225.6 225.1 225.6 225.1 225.6 225.1 225.6 225.1 225.6 225.1 225.6 225.1 | 0.00494 0.00493 0.00491 0.00490 0.00488 0.00487 0.00486 0.00482 0.00482 0.00482 0.00477 0.00475 0.00473 0.00471 0.00468 0.00466 0.00466 0.00465 0.00455 0.00455 0.00455 0.00455 0.00455 0.00455 0.00455 0.00455 0.00445 0.00445 0.00444 0.00444 0.00443 0.00442 0.00441 0.00440 0.00439 | 9.4 9.4 9.4 9.3 9.3 9.3 9.2 9.2 9.1 9.0 9.0 9.0 9.0 9.0 9.0 9.0 9.0 9.0 8.9 8.8 8.8 8.7 8.7 8.6 8.6 8.6 8.5 8.5 8.4 8.4 8.4 8.4 8.3 | 1055 1053 1049 1045 1042 1038 1035 1032 1028 1024 1019 1013 1008 1002 997 992 986 981 975 971 967 963 955 955 955 955 955 955 955 955 955 95 | 1240 1238 1229 1225 1221 1217 1214 1209 1204 1198 1192 1187 1182 1177 1182 1177 1171 1166 1161 1155 1151 1147 1135 1131 1128 1124 1121 1116 1114 1112 1110 1107 1105 1103 | 36 35 34 34 33 32 31 31 30 29 29 28 27 27 26 25 24 24 23 23 | 433 432 432 432 432 431 431 431 431 430 430 430 430 429 429 429 429 429 429 429 429 429 429 |
| | 910.0 900.0 890.0 880.0 850.0 840.0 830.0 820.0 810.0 790.0 780.0 770.0 760.0 750.0 740.0 750.0 740.0 750.0 740.0 750.0 660.0 660.0 660.0 650.0 640.0 630.0 620.0 610.0 600.0 590.0 | 175.7 175.1 174.6 174.0 173.4 172.8 172.5 171.8 171.2 170.4 169.5 168.7 167.0 166.2 165.4 164.5 163.7 163.0 162.4 164.5 163.7 163.0 162.4 164.5 163.7 163.0 162.4 164.8 161.2 160.6 160.0 159.4 158.8 158.3 157.6 157.3 156.9 156.6 156.2 155.9 | 0.0 | 176.0 175.7 175.1 174.6 174.0 173.4 172.8 172.5 171.8 171.2 170.4 169.5 168.7 167.9 167.0 166.2 165.4 164.5 163.7 163.0 162.4 161.8 161.2 160.6 160.0 159.4 158.8 157.3 156.9 156.6 156.2 155.9 | 252.2 251.8 250.9 250.1 249.3 248.5 247.7 247.2 246.3 245.3 244.2 243.0 241.8 244.2 243.0 241.8 244.2 239.4 238.2 237.1 235.9 234.7 233.7 232.8 232.0 231.1 230.3 229.4 228.6 227.7 227.0 226.1 225.6 225.1 225.6 225.1 225.6 225.1 225.6 225.1 225.6 225.1 225.6 225.1 225.6 225.1 225.6 225.1 225.6 225.1 | 0.00494 0.00493 0.00491 0.00490 0.00488 0.00487 0.00486 0.00482 0.00482 0.00482 0.00477 0.00475 0.00473 0.00471 0.00468 0.00466 0.00464 0.00461 0.00459 0.00455 0.00455 0.00455 0.00455 0.00455 0.00453 0.00451 0.00445 0.00444 0.00444 0.00444 0.00441 0.00441 0.00440 | 9.4 9.4 9.4 9.3 9.3 9.3 9.2 9.2 9.1 9.0 9.0 9.0 9.0 9.0 9.0 9.0 9.0 9.0 8.9 8.8 8.8 8.7 8.7 8.7 8.6 8.6 8.6 8.5 8.5 8.4 8.4 8.4 | 1055 1053 1049 1045 1042 1038 1035 1032 1028 1024 1019 1013 1008 1002 997 992 986 981 975 971 967 963 955 951 947 943 940 935 933 930 928 926 923 | 1240 1238 1223 1229 1225 1221 1217 1214 1209 1204 1198 1192 1187 1182 1177 1182 1177 1171 1166 1161 1155 1151 1147 1135 1131 1128 1124 1121 1116 1114 1112 1110 1107 1105 | 36 35 34 34 33 32 31 31 30 29 29 28 27 27 26 25 24 24 23 | 433 433 432 432 432 431 431 431 431 430 430 430 430 430 429 429 429 429 429 429 429 429 429 429 |
| | 910.0 900.0 890.0 880.0 870.0 860.0 850.0 840.0 820.0 810.0 790.0 780.0 770.0 760.0 750.0 740.0 750.0 740.0 750.0 740.0 750.0 660.0 660.0 650.0 640.0 650.0 640.0 650.0 650.0 630.0 590.0 580.0 570.0 | 175.7 175.1 174.6 174.0 173.4 172.8 172.5 171.8 171.2 170.4 169.5 168.7 167.0 166.2 165.4 164.5 163.7 163.0 162.4 164.5 163.7 163.0 162.4 164.5 163.7 163.0 162.4 164.5 163.7 163.0 162.4 164.5 163.7 163.0 162.4 154.8 155.4 155.6 | 0.0 0.0 0.0 0.0 0.0 0.0 0.0 0.0 0.0 0.0 | 176.0 175.7 175.1 174.6 174.0 173.4 172.8 172.5 171.8 171.2 170.4 169.5 168.7 167.9 167.0 166.2 165.4 164.5 163.7 163.0 162.4 161.8 161.2 160.6 160.0 159.4 158.8 158.3 157.6 157.3 156.9 156.6 156.2 155.5 155.6 | 252.2 251.8 250.9 250.1 249.3 248.5 247.7 247.2 246.3 245.3 244.2 243.0 241.8 244.2 243.0 241.8 244.2 239.4 239.4 237.1 235.9 234.7 233.7 232.8 232.0 231.1 230.3 229.4 225.6 225.1 | 0.00494 0.00493 0.00491 0.00490 0.00488 0.00487 0.00486 0.00482 0.00482 0.00482 0.00477 0.00475 0.00473 0.00471 0.00468 0.00466 0.00466 0.00466 0.00465 0.00455 0.00455 0.00455 0.00455 0.00455 0.00455 0.00455 0.00455 0.00445 0.00445 0.00444 0.00444 0.00443 0.00442 0.00441 0.00443 0.00445 0.00445 0.0045 0.0045 0.0045 0.0045 0.0045 0.0045 0.0045 0.0045 0.0045 0.0045 0.0045 0 | 9.4 9.4 9.4 9.3 9.3 9.3 9.2 9.2 9.1 9.0 9.0 9.0 9.0 9.0 9.0 9.0 9.0 9.0 8.9 8.8 8.8 8.7 8.7 8.6 8.6 8.6 8.5 8.5 8.4 8.4 8.4 8.4 8.3 8.3 | $\begin{array}{c} 1055\\ 1053\\ 1049\\ 1045\\ 1042\\ 1038\\ 1035\\ 1032\\ 1028\\ 1024\\ 1019\\ 1013\\ 1008\\ 1002\\ 997\\ 992\\ 986\\ 981\\ 975\\ 971\\ 967\\ 963\\ 955\\ 951\\ 947\\ 943\\ 940\\ 935\\ 955\\ 951\\ 947\\ 943\\ 940\\ 935\\ 933\\ 930\\ 928\\ 926\\ 923\\ 921\\ 921\\ 921\\ \end{array}$ | 1240 1238 1229 1225 1221 1217 1214 1209 1204 1198 1192 1187 1182 1177 1182 1177 1171 1166 1161 1155 1151 1147 1135 1131 1128 1124 1121 1116 1114 1112 1110 1107 1105 1103 | 36 35 34 34 33 32 31 31 30 29 29 28 27 27 26 25 24 24 23 22 | 433 432 432 432 432 431 431 431 431 430 430 430 430 429 429 429 429 429 429 429 429 429 429 |
| | 910.0 900.0 890.0 880.0 870.0 860.0 850.0 840.0 830.0 820.0 810.0 790.0 780.0 770.0 760.0 750.0 740.0 730.0 710.0 740.0 750.0 690.0 690.0 650.0 640.0 650.0 640.0 650.0 650.0 590.0 550.0 570.0 | 175.7 175.1 174.6 174.0 173.4 172.8 172.5 171.8 171.2 170.4 169.5 168.7 167.0 166.2 165.4 164.5 163.7 163.0 162.4 164.5 163.7 163.0 162.4 164.5 163.7 163.0 162.4 164.5 163.7 163.0 162.4 154.8 157.6 155.6 155.5 155.6 155.7 | 0.0 0.0 0.0 0.0 0.0 0.0 0.0 0.0 0.0 0.0 | 176.0 175.7 175.1 174.6 174.0 173.4 172.8 172.5 171.8 171.2 170.4 169.5 168.7 167.9 167.0 166.2 165.4 164.5 163.7 163.0 162.4 161.8 161.2 160.6 160.0 159.4 158.8 158.3 157.6 157.3 156.9 156.6 155.7 | 252.2 251.8 250.9 250.1 249.3 248.5 247.7 247.2 246.3 245.3 244.2 243.0 241.8 244.2 243.0 241.8 244.2 239.4 238.2 237.1 235.9 234.7 233.7 232.8 232.0 231.1 230.3 229.6 227.7 227.0 226.1 225.6 225.1 | 0.00494 0.00493 0.00491 0.00490 0.00488 0.00487 0.00486 0.00482 0.00482 0.00482 0.00477 0.00475 0.00475 0.00473 0.00471 0.00466 0.00466 0.00466 0.00466 0.00465 0.00455 0.00455 0.00455 0.00455 0.00455 0.00455 0.00455 0.00455 0.00445 0.00445 0.00444 0.00444 0.00443 0.00442 0.00443 0.00439 0.004390 | 9.4 9.4 9.4 9.3 9.3 9.3 9.2 9.2 9.1 9.0 9.0 9.0 9.0 9.0 9.0 9.0 9.0 9.0 8.9 8.8 8.8 8.7 8.7 8.6 8.6 8.6 8.5 8.5 8.5 8.4 8.4 8.4 8.4 8.3 8.3 | 1055 1053 1049 1045 1042 1038 1035 1032 1028 1024 1019 1013 1008 1002 997 992 986 981 975 971 967 963 955 951 947 943 940 935 933 930 928 926 923 921 921 922 | 1240 1238 1223 1229 1225 1221 1217 1214 1209 1204 1198 1192 1187 1182 1177 1182 1177 1171 1166 1161 1155 1151 1147 1135 1131 1128 1124 1121 1116 1114 1128 1124 1121 1116 1114 1128 1124 1121 1105 1103 1103 | 36 35 34 34 33 33 32 31 31 30 29 29 29 29 29 29 29 29 29 29 29 29 29 | 433 432 432 432 432 431 431 431 431 430 430 430 430 429 429 429 429 429 429 429 429 429 429 |
| | 910.0 900.0 890.0 880.0 870.0 860.0 850.0 840.0 820.0 810.0 790.0 780.0 770.0 760.0 750.0 740.0 750.0 740.0 750.0 740.0 750.0 660.0 660.0 650.0 640.0 650.0 640.0 650.0 650.0 630.0 590.0 580.0 570.0 | 175.7 175.1 174.6 174.0 173.4 172.8 172.5 171.8 171.2 170.4 169.5 168.7 167.0 166.2 165.4 164.5 163.7 163.0 162.4 164.5 163.7 163.0 162.4 164.5 163.7 163.0 162.4 164.5 163.7 163.0 162.4 164.5 163.7 163.0 162.4 154.8 155.4 155.6 | 0.0 0.0 0.0 0.0 0.0 0.0 0.0 0.0 0.0 0.0 | 176.0 175.7 175.1 174.6 174.0 173.4 172.8 172.5 171.8 171.2 170.4 169.5 168.7 167.9 167.0 166.2 165.4 164.5 163.7 163.0 162.4 161.8 161.2 160.6 160.0 159.4 158.8 158.3 157.6 157.3 156.9 156.6 156.2 155.5 155.6 | 252.2 251.8 250.9 250.1 249.3 248.5 247.7 247.2 246.3 245.3 244.2 243.0 241.8 244.2 243.0 241.8 244.2 239.4 239.4 237.1 235.9 234.7 233.7 232.8 232.0 231.1 230.3 229.4 225.6 225.1 | 0.00494 0.00493 0.00491 0.00490 0.00488 0.00487 0.00486 0.00482 0.00482 0.00482 0.00477 0.00475 0.00473 0.00471 0.00468 0.00466 0.00466 0.00466 0.00465 0.00455 0.00455 0.00455 0.00455 0.00455 0.00455 0.00455 0.00455 0.00445 0.00445 0.00444 0.00444 0.00443 0.00442 0.00441 0.00443 0.00445 0.00445 0.0045 0.0045 0.0045 0.0045 0.0045 0.0045 0.0045 0.0045 0.0045 0.0045 0.0045 0 | 9.4 9.4 9.4 9.3 9.3 9.3 9.2 9.2 9.1 9.0 9.0 9.0 9.0 9.0 9.0 9.0 9.0 9.0 8.9 8.8 8.8 8.7 8.7 8.6 8.6 8.6 8.5 8.5 8.4 8.4 8.4 8.4 8.3 8.3 | $\begin{array}{c} 1055\\ 1053\\ 1049\\ 1045\\ 1042\\ 1038\\ 1035\\ 1032\\ 1028\\ 1024\\ 1019\\ 1013\\ 1008\\ 1002\\ 997\\ 992\\ 986\\ 981\\ 975\\ 971\\ 967\\ 963\\ 955\\ 951\\ 947\\ 943\\ 940\\ 935\\ 955\\ 951\\ 947\\ 943\\ 940\\ 935\\ 933\\ 930\\ 928\\ 926\\ 923\\ 921\\ 921\\ 921\\ \end{array}$ | 1240 1238 1229 1225 1221 1217 1214 1209 1204 1198 1192 1187 1182 1177 1182 1177 1171 1166 1161 1155 1151 1147 1135 1131 1128 1124 1121 1116 1114 1112 1110 1107 1105 1103 | 36 35 34 34 33 32 31 31 30 29 29 28 27 27 26 25 24 24 23 22 | 433 432 432 432 432 431 431 431 431 430 430 430 430 429 429 429 429 429 429 429 429 429 429 |

8

| 540.0 | 0 155.5 | 0.0 | 155.5 | 223.0 | 0.00439 | 8.3 | 921 | 1103 | 21 | 424 |
|----------------|---------|------------|----------------|----------------|--------------------|------------|------------|--------------|----------|------------|
| 530.0 | 0 155.0 | 0.0 | 155.0 | 222.4 | 0.00438 | 8.3 | 918 | 1100 | 21 | 423 |
| 520.0 | | 0.0 | 154.5 | 221.6 | 0.00436 | 8.3 | 914 | 1097 | 20 | 423 |
| 510.0 | | 0.0 | 153.9 | 220.8 | 0.00435 | 8.3 | 910 | 1093 | 20 | 423 |
| 500.0 | | 0.0 | 153.4 | 220.0 | 0.00433 | 8.2 | 907 | 1089 | 20 | 423 |
| 490.0 | | 0.0 | 152.8 | 219.2 | 0.00432 | 8.2 | 903 | 1086 | 19 | 422 |
| 480.0 | | 0.0 | 152.3 | 218.4 | 0.00430 | 8.2 | 899 | 1082 | 19 | 422 |
| 470.0 | | 0.0 | 151.7 | 217.7 | 0.00429 | 8.1 | 895 | 1078 | 18 | 422 |
| 460.0 | | 0.0 | 151.2 | 216.9 | 0.00427 | 8.1 | 892 | 1075 | 18 | 422 |
| 450.0 | | 0.0 | 150.7 | 216.2 | 0.00426 | 8.1 | 888 | 1071 | 18 | 421 |
| 440.0 | | 0.0 | 150.2 | 215.4 | 0.00424 | 8.1 | 885 | 1068 | 17 | 421 |
| 430.0 | | 0.0 | 149.7 | 214.7 | 0.00423 | 8.0 | 881 | 1065 | 17 | 421 |
| 420.0 | | 0.0 | 149.1 | 214.0 | 0.00421 | 8.0 | 878 | 1061 | 16 | 421 |
| 410.0 | | 0.0 | 148.6 | 213.3 | 0.00420 | 8.0 | 874 | 1058 | 16 | 420 |
| 400.0 | | 0.0 | 148.1 | 212.6 | 0.00419 | 7.9 | 871 | 1055 | 16 | 420 |
| 390.0 | | 0.0 | 147.6 | 211.8 | 0.00417 | 7.9 | 867 | 1051 | 15 | 420 |
| 380.0 | | 0.0 | 147.3 | 211.3 | 0.00416 | 7.9 | 865 | 1049 | 15 | 420 |
| 370.0 | | 0.0 | 146.9 | 210.8 | 0.00415 | 7.9 | 862 | 1046 | 15 | 419 |
| 360.0 | | 0.0 | 146.5 | 210.3 | 0.00414 | 7.9 | 860 | 1044 | 14 | 419 |
| 350.0 | | 0.0 | 146.2 | 209.7 | 0.00413 | 7.8 | 857 | 1042 | 14 | 418 |
| 340.0 | | 0.0 | 145.8 | 209.2 | 0.00412 | 7.8 | 855 | 1039 | 13 | 416 |
| 330.0 | | 0.0 | 145.4 | 208.7 | 0.00411 | 7.8 | 852 | 1037 | 13 | 415 |
| 320.0 | | 0.0 | 145.0 144.7 | 208.1 207.6 | 0.00410 | 7.8 | 849 847 | 1034 1032 | 13 | 413 412 |
| 310.0 300.0 | | 0.0 0.0 | 144.7 | 207.6 | 0.00409 0.00408 | 7.8 7.7 | 844 | 1032 | 12 12 | 412 |
| 290.0 | | 0.0 | 144.2 | 207.0 | 0.00408 | 7.7 | 839 | 1028 | 11 | 409 407 |
| 290.0 | | 0.0 | 143.5 | 200.0 | 0.00408 | 7.7 | 833 | 1024 | 11 | 407 404 |
| 270.0 | | 0.0 | 142.7 | 204.8 | 0.00404 | 7.6 | 826 | 1010 | 11 | 404 |
| 260.0 | | 0.0 | 141.7 | 203.4 | 0.00401 | 7.5 | 818 | 1010 | 10 | 398 |
| 250.0 | | 0.0 | 140.5 | 199.6 | 0.00398 | 7.5 | 808 | 990 | 10 | 395 |
| 240.0 | | 0.0 | 137.5 | 197.4 | 0.00389 | 7.4 | 797 | 977 | 9 | 391 |
| 230.0 | | 0.0 | 135.7 | 194.9 | 0.00385 | 7.3 | 784 | 964 | 9 | 387 |
| 220. | | 0.0 | 133.8 | 192.1 | 0.00379 | 7.2 | 770 | 948 | 9 | 383 |
| 210.0 | | 0.0 | 131.6 | 189.1 | 0.00373 | 7.1 | 755 | 931 | 8 | 378 |
| 200.0 | | 0.0 | 129.3 | 185.8 | 0.00367 | 6.9 | 739 | 913 | 8 | 374 |
| 190.0 | | 0.0 | 126.9 | 182.3 | 0.00360 | 6.8 | 722 | 893 | 7 | 369 |
| 180.0 | | 0.0 | 124.3 | 178.7 | 0.00353 | 6.7 | 703 | 873 | 7 | 363 |
| 170.0 | | 0.0 | 121.5 | 174.7 | 0.00346 | 6.5 | 683 | 850 | 7 | 358 |
| 160.0 | 0 118.5 | 0.0 | 118.5 | 170.4 | 0.00337 | 6.4 | 661 | 825 | 6 | 352 |
| 150.0 | 0 115.4 | 0.0 | 115.4 | 166.0 | 0.00329 | 6.2 | 638 | 800 | 6 | 346 |
| 140.0 | 0 112.1 | 0.0 | 112.1 | 161.2 | 0.00320 | 6.0 | 614 | 772 | 5 | 340 |
| 130.0 | 0 108.6 | 0.0 | 108.6 | 156.3 | 0.00310 | 5.8 | 589 | 744 | 5 | 333 |
| 120.0 | 0 32.7 | 0.0 | 32.7 | 48.3 | 0.00102 | 1.8 | 99 | 181 | 5 | 327 |
| 110.0 | 0 26.1 | 0.0 | 26.1 | 39.0 | 0.00084 | 1.4 | 70 | 145 | 4 | 320 |
| 100.0 | 0 19.4 | 0.0 | 19.4 | 29.4 | 0.00065 | 1.0 | 44 | 113 | 4 | 312 |
| 90.0 | 0 12.5 | 0.0 | 12.5 | 19.6 | 0.00046 | 0.7 | 22 | 84 | 4 | 305 |
| 80.0 | 0 5.5 | 0.0 | 5.5 | 9.7 | 0.00027 | 0.3 | 5 | 60 | 3 | 297 |
| 70. | | 0.0 | 0.0 | 1.8 | 0.00012 | 0.6 | 2 | 51 | 3 | 289 |
| 60. | | 0.0 | 153.0 | 219.5 | 0.00432 | 4.0 | 675 | 675 | 2 | 281 |
| 50.0 | | 0.0 | 0.0 | 1.8 | 0.00012 | 0.6 | 2 | 2 | 2 | 272 |
| 40.0 | | 0.0 | 0.0 | 1.8 | 0.00012 | 0.6 | 2 | 2 | 2 | 263 |
| 30. | | 0.0 | 0.0 | 1.8 | 0.00012 | 0.6 | 2 | 2 | 1 | 254 |
| 20. | | 0.0 | 0.0 | 1.8 | 0.00012 | 0.6 | 2 | 2 | 1 | 245 |
| 10.0 | | 0.0 | 0.0 | 1.8 | 0.00012 | 0.6 | 2 | 2 | 0 | 236 |
| 0.0 | 0 0.0 | 0.0 | 0.0 | 1.8 | 0.00012 | 0.6 | 2 | 2 | 0 | 228 |
| | | | | | | | | | | |

Comments

WIE12731-153_Frac-out Calcs_Landfall



White Cross Offshore Windfarm

Appendix 5.B: Outline Construction Environmental Management Plan





| Document Code: | FLO-WHI-REP-0016-05 | | | |
|--------------------------------|----------------------------------|----------------------|--|--|
| Contractor Document Number: | PC2978-RHD-ZZ-XX- RP-Z-0384 | | | |
| Version Number: | 00 | | | |
| Date: | <i>Issue Date 09/08/2023</i> | | | |
| Prepared by: | ТМ | Electronic Signature | | |
| Checked by: | СВ | Electronic Signature | | |
| Owned by: | PT | Electronic Signature | | |
| Approved by Client: | OG | Electronic Signature | | |

| Version Number | Reason for Issue / Major Changes | Date of Change |
|-------------------|-------------------------------------|----------------|
| 00 | For Issue | 09/08/2023 |



Table of Contents

| 1. | Intr | troduction1 | | | | | |
|----|--|----------------------------|---|-----|--|--|--|
| 2. | Purp | urpose of the Outline CEMP | | | | | |
| 3. | Legislative and Regulatory Compliance 2 | | | | | | |
| 3 | 3.1 Town and Country Planning Act 1990 2 | | | | | | |
| 3 | .2 | Leg | al compliance | . 2 | | | |
| 3 | .3 | Gui | dance | . 3 | | | |
| 4. | Proj | ect I | Description and Environmental Sensitivities | . 3 | | | |
| 5. | Man | age | ment of Key Environmental Issues | . 5 | | | |
| 5 | .1 | | se and vibration | | | | |
| 5 | .2 | Ter | restrial ecology | . 6 | | | |
| | 5.2. | 1 | Invasive and Non-Native Species | . 6 | | | |
| | 5.2. | 2 | Hedgerow Removal | . 7 | | | |
| 5 | .3 | Ter | restrial archaeology and cultural heritage | . 7 | | | |
| 5 | .4 | Was | stewater discharges | . 8 | | | |
| 5 | .5 | Oils | , fuels, and chemicals | . 8 | | | |
| | 5.5. | 1 | Control of Substances Hazardous to Health (COSHH) | . 8 | | | |
| 5 | .6 | Was | ste management and circular economy | . 9 | | | |
| 5 | .7 | Tra | ffic management | 10 | | | |
| 5 | .8 | Sur | face water management | 11 | | | |
| 5 | .9 | Wat | ter abstraction | 12 | | | |
| 5 | .10 | Emi | issions to air | 12 | | | |
| | 5.10 |).1 | IAQM best practice measures | 12 | | | |
| | 5.10 |).2 | NRMM measures | 15 | | | |
| 5 | .11 | UXC | D Risk | 16 | | | |
| 6. | Env | ironr | mental Management Structure and Responsibilities | 16 | | | |
| 7. | Env | ironr | mental Incident Response and Contingency | 17 | | | |
| 7 | .1 | Eme | ergency response plan | 17 | | | |
| 7 | .2 | Rep | porting | 18 | | | |
| 7 | .3 | Nor | nconformance | 18 | | | |
| 8. | Mor | itori | ng | 18 | | | |
| 8 | .1 | Site | e inspections and environmental monitoring | 18 | | | |
| 8 | .2 | Environmental audits | | | | | |



| 9. | Trai | ning and Awareness | | |
|-----|---|---|--|--|
| ç | 0.1 | Project/site inductions | | |
| ç | .2 | Toolbox Talks (TBTs)20 | | |
| ç | .3 | Environmental notice board20 | | |
| 10. | Con | nmunication and Reporting20 | | |
| 1 | 0.1 | Meetings20 | | |
| 1 | 0.2 | Community complaints21 | | |
| 1 | .0.3 | Community liaison and land use21 | | |
| 1 | 0.4 | Stakeholders engagement22 | | |
| 11. | Sub | -Contractor Management22 | | |
| 12. | Sus | tainable Construction | | |
| 13. | Refe | erences23 | | |
| Anı | nex 1 | : Waste Audit Statement | | |
| 1. | Intr | oduction24 | | |
| 2. | Poli | cy24 | | |
| 3. | Stru | cture of Waste Audit Statement25 | | |
| 4. | Was | ste Audit Statement | | |
| 2 | .1 | Project and Site Description25 | | |
| 2 | .2 | Step to minimise generation of waste during excavation, demolition and construction26 | | |
| | 4.3 Type and volume of the waste to be generated during excavation, demolition and construction | | | |
| 2 | ł.4 | Steps to be taken to achieve the re-use and recycling percentages | | |
| 2 | ł.5 | Type and volume of the waste to be generated during operation | | |
| 2 | .6 | Waste Collection and Sustainable Waste Management Principles | | |

Table of Figures

| Figure 4.1 | Onshore Development Area | 4 |
|------------|--------------------------|---|
|------------|--------------------------|---|



| diossary of Actoryms | | | | |
|----------------------|--|--|--|--|
| Acronym | Definition | | | |
| CEMP | Construction Environmental Management Plan | | | |
| | | | | |
| COSHH | Control of Substances Hazardous to Health | | | |
| EA | Environment Agency | | | |
| EIA | Environmental Impact Assessment | | | |
| EMS | Environmental Management System | | | |
| ES | Environmental Statement | | | |
| EU | European Union | | | |
| HSE | Health Safety Environment | | | |
| km | Kilometre | | | |
| MHWS | Mean High Water Springs | | | |
| ММО | Marine Management Organisation | | | |
| MW | Megawatts | | | |
| NE | Natural England | | | |
| PEMP | Project Environmental Management Plan | | | |
| PPG | Pollution Prevention Guidance | | | |
| SAC | Special Area of Conservation | | | |
| SSSI | Site of Special Scientific Interest | | | |
| SUDS | Sustainable Urban Drainage Systems | | | |
| ТВТ | Toolbox Talk | | | |
| ТСРА | Town and Country Planning Act | | | |
| UK | United Kingdom | | | |
| WSI | Written Scheme of Investigation | | | |

Glossary of Acronyms



Glossary of Terminology

| Defined Term | Description |
|--|---|
| Applicant | White Cross Offshore Windfarm Limited |
| Environmental Impact Assessment (EIA) | Assessment of the potential impact of the proposed Project on the physical, biological and human environment during construction, operation and decommissioning. |
| Export Cable Corridor | The area in which the export cables will be laid, either from the Offshore Substation or the inter-array cable junction box (if no offshore substation), to the NG Onshore Substation comprising both the Offshore Export Cable Corridor and Onshore Export Cable Corridor. |
| Landfall | Where the offshore export cables come ashore |
| Mean high water springs | The average tidal height throughout the year of two successive high waters during those periods of 24 hours when the range of the tide is at its greatest. |
| Mean low water springs | The average tidal height throughout a year of two successive low waters during those periods of 24 hours when the range of the tide is at its greatest. |
| Mitigation | Mitigation measures have been proposed where the assessment identifies that an aspect of the development is likely to give rise to significant environmental impacts and discussed with the relevant authorities and stakeholders in order to avoid, prevent or reduce impacts to acceptable levels. For the purposes of the EIA, two types of mitigation are defined: |
| | Embedded mitigation: consisting of mitigation measures that are identified and adopted as part of the evolution of the project design, and form part of the project design that is assessed in the EIA |
| | Additional mitigation: consisting of mitigation measures that are identified during the EIA process specifically to reduce or eliminate any predicted significant impacts. Additional mitigation is therefore subsequently adopted by WCOWL as the EIA process progresses. |
| National Grid Onshore Substation | Part of an electrical transmission and distribution system. Substations transform voltage from high to low, or the reverse by means of the electrical transformers. |
| National Grid Connection Point | The point at which the White Cross Offshore Windfarm connects into the distribution network at East Yelland substation and the distributed electricity network. From East Yelland substation electricity is transmitted to Alverdiscott where it enters the national transmission network. |
| Onshore Export Cables | The cables which bring electricity from MLWS at the Landfall to the White Cross Onshore Substation and onward to the NG grid connection point at East Yelland. |
| Onshore Export Cable Corridor | The proposed onshore area in which the export cables will be laid, from MLWS at the Landfall to the White Cross Onshore Substation and onward to the NG grid connection point at East Yelland. |
| Onshore Infrastructure | The combined name for all infrastructure associated with the Project from MLWS at the Landfall to the NG grid connection point at East Yelland. The onshore infrastructure will form part of a separate planning application to the Local Planning Authority (LPA) under the Town and Country Planning Act 1990 |
| the Onshore Project | The Onshore Project for the onshore TCPA application includes all elements onshore of MLWS. This includes the infrastructure associated with the offshore export cable (from MLWS), landfall, Onshore Export Cable and associated infrastructure and new Onshore Substation (if required). |



| Defined Term | Description |
|--|---|
| White Cross Offshore Windfarm Limited | White Cross Offshore Windfarm Ltd (WCOWL) is a joint venture between Cobra Instalaciones Servicios, S.A., and Flotation Energy Ltd |
| White Cross Offshore Windfarm | Up to 100MW capacity offshore windfarm including associated onshore and offshore infrastructure |
| White Cross Onshore Substation | A new substation built specifically for the White Cross project. It is required to ensure electrical power produced by the offshore windfarm is compliant with NG electrical requirements at the grid connection point at East Yelland. |
| Windfarm Site | The area within which the wind turbines, Offshore Substation Platform and inter- array cables will be present |
| Works completion date | Date at which construction works are deemed to be complete and the windfarm is handed to the operations team. In reality, this may take place over a period of time. |



Appendix 5.B: Outline Construction Environmental Management Plan

1. Introduction

- 1. There are potential onshore environmental sensitivities associated with the Onshore Project, which need to be identified and considered before construction of its associated infrastructure takes place. These potential effects are outlined in the Onshore Project's Environmental Statement (ES), including embedded mitigation in the form of good practice that will require an adherence to during the construction phase as a minimum standard. A description of the proposed development is presented in **Chapter 5: Project Description**. The Onshore Project infrastructure is shown in **Figure 4.1**.
- 2. Offshore Wind Limited (henceforth the 'Applicant') recognises from feedback during the Environmental Impact Assessment (EIA) consultation and stakeholder engagement process, that the provision of an Outline Construction Environmental Management Plan (Outline CEMP) for the Onshore Project is required. The Outline CEMP adds value by demonstrating the linkages between the ES, site activities, and likely conditions associated with the Town and Country Planning Act 1990 (TCPA, 1990).

2. Purpose of the Outline CEMP

- 3. The purpose of the Outline CEMP is to set out the framework of the CEMP. It sets out the controls and processes that will be developed and adopted in the CEMP to mitigate environmental impacts throughout the construction phase of the Onshore Project and measures set out to comply with consent conditions.
- 4. The CEMP will be prepared by the Principal Contractor appointed by the Applicant. Principal Contractors will be responsible for the construction of the main infrastructure associated with the Onshore Project including the Onshore Export Cable and Onshore Substation.
- 5. The Principal Contractor is required to operate an Environmental Management System (EMS) based on the requirements of ISO 14001:2015, which describes the processes and procedures by which the environmental issues are managed in line with the relevant legislation and standards, pollution prevention and continual improvement.
- 6. Typical contents for an Onshore Project CEMP are set out below. Outline content for each section is described in:



- Section 4: Project Description and Environmental Sensitivities
- Section 5: Management of Key Environmental Issues
- Section 6: Environmental Management Structure and Responsibilities
- Section 7: Environmental Incident Response and Contingency
- Section 8: Monitoring
- Section 9: Training and Awareness
- Section 10: Communication and Reporting
- Section 11: Sub-Contractor Management
- Section 12: Sustainable Construction

3. Legislative and Regulatory Compliance

3.1 Town and Country Planning Act 1990

- 7. Planning permission under TCPA 1990 is required for the Onshore Project infrastructure (landward of MLWS). The Town and Country Planning Act 1990 will be the key permission to be adhered to for the Onshore Project and the planning conditions will need to be taken into consideration during the development of the CEMP.
- 8. The Principal Contractor must ensure that all relevant planning conditions for the Onshore Project are complied with.

3.2 Legal compliance

- The ES identified the legal requirements which the Onshore Project has to comply with. The environmental legislation is covered in Chapter 3: Policy and Legislative Context of the Onshore Project ES and topic specific legislation presented in the technical chapters of the ES (Chapter 8 to 24).
- 10. The Principal Contractor will be required to ensure that all relevant environmental legislation and good practice are complied with on site.
- 11. The Principal Contractor will be responsible for applying for and obtaining any permits/licenses related to the construction activities. Specific consents and licenses will be applied for to Government bodies such as Natural England, the Lead Local Flood Authority and the Environment Agency (EA).
- 12. Specific limits for emissions to air, discharges to the marine environment and working practices (such as seasonal exclusions) are contained within these consents/licenses and shall not be breached at any time.



3.3 Guidance

13. Good Practice Guidance/Industry Standards such as Pollution Prevention Guidance Notes and other guidance documents are available from the EA and Marine Management Organisation (MMO) websites. As requested within the MMO's Scoping Opinion (Case reference: EIA/2022/00002), PPG5 – Works and maintenance in or near water¹ and PPG6 – Working at construction and demolition sites will be adhered to².

4. Project Description and Environmental Sensitivities


14. **Chapter 5: Project Description** of the Onshore Project ES provides a description of the Onshore Project and sets out the Project Design Envelope. The Onshore Development Area is shown in **Figure 4.1**.

1

2

https://assets.publishing.service.gov.uk/government/uploads/system/uploads/attachment_data/file/4851 99/pmho1107bnkg-e-e.pdf

https://assets.publishing.service.gov.uk/government/uploads/system/uploads/attachment_data/file/4852 15/pmho0412bwfe-e-e.pdf





- 15. Following the final detailed design phase, this section of the CEMP will set out information with regard to the detailed design and the associated environmental sensitivities. In particular, sensitive ecological, archaeological or human receptors, such as protected habitats, protected wrecks, constraints from other infrastructure, site layout plans, and the scope of works to be undertaken, will be considered.
- 16. The Principal Contractor for the construction of the Onshore Project will be required to prepare an Aspect and Impacts Register as part of their Environmental Management System (EMS).

5. Management of Key Environmental Issues

- 17. This section should refer to relevant associated environmental documents which form part of the Principal Contractor EMS and project/site specific documentation that is required to be developed as part of the CEMP.
- 18. The controls and procedures to be adopted to mitigate the environmental impacts associated with the development would cover the following issues:
 - Noise and vibration
 - Terrestrial ecology
 - Terrestrial archaeology and cultural heritage
 - Wastewater discharges
 - Oils, fuel, and chemicals
 - Waste management and circular economy
 - Traffic management
 - Surface water management
 - Water abstraction
 - Emissions to air
 - UXO risk
 - Project programme and working hours.
- 19. It is recognised that some of the issues identified above relate only to the terrestrial environment, whilst others will apply to both the onshore and offshore construction activities. A separate offshore specific Outline CEMP has been produced and submitted as part of the Offshore Project ES.

5.1 Noise and vibration

20. There is the potential for noise and vibration to be generated during the construction process, especially from heavy plant and machinery. Measures will be required to be implemented on site to minimise any effects and a programme of monitoring may be required.



- 21. Within **Chapter 18: Noise and Vibration** (Section 22.4.1), of the Onshore Project ES, receptors that may be sensitive to noise and vibration effects are identified, along with proposed mitigation measures. It is the responsibility of the Principal Contractor to have in place adequate controls measure to avoid and minimise noise and vibration impacts during the construction phase. Proposed mitigation within **Chapter 18: Noise and Vibration** includes:
 - Commitment to Best Practicable Means (BPM) implemented during the construction phase, detailed in the Construction Noise and Vibration Management Plan
 - Temporary screening at the Landfall and along the haul road
 - Traffic management measures specified in Construction Traffic Management Plan (CTMP). A CTMP is included in **Appendix 19.B**.

5.2 Terrestrial ecology

- 22. Chapter 16: Onshore Ecology and Ornithology within the Onshore Project ES identifies areas of conservation/protection and sets out appropriate mitigation (Section 16.3.6).
- 23. It is the responsibility of the Principal Contractor to have in place adequate controls measure to avoid and minimise impacts on the flora and fauna and any protected species. The CEMP will provide details of the extent and location of the standoff. As such, the features of this SSSI and SAC would not be directly affected by the proposed crossing works and no change to Braunton Barrows SAC/ SSSI is predicted.
- 24. Precautionary measures to ensure legal compliance will be incorporated within the CEMP as detailed in **Section 16.3.6.** These include pre-construction surveys, habitat manipulation and vegetation clearance. The Principal Contractor will employ an Ecological Clerk of Works (ECoW) prior to the commencement of works to ensure that the specified protection and mitigation measures are appropriately implemented.
- 25. Lighting of habitats suitable for foraging or commuting bats will be avoided, and where the use of lighting is necessary within the Onshore Development Area, then the lighting will be minimised during the period when bats are active. The CEMP will provide further detail on lighting requirements.

5.2.1 Invasive and Non-Native Species

- 26. An Invasive and Non-Native Species (INNS) Management Plan will be detailed in the CEMP which will include the following measures:
 - A plan of all INNS locations and extents
 - A protocol for removing INNS and for managing the waste generated



- Good site practice measures for managing the spread of invasive species during works at or near to watercourses
- A requirement for an ECoW and details of their responsibilities with respect to non-native invasive species.

5.2.2 Hedgerow Removal

- 27. Prior to the commencement of any works to a hedgerow, an ECoW will be present on site to ensure that the specified protection and mitigation measures are appropriately implemented. Replacement planting of removed hedgerows and trees will be implemented during the first suitable period following completion of the construction works. Gaps in hedges will be present initially until the new planting matures.
- 28. The species list for re-instatement will be of UK and local provenance species, such as hawthorn, blackthorn, field maple *Acer campestre*, dog-rose *Rosa canina*, hazel *Corylus avellana*, dogwood *Cornus sanguinea*, crab apple *Malus sylvestris* and holly *Ilex aquifolium*. Replanting of hedgerow trees will use either pedunculate oak *Quercus robu*r or a like for like replacement if other native species are to be removed, as appropriate. It is likely that the reinstatement will increase the range of species present in some sections of hedgerow which are currently species poor.
- 29. Ecological enhancement will involve reinstating pre-existing gaps in hedgerows within the Onshore Development Area.

5.3 Terrestrial archaeology and cultural heritage

- 30. Chapter 17: Onshore Archaeology and Cultural Heritage within the Onshore Project ES identifies sites of potential archaeological importance, and these will be identified in the Written Scheme of Investigation (WSI) with appropriate mitigation, such as establishment of exclusion and buffer zones clearly marked out. The CEMP should include the measures to be adopted to communicate awareness of sensitive archaeological sites to the Project team and procedures to be adopted in the event of an unanticipated find.
- 31. An Outline Onshore Written Scheme of Investigation (WSI) (**Appendix 17.E**) is submitted alongside the Outline CEMP.
- 32. The Principal Contractor is required to prepare site specific WSIs and final preconstruction and construction mitigation WSIs and be agreed with and approved by the relevant planning authority in consultation with Devon County Council Historic Environment Team (DCC HET) (and Historic England (HE), as required) in the post-consent stages of the project.



5.4 Wastewater discharges

- 33. The Principal Contractor will be responsible for obtaining any permits from the regulator associated with the use of septic tanks or other effluent/washout water treatment facilities. In addition, they will be responsible for monitoring and recording specified volumetric, quality or reference conditions, to demonstrate compliance.
- 34. Waste sludge from septic tanks and effluents from cesspits and sewage holding tanks must be removed by a suitably licenced and registered waste carrier in accordance with Duty of Care requirements.
- 35. Monitoring records in relation to the disposal of grey water, foul water, bilge water or ballast water during the construction phase must be retained.

5.5 Oils, fuels, and chemicals

- 36. It is the responsibility of each Principal Contractor to have in place adequate controls for the delivery, storage and use of fuels, oils and chemicals on site, and other materials as required.
- 37. The Principal Contractor must consider the delivery, storage, and handling of hazardous materials, in particular oils and fuels, taking into account the legal requirements and good practice guidelines.
- 38. Oils and chemicals must be clearly labelled, and the Principal Contractor should retain an up-to-date hazardous substance register. Activities involving the handling of large quantities of hazardous materials, such as deliveries and refuelling, should have detailed method statements in place and be undertaken by designated and trained personnel.
- 39. Oil and fuel storage tanks must be robust and provide adequate secondary containment and be located in designated areas taking into account security, the location of sensitive receptors and pathways such as drains and watercourses, and safe access and egress for plant and manual handling.
- 40. Spill response materials should be provided nearby and be readily accessible, with project personnel trained in spill response.

5.5.1 Control of Substances Hazardous to Health (COSHH)

41. The Principal Contractor is responsible for ensuring that all materials ordered or brought to site listed as hazardous under the Control of Substances Hazardous to Health (COSHH) Regulations are accompanied with a hazardous information sheet. The Principal Contractor will comply with the COSHH Regulations.



5.6 Waste management and circular economy

42. Waste generated during the excavation, demolition and construction of the Onshore Project will be managed by the Principal Contractor in accordance with the waste hierarchy. The waste hierarchy requires the producer/holder of a waste to demonstrate that the priorities outlined in **Table 5.1** have been considered in the priority order, and to determine the most suitable waste management option for all wastes prior to removal from site. The Applicant will aim to prevent, reuse, recycle and/or recover waste where practical and economically feasible prior to considering disposal.

Table 5.1 The Waste Hierarchy

| Waste Hierarchy | Relevant activity |
|----------------------|--|
| Prevention | Using less material in design and manufacture, keeping products for longer, re-use, using less hazardous materials. |
| Preparing for re-use | Checking, cleaning, repairing, refurbishing, whole items, or spare parts. |
| Recycling | Turning waste into a new substance or product, includes composting if it meets quality protocols. |
| Other recovering | Includes anaerobic digestion, incineration with energy recovery, gasification and pyrolysis which produce energy (fuels, heat, and power) and materials from waste, some backfilling. |
| Disposal | Landfill and incineration without energy recovery. |

Table reproduced from Defra website: <u>https://www.gov.uk/waste-legislation-and-regulations</u>

- 43. The design of the Onshore Project will consider sustainability principals to make sure that over ordering on materials such a substation components, cement bound sand, ducting, tape, tiles and cables is kept to a minimum. As part of the preliminary design of the Onshore Project for the planning application estimates on the likely material quantities to be used during the construction phase have been provided by the engineering team. These quantities will be further refined as the project moves through the detailed design and will be monitored through the use of a Quantity Surveyor during the construction phase of the Onshore Project.
- 44. During construction the Principal Contractor will be responsible for the collection, storage and disposal of any waste produced as part of the Onshore Project and will be required to prepare a Site Waste Management Plan (SWMP) in line with legislation, good practice. The SWMP will be developed post-consent to ensure the proper handling and protocols are in place to deal with any generated wastes. The Plan will record the following information, as a minimum:
 - The types and quantities of waste generated



- The management approach for each waste type (Reuse, Recycle, Recover, Dispose) including any treatment
- The storage arrangements for each waste type
- The site waste monitoring and reporting arrangements
- Waste carrier details and waste management/disposal facilities.
- 45. Adoption of a CL:AIRE Industry Code of Practice to manage the re-use and disposal of excavated soils within the Onshore Development Area would also be incorporated as an additional mitigation measure in the CEMP, this would aid in maximising sustainability and provide an audit trail to demonstrate the appropriate use of materials. A Materials Management Plan will be drafted in advance of any construction works, this would include chemical screening criteria in order to ensure that imported and/or reused materials are chemically suitable for use. If materials identified as containing asbestos are identified, then a specialist contractor would be employed to aid in its removal from Onshore Project Area, in line with current legislation.
- 46. Circular economy principles will be considered, where practical and economically feasible, specifically the priority area of circular construction and adopting circular economy interventions such as:
 - adopting circular design principles and construction processes, particularly the opportunity to create a physical and virtual resource recovery and material exchange hub to make better use of material wasted in construction
 - supporting the growth of regional specialist circular products and services in the construction industry.
- 47. Further information is contained within the Waste Audit Statement (refer to **Annex 1**).

5.7 Traffic management

- 48. Chapter 19: Traffic and Transport within the Onshore Project ES identified that during the construction phase for onshore aspects of the development, there will be traffic movements within the site boundary in addition to associated traffic movements on the local road network, including heavy goods vehicles, which may give rise to significant environment effects. Measures to address associated impacts are set out in Appendix 23.B: Outline Construction Traffic Management Plan (CTMP) and will be developed into a full CTMP which will be part of the CEMP.
- 49. The list below sets out the implementation of each of the measures that will be implemented by the Applicant, Principal Contractor and the Traffic Management Coordinator (TMCo). The exact details and associated timescales will be



established in consultation with Devon County Council as part of the preparation of the final CTMP:

- Appointment of a TMCo
- Obtain technical approval for construction of accesses and crossings
- Implement direction signing
- Establish monitoring systems:
 - Delivery booking system
 - Highway condition
 - Unique vehicle identifier
 - Telephone reporting system.
- Agree scope of and undertake pre-commencement highway condition surveys.
- Agree and implement measures for each access to control the deposition of detritus on the public highway
- Inspect the highway for detritus and request regular cleansing as required.
- Monitoring of CTMP measures:
 - HGV trips
 - Accidents and near misses
 - Employee mode share
 - Complaints.
- Produce monthly monitoring reports
- Update condition surveys and agree any remedial works.

5.8 Surface water management

- 50. Chapter 14: Water Resources and Flood Risk within the Onshore Project ES identifies considers impacts to water resources and flood risk and sets out appropriate mitigation (Section 16.3.6). Appendix 14.C: Flood Risk Assessment provides an assessment of flood risk and the measures to reduce flood risk within the Onshore Development Area.
- 51. For onshore construction sites, the CEMP should include a detailed surface water management design/drainage plan for the Onshore Project. The plan should detail the surface water management measures to be implemented during the works. The detailed design should be supported by the rationale for selecting the chosen mitigation measures, together with associated calculations and methodologies for sizing. Where appropriate, the principles of Sustainable Urban Drainage Schemes (SUDS) should be applied.
- 52. During construction, the haul road will be bound by parallel drainage channels (one on each side) to intercept drainage within the working width. Depending upon the precise location, water from the channels will be infiltrated or



discharged into the local drainage network via temporary interceptor drains and / or silt traps. Mitigation measures must be maintained and monitored on a regular basis. A record of inspections of mitigation measures and any required maintenance carried out by the Contractor must be maintained.

53. The Principal Contract will include for provision of an Agricultural Liaison Officer (ALO) and/or local specialised drainage contractor to manage impacts on agricultural drainage during construction including maintaining and/or reinstating land drainage systems. The CEMP will detail the approach to pre- and post-construction drainage plans on agricultural fields.

5.9 Water abstraction

54. For onshore construction sites, abstraction of water may be required for potable supply or for use during site activities, such as concrete batching or washing. The Principal Contractor is responsible for obtaining from the regulator (such as the Environment Agency), in advance of use, any permits for the use of abstracted water during the construction related activities and for monitoring and recording associated abstraction rates or other licence requirements to demonstrate compliance.

5.10 Emissions to air

- 55. For onshore construction sites, the CEMP will consider the potential for dust nuisance to arise. The Principal Contractor is responsible for implementing appropriate mitigation measures to suppress dust and minimise emissions to air during the construction works. Measures to address potential emissions to the air are set out in **Chapter 13: Air Quality** (**Section 13.3.6**) and include:
 - Best practice measures as recommended by the Institute of Air Quality Management (IAQM)
 - Non-Road Mobile Machinery (NRMM) measures

5.10.1 IAQM best practice measures

- 56. These measures will be secured within the final CEMP.
 - Communications:
 - Develop and implement a stakeholder communications plan that includes community engagement before work commences on site
 - Display the name and contact details of person(s) accountable for air quality and dust issues on the site boundary. This may be the environment manager/engineer or the site manager
 - Display the head or regional office contact information.
 - Dust Management:



- Develop and implement a Dust Management Plan (DMP) (this will form part of the CEMP), which may include measures to control other emissions, approved by the local authority. The level of detail will depend on the risk and should include as a minimum the highly recommended measures in this document. The desirable measures should be included as appropriate for the site
- Record all dust and air quality complaints, identify cause(s), take appropriate measures to reduce emissions in a timely manner, and record the measures taken
- Make the complaints log available to the local authority when asked
- Record any exceptional incidents that cause dust and/or air emissions, either on- or off-site, and the action taken to resolve the situation in the logbook
- Hold regular liaison meetings with other high risk construction sites within 500m of the site boundary, to ensure plans are co-ordinated and dust and particulate matter emissions are minimised. It is important to understand the interactions of the off-site transport/deliveries which might be using the same strategic road network routes
- Undertake daily on-site and off-site inspection, where receptors (including roads) are nearby, to monitor dust, record inspection results, and make the log available to the local authority when asked. This should include regular dust soiling checks of surfaces such as street furniture, cars and windowsills within 100m of site boundary, with cleaning to be provided if necessary
- Carry out regular site inspections to monitor compliance with the DMP, record inspection results, and make an inspection log available to the local authority when asked
- Increase the frequency of site inspections by the person accountable for air quality and dust issues on site when activities with a high potential to produce dust are being carried out and during prolonged dry or windy conditions
- Plan site layout so that machinery and dust causing activities are located away from receptors, as far as is possible
- Erect solid screens or barriers around dusty activities or the site boundary that are at least as high as any stockpiles on site
- Fully enclose site or specific operations where there is a high potential for dust production and the site is active for an extensive period
- Avoid site runoff of water or mud
- Keep site fencing, barriers and scaffolding clean using wet methods
- Remove materials that have a potential to produce dust from site as soon as possible, unless being re-used on site. If they are being re-used on-site cover as described below.
- Manage stockpiles to prevent wind whipping
- Ensure all vehicles switch off engines when stationary no idling vehicles
- Avoid the use of diesel or petrol powered generators and use mains electricity or battery powered equipment where practicable



- Impose and signpost a maximum-speed-limit of 15mph on surfaced and 10mph on unsurfaced haul roads and work areas (if long haul routes are required these speeds may be increased with suitable additional control measures provided, subject to the approval of the nominated undertaker and with the agreement of the local authority, where appropriate)
- Produce a Construction Traffic Management Plan to manage the sustainable delivery of goods and materials. Further details provided in Appendix 19.B: Outline Construction Traffic Management Plan
- Implement a Travel Plan that supports and encourages sustainable travel (public transport, cycling, walking, and car-sharing). Further details provided in Chapter 19: Traffic and Transport
- Only use cutting, grinding or sawing equipment fitted or in conjunction with suitable dust suppression techniques such as water sprays or local extraction, e.g., suitable local exhaust ventilation systems
- Ensure an adequate water supply on the site for effective dust/particulate matter suppression/mitigation, using non-potable water where possible and appropriate
- Use enclosed chutes and conveyors and covered skips
- Minimise drop heights from handling equipment and use fine water sprays on such equipment wherever appropriate
- Ensure equipment is readily available on site to clean any dry spillages and clean up spillages as soon as reasonably practicable after the event using wet cleaning methods
- Avoid bonfires and burning of waste materials.
- Construction:
 - Ensure sand and other aggregates are stored in appropriate manner to minimise dust generation for example the use of bunded areas
 - Avoid scabbling (roughening of concrete surfaces) if possible
 - Ensure bulk cement and other fine powder materials are delivered in enclosed tankers and stored in silos with suitable emission control systems to prevent escape of material and overfilling during delivery
 - For smaller supplies of fine power materials ensure bags are sealed after use and stored appropriately to prevent dust.
- Earthworks:
 - Manage earthworks and exposed areas/soil stockpiles to stabilise surfaces
 - Use Hessian, mulches or trackifiers where it is not possible to re-vegetate or cover with topsoil, as soon as practicable.
- Trackout:



- Use water-assisted dust sweeper(s) on the access and local roads, to remove, as necessary, any material tracked out of the site
- Avoid dry sweeping of large areas
- Ensure vehicles entering and leaving sites are covered to prevent escape of materials during transport
- Inspect on-site haul routes for integrity and instigate necessary repairs to the surface as soon as reasonably practicable
- Record all inspections of haul routes and any subsequent action in a site logbook
- Install hard surfaced haul routes where practicable, which are regularly damped down with fixed or mobile sprinkler systems, or mobile water bowsers and regularly cleaned
- Ensure there is an adequate area of hard surfaced road between the wheel wash facility and the site exit, wherever site size and layout permits
- Locate access gates at least 10m from receptors where possible.

5.10.2 NRMM measures

- 57. The following mitigation measures specific to NRMM will be secured within the final CEMP submitted post-consent.
- 58. NRMM and plant should be well maintained. If any emissions of dark smoke occur, then the relevant machinery should stop immediately, and any problem rectified.
- 59. In addition, the following controls should apply to NRMM:
 - All NRMM should use fuel equivalent to ultralow sulphur diesel (fuel meeting the specification within EN590:2004) where practicable
 - All NRMM should comply with the appropriate NRMM regulations
 - All NRMM would be fitted with Diesel Particulate Filters (DPF) conforming to defined and demonstrated filtration efficiency (load/duty cycle permitting)
 - The ongoing conformity of plant retrofitted with DPF, to a defined performance standard, should be ensured through a programme of onsite checks
 - Fuel conservation measures should be implemented, including instructions to

 (i) throttle down or switch off idle construction equipment;
 (ii) switch off the
 engines of trucks while they are waiting to access the site and while they are
 being loaded or unloaded and (iii) ensure equipment is properly maintained to
 ensure efficient fuel consumption.
- 60. Consideration should also be given to the siting of NRMM within the working area. Where practicable, locating generators and plant at the greatest distance from receptors will reduce the potential for air quality effects.



5.11 UXO Risk

61. Chapter 24: Major Accidents and Disasters considers the risk of Unexploded Ordinance (UXO). UXOs are remnants of past military activities that may still pose a significant threat to the safety and well-being of construction personnel and the surrounding environment. Surveys and assessments of the construction site, identifying potential UXO presence or historical activities will be undertaken by the Principal Contractor. In the event of any suspected or confirmed UXO findings, Principal Contractor will be required to implement appropriate measures, such as notifying relevant authorities, establishing exclusion zones, and engaging specialised personnel for safe removal and disposal. This approach aims to safeguard the construction workforce, local communities, and the environment, ensuring a secure and responsible construction process.

6. Environmental Management Structure and Responsibilities

- 62. The Principal Contractor is required to outline the environmental management roles and responsibilities for the Onshore Project in this section. This includes identification of key site staff, their environmental management responsibilities and how these links with other members of the Project team, such as the Project Manager, the project Health and Safety/Environmental Manager(s) and/or Advisors and environmental specialists such as an ECoW, TMCo ALO and Archaeological Coordinator.
- 63. The contact details for the individuals listed should also be included in this section or attached as an appendix to the CEMP.
- 64. The Construction Design and Management (CDM) Regulations of 2015 are a comprehensive set of legal guidelines implemented in the United Kingdom to ensure the safe and efficient management of construction projects. These regulations aim to prioritise health and safety considerations throughout the entire project lifecycle, from the design stage to completion and beyond. The CDM Regulations outline the roles and responsibilities of all parties involved, including clients, designers, contractors, and workers, in fostering a proactive safety culture. By encouraging collaboration, risk assessment, and proper planning, the CDM Regulations seek to reduce accidents, injuries, and health hazards within the construction industry, ultimately contributing to the delivery of successful and secure projects.
- 65. The different roles and summary of duties set out in the CDM regs 2015 include:
 - Commercial clients Organisations or individuals for whom the construction project is carried. Done as part of a business. Main duties include:



- Making suitable arrangements for managing a project
- Ensuring sufficient resources and time are allocated
- Ensuring other duty holders are appointed as appropriate
- Ensuring the principal designer and principal contractor carry out their duties
- Ensuring welfare facilities are provided.
- Domestic clients People who have construction work carried out on their own home.
- Designers Organisations or individuals who as part of a business, prepare or modify designs for a building, product or system relating to construction work.
- Principal designers Designers appointed by the client in projects involving more than one contractor. They can be an organisation or an individual with sufficient knowledge, experience and ability to carry out the role.
- Principal contractors Contractors appointed by the client to coordinate the construction phase of a project where it involves more than one contractor. Main duties include:
 - Plan, manage, monitor and coordinate health and safety in the construction phase of a project
 - Ensure suitable site inductions and reasonable steps to prevent unauthorised access are in place
 - Ensure workers are consulted and engaged in securing their health and safety
 - Ensure welfare facilities are provided.
- Contractors Those who carry out the actual construction work, contractors can be an individual or a company.
- Workers Those working for or under the control of contractors on a construction site.

7. Environmental Incident Response and Contingency

66. The Principal Contractor is required to include in this section the environmental incident response and contingency procedure. It is essential that any environmental incidents are reported and managed appropriately and appropriate mitigation measures are implemented to avoid future occurrences.

7.1 Emergency response plan

67. Principal Contractors will be required to have an environmental emergency response plan. This will be in additional to individual management plans already in place for day-to-day operations. The plan should identify the key personnel who can respond promptly in the event of an environmental incident, including a response flow chart and with details how to report and respond to an environmental incident (e.g., local spill kits, waste reception facilities, manage



dropped objects in the marine environment and offsite emergency response resources). The plan needs to include the protocol of how to deal with flood events and ensure that the project is signing up to EA flood warning system for the area.

68. Potential impacts from frac-out and drill fluid release will be considered within the CEMP. The Principal Contractor will, wherever possible use drilling fluids that are on the PLONOR list (Poses Little Or No Risk), the list is controlled and maintained by The Centre for Environment, Fisheries and Aquaculture Science (CEFAS). Products on the list are safe for discharge into the offshore or onshore environment, engagement with the relevant statutory bodies is still required but vastly reduced. The Principal Contractor will be required to have an environmental emergency response plan that includes the response to potential frac out incidents.

7.2 Reporting

- 69. The Principal Contractor is responsible for reporting and recording the environmental incidents and near misses in line with the Principal Contractor Environmental Management System.
- 70. Principal Contractor is required to produce performance monthly reports to demonstrate how the environmental objectives and targets are being met.

7.3 Nonconformance

71. If an environmental incident or deviation from the EMS procedures should occur, it shall be thoroughly investigated by the Principal Contractor to establish the root cause and prevent any recurrence. The Principal Contractor is required to outline the procedure for managing nonconformances and the process of implementing corrective actions.

8. Monitoring

- 72. The Principal Contractor is responsible for establishing a programme of performance and compliance monitoring will be established for the Onshore Project.
- 73. The Principal Contractor is required to include a monitoring process for complying with environmental permits and consents (i.e. water quality monitoring protocol agreed with the EA).

8.1 Site inspections and environmental monitoring

74. The Principal Contractor, or appointed delegate, will undertake site inspections on weekly basis. These site inspections should be undertaken by a component



person which should, as a minimum, and where relevant, cover the key issues outlined within this document. Weekly inspections should be complimented by audits to ensure legal compliance.

75. The Principal Contractor is responsible for ensuring the close out of any actions identified during the inspections. Records of the inspections carried out should be retained onsite by the Principal Contractor and a copy provided to the Applicant; any remedial actions required must also be recorded.

8.2 Environmental audits

- 76. Environmental audits should comprise both internal and external audits.
- 77. The Principal Contractor is responsible for developing and implementing an audit programme to audit construction sites on a periodic basis. The Principal Contractor's environmental audits shall be carried out by experienced auditors, either from within the Principal Contractor's environmental team, or via delegated specialists.
- 78. All actions raised from the audits shall be logged in line with the company audit procedure. Any nonconformances identified during the audit should be tracked, and closed out in a timely manner.

9. Training and Awareness

- 79. A range of mechanisms are used for training and raising awareness of project environmental issues; these include environmental inductions, TBTs, environmental notice boards, and environmental bulletins and alerts.
- 80. The Principal Contractor must ensure that all staff including any sub-contractors are trained in the Onshore Project's environmental emergency response procedures, so that they are able and prepared to respond to an incident promptly and effectively on-site. Where appropriate, the Applicant may request environmental emergency response plans to be tested on-site by the Principal Contractor.

9.1 Project/site inductions

- 81. All site personnel will be required to have a site induction that includes an environmental component. The Principal Contractor is responsible for preparing and delivering the site induction and maintain documented attendee records for the on-site personnel.
- 82. It is expected that the environmental management contents of site inductions will include reference to compliance with:
 - environmental management contacts



- site specific environmental sensitivities
- waste management arrangements
- water and wastewater management
- hazardous material management
- fuel, oil and chemical management
- environmental emergency response
- reporting of incidents and complaints
- UXO risk management
- Construction traffic management.

9.2 Toolbox Talks (TBTs)

- 83. TBTs are considered to be an effective method for the dissemination of information relating to work activities. Environmental TBTs will be required to be delivered by the Principal Contractor to on-site personnel as required. They also in part be delivered by the relevant member of the project team as well as the health, safety and environment (HSE) team. Toolbox talks are an opportunity for the Principal Contractor to disclose any other environmental sensitivities that the sub-Contractors must be aware of.
- 84. It is the responsibility of the Principal Contractor to ensure that all personnel attending the TBT have signed a TBT attendance sheet; TBT attendance sheets are likely to be inspected as part of environmental audits.

9.3 Environmental notice board

- 85. The Principal Contractor is required to display, in an appropriate and prominent location, copies of relevant environmental management information, including but not limited to the following:
 - Environmental policies
 - Key contacts details, including Principal Contractor's environmental management representative
 - Environmental bulletins
 - Site location plan showing ecologically/archaeologically sensitive areas, key management areas and location of contingency materials/features
 - Emergency response contact details
 - Emergency response flowchart.

10. Communication and Reporting

10.1 Meetings

86. Regular HSA meetings are required to be held on all construction sites, and are likely to comprise representatives from the Applicant's project team, the Principal



Contractor, and key sub-contractors. Minutes of meetings will be recorded, and standard agenda items will include items such as: status of outstanding items, reports of environmental incidents or complaints, stakeholder engagement, TBTs issued/delivered, and key findings of environmental inspections and audits. All reporting will be undertaken as stated in Health, Safety, Environmental and Quality minimum requirements document.

87. The Principal Contractor is expected to convene regular project team meetings to convey environmental information to the Project team, including subcontractors and to raise awareness of environmental issues.

10.2 Community complaints

- 88. The Applicant values its relationship with the communities that surround the Onshore Project. All work shall be carefully planned to minimise disturbance to the local communities.
- 89. The Principal Contractor must have a procedure in place to report public complaints and ensure that any complaints are reported to the Project team and investigated promptly.

10.3 Community liaison and land use

- 90. A public/community relations plan will be developed for the Onshore Project by the Principal Contractor. The purpose of the plan, which must be developed in liaison with the Project team, should set out the approach to community liaison for the duration of the Onshore Project. For the Onshore Project an Ecological Clerk of Works will be appointed, as required.
- 91. The Principal Contractor needs to outline the process that will limit and manage the timing of construction activities at Landfall up to Mean High Water Springs (MHWS) with the potential to affect public use of Saunton Sands Beach. These measures will include:
 - Communication and engagement activities to ensure that visitors to Saunton Sands are aware of the timing and extent of construction activities in the nearshore/intertidal zone
 - Maintaining access to Saunton Sands during construction no closure of the beach
 - Providing safety marshals for the protection of the public
 - Apply health and safety requirements proportionately: for example, balance the need for fencing/hoarding/barriers in nearshore/intertidal zone to protect swimmers and surfers from accessing construction and/or maintenance works with the need to maintain access to Saunton Sands.



- 92. The Onshore Project has the opportunity to enhance community safety at Saunton Sands by providing resources and by increasing capacity for human intervention if people are attempting or considering self-harm. It is acknowledged that a self-harm event, leading to injury or fatality, is low probability but that it would also be very serious.
- 93. The additional enhancement would comprise of signs that provide information about safety and sources of help for those considering self-harm; and training for safety marshals to train increased awareness about self-harm and actions to take. The CEMP will include water safety risk assessment and water safety plans and relevant training for safety marshals and other operation and maintenance workers.
- 94. The Principal Contractor must observe public rights of way and maintenance of flood defences where project activities may impact on these issues. A Public Rights of Way Strategy is provided in **Appendix 15.A**.

10.4 Stakeholders engagement

95. Reference should also be made to any reporting requirements in relation to stakeholders set out under the TCPA (1990). Interactions with stakeholders such as Natural England, Environment Agency (EA), Local Planning Authority, etc. should also be covered in this section.

11. Sub-Contractor Management

96. The CEMP will set out how the Principal Contractor manages their sub-Contractors. This may range from the selection and assessment processes through to the assessment of performance on site.

12. Sustainable Construction

- 97. The Sustainable Construction guidance issued by the Institute of Environmental Management and Assessment (2008) states the following: "Application of sustainable development to the construction industry, whereby the construction and management of a development is based on principles of resource efficiency and the protection/enhancement of natural and built heritage. Sustainable construction comprises such matters as site planning and design, material selection, resource and energy use, recycling, and waste minimisation". (Institute of Environmental Management and Assessment, 2008).
- 98. The Principal Contractor is required to outline in this section how the sustainable construction principles are embedded during the design phase and construction phases of the Onshore Project.



13. References

Institute of Environmental Management and Assessment (2008) Environmental Management Plans Practitioner, Volume 12. Available at: https://www.google.com/url?sa=t&rct=j&q=&esrc=s&source=web&cd=&cad=rja&u act=8&ved=2ahUKEwic37H1xqf9AhVRsKQKHQSWB7sQFnoECBgQAQ&url=https%3A %2F%2Fwww.iema.net%2Fdownload-

document%2F7014&usg=AOvVaw37vBz691GKel7dL9wojy1G. [Accessed February 2023]

Environment Agency (2014) Pollution Prevention Guidance. Available at: https://www.gov.uk/government/collections/planning-practice-guidance. [Accessed February 2023].

Health and Safety Executive (2015). Construction (Design and Management) Regulations 2015. https://www.hse.gov.uk/construction/cdm/2015/summary.htm. [Accessed July 2023].



Annex 1: Waste Audit Statement

1. Introduction

- 99. This Waste Audit Statement has been produced by the Applicant in order to address the North Devon Council (NDC) requirement for details in relation to waste management regarding the proposals for the Onshore Project.
- 100. The purpose of this document is to provide a draft of the Wate Audit Statement and to demonstrate that appropriate waste management measures will be developed and implemented during all phases of the Onshore Project.

2. Policy

- 101. The Devon County Council (DCC) have produced the Devon Waste Plan 2011-2031³ and a Supplementary Planning Document (SPD) on Waste Management and Infrastructure⁴ which sets out the requirement for a Waste Audit Statement for 'major development' applications⁵. The SPD provides guidance to local planning authorities and developers to assist in implementation of three of the Waste Plan's policies dealing with waste prevention, waste management infrastructure and the protection of waste management capacity:
 - Policy W4: Waste Prevention and Policy
 - Policy W10: Protection of Waste Management Capacity
 - W21: Making Provision for Waste Management.
- 102. This Waste Audit Statement will be updated and resubmitted to NDC for approval once the detailed design of the Onshore Project is complete. A condition that a revised Waste Audit Statement be produced, and that all works will be undertaken in accordance with the approved Waste Audit Statement will likely be attached to the consent for the Onshore Project following the example as set out in Appendix C of the SPD.

³ <u>https://www.devon.gov.uk/planning/planning-policies/minerals-and-waste-policy/devon-waste-plan/</u>
<u>4</u> <u>https://www.devon.gov.uk/planning/planning-policies/minerals-and-waste-policy/supplementary-planning-document/</u>

⁵ The Onshore Project is considered 'major development' as it has a site area of 1 hectare or more as defined in Appendix A of the SPD.



3. Structure of Waste Audit Statement

- 103. This statement includes all information outlined in the waste audit template provided in Appendix B of the SPD. In line with Appendix B of the SPD, the Waste Audit Statement provides:
 - Description of the site
 - Steps to be taken to minimise waste the amount of waste generated during excavation, demolition and construction
 - Type and volume of the waste to be generated during excavation, demolition and construction
 - Steps to be taken to achieve the re-use and recycling percentages
 - Type and volume of the waste to be generated during operation
 - How waste collection and sustainable waste management principles are incorporated into the development.

4. Waste Audit Statement

4.1 Project and Site Description

- 104. The Onshore Project comprises the construction of the following onshore infrastructure assets (landward of Mean Low Water Springs):
 - Onshore export cables (approximately 8km)
 - White Cross Onshore substation
 - Temporary main construction compound and temporary construction compounds
 - Transition Joint Bay, jointing bays and link boxes
 - Access roads and haul roads
 - Grid connection works within the existing East Yelland substation.
- 105. The Onshore Project includes approximately 8km of export cable which crosses a variety land uses as follows:
 - Saunton Sands Beach and Car Park
 - Saunton Golf Course
 - Arable farmland
 - Field boundaries and drainage ditches
 - Sandy Lane
 - River Taw / Taw Estuary
 - Pastural Fields
 - Tarka Trail
 - Infrastructure such as roads.



4.2 Step to minimise generation of waste during excavation, demolition and construction

106. Waste generated during the excavation, demolition and construction of the Onshore Project will be managed by the Principal Contractor in accordance with the waste hierarchy. The waste hierarchy requires the producer/holder of a waste to demonstrate that the priorities outlined in **Table 5.1** have been considered in the priority order, and to determine the most suitable waste management option for all wastes prior to removal from site. The Applicant will aim to prevent, reuse, recycle and/or recover waste where practical and economically feasible prior to considering disposal.

| Waste Hierarchy | Relevant activity |
|----------------------|---|
| Prevention | Using less material in design and manufacture, keeping products for longer, re-use, using less hazardous materials. |
| Preparing for re-use | Checking, cleaning, repairing, refurbishing, whole items, or spare parts. |
| Recycling | Turning waste into a new substance or product, includes composting if it meets quality protocols. |
| Other recovering | Includes anaerobic digestion, incineration with energy recovery, gasification and pyrolysis which produce energy (fuels, heat, and power) and materials from waste, some backfilling. |
| Disposal | Landfill and incineration without energy recovery. |

Table 4.1 The Waste Hierarchy

Table reproduced from Defra website: <u>https://www.gov.uk/waste-legislation-and-regulations</u>

- 107. The design of the Onshore Project will consider sustainability principals to make sure that over ordering on materials such a substation components, cement bound sand, ducting, tape, tiles and cables is kept to a minimum. As part of the preliminary design of the Onshore Project for the planning application estimates on the likely material quantities to be used during the construction phase have been provided by the engineering team. These quantities will be further refined as the project moves through the detailed design and will be monitored through the use of a Quantity Surveyor during the construction phase of the Onshore Project.
- 108. The Onshore Project has been designed with an operational lifetime of at least 25 years in order to align with the operational lifetime of the infrastructure from the Offshore Project, such as the wind turbine generators. Therefore, the materials to be used will be of a long-life span designed to be used for the minimum 25 years.



109. The SPD does not require that a Waste Audit Statement be produced for the decommissioning stage of projects, therefore any measures to be implemented during decommissioning are outside the scope of this Waste Audit Statement. However as set out within the Chapter 5: Project Description of the ES produced for the Onshore Project the decommissioning could be subject to a separate consenting process, which would likely require the production of a Waste Audit Statement in accordance with the relevant policy, legislation and guidance at the time.

4.3 Type and volume of the waste to be generated during excavation, demolition and construction

- 110. Demolition is not required as part of the Onshore Project due to its nature and therefore has not been considered further.
- 111. Excavation is identified as a 'waste' generating activity. It is considered that excavation during the Onshore Project will mainly comprise of the excavation of site soils to facilitate the installation of infrastructure, for example the excavation of the trenches for the instillation of the export cable.
- 112. Soils produced during the excavation will be re-used to backfill the subsequent excavation, or elsewhere on site, for example in the construction of the Onshore Substation to create the building platform to provide the required finished floor level to mitigate the flood risk. Excavated material will be removed from site either for re-use or recycling where no on-site re-use is possible.
- 113. Construction has the potential to create a variety of waste streams such as excess building materials, packaging or general waste generated from on-site activities. This includes the aggregates used for the construction of the temporary compounds, haul roads and other working area which will need to be removed before reinstatement.
- 114. At this stage the values some of these construction waste streams are not known, and without the detailed design would be difficult to estimate. However all the management of all construction waste streams will be undertaken in accordance with a Site Waste Management Plan (SWMP) which will be produced by the Principal Contractor (see **Section 4.6** below).
- 115. Indicative values of the known waste streams these have been summarised in Table4.2. An updated Waste Audit Statement will be provided once the design as been progressed sufficiently to provide further estimates.



Table 4.2 Construction Waste

| Material | Quantity | | | | | | |
|---|---------------------------------------|-------------------------------|--------------------------------|---------------------------------|----------------------------------|-------------------|-----------------------|
| | Total estimated amount (tonnes) | % to be re-used on-site | % to be re-used off-site | % to be recycled on- site | % to be recycled off- site | % to be recovered | % to be landfilled |
| Inert (waste that o | does not undergo | any signi | ficant phy | sical, chemica | l, or biological | transformations | (for example |
| concrete, bricks, r | | 4 = | | | 05 | | |
| Aggregate (Construction Consolidation Site Landfall HDD Compound Haul Road HDD compounds HDD installation Landfall transition bays Joint Bays Substation – Compound and Access Road) | 68,371 | 15 | | | 85 | | |
| Excavated materials (Cable Trench Substation access road | 40,500 | 34 | | | 66 | | |



| Material | Quantity |
|---|--|
| Subtation building platform Landfall Transitions Bay Joint Bays) | |
| Non-Hazardous (waste which does not cause harm to human health or the environment) | Estimated amounts of non-hazardous waste are unknown at this stage. An updated Waste Audit Statement will be provided once the project design is sufficiently progressed. |
| Hazardous (Waste which contains substances or has properties that might make it harmful to human health or the environment) | Estimated amounts of hazardous waste are unknown at this stage. An updated Waste Audit Statement will be provided once the project design is sufficiently progressed. The CEMP will include specific measures that are protective of controlled waters in relation to the storage of fuels, oils, lubricants, wastewater, and other chemicals during the works. |



4.4 Steps to be taken to achieve the re-use and recycling percentages

- 116. The excavated material generated during the construction phase will be properly segregated and stored, as set out in the OCMEP, in order that it can be re-used to backfill the excavations or elsewhere on site. Where is can't be re-used will be taken off-site for recycling using a local appropriately licensed site.
- 117. The aggregates used during the construction will be re-used where possible on the site, for example to provide the subbase materials for the permanent access road and substation permanent compound. The aggregates that can not be re-used will be recycled using a local appropriately licensed site.
- 118. Methods and commitments for preparing other construction waste streams for reuse and recycling on site are not known at this stage. Re-use and recycling will be undertaken on site where possible. The nearest suitable facility for hazardous waste or waste not re-used or recycled on site will be provide in an updated version of the Waste Audit Statement to be submitted and approved in advance of construction.

4.5 Type and volume of the waste to be generated during operation

- 119. On the basis of what is proposed during its operational phase it is unlikely that there will be waste generated. This has therefore not been considered further nor has the requirements for access for waste disposal vehicles or storage requirements.
- 120. Any waste that is generated, for example from the maintenance or servicing of the export cables and/or substation equipment, will be managed in accordance with the waste hierarchy (see **Table 5.1**).Given that any such waste will likely be of a high value, such as substation equipment or components, where prevention is not possible the majority of the waste will likely be re-used or recycled.

4.6 Waste Collection and Sustainable Waste Management Principles

- 121. During construction the Principal Contractor will be responsible for the collection, storage and disposal of any waste produced as part of the Onshore Project and will be required to prepare a Site Waste Management Plan (SWMP) in line with legislation, good practice. The SWMP will be developed post-consent to ensure the proper handling and protocols are in place to deal with any generated wastes. The Plan will record the following information, as a minimum:
 - The types and quantities of waste generated



- The management approach for each waste type (Reuse, Recycle, Recover, Dispose) including any treatment
- The storage arrangements for each waste type
- The site waste monitoring and reporting arrangements
- Waste carrier details and waste management/disposal facilities.
- 122. Adoption of a CL:AIRE Industry Code of Practice to manage the re-use and disposal of excavated soils within the Onshore Development Area would also be incorporated as an additional mitigation measure in the CEMP, this would aid in maximising sustainability and provide an audit trail to demonstrate the appropriate use of materials. A Materials Management Plan will be drafted in advance of any construction works, this would include chemical screening criteria in order to ensure that imported and/or reused materials are chemically suitable for use. If materials identified as containing asbestos are identified, then a specialist contractor would be employed to aid in its removal from Onshore Project Area, in line with current legislation.
- 123. Circular economy principles will be considered, where practical and economically feasible, specifically the priority area of circular construction and adopting circular economy interventions such as:
 - adopting circular design principles and construction processes, particularly the opportunity to create a physical and virtual resource recovery and material exchange hub to make better use of material wasted in construction
 - supporting the growth of regional specialist circular products and services in the construction industry.



White Cross Offshore Windfarm

Appendix 5.C: Outline Drainage Strategy





| Document Code: | FLO-WHI-REP-0016-05 | |
|-----------------------------|--------------------------------|----------------------|
| Contractor Document Number: | PC2978-RHD-ZZ- XX-RP-Z-0611 | |
| Version Number: | 00 | |
| Date: | 11/08/2023 | |
| Prepared by: | Ю | Electronic Signature |
| Checked by: | BA | Electronic Signature |
| Owned by: | СВ | Electronic Signature |
| Approved by Client: | OG | Electronic Signature |

| Version Number | Reason for Issue / Major Changes | Date of Change |
|-------------------|----------------------------------|----------------|
| 00 | For Issue | 11/08/2023 |



REPORT

White Cross Offshore Windfarm

Drainage Strategy Report

Client: Offshore Wind Limited

Reference:S2Status:S2/P03Date:7 August 2023



HASKONINGDHV UK LTD.

2 Abbey Gardens Great College Street London SW1P 3NL United Kingdom Mobility & Infrastructure VAT registration number: 792428892

+44 207 2222115 **T**

info.london@uk.rhdhv.com E

royalhaskoningdhv.com W

| Document title: | White Cross Offshore Windfarm |
|--|--|
| Reference: Status: Date: Project name: Project number: | P03/S2 7 August 2023 White Cross Offshore Windfarm |
| Drafted by: | 10 |
| Checked by: | ВА |
| Date: | 03-08-2023 |
| Approved by: | DJ |
| Date: | 20-07-2023 |
| | |

Classification

Click to enter "Classified"

Unless otherwise agreed with the Client, no part of this document may be reproduced or made public or used for any purpose other than that for which the document was produced. HaskoningDHV UK Ltd. accepts no responsibility or liability whatsoever for this document other than towards the Client.

Please note: this document contains personal data of employees of HaskoningDHV UK Ltd.. Before publication or any other way of disclosing, this report needs to be anonymized, unless anonymisation of this document is prohibited by legislation.

i



Table of Contents

| 1 | Introduction | 1 |
|-----|---------------------------------|---|
| 1.1 | Background | 1 |
| 1.2 | Purpose of this Document | 2 |
| 2 | Site Description | 3 |
| | Site Location | 3 |
| 2.1 | 3 | |
| 2.2 | Topography | 4 |
| 2.3 | Geology | 4 |
| 2.4 | Existing Watercourses | 4 |
| 3 | Proposed Drainage Strategy | 5 |
| 3.2 | Proposed Surface Water Strategy | 6 |
| 4 | Water Quality | 6 |
| 5 | Conclusions | 7 |
| | | |

Table of Tables

| Table 2-1: Existing Site Surroundings | 3 |
|---------------------------------------|---|
| Table 3-1: Summary of SuDS Provision | 6 |

Table of Figures

| Figure 2-1: Existing Site Location Plan | 3 |
|--|---|
| Figure 2-2: Existing bedrock underlying the site (British Geological Society Maps) | 5 |

Appendices

Annex A – Proposed Site Plan /Architectural Plans

- Annex B As Built information.
- Annex C– Proposed Drainage Strategy Plans
- Annex D Hydraulic Calculations



1 Introduction

1.1 Background

- 1.1.1 Royal HaskoningDHV was commissioned by Offshore Wind Limited (here in referred to as 'the Applicant') to prepare a Outline Drainage Strategy to support the proposed construction of onshore infrastructure associated with the White Cross Offshore Windfarm.
- 1.1.2 The White Cross Offshore Windfarm is a proposed floating offshore windfarm located in the Celtic Sea with a capacity of up to 100MW. The 'Onshore Project', entailing all infrastructure of the project landward of Mean Low Water Springs (MLWS), requires a Town and Country Planning Act 1990 (TCPA) application. A separate Section 36 (under the Electricity Act 1989) and Marine Licence (ML) application for Offshore Project components (seaward of Mean High Water Springs (MHWS)), which has been submitted as a to the Marine Management Organisation (MMO) following the MMO confirming that they would not consent the Onshore Infrastructure of the Windfarm Project.
- 1.1.3 The Onshore Project includes the infrastructure associated with the Landfall at Saunton Sands (to MLWS) where the onshore elements connect to the Offshore Project infrastructure, Onshore Export Cable (including joint bays and link boxes), Taw Estuary Crossing, a new White Cross Onshore Substation, and an Interconnecting Cable to the Grid Connection Point at the existing East Yelland Substation.
- 1.1.4 The set of consents/permission required in order for the Project as a whole to proceed are outlined below:
 - Planning permission under the Town and Country Planning Act 1990 (TCPA) 1990) is required for the following Onshore Project infrastructure (landward of MLWS):
 - Offshore export cables (from MLWS to above MHWS at the Landfall and Transition Joint Bay (TJB))
 - Onshore export cables (2 x 66 kilovolts (kV) or 1 x 132kV from Landfall to White Cross Onshore Substation and 132kV from the White Cross Onshore Substation to Grid Connection Point) – excluding section below MLWS at the Taw Estuary crossing
 - White Cross Onshore Substation
 - Temporary main construction compound and temporary construction compounds
 - Transition Joint Bay, jointing bays, link boxes, access roads and haul roads
 - Grid Connection Point.
- 1.1.5 Consent under the Section 36 of the Electricity Act 1989 and a Marine Licence under the Marine and Coastal Access Act 2009 (MCAA 2009) from the MMO are required for the following generation assets (within the Windfarm Site):
 - Wind Turbine Generators
 - Semi-submersible floating platforms
 - Subsea catenary mooring lines
 - Anchoring solutions (drag embedment anchors, suction anchor or pin piles)
 - Inter-array cables and associated protection
 - Other associated offshore infrastructure, such as navigational markers.



- A second Marine Licence is required to enable the option for an Offshore Transmission Owner (OFTO) to be appointed under The Electricity (Competitive Tenders for Offshore Transmission Licences) Regulations 2015 for the following transmission assets (to MHWS):
- Offshore Substation Platform
- Offshore export cable
- Other associated offshore infrastructure, such as navigational markers.
- 1.1.6 The Section 36 and Marine Licences applications were submitted to the MMO on 14th March 2023.
- 1.1.7 Further detail on the consenting regime and relevant legislation is presented in **Chapter 3: Policy** and Legislative Context.

1.2 Purpose of this Document

- 1.2.1 The purpose of this report is to present the proposed Outline Drainage Strategy for the proposed development at the application site and support the Flood Risk Assessment (FRA) in providing justification to regulators and other stakeholders that the proposed development is feasible.
- 1.2.2 This Drainage Strategy has been prepared in line with national policy requirements, and ultimately aims to support the future outline planning application for the application site. This report should be read in conjunction with the FRA (Ref. PC2978-RHD-ZZ-XX-DR-Z-0266), prepared by Royal HaskoningDHV.
- 1.2.3 The information outlined in this report has been developed in accordance with the National Planning Policy Framework (NPPF) along with advice and guidance from the Environment Agency, The Sustainable Drainage System (SuDS) Manual, and Lead Local Flood Authority (LLFA) local policies. In deducing the conclusions contained herein, Royal HaskoningDHV engaged in the following exercises:
 - Review of the LIDAR Survey Information
 - Undertook existing surface Water Run-off Calculation
 - Defined allowable surface Water Discharge
 - Undertook a Quick Storage Estimates calculations to define the volume of surface water storage required
 - Outline drainage design following a high-level proposed site level strategy
 - Full microdrainage network assessment of the proposals.
- 1.2.4 This Report references the priorities and preferences of National policies and in particular Devon County Council s' LLFA Guidance Documents¹. It outlines the drainage strategy by exploring SuDS options which allow regulators and other stakeholders to assess whether the development is feasible.

2

¹ https://www.devon.gov.uk/floodriskmanagement/planning-and-development/sustainable-drainage/



2 Site Description

2.1 Site Location

- 2.1.1 A Site Location Plan of the Onshore Substation is shown in **Annex A**.
- 2.1.2 The Windfarm Site is located over 52km off the North Cornwall and North Devon coast (westnorth-west of Hartland Point). The Offshore Export Cable will connect the Offshore Substation Platform (if required) to shore. The Export Cable will come ashore at a Landfall at Saunton Sands on the North Devon Coast, and then be routed underground to the East Yelland Substation where it connects into the distribution network. Prior to connecting to the East Yelland Substation the cable will connect to a new White Cross Onshore Substation. A full description of the Onshore Project is given in **Chapter 5: Project Description** of the Onshore Project ES.
- 2.1.3 The site of the proposed Onshore Substation was previously used as an oil and gas storage facility. It is situated at the north-east part of Yelland, north of Barnstaple. The River Taw is located far north of the site. The existing site is approximately 0.99 of brownfield site, however the purposes of this outline drainage strategy and in line with the requirement of the Devon County Council SUDs Design Guidance, will be considered as greenfield. The total area of the proposed development is 1.48ha.

| Direction | Neighbouring Features Description |
|-----------|--|
| West | East Yelland Substation |
| East | Existing Industrial Depot and B3233 |
| North | Immediately north is an industrial depot, far north is River Taw |
| South | Existing Solar Farm, far south is B3233-West Yelland |

Table 2.2.1: Existing Site Surroundings

2.1.4 Table 2.2 presents The site is referenced in paragraph 2.1.2, and a site location plan is shown in Annex A.

Table 2.2 Site Location Information

| Item | Brief Description |
|---|--|
| Site Address and Location | Land to west of Estuary Business Park. Closest postcode is EX31 3HB. |
| Council Area | North Devon Council / Devon County Council |
| Approximate Grid Reference | SS 48217 32177 |
| Total impermeable footprint (including Onshore Substation access road, excluding landscape and embankment) | Approximately 0.5ha |
| Existing greenfield area impact | 0.48ha |



2.2 Topography

2.2.1 The site topography is generally very flat. The existing ground appears to slope in two directions from 5.3mAOD in the north-east direction to approximately 4.83mAOD in the south-west direction.

2.3 Geology

- 2.3.1 Information presented on the BGS online viewer² indicates that the superficial deposits underlying the Site consist of Alluvium, sand and gravel. The bedrock geology underlying the Site consist of Ashton Mudstone Member and Crackington Formation Mudstone and siltstone.
- 2.3.2 Intrusive ground investigation evaluating sub soil strata has not been undertaken at this stage, and there is no readily available information from historic boreholes in the vicinity of the site. The information extracted from the BGS website suggests the underlying strata is of cohesive soil composition.

2.4 Existing Watercourses

2.4.1 There appears to be existing land drainage ditches at the northern boundary of the site. River Taw is located to the far north of the site.



Figure 2.1 Existing bedrock underlying the site (British Geological Society Maps)

² https://www.bgs.ac.uk/discovering-geology/maps-and-resources/maps/



3 Proposed Drainage Strategy

- 3.1.1 The proposal involves the installation proposed onshore substation building, control building and associated access road and parking. The proposals consist of a total of 0.64ha of newly introduced impermeable area.
- 3.1.2 Management of surface water is an essential element for reducing flood risk and SuDS techniques are often designed to achieve this in a way that mimics the natural environment. This SuDS Strategy is subject to consents and approval from the Devon County Council. Devon County Council will be formally consulted by North Devon Council as part of the TCPA planning application process.
- 3.1.3 Following a telephone conversation with the office of the Lead Local Flooding Authority, the acceptability of the outline drainage strategy will be determined based on adherence to the dictates of the policies as stated in the Devon County Council (DCC) s' LLFA Guidance Documents. As stated on in paragraph 1.24 on this report, the drainage strategy is based on these DCC preferences and requirements.
- 3.1.4 This SuDS Assessment has been developed in line with the SuDS hierarchical approach outlined in the Flood Risk and Coastal Change Section of the Planning Practice Guidance, which recommends that surface water run-off should be discharged as high up the following hierarchy of drainage options as reasonably practicable:
 - Infiltration into ground
 - To a surface water body
 - To a surface water sewer, highway drain or other drainage system
 - To a combined sewer.
- 3.1.5 As discussed in **Section 2.4**, the BGS mapping indicates the underlying ground conditions to have a cohesive composition. Given the information currently available, it is assumed that surface water discharge methods using infiltration techniques are deemed unsuitable for this site.
- 3.1.6 As noted in **paragraph 2.1.2**, the site was previously used as an oil and gas storage facilities, however the Devon County Council Sustainable Drainage Guidance requires that development for developments on brownfield sites, peak flow control must still match the greenfield run-off rate, especially where there is increase in impermeable surface introduced as a result of a proposed development.
- 3.1.7 The existing greenfield run-off estimate for the site using the HR Wallingford procedure is presented in **Annex C**. The drainage design strategy is sought that the post development discharge rate is no more that the equivalent greenfield run-off rates up to the 1 in 100-year storm event including climate change allowance.
- 3.1.8 This Drainage Strategy is informed by the Flood Risk Assessment (Ref. PC2978-RHD-ZZ-XX-DR-Z-0266), which suggested an Upper End allowance for the future Extreme Water Levels of 6.43mAOD. The FFL of the substation will therefore be at least 300mm above this level (equating to 6.73mAOD). The proposed ground level is 1.4m above the existing ground at the development site.



3.2 Proposed Surface Water Strategy

- 3.2.1 Overall impermeable area contributing surface water run-off is approximately 0.64ha. It is proposed that surface water drainage from all impermeable surfaces are routed via a proprietary treatment system, such as hydro-downstream defenders or similarly equivalent, into an attenuation pond located to the south of the proposed development.
- 3.2.2 Peak surface water run-off is then restricted to the maximum greenfield run-off rate of 3.87l/s for the 1 in 100-year rainfall event. This is to be restricted, via a proposed hydrobrake flow control device at the downstream end of the pond.
- 3.2.3 It is proposed to channel the restricted surface-water flow via a 150mm pipe laid at a minimum gradient of 1 in 150, but ensuring no conflict between this proposed pipe and the proposed/existing underground cables in the vicinity of the works.
- 3.2.4 The proposed drainage strategy is indicated in drawing PC3506-RHD-ZZ-XX-DR-D-0500 (Annex B).
- 3.2.5 The proposed attenuation pond contributes approximately 433m³ of storage. Maximum depth of the pond is approximately 1.2m with a minimum side slope of 1 in 3. The geometry of the pond ensures a free board of approximately 0.15m is secured in the 1 in 100 year plus climate change event.
- 3.2.6 Surface water run-off is contained without flooding during the 1 in 100-year storm event in line with the requirements of the Devon County Council. **Annex C** presents the Full Microdrainage Network calculations modelling the storage and conveyance capacity of the proposed drainage system. A summary of the SuDS provision is provided in **Table 3-1**.

| | | | Discharge Flowrate (l/s) |
|---------------------------------------|-------------|-----|-----------------------------|
| Detention Basin (Attenuation Pond) | Attenuation | 433 | 3.8l/s |

Table 3.1: Summary of SuDS Provision

4 Water Quality

4.1.1 Proposed run-off quality control for the site will include proprietary treatment. A schedule of the size of the oil interceptors is included in **Annex D**. The proposed oil interceptors ensures that that:

TOTAL SUDS MITIGATION INDEX \geq POLLUT(FOR EACH CONTAMINANT)(FOR EACH


POLLUTION HARDARD INDEX (FOR EACH CONTAMINANT)


4.1.2 **Annex D** includes details of the results of the SIA tools and demonstrates that the proposals are sufficient and meet the required standards for water quality.



5 Conclusions

- 5.1.1 The existing site is previously developed. The Devon County Council Sustainable Drainage requires proposed peak outflow from existing brownfield sites to be the equivalent greenfield runoff rates. The existing ground appear to slope in two directions from 5.3mAOD in the north-east direction to approximately 4.83mAOD in the south-west direction.
- 5.1.2 Information presented on the BGS online viewer indicates the bedrock geology underlying the Site consist of Ashton Mudstone Member and Crackington Formation Mudstone and siltstone. The BGS mapping indicates the underlying ground conditions to have a cohesive composition. It is assumed that surface water discharge methods using infiltration techniques are deemed unsuitable for this site. Infiltration tests to BRE 365 should be conducted to verify this assumption.
- 5.1.3 Extensive topographical survey will be undertaken during detailed design to verify the presence, direction of water flow and the existing invert levels of the land drains in the vicinity of the site.
- 5.1.4 The surface water drainage from approximately 0.64ha of impermeable surfaces will be routed via a proprietary treatment system, into an attenuation pond providing a storage volume of approximately 433m³.
- 5.1.5 Peak surface water run-off is restricted via a hydro-brake flow control device to the maximum greenfield run-off rate of 3.87l/s for the 1 in 100-year rainfall event including climate change allowances. This is to be restricted surface water outflow is directed into existing land drains located northwest of the development.
- 5.1.6 There will be no increase in flood risk from the site to the surrounding area due to the restricted run-off rates and inclusion of SuDS. This SuDS Assessment/Drainage Strategy demonstrates to regulators and other stakeholders that the proposed development is feasible.





| | NOTES |
|----------------------------------|--|
| | 1. ALL DIMENSIONS ARE IN MILLIMETRES UNLESS NOTED OTHERWISE. |
| | 2. ALL LEVELS ARE IN METRES ABOVE CHART DATUM UNLESS NOTED OTHERWISE. |
| | 3. THIS DRAWING IS TO BE READ IN CONJUNCTION WITH ALL RELEVANT ENGINEERS DRAWINGS AND PROJECT SPECIFICATION. |
| | 4. WORKS TO BE UNDERTAKEN IN ACCORDANCE WITH THE SPECIFICATION FOR HIGHWAYS WORKS (SHW) UNLESS NOTED OTHERWISE. |
| | ALL DIMENSIONS AND LEVELS ARE TO BE VERIFIED AND CONFIRMED ON SITE PRIOR TO WORK COMMENCING. |
| | 6. ANY DISCREPENCIES TO OR OMISSIONS ARE TO BE REPORTED TO THE PROJECT MANAGER FOR FURTHER INSTRUCTIONS BEFORE COMMENCEMENT OF WORKS. |
| | |
| | LEGEND |
| | PROPOSED SURFACE WATER SEWER AND MANHOLE G |
| | G ⋈ PROPOSED GULLY |
| | EXISTING OVERHEAD ELECTRICAL CABLE |
| | EXISTING UNDERGROUND ELECTRICAL CABLE |
| | TEMPORARY CONSTRUCTION COMPOUND |
| | PROPOSED DETENTION BASIN |
| | PROPOSED GRADED EMBANKMENT |
| | PROPOSED FILTER DRAIN AT THE TOE OF EMBANKMENT |
| | RWP PROPOSED RAINWATER OUTLET FROM ROOF |
| | P05 08-09-23 GULLY POSITIONS AND MANHOLE REFRENCES IO OA DJ P04 20-07-23 REVISED TO INCLUDE UPDATED SITE PLAN IO OA DJ |
| | P01 16-05-23 FIRST ISSUE IO OA DJ |
| | REV DATE DESCRIPTION BY CHK APP REVISIONS |
| | DRAWING STATUS PRELIMINARY |
| | CLIENT |
| | OFFSHORE WIND LIMITED |
| | WHITE CROSS WINDFARM |
| | OUTLINE SURFACE WATER DRAINAGE STRATEGY |
| | Portland Street, Manchester One, 9th Floor Manchester, M1 3LF Tel +44(0)161 2361018 Email info.manchester@uk.rhdhv.com Website www.royalhaskoning.com HaskoningDHV Enhancing Society Together |
| 5 0 10 20 30m SCALE IN METRES | DRAWN CHECKED APPROVED DW IO PPV DATE SCALE AT A1 PROJECT NUMBER |
| C HaskoningDHV UK Ltd. | OCT-22 1:500 PC2978 DRAWING No. REVISION PC3506-RHD-ZZ-XX-DR-D-0500 P05 |
| | |

| HaskoningDHV UK Limited | Page 1 | |
|-------------------------|-------------------------|---------------------------|
| Rightwell House | ATTENUATION VOLUME | |
| Bretton, Peterborough | PLOT 1 BIRKENHEAD | Contraction of the second |
| Surrey, PE3 8DW | | Micro |
| Date 05/05/2023 11:57 | Designed by IOJO | Drainage |
| File | Checked by PVICENTE | Diamage |
| Innovyze | Source Control 2020.1.3 | |

Half Drain Time : 1080 minutes.

| | Storm | | Max | Max | Max | Max | Max | Max | Status |
|-----|---------|-----|--------|-------|--------------|---------|------------------|--------|--------|
| | Event | | Level | Depth | Infiltration | Control | Σ Outflow | Volume | |
| | | | (m) | (m) | (1/s) | (l/s) | (l/s) | (m³) | |
| 1 - | | | 07 754 | 0 054 | 0.0 | 0 0 | 0.0 | 105 0 | 0.77 |
| 15 | min Sum | mer | 97.754 | 0.254 | 0.0 | 0.0 | 0.0 | 125.2 | ОК |
| 30 | min Sum | mer | 97.850 | 0.350 | 0.0 | 1.1 | 1.1 | 172.7 | ОК |
| 60 | min Sum | mer | 97.954 | 0.454 | 0.0 | 3.4 | 3.4 | 224.2 | ΟK |
| 120 | min Sum | mer | 98.069 | 0.569 | 0.0 | 3.8 | 3.8 | 281.3 | ΟK |
| 180 | min Sum | mer | 98.138 | 0.638 | 0.0 | 3.9 | 3.9 | 315.0 | ΟK |
| 240 | min Sum | mer | 98.183 | 0.683 | 0.0 | 3.9 | 3.9 | 337.5 | ΟK |
| 360 | min Sum | mer | 98.240 | 0.740 | 0.0 | 3.9 | 3.9 | 365.5 | ΟK |
| 480 | min Sum | mer | 98.277 | 0.777 | 0.0 | 3.9 | 3.9 | 384.0 | ΟK |

| | Storm Event | Rain (mm/hr) | Flooded Volume (m³) | Discharge Volume (m³) | Time-Peak (mins) |
|-----|----------------|-----------------|---------------------------|-----------------------------|---------------------|
| 15 | min Summer | 104.373 | 0.0 | 0.0 | 27 |
| 30 | min Summer | 72.185 | 0.0 | 20.5 | 42 |
| 60 | min Summer | 47.821 | 0.0 | 78.6 | 70 |
| 120 | min Summer | 30.679 | 0.0 | 143.1 | 128 |
| 180 | min Summer | 23.321 | 0.0 | 184.2 | 188 |
| 240 | min Summer | 19.055 | 0.0 | 213.9 | 246 |
| 360 | min Summer | 14.198 | 0.0 | 256.5 | 364 |
| 480 | min Summer | 11.527 | 0.0 | 289.7 | 482 |
| | (| ©1982-20 |)20 Inn | ovyze | |

| HaskoningDHV UK Limited | | | |
|-------------------------|-------------------------|---------------------------|--|
| Rightwell House | ATTENUATION VOLUME | | |
| Bretton, Peterborough | PLOT 1 BIRKENHEAD | Contraction of the second | |
| Surrey, PE3 8DW | | Micro | |
| Date 05/05/2023 11:57 | Designed by IOJO | Drainage | |
| File | Checked by PVICENTE | Diamage | |
| Innovyze | Source Control 2020.1.3 | | |

| | Storm Event | | Max Level (m) | Max Depth (m) | Max Infiltration (1/s) | Max Control (l/s) | Max Σ Outflow (l/s) | Max Volume (m³) | Status |
|------|----------------|-------|---------------------|---------------------|------------------------------|-------------------------|---------------------------|-----------------------|--------|
| 600 | min Su | ummer | 98.302 | 0.802 | 0.0 | 3.9 | 3.9 | 396.4 | ΟK |
| 720 | min Su | ummer | 98.319 | 0.819 | 0.0 | 3.9 | 3.9 | 404.6 | ΟK |
| 960 | min Su | ummer | 98.344 | 0.844 | 0.0 | 3.9 | 3.9 | 416.7 | ΟK |
| 1440 | min Su | ummer | 98.372 | 0.872 | 0.0 | 3.9 | 3.9 | 430.9 | ΟK |
| 2160 | min Su | ummer | 98.386 | 0.886 | 0.0 | 3.9 | 3.9 | 437.6 | ΟK |
| 2880 | min Su | ummer | 98.379 | 0.879 | 0.0 | 3.9 | 3.9 | 434.1 | ΟK |
| 4320 | min Su | ummer | 98.334 | 0.834 | 0.0 | 3.9 | 3.9 | 412.1 | ΟK |
| 5760 | min Su | ummer | 98.273 | 0.773 | 0.0 | 3.9 | 3.9 | 381.8 | ΟK |
| 7200 | min Su | ummer | 98.211 | 0.711 | 0.0 | 3.9 | 3.9 | 351.4 | ΟK |

| | Stor Ever | | Rain (mm/hr) | Flooded Volume (m³) | Discharge Volume (m³) | Time-Peak (mins) | |
|------|--------------|--------|-----------------|---------------------------|-----------------------------|---------------------|--|
| 600 | min | Summer | 9.797 | 0.0 | 316.7 | 602 | |
| 720 | min | Summer | 8.572 | 0.0 | 339.5 | 700 | |
| 960 | min | Summer | 6.935 | 0.0 | 376.8 | 812 | |
| 1440 | min | Summer | 5.133 | 0.0 | 429.3 | 1068 | |
| 2160 | min | Summer | 3.788 | 0.0 | 503.7 | 1476 | |
| 2880 | min | Summer | 3.049 | 0.0 | 551.0 | 1880 | |
| 4320 | min | Summer | 2.239 | 0.0 | 620.6 | 2684 | |
| 5760 | min | Summer | 1.796 | 0.0 | 678.3 | 3464 | |
| 7200 | min | Summer | 1.516 | 0.0 | 723.6 | 4184 | |
| | | C | 1982-20 | 20 Inno | vyze | | |

| HaskoningDHV UK Limited | Page 3 | |
|-------------------------|-------------------------|---------------------------|
| Rightwell House | ATTENUATION VOLUME | |
| Bretton, Peterborough | PLOT 1 BIRKENHEAD | Contraction of the second |
| Surrey, PE3 8DW | | Micro |
| Date 05/05/2023 11:57 | Designed by IOJO | Drainage |
| File | Checked by PVICENTE | Diamage |
| Innovyze | Source Control 2020.1.3 | |

| | Storm Event | | Max Level (m) | Max Depth (m) | Max Infiltration (l/s) | Max Control (1/s) | Max Σ Outflow (1/s) | Max Volume (m³) | Status |
|-------|----------------|------|---------------------|---------------------|------------------------------|-------------------------|---------------------------|-----------------------|--------|
| 8640 | min Sum | nmer | 98.154 | 0.654 | 0.0 | 3.9 | 3.9 | 323.2 | ОК |
| 10080 | min Sun | nmer | 98.105 | 0.605 | 0.0 | 3.9 | 3.9 | 298.9 | ОК |
| 15 | min Wir | nter | 97.784 | 0.284 | 0.0 | 0.0 | 0.0 | 140.3 | ОК |
| 30 | min Wir | nter | 97.889 | 0.389 | 0.0 | 2.5 | 2.5 | 192.4 | ОК |
| 60 | min Wir | nter | 98.008 | 0.508 | 0.0 | 3.7 | 3.7 | 251.1 | ОК |
| 120 | min Wir | nter | 98.140 | 0.640 | 0.0 | 3.9 | 3.9 | 316.3 | ОК |
| 180 | min Wir | nter | 98.219 | 0.719 | 0.0 | 3.9 | 3.9 | 355.0 | ОК |
| 240 | min Wir | nter | 98.271 | 0.771 | 0.0 | 3.9 | 3.9 | 381.0 | ОК |
| 360 | min Wir | nter | 98.338 | 0.838 | 0.0 | 3.9 | 3.9 | 414.0 | O K |

| | Storm Event | Rain (mm/hr) | Flooded Volume (m³) | Discharge Volume (m³) | Time-Peak (mins) |
|-------|----------------|-----------------|---------------------------|-----------------------------|---------------------|
| 8640 | min Summer | 1.320 | 0.0 | 762.0 | 4928 |
| 10080 | min Summer | 1.174 | 0.0 | 794.8 | 5640 |
| 15 | min Winter | 104.373 | 0.0 | 0.0 | 27 |
| 30 | min Winter | 72.185 | 0.0 | 40.6 | 41 |
| 60 | min Winter | 47.821 | 0.0 | 106.0 | 68 |
| 120 | min Winter | 30.679 | 0.0 | 178.3 | 126 |
| 180 | min Winter | 23.321 | 0.0 | 224.2 | 184 |
| 240 | min Winter | 19.055 | 0.0 | 257.4 | 242 |
| 360 | min Winter | 14.198 | 0.0 | 305.0 | 358 |
| | ©1 | 1982-202 | 20 Inno | vyze | |

| HaskoningDHV UK Limited | | Page 4 |
|-------------------------|-------------------------|---------------------------|
| Rightwell House | ATTENUATION VOLUME | |
| Bretton, Peterborough | PLOT 1 BIRKENHEAD | Contraction of the second |
| Surrey, PE3 8DW | | Micro |
| Date 05/05/2023 11:57 | Designed by IOJO | Drainage |
| File | Checked by PVICENTE | Diamage |
| Innovyze | Source Control 2020.1.3 | |

| | Storm Event | | Max Level (m) | Max Depth (m) | Max Infiltration (1/s) | Max Control (1/s) | Max Σ Outflow (1/s) | Max Volume (m³) | Status |
|------|----------------|-------|---------------------|---------------------|------------------------------|-------------------------|---------------------------|-----------------------|--------|
| 480 | min Wi | inter | 98.383 | 0.883 | 0.0 | 3.9 | 3.9 | 436.4 | ОК |
| 600 | min Wi | inter | 98.415 | 0.915 | 0.0 | 3.9 | 3.9 | 451.9 | ΟK |
| 720 | min Wi | inter | 98.437 | 0.937 | 0.0 | 3.9 | 3.9 | 463.0 | ΟK |
| 960 | min Wi | inter | 98.464 | 0.964 | 0.0 | 3.9 | 3.9 | 476.3 | ΟK |
| 1440 | min Wi | inter | 98.481 | 0.981 | 0.0 | 3.9 | 3.9 | 484.6 | ΟK |
| 2160 | min Wi | inter | 98.479 | 0.979 | 0.0 | 3.9 | 3.9 | 483.5 | ΟK |
| 2880 | min Wi | inter | 98.450 | 0.950 | 0.0 | 3.9 | 3.9 | 469.2 | ΟK |
| 4320 | min Wi | inter | 98.357 | 0.857 | 0.0 | 3.9 | 3.9 | 423.5 | ΟK |
| 5760 | min W | inter | 98.253 | 0.753 | 0.0 | 3.9 | 3.9 | 372.0 | ΟK |

| | Sto: Ever | | Rain (mm/hr) | Flooded Volume (m ³) | Discharge Volume (m³) | Time-Peak (mins) | |
|------|--------------|--------|-----------------|--|-----------------------------|---------------------|--|
| 480 | min | Winter | 11.527 | 0.0 | 342.0 | 472 | |
| 600 | min | Winter | 9.797 | 0.0 | 372.0 | 586 | |
| 720 | min | Winter | 8.572 | 0.0 | 397.3 | 698 | |
| 960 | min | Winter | 6.935 | 0.0 | 438.0 | 916 | |
| 1440 | min | Winter | 5.133 | 0.0 | 488.8 | 1168 | |
| 2160 | min | Winter | 3.788 | 0.0 | 582.0 | 1624 | |
| 2880 | min | Winter | 3.049 | 0.0 | 634.8 | 2072 | |
| 4320 | min | Winter | 2.239 | 0.0 | 712.5 | 2904 | |
| 5760 | min | Winter | 1.796 | 0.0 | 777.7 | 3688 | |
| | | © | 1982-20 | 20 Innc | ovyze | | |

| HaskoningDHV UK Limited | | Page 5 |
|-------------------------|-------------------------|----------|
| Rightwell House | ATTENUATION VOLUME | |
| Bretton, Peterborough | PLOT 1 BIRKENHEAD | |
| Surrey, PE3 8DW | | Micro |
| Date 05/05/2023 11:57 | Designed by IOJO | Drainage |
| File | Checked by PVICENTE | Drainage |
| Innovyze | Source Control 2020.1.3 | |

| Storm | Max | Max | Max | Max | Max | Max | Status |
|------------------|--------|-------|--------------|---------|------------------|--------|--------|
| Event | Level | Depth | Infiltration | Control | Σ Outflow | Volume | |
| | (m) | (m) | (1/s) | (l/s) | (1/s) | (m³) | |
| | | | | | | | |
| 7200 min Winter | 98.160 | 0.660 | 0.0 | 3.9 | 3.9 | 325.9 | ОК |
| 8640 min Winter | 98.083 | 0.583 | 0.0 | 3.9 | 3.9 | 288.2 | ΟK |
| 10080 min Winter | 98.025 | 0.525 | 0.0 | 3.7 | 3.7 | 259.4 | O K |

| Storm | Rain | Flooded | Discharge | Time-Peak |
|------------------|---------|---------|-----------|-----------|
| Event | (mm/hr) | Volume | Volume | (mins) |
| | | (m³) | (m³) | |
| | | | | |
| 7200 min Winter | 1.516 | 0.0 | 828.4 | 4400 |
| 8640 min Winter | 1.320 | 0.0 | 871.6 | 5096 |
| 10080 min Winter | 1.174 | 0.0 | 908.7 | 5752 |

| HaskoningDHV UK Limited | | | | | Page 6 |
|---|-----------------------------|----------------------------------|------------------------------|------------|----------|
| Rightwell House | ATTENUATION | VOLUME | | | |
| Bretton, Peterborough | PLOT 1 BIRK | ENHEAD | | | |
| Surrey, PE3 8DW | | | | | Micco |
| Date 05/05/2023 11:57 | Designed by | IOJO | | | |
| File | Checked by | PVICENTE | | | Drainage |
| Innovyze | _ | rol 2020.1.3 | | | |
| | | | | | |
| | Model Det | ails | | | |
| Storag | e is Online Cover | Level (m) 100.000 | | | |
| <u>(</u> | Cellular Storage | e Structure | | | |
| Invert Level (m) Infiltration Coefficient Base (m/hr) Depth (m) Area (m ²) Inf. Area (m ²) Dep 0.000 520.0 0.0 | 0.00000 | _ | Factor (m) Area (| 2.0 | |
| Hydro- | -Brake® Optimum | Outflow Control | | | |
| | | | | | |
| Unit Reference MD-SHE-008 Design Head (m) | 2.200 | | ımp Availabl Diameter (mm | | |
| Design Head (M) Design Flow (1/s) | 2.200 | | ert Level (mm | , | |
| Flush-Flo™ | | Ainimum Outlet Pipe I | | , | |
| Objective Minimise Application | upstream storage Surface | Suggested Manhole I | Diameter (mm |) 1200 | |
| Control Points Head | (m) Flow (l/s) | Control Points | Head (m) | Flow (l/s) | |
| | 200 5.0 391 3.9 Mea | Kick-Fl an Flow over Head Rar | | | |
| The hydrological calculations have been based on the another type of control device other than a Hydro-Bra | | | | | |

| HaskoningDHV UK Limited | | Page 7 |
|-------------------------|-------------------------|-----------|
| Rightwell House | ATTENUATION VOLUME | |
| Bretton, Peterborough | PLOT 1 BIRKENHEAD | |
| Surrey, PE3 8DW | | Micro |
| Date 05/05/2023 11:57 | Designed by IOJO | Drainage |
| File | Checked by PVICENTE | Dialitage |
| Innovyze | Source Control 2020.1.3 | · · · · · |

Hydro-Brake® Optimum Outflow Control

| Depth (m) | Flow (l/s) |
|-----------|------------|-----------|------------|-----------|------------|-----------|------------|-----------|------------|-----------|------------|
| 0.100 | 2.8 | 0.600 | 3.8 | 1.600 | 4.3 | 2.600 | 5.4 | 5.000 | 7.3 | 7.500 | 8.9 |
| 0.200 | 3.6 | 0.800 | 3.1 | 1.800 | 4.5 | 3.000 | 5.8 | | 7.7 | 8.000 | 9.2 |
| 0.300 | 3.9 | 1.000 | 3.5 | 2.000 | 4.8 | 3.500 | 6.2 | 6.000 | 8.0 | 8.500 | 9.4 |
| 0.400 | 3.9 | 1.200 | 3.8 | 2.200 | 5.0 | 4.000 | 6.6 | 6.500 | 8.3 | 9.000 | 9.7 |
| 0.500 | 3.9 | 1.400 | 4.0 | 2.400 | 5.2 | 4.500 | 7.0 | 7.000 | 8.6 | 9.500 | 10.0 |

| HaskoningDHV UK Limited | | Page 1 |
|--|--|-------------------------|
| Rightwell House | Drainage Strategy | |
| Bretton, Peterborough | White Cross Offshore Windfarm | and the second second |
| Surrey, PE3 8DW | | Micro |
| Date 28/05/2023 21:45 | Designed by IO | Drainan |
| File Surfacewater Network.MDX | Checked by BA | bianiagi |
| Innovyze | Network 2020.1.3 | |
| | by the Modified Rational Method Criteria for Storm | <u>d</u> |
| Pipe Sizes STA | NDARD Manhole Sizes STANDARD | |
| Ma Maximum Time o Vo Add Flo Minim Maxim Min Design Dept Min Vel for Min Slope | Model - England and Wales Return Period (years) 100 M5-60 (mm) 16.500 Ratio R 0.281 ximum Rainfall (mm/hr) 50 f Concentration (mins) 30 Foul Sewage (l/s/ha) 0.000 lumetric Runoff Coeff. 0.750 PIMP (%) 100 w / Climate Change (%) 0 num Backdrop Height (m) 0.200 num Backdrop Height (m) 1.500 h for Optimisation (m) 1.200 Auto Design only (m/s) 1.00 for Optimisation (1:X) 500 ed with Level Soffits | |
| Time Ar | ea Diagram for Storm | |
| Time Area (mins) (ha) 0-4 0.073 | Time Area Time Area (mins) (ha) (mins) (ha) 4-8 0.468 8-12 0.073 | |
| | ' ' | |
| Total Area | Contributing (ha) = 0.614 | |
| Total Pip | pe Volume (m³) = 47.077 | |
| Network I | Design Table for Storm | |
| | | |
| « - Indica | tes pipe capacity < flow | |
| | | |
| PN Length Fall Slope I.Area T.E. (m) (m) (1:X) (ha) (mins | Base k HYD DIA Sectio) Flow (l/s) (mm) SECT (mm) | on Type Auto Design |
| Netw | ork Results Table | |
| PN Rain T.C. US/ILΣI.Are (mm/hr) (mins) (m) (ha) | | Cap Flow (l/s) (l/s) |
| | | |

| - | well Ho | ouse | | | Dra | ainage | Stra | tegy | | | | [| | |
|--|---|---|---|--|---|-----------------------|--|--|--|---|--|---|--|---|
| Brett | con, Per | | ouah | | | - | | ffsho | re Wir | ndfar | m | he - | | |
| | ey, PE3 | | Jugii | | **11_ | UI | 555 0 | | ,,,_1 | | | 1112 | |) in the |
| | 28/05/2 | | 1.45 | | Der | signed | htz 7 | 0 | | | | MIC | and in case of the local division of the loc | |
| | Surface | | | onle MD | | - | - | | | | | Dra | ina | qe |
| | | ewater | Netw | OIK.MD. | | ecked | | | | | | | | 9 |
| Innov | yze | | | | | twork | | | | | | | | |
| | | | | <u>Netwo</u> : | rk Desi | gn Tak | ole fo | or Sto | rm | | | | | |
| PN | Length (m) | Fall (m) | Slope (1:X) | I.Area (ha) | n T.E. (mins) | | .se (1/s) | k (mm) | HYD SECT | DIA (mm) | Sect | ion T | 'ype | Aut Desi |
| 1.000 | 71.553 | 0.239 | 300.0 | 0.023 | 5.00 | | 0.0 | 0.600 | 0 | 300 | Pipe | e/Cond | luit. | ð |
| | 14.359 | | | | | | | 0.600 | | | | /Cond | | |
| | 13.917 | | | | | | | 0.600 | | | | /Cond | | Ĵ |
| 2.000 | 63.816 | 0.213 | 300.0 | 0.024 | 5.00 | | 0.0 | 0.600 | 0 | 300 | Pipe | e/Cond | luit | 8 |
| 1 003 | 45.487 | 0 152 | 300 0 | 0.024 | 0.00 | | 0 0 | 0.600 | 0 | 300 | Pinc | e/Cond | 1111+ | ھ |
| | 43.407 36.675 | | | | | | | 0.600 | | | - | e/Cond | | 8 |
| | 19.814 | | | | | | | 0.600 | | | _ | e/Cond | | U U |
| | 34.169 | | | | | | | 0.600 | | | - | e/Cond | | ļ |
| | | | | | | | | | | | _ | | | Ī |
| | 25.423 | | | | | | | 0.600 | | | - | /Cond | | ď |
| 4.001 | 40.066 | 0.135 | 297.6 | 0.071 | 0.00 | | 0.0 | 0.600 | 0 | 300 | Pipe | e/Cond | luit | ď |
| | 16.825 | | | | 0.00 | | 0.0 | 0.600 | 0 | 300 | Pipe | e/Cond | luit | 8 |
| 5.000 | 43.815 | 0 219 | 200 0 | 0.071 | F 00 | | | | | | - · | 1 | 1 | 8 |
| | | | | | | | | 0.600 | | | | e/Cond | | |
| | 19.668 | | | | | | | 0.600 0.600 | | | | e/Cond e/Cond | | |
| | | | | 0.000 | | | 0.0 | 0.600 | | | | | | 9 |
| | 19.668 Rain | 0.066 n T . | 300.0 C. U | 0.000 <u>Ν</u> s/il Σ | 0.00 Vetwork I.Area | <u>Resul</u> Σ Bas | 0.0 <u>ts Ta</u> se : | 0.600 <u>ble</u> Foul A | o Add Fla | 300 Sw V | Pipe T el | Cond Cap | luit Flo | w |
| 5.001 | 19.668 Rain | 0.066 n T . | 300.0 C. U | 0.000 <u>Ν</u> s/il Σ |) 0.00 Vetwork | <u>Resul</u> Σ Bas | 0.0 <u>ts Ta</u> se : | 0.600 <u>ble</u> Foul A | o Add Fla | 300 Sw V | Pipe T el | Cond Cap | luit Flo | w |
| 5.001 PN 1.00 | 19.668 Rain (mm/h | 0.066 n T. r) (mi 00 6 | 300.0 C. U: .ns) | 0.000 <u>N</u> s/il E (m) .500 |) 0.00 <i>'etwork</i> I.Area (ha) I 0.023 | <u>Resul</u> Σ Bas | 0.0 <u>ts Ta</u> se : L/s) (| 0.600 <u>ble</u> Foul A 1/s) 0.0 | • Add Fla (1/s) 0 | 300 V V (m .0 0 | Pipe el /s) .90 | Cap (1/s) 63.8 | luit Fla (1/ 3 | w s) .1 |
| PN 1.00 1.00 | 19.668 Rain (mm/h 00 50. 01 50. | 0.066 n T. r) (mi 00 6 00 6 | 300.0 C. U: .ns) 5.32 4 5.59 4 | 0.000 <u>N</u> S/IL E (m) .500 .261 |) 0.00 Vetwork I.Area (ha) I 0.023 0.046 | <u>Resul</u> Σ Bas | 0.0 <u>ts Ta</u> se : l/s) (0.0 0.0 | 0.600 <u>ble</u> Foul A (1/s) 0.0 0.0 | 0 Add Flo (1/s) 0 0 | 300 v v (m .0 0 | Pipe Fel (/s) .90 | Cap (1/s) 63.8 63.8 | fluit Flc (1/ 3 6 | w s) .1 .2 |
| 5.001 PN 1.00 | 19.668 Rain (mm/h 00 50. 01 50. | 0.066 n T. r) (mi 00 6 00 6 | 300.0 C. U: .ns) | 0.000 <u>N</u> S/IL E (m) .500 .261 |) 0.00 <i>'etwork</i> I.Area (ha) I 0.023 | <u>Resul</u> Σ Bas | 0.0 <u>ts Ta</u> se : L/s) (| 0.600 <u>ble</u> Foul A 1/s) 0.0 | 0 Add Flo (1/s) 0 0 | 300 v v (m .0 0 | Pipe el /s) .90 | Cap (1/s) 63.8 | fluit Flc (1/ 3 6 | w s) .1 |
| 5.001 PN 1.00 1.00 | Rain (mm/h 00 50. 01 50. 02 50. | 0.066 n T. r) (mi 00 6 00 6 00 6 | 300.0 C. U: .ns) 5.32 4 5.59 4 | 0.000 <u>N</u> S/IL E (m) .500 .261 .214 |) 0.00 Vetwork I.Area (ha) I 0.023 0.046 | <u>Resul</u> Σ Bas | 0.0 <u>ts Ta</u> se : l/s) (0.0 0.0 | 0.600 <u>ble</u> Foul A (1/s) 0.0 0.0 | 0 add Fla (1/s) 0 0 0 | 300 V V (m .0 0 .0 0 | Pipe Fel (/s) .90 | Cap (1/s) 63.8 63.8 | Flc (1/ 3 6 9 | w s) .1 .2 |
| PN 1.00 1.00 | Rain (mm/h 00 50. 01 50. 02 50. 00 50. | 0.066 n T. r) (mi 00 6 00 6 00 6 | 300.0 C. US ns) 5.32 4 5.59 4 5.84 4 | 0.000 <u>N</u> 5/IL E (m) .500 .261 .214 .400 |) 0.00 <u>Vetwork</u> I.Area (ha) I 0.023 0.046 0.069 | <u>Resul</u> Σ Bas | 0.0 <u>ts Ta</u> se : 1/s) (0.0 0.0 0.0 | 0.600 <u>ble</u> Foul A (1/s) 0.0 0.0 0.0 | 0 add Fla (l/s) 0 0 0 0 0 | 300 V V (m .0 0 .0 0 .0 0 | Pipe el (/s) .90 .90 | Cap (1/s) 63.8 63.8 63.8 | Fl ((1/ 3 6 9 3 | w s) .1 .2 .3 .2 |
| PN 1.00 1.00 2.00 | 19.668 Rain (mm/h 00 50. 01 50. 02 50. 00 50. 00 50. 00 50. 00 50. 00 50. 00 50. 00 50. | 0.066 n T. r) (mi 00 6 00 6 00 6 00 6 00 6 | 300.0 C. U (ns) 5.32 4 5.59 4 5.84 4 5.18 5 | 0.000 <u>N</u> S/IL E (m) .500 .261 .214 .400 .167 | 0.000 Vetwork I.Area (ha) I 0.023 0.046 0.069 0.024 | <u>Resul</u> Σ Bas | 0.0 <u>ts Ta</u> se 1/s) 0.0 0.0 0.0 0.0 0.0 | 0.600 <u>ble</u> Foul A (1/s) 0.0 0.0 0.0 0.0 0.0 | 0 Add Fla (l/s) 0 0 0 0 0 0 0 0 0 0 0 0 0 | 300 v v (m .0 0 .0 0 .0 0 .0 0 | Pipe el /s) .90 .90 .90 | Cap (1/s) 63.8 63.8 63.8 63.8 | fla fla (1/ 3 6 9 3 15 | w s) .1 .2 .3 .2 .8 |
| PN 1.00 1.00 2.00 1.00 | I9.668 Rain (mm/h 00 50. 01 50. 02 50. 00 50. 00 50. 00 50. 00 50. 00 50. 00 50. 03 50. 04 50. | 0.066 n T. (mi 00 6 00 6 00 6 00 6 00 7 00 8 | 300.0 C. U: ns) 5.32 4 5.59 4 5.84 4 5.18 5 7.68 4 | 0.000 <u>N</u> 5/IL E (m) .500 .261 .214 .400 .167 .015 |) 0.00 <u>Vetwork</u> I.Area (ha) I 0.023 0.023 0.046 0.069 0.024 0.117 | <u>Resul</u> Σ Bas | 0.0 <u>ts Ta</u> se 1/s) 0.0 0.0 0.0 0.0 0.0 0.0 | 0.600 <u>ble</u> Foul A (1/s) 0.0 0.0 0.0 0.0 0.0 0.0 | 0 Add Fla (l/s) 0 0 0 0 0 0 0 0 0 0 0 0 0 | 300 v v (m 0 0 0 0 0 0 0 0 0 0 0 0 0 | Pipe el /s) .90 .90 .90 .90 | Cap (1/s) 63.8 63.8 63.8 63.8 63.8 | Flc (1/ 3 6 9 3 15 25 | w s) .1 .2 .3 .2 .8 |
| PN 1.000 1.000 1.000 2.000 1.000 1.000 | 19.668 Rain (mm/h 00 50. 01 50. 02 50. 00 50. 01 50. 02 50. 03 50. 04 50. 00 50. 00 50. | 0.066 n T. (mi 00 6 00 6 00 6 00 6 00 7 00 8 00 5 | 300.0 C. U: .ns) 5.32 4 5.59 4 5.84 4 5.18 5 . 68 4 5.36 4 | 0.000 <u>N</u> 5/IL E (m) .500 .261 .214 .400 .167 .015 .000 | 0 0.00 Vetwork I.Area (ha) I 0.023 0.046 0.069 0.024 0.117 0.188 | <u>Resul</u> Σ Bas | 0.0 <u>ts Ta</u> se 1/s) 0.0 0.0 0.0 0.0 0.0 0.0 0.0 | 0.600 <u>ble</u> Foul A (1/s) 0.0 0.0 0.0 0.0 0.0 0.0 0.0 | 0 4dd Fla (1/s) 0 0 0 0 0 0 0 0 0 0 0 0 0 | 300 v v (m 0 0 0 0 0 0 0 0 0 0 0 0 0 | Pipe el /s) .90 .90 .90 .90 .90 .90 | Cap (1/s) 63.8 63.8 63.8 63.8 63.8 63.8 | Flc (1/ 3 6 9 3 15 25 | ₩ s) .1 .2 .3 .2 .8 .5 .6 |
| PN 1.000 1.000 1.000 1.000 1.000 3.000 1.000 | 19.668 Rain (mm/h 00 50. 01 50. 02 50. 03 50. 04 50. 00 50. 00 50. 00 50. 00 50. 00 50. 00 50. 00 50. 00 50. 00 50. | 0.066 n T. (mi 00 6 00 6 00 6 00 6 00 7 00 8 00 5 00 8 | 300.0 C. U : .ns) 5. 32 4 5. 59 4 5. 84 4 5. 18 5 7. 68 4 4. 36 4 5. 57 5 5. 99 3 | 0.000 <u>N</u> (m) .500 .261 .214 .400 .167 .015 .000 .893 | <pre>0 0.00 Vetwork I.Area (ha) I 0.023 0.046 0.069 0.024 0.117 0.188 0.071 0.330</pre> | <u>Resul</u> Σ Bas | 0.0 <u>ts Ta</u> se 1/s) 0.0 0.0 0.0 0.0 0.0 0.0 0.0 0. | 0.600 <u>ble</u> Foul A (1/s) 0.0 0.0 0.0 0.0 0.0 0.0 0.0 0. | 0 4dd F14 (1/s) 0 0 0 0 0 0 0 0 0 0 0 0 0 | 300 v v (m .0 0 .0 0 .0 0 .0 0 .0 0 | Pipe el (/s) .90 .90 .90 .90 .90 .58 .91 | Cap (1/s) 63.8 63.8 63.8 63.8 63.8 63.8 10.2 64.0 | Huit Fla (1/ 3 6 9 3 15 25 9 44 | ₩ s) .1 .2 .3 .2 .8 .5 .6 .7 |
| PN 1.000 1.000 1.000 1.000 1.000 3.000 | 19.668 Rain (mm/h 00 50. 01 50. 02 50. 03 50. 04 50. 05 50. 05 50. 05 50. 05 50. 00 50. | 0.066 n T. (mi 00 6 00 6 00 6 00 7 00 8 00 5 00 8 00 5 | 300.0 C. U: .ns) 5.32 4 5.59 4 5.84 4 5.18 5 2.68 4 4.36 4 5.57 5 | 0.000 <u>N</u> S/IL E (m) .500 .261 .214 .400 .167 .015 .000 .893 .000 | 0 0.00 Vetwork I.Area (ha) I 0.023 0.046 0.029 0.024 0.117 0.188 0.071 | <u>Resul</u> Σ Bas | 0.0 <u>ts Ta</u> se 1/s) (0.0 0.0 0.0 0.0 0.0 0.0 0.0 0. | 0.600 <u>ble</u> Foul A (1/s) 0.0 0.0 0.0 0.0 0.0 0.0 0.0 0. | 0 4dd F14 (1/s) 0 0 0 0 0 0 0 0 0 0 0 0 0 | 300 v v (m .0 0 .0 0 .0 0 .0 0 .0 0 .0 0 | Pipe el (/s) .90 .90 .90 .90 .90 .58 | Cap (1/s) 63.8 63.8 63.8 63.8 63.8 63.8 63.8 10.2 | Huit Fla (1/ 3 6 9 3 155 255 9 44 9 | ₩ s) .1 .2 .3 .2 .8 .5 .6 .7 .6 |
| <pre>5.001 PN 1.00 1.00 2.00 1.00 3.00 1.00 4.00</pre> | 19.668 Rain (mm/h 00 50. 01 50. 02 50. 03 50. 04 50. 05 50. 05 50. 00 50. 00 50. 00 50. 00 50. 00 50. 00 50. 00 50. 00 50. | 0.066 n T. r) (mi 00 6 00 6 00 6 00 7 00 8 00 5 00 8 00 5 00 8 | 300.0 C. U : .ns) 5. 32 4 5. 59 4 5. 9 4 5. 84 4 5. 18 5 7. 68 4 4. 36 4 5. 57 5 5. 99 3 5. 74 5 | 0.000 <u>N</u> S/IL 2 (m) .500 .261 .214 .400 .167 .015 .000 .893 .000 .765 |) 0.00 Vetwork I.Area (ha) I 0.023 0.046 0.069 0.024 0.117 0.188 0.071 0.330 0.071 | <u>Resul</u> Σ Bas | 0.0 <u>ts Ta</u> se 1/s) 0.0 0.0 0.0 0.0 0.0 0.0 0.0 0. | 0.600 <u>ble</u> Foul P (1/s) 0.0 0.0 0.0 0.0 0.0 0.0 0.0 0. | o add F1((1/s) 0 0 0 0 0 0 0 0 0 0 0 0 0 | 300 v v (m .0 0 .0 0 .0 0 .0 0 .0 0 .0 0 .0 0 | Pipe el (/s) .90 .90 .90 .90 .58 .91 .58 .91 | Cap (1/s) 63.8 63.8 63.8 63.8 63.8 63.8 10.2 64.0 10.2 | Huit Flc (1/ 3 6 9 3 15 25 9 44 9 44 9 | ₩ s) .1 .2 .3 .2 .8 .5 .6 .7 .6 .2 |
| PN 1.00 1.00 1.00 2.00 1.00 3.00 1.00 4.00 4.00 | 19.668 Rain (mm/h 00 50. 01 50. 02 50. 03 50. 04 50. 05 50. 06 50. 07 50. 08 50. 09 50. 00 50. 00 50. 00 50. 00 50. 01 50. 02 50. | 0.066 n T. r) (mi 00 6 00 6 00 6 00 7 00 8 00 5 00 8 00 5 00 8 00 5 00 8 00 5 00 8 | 300.0 C. U : ns) 5.32 4 5.59 4 5.84 4 5.18 5 4.68 4 5.57 5 5.36 4 5.57 5 5.99 3 5.74 5 5.47 4 | 0.000 <u>N</u> S/IL 2 (m) .500 .261 .214 .400 .167 .015 .000 .893 .000 .765 .778 |) 0.00 Vetwork I.Area (ha) I 0.023 0.024 0.024 0.024 0.117 0.188 0.071 0.330 0.071 0.330 | <u>Resul</u> Σ Bas | 0.0 <u>ts Ta</u> se l/s 0.0 0.0 0.0 0.0 0.0 0.0 0.0 0. | 0.600 <u>ble</u> Foul A (1/s) 0.0 0.0 0.0 0.0 0.0 0.0 0.0 0. | 0 4dd F1((1/s) 0 0 0 0 0 0 0 0 0 0 0 0 0 | 300 v v (m 0 0 0 0 0 0 0 0 0 0 0 0 0 | Pipe el (/s) .90 .90 .90 .90 .58 .91 .58 .91 | Cap (1/s) 63.8 63.8 63.8 63.8 63.8 63.8 63.8 10.2 64.0 10.2 64.1 63.4« | Huit Flc (1/ 3 6 9 3 15 25 9 44 9 19 19 73 | ₩ s) .1 .2 .3 .2 .8 .5 .6 .7 .6 .2 |

| Hasko | ningDH | V UK I | Limite | d | | | | | | | | Page | e 3 | |
|-------|---------------|-------------|------------------|---------------------|----------------|-------------|--------------|--------------------|-------------|-------------|----------|----------------|--------------------------|--|
| Right | well Ho | ouse | | | Dra | ainage | e Str | ategy | | | | | | |
| 3rett | on, Pe | terbor | cough | | Whi | ite Cr | coss | Offsho | re Win | dfar | m | | 1 | |
| | y, PE3 | | | | | | | | | | | Mid | TO | |
| | 28/05/2 | | | | | signed | - | | | | | Dra | inar | 10 |
| | | ewater | n Netw | ork.MDX | | ecked | | | | | | Bit | | <u> </u> |
| Innov | yze | | | | Net | twork | 2020 | .1.3 | | | | | | |
| | | | | Networ | k Desi | gn Tal | ble f | for Sto | orm | | | | | |
| PN | Length (m) | Fall (m) | Slope (1:X) | e I.Area (ha) | T.E. (mins) | | ise (1/s) | k) (mm) | HYD SECT | DIA (mm) | Sect | tion | Туре | Auto Desig |
| .007 | 21.995 | 0.073 | 300.0 | 0.000 | 0.00 | | 0.0 | 0 0.600 | 0 | 300 | Pipe | e/Con | duit | 8 |
| | | | | 0.000 | 0.00 | | | 0 0.600 | | | - | e/Con | | Į |
| | | | | 0.000 | 0.00 | | | 0 0.600 0 0.600 | | | | e/Con e/Con | | r 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 |
| | | | 100.0 | | etwork | | | | Ū | 0,0 | 1 - 10 4 | , | | Ű |
| PN | Rain | | .C. U | <u></u> s/il Σ i | | <u>Σ</u> Ba | | Foul 1 | | | əl | 0 | | |
| PN | (mm/h | | | - | | Iow (| | | (1/s) | | | Cap (1/s) | Flo [.] (1/s | |
| 1.00 | 7 50. | 00 9 | 9.71 3 | .723 | 0.614 | | 0.0 | 0.0 | 0. | .0 0 | .90 | 63.8« | 83. | 1 |
| 1.00 | | |).12 3 | | 0.614 | | 0.0 | 0.0 | | | | 115.0 | | |
| 1.00 | | |).90 3 L.51 3 | | 0.614 0.614 | | 0.0 | 0.0 0.0 | | | | 163.1 163.1 | | |
| | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | |

| HaskoningDHV UK Limited | | Page 4 |
|-------------------------------|-------------------------------|------------|
| Rightwell House | Drainage Strategy | |
| Bretton, Peterborough | White Cross Offshore Windfarm | the second |
| Surrey, PE3 8DW | | Mirro |
| Date 28/05/2023 21:45 | Designed by IO | Drainago |
| File Surfacewater Network.MDX | Checked by BA | Diamage |
| Innovyze | Network 2020.1.3 | |

PIPELINE SCHEDULES for Storm

Upstream Manhole

| PN | - | Diam (mm) | | C.Level (m) | I.Level (m) | D.Depth (m) | | MH DIAM., L*W (mm) |
|-------|---|--------------|-----|----------------|----------------|----------------|--------------|-----------------------|
| 1.000 | 0 | 300 | 01 | 5.300 | 4.500 | 0.500 | Open Manhole | 1200 |
| 1.001 | 0 | 300 | 02 | 6.000 | 4.261 | 1.439 | Open Manhole | 1200 |
| 1.002 | 0 | 300 | 03 | 6.300 | 4.214 | 1.786 | Open Manhole | 1200 |
| 2.000 | 0 | 300 | 16 | 6.400 | 5.400 | 0.700 | Open Manhole | 1200 |
| 1.003 | 0 | 300 | 04 | 6.300 | 4.167 | 1.833 | Open Manhole | 1200 |
| 1.004 | 0 | 300 | 05 | 6.300 | 4.015 | 1.985 | Open Manhole | 1200 |
| 3.000 | 0 | 150 | Н07 | 6.300 | 5.000 | 1.150 | Open Manhole | 1200 |
| 1.005 | 0 | 300 | 06 | 6.300 | 3.893 | 2.107 | Open Manhole | 1200 |
| 4.000 | 0 | 150 | 07 | 6.300 | 5.000 | 1.150 | Open Manhole | 1200 |
| 4.001 | 0 | 300 | 08 | 6.300 | 4.765 | 1.235 | Open Manhole | 1200 |
| 1.006 | 0 | 300 | 09 | 6.200 | 3.778 | 2.122 | Open Manhole | 1200 |
| 5.000 | 0 | 300 | 10 | 6.300 | 5.300 | 0.700 | Open Manhole | 1200 |

Downstream Manhole

| PN | - | Slope (1:X) | | C.Level (m) | I.Level (m) | D.Depth (m) | | MH DIAM., L*W (mm) |
|-------|--------|----------------|----|----------------|----------------|----------------|--------------|-----------------------|
| 1.000 | 71.553 | 300.0 | 02 | 6.000 | 4.261 | 1.439 | Open Manhole | 1200 |
| 1.001 | 14.359 | 300.0 | 03 | 6.300 | 4.214 | 1.786 | Open Manhole | 1200 |
| 1.002 | 13.917 | 300.0 | 04 | 6.300 | 4.167 | 1.833 | Open Manhole | 1200 |
| 2.000 | 63.816 | 300.0 | 04 | 6.300 | 5.187 | 0.813 | Open Manhole | 1200 |
| 1.003 | 45.487 | 300.0 | 05 | 6.300 | 4.015 | 1.985 | Open Manhole | 1200 |
| 1.004 | 36.675 | 300.0 | 06 | 6.300 | 3.893 | 2.107 | Open Manhole | 1200 |
| 3.000 | 19.814 | 300.0 | 06 | 6.300 | 4.934 | 1.216 | Open Manhole | 1200 |
| 1.005 | 34.169 | 298.2 | 09 | 6.200 | 3.778 | 2.122 | Open Manhole | 1200 |
| 4.000 | 25.423 | 300.0 | 08 | 6.300 | 4.915 | 1.235 | Open Manhole | 1200 |
| 4.001 | 40.066 | 297.6 | 09 | 6.200 | 4.631 | 1.269 | Open Manhole | 1200 |
| 1.006 | 16.825 | 303.8 | 12 | 6.200 | 3.723 | 2.177 | Open Manhole | 1200 |
| 5.000 | 43.815 | 200.0 | 11 | 6.200 | 5.081 | 0.819 | Open Manhole | 1200 |
| | | | | ©1982 | 2-2020 1 | Innovyze | | |
| | | | | | | | | |

| HaskoningDHV UK Limited | | Page 5 |
|-------------------------------|-------------------------------|------------|
| Rightwell House | Drainage Strategy | |
| Bretton, Peterborough | White Cross Offshore Windfarm | the second |
| Surrey, PE3 8DW | | Mirro |
| Date 28/05/2023 21:45 | Designed by IO | Drainago |
| File Surfacewater Network.MDX | Checked by BA | Diamage |
| Innovyze | Network 2020.1.3 | |

PIPELINE SCHEDULES for Storm

Upstream Manhole

| PN | Hyd Sect | | MH Name | C.Level (m) | I.Level (m) | D.Depth (m) | MH Connection | MH DIAM., L*W (mm) |
|----------------------------------|-------------|--------------------------|----------------------|----------------------------------|----------------------------------|----------------|--|------------------------------|
| 5.001 | 0 | 300 | 11 | 6.200 | 5.081 | 0.819 | Open Manhole | 1200 |
| 1.007 1.008 1.009 1.010 | 0 0 0 | 300 375 375 375 | 12 13 14 15 | 6.200 4.850 4.800 4.800 | 3.723 3.575 3.490 3.024 | 0.900 0.935 | Open Manhole Open Manhole Open Manhole Open Manhole | 1200 1350 1350 1350 |

Downstream Manhole

| PN | Length (m) | Slope (1:X) | | C.Level (m) | I.Level (m) | D.Depth (m) | MH Connection | MH DIAM., L*W (mm) |
|----------------|--------------------------------------|----------------|----------------|----------------------------------|----------------------------------|----------------|--|---------------------------|
| 5.001 | 19.668 | 300.0 | 12 | 6.200 | 5.015 | 0.885 | Open Manhole | 1200 |
| 1.008 1.009 | 21.995 25.489 69.832 53.379 | 300.0 150.0 | 13 14 15 | 4.850 4.800 4.800 4.800 | 3.650 3.490 3.024 2.668 | 0.935 1.401 | Open Manhole Open Manhole Open Manhole Open Manhole | 1350 1350 1350 0 |

Free Flowing Outfall Details for Storm

| Outfall | Outfall C. | Level | I. | Level | | Min | D,L | W |
|-------------|------------|-------|----|-------|----|-------|------|------|
| Pipe Number | Name | (m) | | (m) | I. | Level | (mm) | (mm) |
| | | | | | | (m) | | |
| 1.010 | | 4.800 | | 2.668 | | 0.000 | 0 | 0 |

Simulation Criteria for Storm

| Volumetric Runoff Coeff | 0.750 |
|-------------------------------------|-------|
| Areal Reduction Factor | 1.000 |
| Hot Start (mins) | 0 |
| Hot Start Level (mm) | 0 |
| Manhole Headloss Coeff (Global) | 0.500 |
| Foul Sewage per hectare (l/s) | 0.000 |
| Additional Flow - % of Total Flow | 0.000 |
| MADD Factor * 10m³/ha Storage | 2.000 |
| Inlet Coeffiecient | 0.800 |
| Flow per Person per Day (l/per/day) | 0.000 |
| Run Time (mins) | 60 |
| Output Interval (mins) | 1 |
| | |

| HaskoningDHV UK Limited | | Page 6 |
|-------------------------------|-------------------------------|------------|
| Rightwell House | Drainage Strategy | |
| Bretton, Peterborough | White Cross Offshore Windfarm | the second |
| Surrey, PE3 8DW | | Mirro |
| Date 28/05/2023 21:45 | Designed by IO | Drainago |
| File Surfacewater Network.MDX | Checked by BA | Diamage |
| Innovyze | Network 2020.1.3 | |

Simulation Criteria for Storm

Number of Input Hydrographs 0 Number of Storage Structures 1 Number of Online Controls 1 Number of Time/Area Diagrams 0 Number of Offline Controls 0 Number of Real Time Controls 0

Synthetic Rainfall Details

| Rainfall Model | | FSR | | Profile Type | Summer |
|-----------------------|---------|-----------|-------|-----------------|--------|
| Return Period (years) | | 100 | | Cv (Summer) | 0.750 |
| Region | England | and Wales | | Cv (Winter) | 0.840 |
| M5-60 (mm) | | 16.500 | Storm | Duration (mins) | 30 |
| Ratio R | | 0.281 | | | |

| Rightwell House Bretton, Peterborc Surrey, PE3 8DW Date 28/05/2023 21 | | | | | | | | | P | age 7 |
|--|--|---|--|---|--|--|---|--------------|--|-------------------|
| urrey, PE3 8DW | | | Dra | ainage | Strate | gy | | | 0 | |
| - | ough | | Whi | ite Cro | oss Off | shore | Wind | farm | - h | L. |
| -+- 20/0E/2022 21 | | | | | | | | | Ν | /irrn |
| ate 28/05/2023 21 | 1:45 | | Des | signed | by IO | | | | h | lcainan |
| ile Surfacewater | Networ | ck.MD | X Che | ecked l | by BA | | | | - | лашац |
| nnovyze | | | Net | twork 2 | 2020.1. | 3 | | | | |
| | | | | | | | | | | |
| | | <u> On 1</u> | ine Cor | itrols | for St | orm | | | | |
| Hydro-Brake® |) Optin | ium Ma | anhole: | 13, D | S/PN: 1 | .008, | Volu | me (| ′m³): | 3.3 |
| | | τ | Jnit Ref | erence | MD-SHE- | -0090-3 | 800-1 | 200- | 3800 | |
| | | | esign He | | - | | | | .200 | |
| | | Desi | gn Flow | | | | | | 3.8 | |
| | | | | h-Flo™ | | | | | ated | |
| | | | - | ective cation | Minimi | lse ups | tream | | rage face | |
| | | S | Sump Ava | | | | | Dui | Yes | |
| | | | Diamete | | | | | | 90 | |
| | | | vert Lev | | | | | 3 | .575 | |
| Minimum | | | | | | | | | 150 | |
| Sugges | ted Mar | nhole | Diamete | r (mm) | | | | | 1200 | |
| | Co | ontrol | . Points | | Head (m |) Flow | (1/s |) | | |
| I | Design | Point | (Calcul | | | | 3. | | | |
| | | | | n-Flo™ <-Flo® | | | 3. 3. | | | |
| Ν | Mean Fl | ow ov | er Head | | 0.75 | _ | 3. | | | |
| | calcula | tions | have h | een bas | ad on t | he ttee | d/Dis | char | qe re | |
| The hydrological for the Hydro-Braidevice other than calculations will | ke® Opt a Hydr | imum o-Bra | as spec ke Optin | | Should | l anoth | er ty | pe o | f con | trol |
| for the Hydro-Bra | ke® Opt a Hydr be inv | imum 0-Bra valida | as spec ike Optin ited | mum® be | Should utilis | l anoth ed the | er ty n the | pe o se s | f con torage | trol e routing |
| for the Hydro-Bra device other than calculations will Depth (m) | ke® Opt a Hydr be inv Flow (| imum co-Bra alida (1/s) | as spec lke Optin ted Depth (| mum® be m) Flow | Should a utilis a (1/s) | l anoth ed the Depth | er ty n the (m) H | pe o se s | f con [.] torage (1/s) | trol e routing |
| for the Hydro-Bra device other than calculations will Depth (m) 0.100 | ke® Opt a Hydr be inv Flow (| imum 20-Bra 21/s) 2.8 | as spec ike Optin ited Depth (1 1.6 | mum® be m) Flo v 00 | Should e utilis a (1/s) 4.3 | l anoth ed the Depth 5. | er ty n the | pe o se s | f con torage | trol e routing |
| for the Hydro-Bra device other than calculations will Depth (m) | ke® Opt a Hydr be inv Flow (| imum co-Bra alida (1/s) | as spec lke Optin ted Depth (| mum® be m) Flow 00 00 | Should a utilis a (1/s) | l anoth sed the Depth 5. 5. | er ty n the (m) H 000 | pe o se s | f con [.] torage (1/s) 7.4 | trol e routing |
| for the Hydro-Bra device other than calculations will Depth (m) 0.100 0.200 0.300 0.400 | ke® Opt a Hydr be inv Flow (| imum ro-Bra valida (1/s) 2.8 3.6 3.8 3.8 | as spec ke Optin ted Depth (1.6 1.8 2.0 2.2 | mum® be m) Flow 00 00 00 00 | Should e utilis v (l/s) 4.3 4.6 4.8 5.0 | l anoth sed the Depth 5. 5. 6. | er ty n the (m) I 000 500 000 500 | pe o se s | f con torage (1/s) 7.4 7.7 8.1 8.4 | trol e routino |
| for the Hydro-Braidevice other than calculations will Depth (m) 0.100 0.200 0.300 0.400 0.500 | ke® Opt a Hydr be inv Flow (| imum co-Bra calida (1/s) 2.8 3.6 3.8 3.8 3.8 3.7 | as spec ke Optin ted Depth (1.6 1.8 2.0 2.2 2.4 | mum® be m) Flow 00 00 00 00 00 00 | Should e utilis v (l/s) 4.3 4.6 4.8 5.0 5.2 | l anoth sed the Depth 5. 5. 6. 7. | er ty n the (m) I 000 500 000 500 000 | pe o se s | f con torage (1/s) 7.4 7.7 8.1 8.4 8.7 | trol e routing |
| for the Hydro-Braidevice other than calculations will Depth (m) 0.100 0.200 0.300 0.400 0.500 0.600 | ke® Opt a Hydr be inv Flow (| imum co-Bra calida (1/s) 2.8 3.6 3.8 3.8 3.8 3.7 3.5 | as spec ke Optin ted Depth (1.6 1.8 2.0 2.2 2.4 2.6 | mum® be m) Flow 00 00 00 00 00 00 00 | Should e utilis v (1/s) 4.3 4.6 4.8 5.0 5.2 5.4 | l anoth sed the Depth 5. 5. 6. 7. 7. | er ty n the (m) I 000 500 000 500 000 500 | pe o se s | f con torage (1/s) 7.4 7.7 8.1 8.4 8.7 9.0 | trol e routing |
| for the Hydro-Braidevice other than calculations will Depth (m) 0.100 0.200 0.300 0.400 0.500 0.600 0.800 | ke® Opt a Hydr be inv Flow (| imum co-Bra valida (1/s) 2.8 3.6 3.8 3.8 3.7 3.5 3.2 | as spec ke Optin ted Depth (1.6 1.8 2.0 2.2 2.4 2.6 3.0 | mum® be m) Flow 00 00 00 00 00 00 00 00 00 | Should e utilis (1/s) 4.3 4.6 4.8 5.0 5.2 5.4 5.8 | Depth 5. 5. 5. 6. 7. 7. 8. | er ty n the (m) I 000 500 000 500 000 500 000 | pe o se s | f con torag (1/s) 7.4 7.7 8.1 8.4 8.7 9.0 9.2 | trol e routing |
| for the Hydro-Braidevice other than calculations will Depth (m) 0.100 0.200 0.300 0.400 0.500 0.600 0.800 1.000 | ke® Opt a Hydr be inv Flow (| imum co-Bra valida (1/s) 2.8 3.6 3.8 3.8 3.7 3.5 3.2 3.5 | as spec ke Optin ted Depth (1.6 1.8 2.0 2.2 2.4 2.6 3.0 3.5 | mum® b∈ m) Flow 00 00 00 00 00 00 00 00 00 0 | Should tutilis (1/s) 4.3 4.6 4.8 5.0 5.2 5.4 5.8 6.3 | Depth 5. 5. 5. 6. 7. 7. 8. 8. | er ty n the (m) I 000 500 000 500 000 500 000 500 000 500 | pe o se s | f con torage (1/s) 7.4 7.7 8.1 8.4 8.7 9.0 9.2 9.5 | trol e routing |
| for the Hydro-Braidevice other than calculations will Depth (m) 0.100 0.200 0.300 0.400 0.500 0.600 0.800 | ke® Opt a Hydr be inv Flow (| imum co-Bra valida (1/s) 2.8 3.6 3.8 3.8 3.7 3.5 3.2 | as spec ke Optin ted Depth (1.6 1.8 2.0 2.2 2.4 2.6 3.0 | mum® b∈ m) Flow 00 00 00 00 00 00 00 00 00 0 | Should e utilis (1/s) 4.3 4.6 4.8 5.0 5.2 5.4 5.8 | Depth 5. 5. 5. 6. 7. 7. 8. 8. | er ty n the (m) I 000 500 000 500 000 500 000 | pe o se s | f con torag (1/s) 7.4 7.7 8.1 8.4 8.7 9.0 9.2 | trol e routin |

| HaskoningDHV UK Limited | | Page 8 |
|-------------------------------|-------------------------------|------------|
| Rightwell House | Drainage Strategy | |
| Bretton, Peterborough | White Cross Offshore Windfarm | the second |
| Surrey, PE3 8DW | | Mirro |
| Date 28/05/2023 21:45 | Designed by IO | Drainago |
| File Surfacewater Network.MDX | Checked by BA | Diamage |
| Innovyze | Network 2020.1.3 | |

Storage Structures for Storm

Tank or Pond Manhole: 13, DS/PN: 1.008

Invert Level (m) 3.575

| Depth (m) | Area (m²) | Depth (m) | Area (m²) | Depth (m) | Area (m²) |
|-----------|-----------|-----------|-----------|-----------|-----------|
| 0.000 | 350.0 | 1.200 | 673.0 | 1.201 | 673.0 |

| naskontnyvav | UK Limite | ed | | | | | Page 9 |
|---|--|--|---|---|---|---|--|
| Rightwell Hor | use | | Drain | age Str | rategy | | |
| Bretton, Pete | erborough | | White | Cross | Offsho | re Windfarm | and the second s |
| Surrey, PE3 | 8DW | | | | | | Micro |
| Date 28/05/2 | 023 21:45 | | Desig | ned by | IO | | Desinado |
| File Surface | water Netw | vork.MDX | Check | ed by E | 3A | | Diamaye |
| Innovyze | | | | rk 2020 | | | |
| <u>1 year Retu</u> | rn Period | Summary oi | f Criti for S | | sults b | y Maximum Le | evel (Rank 1) |
| | | | Hot St eadloss wage per Flow - % ctor * 1 Inle | eduction ot Start cart Lev Coeff c hectar c of Tot .0m ³ /ha et Coeff | (mins) (mins) (Global | 0 0.500 0.000 7 0.000 2.000 5 0.800 | |
| 1 | Number of (| Online Cont | rols 1 | Number | of Time | age Structure /Area Diagram Time Control | ns O |
| Ма | | . Model Region Eng 50 (mm) lood Risk V | Varning sis Time | FSR d Wales 16.600 (mm) 30 | Ra Cv (Su Cv (Wi 00.0 Cine Ine | tio R 0.275 mmer) 0.750 nter) 0.840 DVD Status ertia Status | |
| Retur | P: Duration(; n Period(s; Climate Cl | (years) | | | | | , 600, 5760, |
| US/I | | Return C Period (| | First Surch | | First (Y) Flood | First (Z) Overflow |
| PN Nam | | er 1 | +0% | 100/30 | Summer | 100/30 Winter | 2 |
| | 01 30 Summe | | | 100/30 | | | |
| 1.000 | 01 30 Summe 02 30 Summe | er 1 | | | | | |
| 1.000 1.001 | | | | 100/30 | Summer | | |
| 1.000 1.001 1.002 | 02 30 Summe | er 1 | | 100/30 | Summer | | |
| 1.000 1.001 1.002 2.000 1.003 | 02 30 Summe 03 30 Summe | er 1 er 1 | +0응 +0응 | 100/30 100/30 | | | |
| 1.000 1.001 2.000 1.003 1.004 | 2 30 Summe 03 30 Summe 16 30 Summe 04 30 Summe 05 30 Summe | er 1 er 1 er 1 er 1 | +0응 +0응 | 100/30 30/30 | Summer Summer | | |
| 1.000 1.001 2.000 1.003 1.004 3.000 H0 | 2 30 Summe 03 30 Summe 16 30 Summe 04 30 Summe 05 30 Summe 07 30 Summe | er 1 er 1 er 1 er 1 er 1 er 1 | +0% +0% +0% +0% | 100/30 30/30 30/30 | Summer Summer Summer | | |
| 1.000 (1.001 (2.000 (1.003 (1.004 (3.000 H) 1.005 (| 2 30 Summe 03 30 Summe 16 30 Summe 04 30 Summe 05 30 Summe 07 30 Summe 07 30 Summe 06 30 Summe | er 1 er 1 er 1 er 1 er 1 er 1 er 1 | +0% +0% +0% +0% +0% | 100/30 30/30 30/30 30/30 | Summer Summer Summer Summer | | |
| 1.000 (1.001 (2.000 (1.003 (1.004 (3.000 H) 1.005 (4.000 (| 230 Summe 230 Summe 2330 Summe 2430 Summe 2530 Summe 2630 Summe 2730 Summe 2630 Summe 2730 Summe 2630 Summe 2730 Summe 2030 Summe 2030 Summe 2030 Summe 2030 Summe | er 1 er 1 er 1 er 1 er 1 er 1 er 1 er 1 | +0% +0% +0% +0% +0% +0% +0% | 100/30 30/30 30/30 | Summer Summer Summer Summer | | |
| 1.000 (1.001 (2.000 (1.003 (1.004 (3.000 H) 1.005 (4.000 (| 2 30 Summe 03 30 Summe 16 30 Summe 04 30 Summe 05 30 Summe 07 30 Summe 07 30 Summe 06 30 Summe | er 1 er 1 er 1 er 1 er 1 er 1 er 1 er 1 | +0% +0% +0% +0% +0% | 100/30 30/30 30/30 30/30 | Summer Summer Summer Summer | | |

| HaskoningDHV UK Limited | | Page 10 |
|-------------------------------|-------------------------------|------------|
| Rightwell House | Drainage Strategy | |
| Bretton, Peterborough | White Cross Offshore Windfarm | the second |
| Surrey, PE3 8DW | | Mirro |
| Date 28/05/2023 21:45 | Designed by IO | Drainago |
| File Surfacewater Network.MDX | Checked by BA | Diamage |
| Innovyze | Network 2020.1.3 | |

<u>1 year Return Period Summary of Critical Results by Maximum Level (Rank 1)</u> <u>for Storm</u>

| PN | US/MH Name | Overflow Act. | Water Level (m) | Surcharged Depth (m) | Flooded Volume (m³) | Flow / Cap. | Overflow (1/s) | Half Drain Time (mins) | Pipe Flow (l/s) |
|-------|---------------|------------------|-----------------------|----------------------------|---------------------------|----------------|-------------------|------------------------------|-----------------------|
| 1.000 | 01 | | 4.536 | -0.264 | 0.000 | 0.03 | | | 2.0 |
| 1.001 | 02 | | 4.318 | -0.244 | 0.000 | 0.07 | | | 3.7 |
| 1.002 | 03 | | 4.282 | -0.232 | 0.000 | 0.10 | | | 5.4 |
| 2.000 | 16 | | 5.437 | -0.263 | 0.000 | 0.04 | | | 2.2 |
| 1.003 | 04 | | 4.246 | -0.221 | 0.000 | 0.15 | | | 9.1 |
| 1.004 | 05 | | 4.115 | -0.201 | 0.000 | 0.23 | | | 13.8 |
| 3.000 | H07 | | 5.091 | -0.059 | 0.000 | 0.68 | | | 6.5 |
| 1.005 | 06 | | 4.033 | -0.160 | 0.000 | 0.40 | | | 23.8 |
| 4.000 | 07 | | 5.090 | -0.060 | 0.000 | 0.67 | | | 6.5 |
| 4.001 | 08 | | 4.857 | -0.208 | 0.000 | 0.20 | | | 12.2 |

| | US/MH | | Level |
|-------|-------|--------|----------|
| PN | Name | Status | Exceeded |
| 1.000 | 01 | OK | 1 |
| 1.001 | 02 | OK | |
| 1.002 | 03 | OK | |
| 2.000 | 16 | OK | |
| 1.003 | 04 | OK | |
| 1.004 | 05 | OK | |
| 3.000 | Н07 | OK | |
| 1.005 | 06 | OK | |
| 4.000 | 07 | OK | |
| 4.001 | 08 | OK | |

| HaskoningDHV UK Limited | | Page 11 |
|-------------------------------|-------------------------------|----------|
| Rightwell House | Drainage Strategy | |
| Bretton, Peterborough | White Cross Offshore Windfarm | 1 m |
| Surrey, PE3 8DW | | Mirro |
| Date 28/05/2023 21:45 | Designed by IO | Drainago |
| File Surfacewater Network.MDX | Checked by BA | Diamage |
| Innovyze | Network 2020.1.3 | |
| | | |

<u>1 year Return Period Summary of Critical Results by Maximum Level (Rank 1)</u> <u>for Storm</u>

| PN | US/MH Name | s | torm | | Climate Change | Firs Surcl | t (X) narge | First (Y) Flood | First (Z) Overflow | Overflow Act. |
|-------|---------------|-----|--------|---|-------------------|---------------|----------------|--------------------|-----------------------|------------------|
| 1.006 | 09 | 30 | Summer | 1 | +0% | 30/30 | Summer | | | |
| 5.000 | 10 | 30 | Summer | 1 | +0% | | | | | |
| 5.001 | 11 | 30 | Summer | 1 | +0% | | | | | |
| 1.007 | 12 | 30 | Summer | 1 | +0% | 30/30 | Summer | | | |
| 1.008 | 13 | 600 | Winter | 1 | +0% | 30/180 | Winter | | | |
| 1.009 | 14 | 600 | Winter | 1 | +0% | | | | | |
| 1.010 | 15 | 600 | Winter | 1 | +0% | | | | | |

| PN | US/MH Name | Water Level (m) | Surcharged Depth (m) | | Flow / Cap. | Overflow (l/s) | Half Drain Time (mins) | Flow | Status |
|-------|---------------|-----------------------|----------------------------|-------|----------------|-------------------|------------------------------|------|--------|
| 1.006 | 09 | 3.979 | -0.099 | 0.000 | 0.73 | | | 39.6 | OK |
| 5.000 | 10 | 5.360 | -0.240 | 0.000 | 0.09 | | | 6.4 | OK |
| 5.001 | 11 | 5.148 | -0.232 | 0.000 | 0.12 | | | 6.4 | OK |
| 1.007 | 12 | 3.929 | -0.094 | 0.000 | 0.81 | | | 45.5 | OK |
| 1.008 | 13 | 3.767 | -0.183 | 0.000 | 0.04 | | | 3.6 | OK |
| 1.009 | 14 | 3.528 | -0.336 | 0.000 | 0.02 | | | 3.6 | OK |
| 1.010 | 15 | 3.063 | -0.336 | 0.000 | 0.02 | | | 3.6 | OK |
| | | | | | | | | | |

| PN | • | Level Exceeded |
|-------|----|-------------------|
| 1.006 | 09 | |
| 5.000 | 10 | |
| 5.001 | 11 | |
| 1.007 | 12 | |
| 1.008 | 13 | |
| 1.009 | 14 | |
| 1.010 | 15 | |

| | DHV UI | | | | | | | Page | |
|---|--|--|---|--|---|--|---|--|-------|
| Rightwell | House | e | | Drain | age Str | ategy | | | |
| Bretton, | n 📔 | | | | | | | | |
| Surrey, P. | E3 8DI | W | | | | | | Mic | in i |
| Date 28/0 | 5/202 | 3 21:45 | | Desig | ned by | IO | | Dcai | inaa |
| File Surf | acewa | ter Netwo | rk.MDX | Check | ed by B | A | | DIG | mayı |
| Innovyze | | | | Netwo | rk 2020 | .1.3 | | | |
| 30 year R | Return | Period S | Summary (| | ical Re. Storm | sults | by Maximum | Level (R | ank 1 |
| | Numbe | Ado Flow | Manhole H Foul Se ditional MADD Fa per Pers | Hot St Headloss wage per Flow - 9 Actor * 1 Inle son per I | eduction bt Start cart Lev Coeff (r hectar & of Tot LOm ³ /ha et Coeff Day (l/p | Facto (mins cel (mm Global ce (l/s cal Flo Storag iecien oer/day |) 0) 0.500) 0.000 w 0.000 e 2.000 t 0.800 | res 1 | |
| | Nun | nber of On Der of Off Rainfall | line Con line Con Synth | trols 1 trols 0 etic Rai | Number (Number (nfall De FSR | of Time of Real etails Ra | e/Area Diagra . Time Contro atio R 0.275 | ams O ols O | |
| | | | (mm) | - | 16.600 | Cv (Wi | nter) 0.840 | | |
| | Dī | in for Flo Prc uration(s) | ood Risk Analy ofile(s) (mins) | Warning vsis Time DTS St 30, | 16.600 (mm) 30 estep F catus 60, 120, | Cv (Wi 0.0 'ine In ON , 180, | DVD Status DVD Status ertia Status Summer and 240, 360, 48 , 2880, 4320 7200, 8640 | GOFF GOFF d Winter 80, 600, 0, 5760, 0, 10080 | |
| | Di eturn 1 C: | in for Flo Pro | ood Risk Analy ofile(s) (mins) (years) | Warning vsis Time DTS St 30, | 16.600 (mm) 30 estep F catus 60, 120, 60, 1440 | Cv (Wi 0.0 Vine In ON , 180, 0, 2160 | DVD Status DVD Status ertia Status Summer and 240, 360, 48 , 2880, 4320 7200, 8640 1, | 5 OFF 5 OFF d Winter 80, 600, 0, 5760, | |
| | Di eturn 1 | in for Flo Pro uration(s) Period(s) | ood Risk Analy ofile(s) (mins) (years) ange (%) Return | Warning vsis Time DTS St 30, | 16.600 (mm) 30 estep F catus 60, 120, | Cv (Wi 0.0 ¹ ine In ON , 180, 0, 2160 | DVD Status DVD Status ertia Status Summer and 240, 360, 48 , 2880, 4320 7200, 8640 1, | G OFF G OFF d Winter 80, 600, 0, 5760, 0, 10080 30, 100 0, 0, 40 | |
| | Du eturn D C: US/MH Name | in for Flo Pro uration(s) Period(s) limate Cha | ood Risk Analy ofile(s) (mins) (years) ange (%) Return Period | Warning rsis Time DTS St 30, 720, 9 Climate Change +0% | 16.600 (mm) 30 estep F catus 60, 120, 60, 1440 First Surch 100/30 s | Cv (Wi 0.0 Vine In ON , 180, 0, 2160 (X) arge Summer | <pre>.nter) 0.840 DVD Status ertia Status Summer and 240, 360, 48 , 2880, 4320 7200, 8640 1, () First (Y)</pre> | G OFF G OFF H Winter B0, 600, D, 5760, D, 10080 30, 100 D, 0, 40 First Overfl | |
| PN 1.000 1.001 | Du eturn 1 C: US/MH Name 01 02 | in for Flo Pro uration(s) Period(s) limate Cha Storm 30 Summer 30 Summer | Dod Risk Analy ofile(s) (mins) (years) ange (%) Return Period 30 30 | Warning rsis Time DTS St 30, 720, 9 Climate Change +0% +0% | 16.600 (mm) 30 estep F catus 60, 120, 60, 1440 First Surch 100/30 3 100/30 3 | Cv (Wi 0.0 Vine In ON , 180, 0, 2160 (X) arge Summer Summer | nter) 0.840 DVD Status ertia Status Summer and 240, 360, 48 , 2880, 4320 7200, 8640 1, () First (Y) Flood | G OFF G OFF H Winter B0, 600, D, 5760, D, 10080 30, 100 D, 0, 40 First Overfl | |
| PN 1.000 1.001 1.002 | Du eturn 1 C: US/MH Name 01 02 03 | in for Flo Pro uration(s) Period(s) limate Cha 30 Summer 30 Summer 30 Summer | <pre>Dod Risk Analy ofile(s) (mins) (years) ange (%) Return Period 30 30 30</pre> | Warning rsis Time DTS St 30, 720, 9 Climate Change +0% +0% +0% | 16.600 (mm) 30 estep F catus 60, 120, 60, 1440 First Surch 100/30 s | Cv (Wi 0.0 Vine In ON , 180, 0, 2160 (X) arge Summer Summer | nter) 0.840 DVD Status ertia Status Summer and 240, 360, 48 , 2880, 4320 7200, 8640 1, () First (Y) Flood | G OFF G OFF H Winter B0, 600, D, 5760, D, 10080 30, 100 D, 0, 40 First Overfl | |
| PN 1.000 1.001 1.002 2.000 | Du Sturn 1 C: US/MH Name 01 02 03 16 | in for Flo Pro uration(s) Period(s) limate Cha 30 Summer 30 Summer 30 Summer 30 Summer | <pre>bod Risk Analy ofile(s) (mins) (years) ange (%) Return Period 30 30 30 30 30 30</pre> | Warning rsis Time DTS St 30, 720, 9 Climate Change +0% +0% +0% +0% +0% | 16.600 (mm) 30 estep F catus 60, 120, 60, 1440 60, 1440 100/30 3 100/30 3 | Cv (Wi 0.0 Vine In ON , 180, 0, 2160 (X) arge Summer Summer Summer | nter) 0.840 DVD Status ertia Status Summer and 240, 360, 48 , 2880, 4320 7200, 8640 1, () First (Y) Flood | G OFF G OFF H Winter B0, 600, D, 5760, D, 10080 30, 100 D, 0, 40 First Overfl | |
| PN 1.000 1.001 1.002 2.000 1.003 | Du Eturn D C: US/MH Name 01 02 03 16 04 | in for Flo Pro uration(s) Period(s) limate Cha 30 Summer 30 Summer 30 Summer 30 Summer 30 Summer | <pre>Dod Risk Analy Dfile(s) (mins) (years) unge (%) Return Period 30 30 30 30 30 30 30 30 30 30</pre> | Warning rsis Time DTS St 30, 720, 9 Climate Change +0% +0% +0% +0% +0% | 16.600 (mm) 30 estep F catus 60, 120, 60, 1440 First Surch 100/30 : 100/30 : 100/30 : | Cv (Wi 0.0 Vine In ON , 180, 0, 2160 (X) arge Summer Summer Summer | nter) 0.840 DVD Status ertia Status Summer and 240, 360, 48 , 2880, 4320 7200, 8640 1, () First (Y) Flood | G OFF G OFF H Winter B0, 600, D, 5760, D, 10080 30, 100 D, 0, 40 First Overfl | |
| PN 1.000 1.001 1.002 2.000 1.003 1.004 | Du eturn D C: US/MH Name 01 02 03 16 04 05 | in for Flo Pro uration(s) Period(s) limate Cha 30 Summer 30 Summer 30 Summer 30 Summer 30 Summer 30 Summer | <pre>Dod Risk Analy Dfile(s) (mins) (years) unge (%) Return Period 30 30 30 30 30 30 30 30 30 30 30 30 30</pre> | Warning rsis Time DTS St 30, 720, 9 Climate Change +0% +0% +0% +0% +0% +0% | 16.600 (mm) 30 estep F catus 60, 120, 60, 1440 60, 1440 100/30 1 100/30 1 100/30 1 30/30 1 | Cv (Wi 0.0 'ine In ON , 180,), 2160 (X) arge Summer Summer Summer Summer | nter) 0.840 DVD Status ertia Status Summer and 240, 360, 48 , 2880, 4320 7200, 8640 1, () First (Y) Flood | G OFF G OFF H Winter B0, 600, D, 5760, D, 10080 30, 100 D, 0, 40 First Overfl | |
| PN 1.000 1.001 1.002 2.000 1.003 | Du eturn 1 C: US/MH Name 01 02 03 16 04 05 H07 | in for Flo Pro uration(s) Period(s) limate Cha 30 Summer 30 Summer 30 Summer 30 Summer 30 Summer | <pre>bod Risk Analy ofile(s) (mins) (years) unge (%) Return Period 30 30 30 30 30 30 30 30 30 30 30 30 30</pre> | Warning rsis Time DTS St 30, 720, 9 Climate Change +0% +0% +0% +0% +0% | 16.600 (mm) 30 estep F catus 60, 120, 60, 1440 First Surch 100/30 : 100/30 : 100/30 : | Cv (Wi 0.0 'ine In ON , 180, 0, 2160 (X) arge Summer Summer Summer Summer Summer | nter) 0.840 DVD Status ertia Status Summer and 240, 360, 48 , 2880, 4320 7200, 8640 1, () First (Y) Flood | G OFF G OFF H Winter B0, 600, D, 5760, D, 10080 30, 100 D, 0, 40 First Overfl | |
| PN 1.000 1.001 1.002 2.000 1.003 1.004 3.000 | Du eturn 1 C: US/MH Name 01 02 03 16 04 05 H07 06 | in for Flo Pro uration(s) Period(s) limate Cha 30 Summer 30 Summer 30 Summer 30 Summer 30 Summer 30 Summer 30 Summer | <pre>bod Risk Analy ofile(s) (mins) (years) unge (%) Return Period 30 30 30 30 30 30 30 30 30 30 30 30 30</pre> | Warning rsis Time DTS St 30, 720, 9 Climate Change +0% +0% +0% +0% +0% +0% +0% | 16.600 (mm) 30 estep F catus 60, 120, 60, 1440 First Surch 100/30 : 100/30 : 30/30 : 30/30 : | Cv (Wi 0.0 'ine In ON , 180, 0, 2160 (X) arge Summer Summer Summer Summer Summer Summer Summer | nter) 0.840 DVD Status ertia Status Summer and 240, 360, 48 , 2880, 4320 7200, 8640 1, () First (Y) Flood | G OFF G OFF H Winter B0, 600, D, 5760, D, 10080 30, 100 D, 0, 40 First Overfl | |
| PN 1.000 1.001 1.002 2.000 1.003 1.004 3.000 1.005 | Du eturn 1 C: US/MH Name 01 02 03 16 04 05 H07 06 07 | in for Flo Pro uration(s) Period(s) limate Cha 30 Summer 30 Summer 30 Summer 30 Summer 30 Summer 30 Summer 30 Summer 30 Summer | <pre>bod Risk Analy ofile(s) (mins) (years) unge (%) Return Period 30 30 30 30 30 30 30 30 30 30 30 30 30</pre> | Warning vsis Time DTS St 30, 720, 9 Climate Change +0% +0% +0% +0% +0% +0% +0% +0% | 16.600 (mm) 30 estep F catus 60, 120, 60, 1440 First Surch 100/30 = 100/30 = 30/30 = 30/30 = | Cv (Wi 0.0 'ine In ON , 180, 0, 2160 (X) arge Summer Summer Summer Summer Summer Summer Summer | nter) 0.840 DVD Status ertia Status Summer and 240, 360, 48 , 2880, 4320 7200, 8640 1, () First (Y) Flood | G OFF G OFF H Winter B0, 600, D, 5760, D, 10080 30, 100 D, 0, 40 First Overfl | |

| HaskoningDHV UK Limited | | Page 13 |
|-------------------------------|-------------------------------|------------|
| Rightwell House | Drainage Strategy | |
| Bretton, Peterborough | White Cross Offshore Windfarm | the second |
| Surrey, PE3 8DW | | Mirro |
| Date 28/05/2023 21:45 | Designed by IO | Drainago |
| File Surfacewater Network.MDX | Checked by BA | Diamage |
| Innovyze | Network 2020.1.3 | |

30 year Return Period Summary of Critical Results by Maximum Level (Rank 1) for Storm

| PN | US/MH Name | Overflow Act. | Water Level (m) | Surcharged Depth (m) | | Flow / Cap. | Overflow (1/s) | Half Drain Time (mins) | Pipe Flow (l/s) |
|-------|---------------|------------------|-----------------------|----------------------------|-------|----------------|-------------------|------------------------------|-----------------------|
| 1.000 | 01 | | 4.558 | -0.242 | 0.000 | 0.08 | | | 4.9 |
| 1.001 | 02 | | 4.452 | -0.110 | 0.000 | 0.24 | | | 12.6 |
| 1.002 | 03 | | 4.448 | -0.065 | 0.000 | 0.33 | | | 17.7 |
| 2.000 | 16 | | 5.460 | -0.240 | 0.000 | 0.09 | | | 5.4 |
| 1.003 | 04 | | 4.448 | -0.019 | 0.000 | 0.40 | | | 24.0 |
| 1.004 | 05 | | 4.436 | 0.121 | 0.000 | 0.60 | | | 35.4 |
| 3.000 | Н07 | | 5.257 | 0.107 | 0.000 | 1.63 | | | 15.6 |
| 1.005 | 06 | | 4.407 | 0.214 | 0.000 | 0.83 | | | 48.8 |
| 4.000 | 07 | | 5.278 | 0.128 | 0.000 | 1.60 | | | 15.5 |
| 4.001 | 08 | | 4.921 | -0.145 | 0.000 | 0.52 | | | 31.0 |

| | US/MH | | Level |
|-------|-------|------------|----------|
| PN | Name | Status | Exceeded |
| 1.000 | 01 | OK | 1 |
| 1.001 | 02 | OK | |
| 1.002 | 03 | OK | |
| 2.000 | 16 | OK | |
| 1.003 | 04 | OK | |
| 1.004 | 05 | SURCHARGED | |
| 3.000 | H07 | SURCHARGED | |
| 1.005 | 06 | SURCHARGED | |
| 4.000 | 07 | SURCHARGED | |
| 4.001 | 08 | OK | |

| HaskoningDHV UK Limited | | Page 14 |
|----------------------------------|--|-------------|
| Rightwell House | Drainage Strategy | |
| Bretton, Peterborough | White Cross Offshore Windfarm | the second |
| Surrey, PE3 8DW | | Mirro |
| Date 28/05/2023 21:45 | Designed by IO | Drainago |
| File Surfacewater Network.MDX | Checked by BA | Diamaye |
| Innovyze | Network 2020.1.3 | |
| 30 year Return Period Summary of | E Critical Results by Maximum Lev for Storm | el (Rank 1) |
| | | |

| PN | US/MH Name | Storm | | | Climate Change | Firs Surcl | t (X) harge | First (Y) Flood | First (Z) Overflow | Overflow Act. |
|-------|---------------|-------|--------|----|-------------------|---------------|----------------|--------------------|-----------------------|------------------|
| 1.006 | 09 | 30 | Summer | 30 | +0% | 30/30 | Summer | | | |
| 5.000 | 10 | 30 | Summer | 30 | +0% | | | | | |
| 5.001 | 11 | 30 | Summer | 30 | +0% | | | | | |
| 1.007 | 12 | 30 | Summer | 30 | +0% | 30/30 | Summer | | | |
| 1.008 | 13 | 720 | Winter | 30 | +0% | 30/180 | Winter | | | |
| 1.009 | 14 | 240 | Winter | 30 | +0% | | | | | |
| 1.010 | 15 | 1440 | Winter | 30 | +0% | | | | | |

| PN | US/MH Name | Water Level (m) | Surcharged Depth (m) | | Flow / Cap. | Overflow (1/s) | Half Drain Time (mins) | Pipe Flow (l/s) | Status |
|-------|---------------|-----------------------|----------------------------|-------|----------------|-------------------|------------------------------|-----------------------|------------|
| 1.006 | 09 | 4.329 | 0.251 | 0.000 | 1.60 | | | 86.3 | SURCHARGED |
| 5.000 | 10 | 5.395 | -0.205 | 0.000 | 0.21 | | | 15.7 | OK |
| 5.001 | 11 | 5.189 | -0.192 | 0.000 | 0.28 | | | 15.7 | OK |
| 1.007 | 12 | 4.182 | 0.159 | 0.000 | 1.82 | | | 102.6 | SURCHARGED |
| 1.008 | 13 | 4.033 | 0.084 | 0.000 | 0.04 | | | 3.8 | SURCHARGED |
| 1.009 | 14 | 3.529 | -0.336 | 0.000 | 0.02 | | | 3.8 | OK |
| 1.010 | 15 | 3.064 | -0.335 | 0.000 | 0.02 | | | 3.8 | OK |

| | US/MH | Level |
|-------|-------|----------|
| PN | Name | Exceeded |
| | | |
| 1.006 | 09 | |
| 5.000 | 10 | |
| 5.001 | 11 | |
| 1.007 | 12 | |
| 1.008 | 13 | |
| 1.009 | 14 | |
| 1.010 | 15 | |

| | gDHV U | | ımited | | | | | | Page 15 | | |
|---|---|--|--|--|--|--|--|--------------------------------|-----------------------|--|--|
| Rightwell | l Hous | е | | | Drain | age Str | rategy | | | | |
| Bretton, | Peter | bord | ough | | White | Cross | Offshc | ore Windfarm | the second | | |
| Surrey, 1 | PE3 8D | W | | | | Mirro | | | | | |
| Date 28/0 | 05/202 | 3 2 | 1:45 | | Desig | Designed by IO | | | | | |
| File Suri | facewa | ter | Networ | rk.MDX | Check | ed by E | 8A | | Drainagi | | |
| Innovyze | | | | | Netwo | rk 2020 | 0.1.3 | | | | |
| | | | | | | | | | | | |
| 100 yea | r Retu | ırn | Period | Summar | y of Cr. | itical | Result | s by Maximum | n Level (Rank | | |
| | | | | | 1) for | Storm | | | | | |
| | | | | | | | | | | | |
| | | | | | | a | | | | | |
| | | | | 51 | mulation Areal Re | | | × 1 000 | | | |
| | | | | | | ot Start | | | | | |
| | | | | | | tart Lev | - | | | | |
| | | | М | | leadloss | | - | | | | |
| | | | | | wage per | | | | | | |
| | | | Add | | Flow - | | | | | | |
| | | | | MADD FC | actor * 1 Inle | ium³/na et Coeff | - | | | | |
| | | | Flow | per Pers | son per l | | | | | | |
| | | | | | | | | | | | |
| | | | | | | | | rage Structur | | | |
| | | | | | | | | e/Area Diagra L Time Contro | | | |
| | NUM | oer | OI UIII | Line Con | LTOIS U | Numper | ol Real | L TIME CONTRO | 15 0 | | |
| | | | | Synth | etic Rai | nfall D | etails | | | | |
| | | Rai | nfall N | - | | FSR | | atio R 0.275 | | | |
| | | | | - | gland an | | | ummer) 0.750 | | | |
| | | | M5-60 | (mm) | | 16.600 | Cv (Wi | inter) 0.840 | | | |
| | Marc | rin : | for Flo | od Risk | Warning | (mm) 30 | 0.0 | DVD Status | OFF | | |
| | nar g | | | | - | | | ertia Status | | | |
| | | | | | DTS St | catus | ON | | | | |
| | | | | | | | | | | | |
| | | | Pro | file(s) | | | | Summer and | Winter | | |
| | D | urat | ion(s) | (mins) | | | | 240, 360, 480 | | | |
| | | | | | 720, 9 | 60, 144 | 0, 2160 |), 2880, 4320, | | | |
| D | oturn | Pori | od (s) | (years) | | | | 7200, 8640 | , 10080 30, 100 | | |
| Г | | | ite Chai | - | | | | | , 0, 40 | | |
| | | | | 5 | | | | | | | |
| | | | | | | | | | | | |
| | | | | | | | | | | | |
| | US/MH | | | Return | Climate | First | (X) | First (Y) | First (Z) | | |
| PN | US/MH Name | | torm | | Climate Change | First Surch | | First (Y) Flood | First (Z) Overflow | | |
| | Name | S | | Period | Change | Surch | arge | Flood | Overflow | | |
| 1.000 | Name 01 | s 30 | Winter | Period 100 | Change +40% | Surch | arge Summer | | Overflow | | |
| | Name 01 02 | s 30 30 | | Period | Change +40응 +40응 | Surch | arge Summer Summer | Flood | Overflow | | |
| 1.000 1.001 | Name 01 02 03 | 30 30 30 | Winter Winter | Period 100 100 | Change +40% +40% +40% +40% | Surch 100/30 100/30 100/30 | arge Summer Summer Summer | Flood | Overflow | | |
| 1.000 1.001 1.002 2.000 1.003 | Name 01 02 03 16 04 | 30 30 30 30 30 30 | Winter Winter Winter Summer Winter | Period 100 100 100 100 100 100 | Change +40% +40% +40% +40% | Surch 100/30 100/30 100/30 | arge Summer Summer Summer | Flood | Overflow | | |
| 1.000 1.001 1.002 2.000 1.003 1.004 | Name 01 02 03 16 04 05 | 30 30 30 30 30 30 30 | Winter Winter Winter Summer Winter Winter | Period 100 100 100 100 100 100 100 100 | Change +40% +40% +40% +40% +40% | Surch 100/30 100/30 100/30 100/30 30/30 | arge Summer Summer Summer Summer | Flood | Overflow | | |
| 1.000 1.001 1.002 2.000 1.003 1.004 3.000 | Name 01 02 03 16 04 05 H07 | 30 30 30 30 30 30 30 30 | Winter Winter Summer Winter Winter Summer | Period 100 100 100 100 100 100 100 100 100 10 | Change +40% +40% +40% +40% +40% +40% | Surch 100/30 100/30 100/30 30/30 30/30 | arge Summer Summer Summer Summer Summer | Flood | Overflow | | |
| 1.000 1.001 2.000 1.003 1.004 3.000 1.005 | Name 01 02 03 16 04 05 H07 06 | 30 30 30 30 30 30 30 30 | Winter Winter Summer Winter Winter Summer Winter | Period 100 100 100 100 100 100 100 100 | Change +40% +40% +40% +40% +40% +40% +40% | Surch 100/30 100/30 100/30 30/30 30/30 30/30 | arge Summer Summer Summer Summer Summer Summer | Flood | Overflow | | |
| 1.000 1.001 1.002 2.000 1.003 1.004 3.000 | Name 01 02 03 16 04 05 H07 06 07 | 30 30 30 30 30 30 30 30 30 | Winter Winter Summer Winter Winter Summer | Period 100 100 100 100 100 100 100 100 100 10 | Change +40% +40% +40% +40% +40% +40% | Surch 100/30 100/30 100/30 30/30 30/30 | arge Summer Summer Summer Summer Summer Summer | Flood | Overflow | | |

| HaskoningDHV UK Limited | | Page 16 |
|-------------------------------|-------------------------------|------------|
| Rightwell House | Drainage Strategy | |
| Bretton, Peterborough | White Cross Offshore Windfarm | the second |
| Surrey, PE3 8DW | | Mirro |
| Date 28/05/2023 21:45 | Designed by IO | Drainago |
| File Surfacewater Network.MDX | Checked by BA | Diamage |
| Innovyze | Network 2020.1.3 | |

100 year Return Period Summary of Critical Results by Maximum Level (Rank <u>1) for Storm</u>

| PN | US/MH Name | Overflow Act. | Water Level (m) | Surcharged Depth (m) | | Flow / Cap. | Overflow (1/s) | Half Drain Time (mins) | Pipe Flow (l/s) |
|-------|---------------|------------------|-----------------------|----------------------------|-------|----------------|-------------------|------------------------------|-----------------------|
| 1.000 | 01 | | 5.300 | 0.500 | 0.001 | 0.13 | | | 8.2 |
| 1.001 | 02 | | 5.290 | 0.728 | 0.000 | 0.56 | | | 29.7 |
| 1.002 | 03 | | 5.280 | 0.766 | 0.000 | 0.63 | | | 33.4 |
| 2.000 | 16 | | 5.480 | -0.220 | 0.000 | 0.16 | | | 9.9 |
| 1.003 | 04 | | 5.266 | 0.799 | 0.000 | 0.65 | | | 38.8 |
| 1.004 | 05 | | 5.226 | 0.910 | 0.000 | 0.80 | | | 47.2 |
| 3.000 | Н07 | | 5.623 | 0.473 | 0.000 | 2.84 | | | 27.2 |
| 1.005 | 06 | | 5.162 | 0.969 | 0.000 | 1.39 | | | 81.7 |
| 4.000 | 07 | | 5.705 | 0.555 | 0.000 | 2.72 | | | 26.3 |
| 4.001 | 08 | | 5.002 | -0.063 | 0.000 | 0.88 | | | 52.6 |

| | US/MH | | Level |
|-------|-------|------------|----------|
| PN | Name | Status | Exceeded |
| 1.000 | 01 | FLOOD | 1 |
| 1.001 | 02 | SURCHARGED | |
| 1.002 | 03 | SURCHARGED | |
| 2.000 | 16 | OK | |
| 1.003 | 04 | SURCHARGED | |
| 1.004 | 05 | SURCHARGED | |
| 3.000 | Н07 | SURCHARGED | |
| 1.005 | 06 | SURCHARGED | |
| 4.000 | 07 | SURCHARGED | |
| 4.001 | 08 | OK | |

| HaskoningDHV UK Limited | Page 17 | |
|-------------------------------|-------------------------------|------------|
| Rightwell House | Drainage Strategy | |
| Bretton, Peterborough | White Cross Offshore Windfarm | the second |
| Surrey, PE3 8DW | | Mirro |
| Date 28/05/2023 21:45 | Designed by IO | Drainago |
| File Surfacewater Network.MDX | Checked by BA | Drainage |
| Innovyze | Network 2020.1.3 | |

100 year Return Period Summary of Critical Results by Maximum Level (Rank <u>1) for Storm</u>

| PN | US/MH Name | Storm | | | Climate Change | | t (X) harge | First (Y) Flood | First (Z) Overflow | Overflow Act. |
|-------|---------------|-------|--------|-----|-------------------|--------|----------------|--------------------|-----------------------|------------------|
| 1.006 | 09 | 30 | Winter | 100 | +40% | 30/30 | Summer | | | |
| 5.000 | 10 | 30 | Summer | 100 | +40% | | | | | |
| 5.001 | 11 | 30 | Summer | 100 | +40% | | | | | |
| 1.007 | 12 | 30 | Summer | 100 | +40% | 30/30 | Summer | | | |
| 1.008 | 13 | 960 | Winter | 100 | +40% | 30/180 | Winter | | | |
| 1.009 | 14 | 2880 | Summer | 100 | +40% | | | | | |
| 1.010 | 15 | 5760 | Summer | 100 | +40% | | | | | |

| PN | US/MH Name | Water Level (m) | Surcharged Depth (m) | | Flow / Cap. | Overflow (1/s) | Half Drain Time (mins) | Pipe Flow (l/s) | Status |
|-------|---------------|-----------------------|----------------------------|-------|----------------|-------------------|------------------------------|-----------------------|------------|
| 1.006 | 09 | 4.938 | 0.860 | 0.000 | 2.61 | | | 141.1 | SURCHARGED |
| 5.000 | 10 | 5.431 | -0.169 | 0.000 | 0.39 | | | 28.6 | OK |
| 5.001 | 11 | 5.234 | -0.147 | 0.000 | 0.51 | | | 28.5 | OK |
| 1.007 | 12 | 4.564 | 0.541 | 0.000 | 2.92 | | | 164.1 | SURCHARGED |
| 1.008 | 13 | 4.463 | 0.514 | 0.000 | 0.04 | | | 3.8 | SURCHARGED |
| 1.009 | 14 | 3.529 | -0.336 | 0.000 | 0.02 | | | 3.8 | OK |
| 1.010 | 15 | 3.064 | -0.335 | 0.000 | 0.02 | | | 3.8 | OK |

| | US/MH | Level |
|-------|-------|----------|
| PN | Name | Exceeded |
| | | |
| 1.006 | 09 | |
| 5.000 | 10 | |
| 5.001 | 11 | |
| 1.007 | 12 | |
| 1.008 | 13 | |
| 1.009 | 14 | |
| 1.010 | 15 | |

| SIMPLE INDEX APPROACH: TO | OL SEPARATION AND A MAIlingford | HPW has been informed of the possibility of the same. The u | , loss, cost, expense or liability howsoever arising out of the use or impossibility to use the thereby indemnifies HRW from and against any damage claim, loss, sense or liability of the tool or any reliance made in respect of the output of such use by any person what if any person, nor that the tool is free from errors. | y resulting from any | | | |
|--|--|--|---|----------------------|--|--|--|
| 1. The steps set out in the tool should be applied fo | each inflow or 'runoff area' (ie each impermeable sur | face area separately discharging to a SuDS component). | | | | | |
| 2. The supporting 'Design Conditions' stated by the | ool must be fully considered and implemented in all c | ases. | | | | | |
| 3. The process that is automated in this tool is desc | bed in the SuDS Manual, Chapter 26 (Section 26.7) | | | | | | |
| 3. Relevant design examples are included in the Su | S Manual Appendix C. | | | | | | |
| 4. Each of the steps below are part of the process se | t out in the flowchart on Sheet 3. | | | | | | |
| 5. Sheet 4 summarises the selections made below a | nd indicates the acceptability of the proposed SuDS co | mponents. | | | | | |
| 6. Interception should be delivered for all upstrea criteria set out in Chapter 4 of the SuDS Manual | n impermeable areas as part of the strategy for wate | er quantity and quality control for the site. This is required | in order to deliver both of the water quality | | | | |
| DROP DOWN LIST | DROP DOWN LIST RELEVANT INPUTS NEED TO BE SELECTED FROM THESE LISTS, FOR EACH STEP | | | | | | |
| USER ENTRY | USER ENTRY CELLS ARE ONLY REQUIRED WHERE INDIC | ATED BY THE TOOL | | | | | |
| STEP 1: Determine the Pollution Hazard Index | for the runoff area discharging to the proposed SuDS s | scheme | | | | | |
| This step requires the user to select the appropriate | land use type for the area from which the runoff is occu | rring | | | | | |
| If the land use varies across the 'runoff area', either: | | | | | | | |
| - use the land use type with the highest Pollution | Hazard Index | | | | | | |
| apply the approach for each of the land use type providing additional treatment. | s to determine whether the proposed SuDS design is sufficient for all. If | it is not, consider collecting more hazardous runoff separately and | | | | | |
| If the generic land use types suggested are not applicable, select 'Ot | er' and enter a description of the land use of the runoff area and agreed | user defined indices in the row below the drop down lists. | | | | | |
| | Runoff Area Land Use Description | Pollution Hazard Indices Hazard Total Suspended Level Solids Metals Hydror | rbons 1 2 | | | | |
| Select land use type from the drop down list (or 'Other' if none applicable): | | | | | | | |

This classification is not appropriate for haulage yards, lorry parks, waste management areas, or 0.7 chemical storage/handling zones

| This step requires the user to select the proposed SuDS components that will be used to treat runoff - before it is discharged to a receiving surface waterbody |
|---|
| or downstream infiltration component |

If the runoff is discharged directly to an infiltration component, without upstream treatment, select 'None' for each of the 3 SuDS components and move to Step 2B

Standard commercial yard or delivery area

Landuse Pollution Hazard Index

This step should be applied to evaluate the water quality protection provided by proposed SuDS components for discharges to receiving surface waters or downstream infiltration components (note: in England and Wates this will include components that allow any amount of infiltration, however small, even where infiltration is not specifically accounted for in the design).

If you have fewer than 3 components, select 'None' for the components that are not required

If the generic land use types in the drop down list above are not applicable, select 'Other' and enter a description of the land use of the runoff area and agreed user defined indices in this row:

If the proposed component is bespoke and/or a proprietary treatment product and not generically described by the suggested components, then 'Proprietary treatment system' or 'User defined indices' should be selected and a description of the component and agreed user defined indices should be entered in the rows below the drop down lists

SuDS Component Description

STEP 2A: Determine the Pollution Mitigation Index for the proposed SuDS components

| Total Suspe | Pollution Mitigation | on Indices |
|-------------|----------------------|--------------|
| Solids | Metals | Hydrocarbons |

0.7

0.7

0.6

0.6


0.7

DESIG

Medium

Medium

| N CONDITIONS | | |
|--------------|---|---|
| 1 | 2 | 3 |



•

STEP 2C: Determine the Combined Pollution Mitigation Indices for the Runoff Area

This is an automatic step which combines the proposed SuDS Pollution Mitigation Indices with any Groundwater Protection Pollution Mitigation Indices

| | Comb Total Susper | bined Pollution Mi nded | itigation Indices | | |
|---|----------------------|----------------------------|-------------------|---|--|
| | Solids | Metals | Hydrocarbons | Note: If the total aggregated mitigation index is > 1 (which is not a realistic outcome), then the outcome is fixed at ">0.95". In this scenario, the proposed | |
| Combined Pollution Mitigation Indices for the Runoff Area | 0.7 | 0.7 | 0.75 | components are likely to have a very high miligation potential for reducing pollutant levels in the runoff and should be sufficient for any proposed land use (note: where risk assessment is required, this outcome would need more detailed verification). | |

STEP 2D: Determine Sufficiency of Pollution Mitigation Indices for Selected SuDS Components

This is an automatic step which compares the Combined Pollution Mitigation Indices with the Land Use Hazard Indices, to determine whether the proposed components are sufficient to manage each pollutant category type

When the combined mitigation index exceeds the land use pollution hazard index, then the proposed components are considered sufficient in providing pollution risk mitigation.

DESIGN CONDITIONS

In England and Wales, where the discharge is to protected surface waters or groundwater, an additional treatment component (ie over and above that required for standard discharges), or other equivalent protection, is required that provides environmental protection in the event of an unexpected pollution event or poor system performance. Protected avriation waters are those designated for dinking water abstraction. In England and Wales, protected groundwater resources are defined as Source Protection 2000. Zon 1. In Norther relativity, and precaultion ay approach may be required and this should be checked with the environmental regulated basis.

Sufficiency of Pollution Mitigation Indices Total Supported Solids Matals Hydrocarbons 1 Note: In order to meet both Water Quality criteria set out In the SuDS Manual (Chapter 4), Interception should be delivered for all impermeable areas wherever possible. Interception delivery and treatment may be met by the same components, but Interception requires separate evaluation.



White Cross Offshore Windfarm Environmental Statement

Appendix 5.D: Onshore Export Cable Corridor Alignment Sheets





Index of Figures


Figure 5.D 1: Onshore Cable Route - Alignment Sheets (Sheet 1 of 5) (FLO-WHI-DWG-0004) Figure 5.D 2: Onshore Cable Route - Alignment Sheets (Sheet 2 of 5) (FLO-WHI-DWG-0005) Figure 5.D 3: Onshore Cable Route - Alignment Sheets (Sheet 3 of 5) (FLO-WHI-DWG-0006) Figure 5.D 4: Onshore Cable Route - Alignment Sheets (Sheet 4 of 5) (FLO-WHI-DWG-0007) Figure 5.D 5: Onshore Cable Route - Alignment Sheets (Sheet 5 of 5) (FLO-WHI-DWG-0008) Figure 5.D 6: Onshore Cable Route - Working Width Alignment Sheets (Sheet 1 of 5) (FLO-WHI-DWG-0015) Figure 5.D 7: Onshore Cable Route - Working Width Alignment Sheets (Sheet 2 of 5) (FLO-WHI-DWG-0016) Figure 5.D 8: Onshore Cable Route - Working Width Alignment Sheets (Sheet 3 of 5) (FLO-WHI-DWG-0017) Figure 5.D 9: Onshore Cable Route - Working Width Alignment Sheets (Sheet 4 of 5) (FLO-WHI-DWG-0018) Figure 5.D 10: Onshore Cable Route - Working Width Alignment Sheets (Sheet 5 of 5) (FLO-WHI-DWG-0019) Figure 5.D 11: Onshore Cable Route - SI Sheets (Sheet 1 of 5) (FLO-WHI-DWG-0009) Figure 5.D 12: Onshore Cable Route - SI Sheets (Sheet 2 of 5) (FLO-WHI-DWG-0010) Figure 5.D 13: Onshore Cable Route - SI Sheets (Sheet 3 of 5) (FLO-WHI-DWG-0011) Figure 5.D 14: Onshore Cable Route - SI Sheets (Sheet 4 of 5) (FLO-WHI-DWG-0012) Figure 5.D 15: Onshore Cable Route - SI Sheets (Sheet 5 of 5) (FLO-WHI-DWG-0013) Figure 5.D 16: Cable Landfall Outline HDD Plan and Profile (FLO-WHI-LAY-0017) Figure 5.D 17: Saunton Golf Club Outline HDD Plan and Profile (FLO-WHI-LAY-0018) Figure 5.D 18: River Taw Outline HDD Plan and Profile (FLO-WHI-LAY-0019) Figure 5.D 19: HDD Site Compound Layout (Landfall / Golf Course Crossings) (FLO-WHI-LAY-0013) Figure 5.D 20: HDD Site Compound Layout (River Taw Crossing) (FLO-WHI-LAY-0014)

Figure 5.D 21: Typical Construction Strip Cross Section (FLO-WHI-DWG-0003)














гие гап










File Path








HDD EXIT POINT E:244059.019, N:137575.762

GEOPHYSICAL SURVEY AREA IN ABEYANCE. PROPOSED TO CARRY OUT 2 x 94m PROFILES (ORANGE LINES) WHICH REQUIRES A WORKING AREA EXTENDING APPROXIMATELY 110m IN EACH DIRECTION (GREEN LINES)



| P02 | 02.08.23 | UPDATED WITH CLIENT COMMENTS. RE-ISSUED FOR INFORMATION | LP | CG | | | | | | | |
|------------|----------|---|----|-----|--|--|--|--|--|--|--|
| P01 | 19.06.23 | ISSUED FOR INFORMATION | LP | GA | | | | | | | |
| Rev | Date | Description | Ву | Chk | | | | | | | |
| Amendments | | | | | | | | | | | |


Broxden House Broxden Business Park Lamberkine Drive Perth PH1 1RA


| Designed By | LP | Director | CG | Waterman Ref | /IE12 | 731-153 | | | | | | |
|------------------|---------|------------------|--------------|--------------|-------|----------|--|--|--|--|--|--|
| Drawn By | LP | Date | JUNE 23 | Scales @ A0 | | 1:2000 | | | | | | |
| Stockton Checker | | Stockton Approve | r | Date | | | | | | | | |
| Project - Origi | nator - | Volume - Level | - Type - Rol | e - Number | I | Revision | | | | | | |
| 12731- | F | > 02 | | | | | | | | | | |
| | | <u> </u> | | | | | | | | | | |




Projects/WIE12731 Stockton HDD/153 - White Cross Phase 2/

File Path







| P02 | 02.08.23 | UPDATED WITH CLIENT COMMENTS. RE-ISSUED FOR INFORMATION | LP | CG |
|---------|----------|--|----|-----|
| P01 | 19.06.23 | ISSUED FOR INFORMATION | LP | GA |
| Rev | Date | Description | Ву | Chk |
| | | Amendments | | |
| Project | t | | | |

| Designed By | LP | Director | CG | Waterman Ref W | E12731-153 | | | | | | | |
|------------------|-----------|-------------------|------------|-------------------|------------|--|--|--|--|--|--|--|
| Drawn By | LP | Date | JUNE 23 | Scales @ A0 | 1:2000 | | | | | | | |
| Stockton Checker | | Stockton Approver | | Date | | | | | | | | |
| Project - Orig | ginator - | Volume - Level - | Type - Rol | e - Number | Revision | | | | | | | |
| 12731- | -153-\ | NIE-ZZ-Z | 7-M3- | 91404 | P02 | | | | | | | |





| EL (m AOD) | 20 15 10 5 -17.58% -17.58% -17.58% 10 -17.58% -17.58% -17.58% -17.58% -17.58% -17.58% -17.58% -10 -10 -17.58% -10 -10 -10 -10 -10 -10 -10 -10 | | | | | | _ | · | | | | | | | | | | | | | | | |
|---|--|--|--|--|---|---|---|---|--|---|----------------------|---|----------------------------------|---|--------------------------------|--|------------------------|-----------------------------------|--|---|-------------------------------------|--|-------------------------------------|
| | 25 — 30 — 35 — 40 — 45 — | | | | | | | | | | | | | | | | | | | | | -0.11% | |
| CHAINAGE (m) | 0+000 0+010 - 0+020 - 0+030 - 0+040 - | 0+060 | 0+110 | 0+150 0+160 - 0+170 - 0+180 - | 0+200 0+210 - 0+220 - 0+230 - 0+240 - | 0+250 0+260 0+270 0+280 0+290 | 0+300 0+310 - 0+320 - 0+330 - 0+340 - | 0+350 - 0+380 - 0+380 - 0+380 - 0+380 - 0+380 - 0+390 | 0+400 0+410 0+420 0+420 | 0+440 | 0+490 - 0+500 | 0+510 0+520 0+530 0+540 0+550 | 0+560 0+570 0+580 | 0+590 - 0+600 0+610 - 0+620 - 0+630 - | 0+640 - 0+650 0+660 - | 0+670 - 0+680 - 0+690 - 0+700 | 0+710 0+720 | 0+740 | - 06/+0 - 08/+0 | 0+800 0+810 - 0+820 - 0+840 - 0+840 - | - 078+0 - 078+0 - 088+0 | 0+890 0+900 0+910 0+910 | 0+920 |
| ONSHORE EXISTING LEVELS (m AOD) | 12.966 13.080 - 13.181 - 13.580 - 14.118 - 14.147 | 14.14/ 13.984 - 13.739 - 13.452 - 13.362 - 13.277 | 13.223 - 13.372 - 16.245 - 15.014 - | 12.462 8.021 - 7.558 - 5.960 - | 4.717 4.298 - 3.972 - 3.662 - 3.393 - | 3.174 | | | | | | | | | | | | | | | | | |
| OFFSHORE EXISTING LEVELS (m AOD) | | | | | | | | | | -4.792 - -4.746 - -4.718 - | -4.739 - | -4.780 - -4.800 - -4.800 - -4.800 - -4.800 - | -4.800 - -4.800 - -4.800 - | -4.800 - -4.749 -4.681 - -4.612 - | -4.476 - -4.407 -4.339 - | -4.270 - -4.202 - -4.134 - -4.065 | -4.003 - -3.992 - | -3.959 | -3.949 - -3.940 - -3.957 - -3.973 - | -3.989 -4.011 -4.070 -4.100 -4.100 | -4.146 - -4.146 - -4.215 - | -4.210 -4.287 -4.359 -4.431 | -4.503 -4.575 -4.627 |
| BORE PROFILE LEVEL (m AOD) (TOP OF PIPE) | 12.966 11.208 - 9.450 - 7.692 - 5.935 - 4.177 | 4.1// 2.419 – 0.661 – -1.061 – -2.717 – -4.306 | -5.829 - -7.284 - -8.674 - -9.996 - | -11.252 -12.441 - -13.563 - -14.619 - | -16.531 -17.387 - -18.176 - -18.898 - -19.554 - | -20.143 -20.666 - -21.122 - -21.511 - -21.833 - | -22.089 -22.278 - -22.401 - -22.456 - -22.468 - | -22.491 - -22.502 - -22.513 - -22.524 - | -22.535 -22.546 - -22.557 - -22.568 - | -22.579 - -22.590 -22.601 - -22.612 - -22.624 - | -22.635 - -22.646 | -22.657 - -22.668 - -22.679 - -22.690 - -22.701 | -22.712 -22.723 -22.734 | -22.745 - -22.756 -22.768 - -22.779 - -22.790 - | | -22.834 - -22.845 - -22.856 - -22.867 | -22.878 - -22.889 - | -22.900 - -22.912 - -22.923 | -22.934 - -22.945 - -22.956 - -22.967 - | -22.978 -22.989 - -23.000 - -23.011 - -23.022 - | -23.056 - -23.056 - -23.057 - | -23.067 - -23.078 - -23.089 -23.100 - | -23.111 - -23.122 - -23.133 - |
| BORE VERTICAL GEOMETRY | G=-17.577% L=69.709m- | | | | =1500.000m < =15.000 =262.001m | | | 1 | | | | | | | 1 | | | | | | | <u> </u> | |

INFERRED EXISTING GROUND PROFILE BETWEEN LIDAR AND BATHYMETRIC SURVEY DATA. LIDAR SURVEY DATA EXTENTS OFFSHORE BUT HAS BEEN CLIPPED AS APPEARS TO BE PICKING UP WATER LEVEL AT TIME OF SURVEY

20 —









This drawing should not be scaled. Dimensions to be verified on site. Any discrepancies should be referred to the Engineer prior to work being put in hand. This drawing is the property of Waterman Infrastructure & Environment Limited, and the drawing is issued on the condition that it is not copied reproduced, retained or disclosed any unauthorised person, either wholly or in part without the consent in writing of Waterman Infrastructure & Environment Limited Pickfords Wharf, Clink Street, London SE1 9DG t 020 7928 7888 f 03333 444 501 GENERAL NOTES OFFSHORE . THIS DRAWING IS TO BE READ IN CONJUNCTION WITH ALL ENGINEER'S, ARCHITECT'S OR OTHER RELEVANT DRAWINGS -----AND SPECIFICATIONS. 2. ALL DIMENSIONS AND LEVELS ARE TO BE CHECKED ON SITE BY THE CONTRACTOR PRIOR TO PREPARING ANY WORKING DRAWINGS OR COMMENCING ON SITE. 3. THE CONTRACTOR MUST ENSURE AND WILL BE HELD RESPONSIBLE FOR THE OVERALL STABILITY OF THE BUILDING/STRUCTURE/EXCAVATION AT ALL STAGES OF THE 4. ALL WORK BY THE CONTRACTOR MUST BE CARRIED OUT IN SUCH A WAY THAT ALL REQUIREMENTS UNDER THE HEALTH AND SAFETY AT WORK ACT ARE SATISFIED. 5. ALL WORK IS TO BE CARRIED OUT IN COMPLIANCE WITH THE REQUIREMENTS OF THE RELEVANT STATUTORY AUTHORITIES AND REGULATIONS. _____ 705% T R =5000.000m G =7.049% K =50.000 L =357.991m L =20.231m

WIF12731-1

A0-Wat-SDL-S

FLOTATION ENERGY LTD

FOR PLANNING SUBMISSION

110-099-DRG-

FLO-WHI-LAY-0017



| | Гe | 25 20 15 10 | | | · | -8.(| 2% | | | |
|------------------|-------|--|---------|----------|---------|-----------------|--------------|----------|----------|----------------------|
| | Level | 0-1 -5-1 -10-1 -15-1 -20-1 | | | | | | | | |
| Chainage | | - ² 000.0 | 10.000 | 20.000 | 30.000 | 40.000 | 60.000 | 70.000 | 80.000 | 90.000 |
| Existing Levels | | 8.743 | 8.569 - | 10.513 - | 9.745 — | 8.543 10.018 | 11.081 - | 10.848 — | 10.998 - | 12.770 — 12.756 — |
| Level Difference |) | -0.014 | 0.614 - | 3.360 | 3.394 — | 2.994 5.271 | 7.136 - | 7.706 | 8.657 - | 11.233 – 12.020 |
| Horizontal Geon | netry | 1 | | | | | | | | |
| Vertical Geomet | ry | | | | | 3 = 8 L =10 | .022 3.74 | % | | |

GOLF COURSE CROSSING - LONGSECTION SCALE: H 1:2000,V 1:2000. DATUM: -25.000

| 0.58% | | | | | | | | | | | | | | % | | | | | | | | | | | | | | | | |
|---|---|--------------------------------|-------------------------------|--|----------------------------------|-----------------------|--|---|--|---------------------|--|---|----------|----------------------------------|----------------------|---------------------------------------|---|---|----------------------------------|----------------------|--|----------------------|--|---|----------------------------------|--------------------|--|--|----------------------------------|--------------------------------------|
| | | | | | | | | | | | | | 11 11 | | | | | | | | | | | | | | | | | |
| 90.000 - 100.000 | 120.000 130.000 140.000 140.000 120.0000 120.00000 120.0000000000 | 160.000 170.000 | 180.000 190.000 200.000 | 210.000 220.000 230.000 240.000 | 260.000 270.000 280.000 | 300.000 | 320.000 330.000 340.000 350.000 | 360.000 370.000 380.000 390.000 390.000 | 410.000 420.000 430.000 440.000 | 450.000 - 460.000 - | 470.000 480.000 490.000 500.000 | 510.000 520.000 530.000 540.000 560.000 | 560.000 | 580.000 590.000 600.000 | 610.000 - 620.000 - | 630.000 - 650.000 - 650.000 - 650.000 | 660.000 670.000 680.000 680.000 700.000 | 710.000 720.000 730.000 730.000 | - 000.067 - 000.077 | 790.000 | 810.000 820.000 830.000 840.000 850.000 | 860.000 - 870.000 - | 880.000 900.000 900.000 900.000 900.000 900.000 900.000 900.000 900.000 900.000 900.000 900.000 900.000 900.000 900.000 900.000 | 920.000 920.000 930.000 940.000 940.000 | 960.000 970.000 980.000 | 990.000 | 1010.000 1020.000 1030.000 1040.000 | 1060.000 1070.000 1080.000 1090.000 | 1110.000 1120.000 1130.000 | 1150.000 1160.000 1178:928 |
| 12.770 – 12.756 – | 12.944 13.763 14.512 13.723 | 13.739 13.453 - 13.887 - | 12.436 – 8.995 – 7.997 | 7.882 | 8.198 8.138 8.022 | 8.761 - 8.761 - 8.761 | 10.486 11.898 15.458 | 15.163 13.924 15.365 12.590 | 12.220 – 12.362 – 12.430 – 12.577 – | 13.165 13.695 — | 14.033 14.138 14.137 14.269 | 14.310 14.392 13.997 13.935 | 13.519 | 13.073 – 14.098 – 13.629 – | 13.735 - 13.853 - | 14.248 – 14.366 – 14.493 | 14.647 | 18.458 17.079 15.813 1 <u>5</u> .873 | 17.302 - 18.433 - 16.645 - | 15.133 15.299 | 15.206 15.406 15.583 15.103 14.361 | 14.491 | 14.672 14.318 14.550 | 10.931 18.731 18.609 16.851 16.851 | 21.090 - 21.760 - 20.882 - | 18.539 16.761 | 16.551 - 16.336 - 16.163 - 15.989 - 14.429 - | 13.817 | 13.961 | 13.097 13.097 12.951 12.796 |
| 11.233 – 12.020 | 12.984 14.455 15.723 15.619 | 15.30/ 15.421 - 15.842 - | 14.333 – 14.335 – 9.779 | 9.606 9.641 9.516 9.616 | 9.633 9.633 9.516 9.343 | 9.909 9.909 | 11.576 12.931 13.359 16.375 | 16.022 14.725 16.108 13.276 | 12.790 | 13.505 | 14.258 14.305 14.326 14.320 | 14.304 14.329 13.876 13.256 | 13.225 - | 12.663 – 13.631 – 13.104 | 13.152 | 13.550 | 13.776 | 17.299 15.862 14.538 1 <u>4</u> .538 | 15.854 | 13.512 - 13.621 - | 13.469 13.612 13.731 13.794 12.394 | 12.467 – 12.359 – | 12.532 | 16.361 | 18.489 | 15.765 - 13.930 | 13.662 | 10.303 9.393 8.857 8.437 7.750 | 7.081 | 2.735 2.735 1.718 0.698 |
| | L =1176.745 | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| R =750.000 K =7.500 L =64.488 L =60.976 L =869.295 G =8.707% L =889.295 | | | | | | | | | | | | 0 7% .827 | | | | | | | | | | | | | | | | | | |

his drawing should not be scaled. Dimensions to be verified on site. Any discrepancies should be referred to the Engineer prior to work being put in hand. This drawing is the property of Waterman Infrastructure & Environment Limited, and the drawing is issued on the condition that it is not copied reproduced, retained or disclosed to any unauthorised person, either wholly or in part without the consent in writing of Waterman Infrastructure & Environment Limited Pickfords Wharf, Clink Street, London SE1 9DG t 020 7928 7888 f 03333 444 501

GENERAL NOTES

- 1. THIS DRAWING IS TO BE READ IN CONJUNCTION WITH ALL ENGINEER'S, ARCHITECT'S OR OTHER RELEVANT DRAWINGS AND SPECIFICATIONS.
- ALL DIMENSIONS AND LEVELS ARE TO BE CHECKED ON SITE BY THE CONTRACTOR PRIOR TO PREPARING ANY WORKING DRAWINGS OR COMMENCING ON SITE.
- THE CONTRACTOR MUST ENSURE AND WILL BE HELD RESPONSIBLE FOR THE OVERALL STABILITY OF THE BUILDING/STRUCTURE/EXCAVATION AT ALL STAGES OF THE WORK.
- ALL WORK BY THE CONTRACTOR MUST BE CARRIED OUT IN SUCH A WAY THAT ALL REQUIREMENTS UNDER THE HEALTH AND SAFETY AT WORK ACT ARE SATISFIED.
- ALL WORK IS TO BE CARRIED OUT IN COMPLIANCE WITH THE REQUIREMENTS OF THE RELEVANT STATUTORY AUTHORITIES AND REGULATIONS.

SITE COMPOUND LAYOUT KEY: 1. 50 KVA GENERATOR 2M X 2M

- 2. TOILET BLOCK 6M X 2M
- 3. DRY/CHANGE ROOM 6M X 2M 4. CANTEEN 6M X 2M
- 5. OFFICE 6M X 2M
- 6. OFFICE 6M X 2M 7. 21 TON TRACKED 360 EXCAVATOR
- 8. DRILL PIPE STORAGE 10M X 2M
- 9. HDD DRILL RIG 16M X 2M 10. POWER PACK 6M X 2M
- 11. CONTROL CABIN 6M X 2M
- 12. MUD LAB 3M X 2M
- 13. MUD ENTRY PIT 3M X 4M
- 14. HIGH PRESSURE MUD PUMP 6M X 2M 15. MUD MIXING TANK 7M X 2M
- 16. 350 KVA GENERATOR 5M X 2M
- 17. RECYCLING UNIT 6M X 2M
- 18. WATER STORAGE TANK 6M X 2M 19. DRY DRILLING FLUID STORAGE 4M X 10M
- 20. WORKSHOP 6M X 2M
- 21. STORES 6M X 2M

| P03 | 11.08.23 | SITE COMPOUND LAYOUTS REMOVED. RE-ISSUED FOR INFORMATION AS PART OF PLANNING SUBMISSION | LP | CG | | | | | | |
|-----|------------|--|----|-----|--|--|--|--|--|--|
| P02 | 10.03.23 | TITLE UPDATED AND DRAFT BANNER REMOVED | LP | CG | | | | | | |
| P01 | 20.05.22 | DRAFT ISSUE FOR INFORMATION ONLY | LP | CG | | | | | | |
| Rev | Date | Description | Ву | Chk | | | | | | |
| | Amendments | | | | | | | | | |

WHITE CROSS FLOATING WINDFARM

SAUNTON GOLF CLUB OUTLINE HDD PLAN AND PROFILE

FLOTATION ENERGY LTD



Stockton Approver

110-099-DRG-021

FLO-WHI-LAY-0018

Project - Originator - Volume - Level - Type - Role - Number Revision

12731-135-WIE-ZZ-XX-M3-C-91006 P03

Stockton Checker

GEOLOGY KEY BLOWN SANDS (SAND DUNES) DRIFT DEPOSITS ROCK

1:2000 0 20m 40m 60m 80m 100m 120m 140m 160m 180m 200m

1:1 0 10 20 30 40 50 60 70 80 90 100

A01 A1



| | 損 <u>12.80%</u> | | | TIDE NOT INDIO WELL BELOW E | CONOMICAL TIDE LOWEST ASTRONO CATED GIVEN LEVE BATHYMETRIC RIVE SSUMED DRY AT LC | IS R BED W TIDE | METRIC SURVEY DA | | WATER LEVEL THUS PREFER | Y WAS LIKELY PIO LAT THE TIME OF RENCE GIVEN TO C DATA AT RIVER | SURVEY | ì | | | | | | | | | | INDICA | ED ON BATH | EP CHANNEL N HYMETRIC SU AWN AS 5m D | URVEY | | | | |
|---------------------|---|---|---|----------------------------------|--|---|---|--|--|--|--------------------------------------|---|---|--|--|--|-------------------------------|---|---|---|--|---|-----------------------------------|--|--|--|-----------------------------------|--|--|
| Level | | | | | | | | | | | | | -0.57% | | | | | | | | | | | 8 | | | 6.55% | | |
| | -15 - -20 - -25 | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| Chainage | 0.000 10.000 30.000 30.000 40.000 | 60.000 70.000 80.000 90.000 100.000 | 110.000 120.000 130.000 140.000 | 160.000 170.000 180.000 | 200.000 210.000 220.000 230.000 240.000 | 260.000 270.000 280.000 290.000 | 310.000 320.000 330.000 350.000 350.000 | 360.000 370.000 380.000 390.000 | 400.000 410.000 420.000 430.000 | 450.000 450.000 460.000 470.000 | 490.000 500.000 510.000 | 520.000 530.000 550.000 550.000 | 560.000 570.000 580.000 590.000 600.000 | 610.000 620.000 630.000 640.000 | 650.000 660.000 670.000 680.000 | 690.000 700.000 710.000 720.000 | 730.000 740.000 750.000 | 760.000 770.000 780.000 790.000 800.000 | 810.000 820.000 830.000 840.000 850.000 | 860.000 870.000 880.000 | 910.000 920.000 930.000 940.000 | 960.000 970.000 980.000 | 1000.000 1010.000 1020.000 | 1030.000 1040.000 1050.000 1050.000 | 1070.000 1080.000 1090.000 1100.000 | 1110.000 1120.000 1130.000 1140.000 | 1160.000 1170.000 1180.000 | 1200.000 1210.000 1220.000 1230.000 | 1240.000 1250.000 1260.000 1270.000 |
| | | | | | | | | | | | | | | | | | 1 1 | | | | | | + 1 1 | | | | + | | |
| Existing Levels | 0.033 0.081 0.123 0.165 0.186 | | 0.094 0.025 0.000 0.013 | 0.150 0.219 0.288 0.356 | 0.425 0.493 0.507 0.516 0.516 0.516 | 0.535 0.530 0.535 0.535 0.539 | 0.549 0.553 0.558 0.558 0.563 | 0.572 0.577 0.581 0.586 | 0.590 0.595 0.598 0.579 | 0.560 0.541 0.521 0.502 0.833 | 0.403 0.464 0.445 0.426 | 0.406 0.387 0.368 0.368 0.349 | 0.330 0.318 0.305 0.292 0.279 | 0.266 0.253 0.240 0.227 | 0.215 0.202 0.189 0.177 | 0.167 0.156 0.149 0.138 | 0.134 0.123 0.102 | 0.086 0.088 0.090 0.093 | 0.097 0.100 0.102 0.102 0.107 | 0.109 0.111 0.114 0.116 0.116 | 0.121 0.123 0.125 0.128 | 0.132 0.135 0.135 0.137 0.137 | | 0.148 0.151 0.153 0.155 | 0.153 0.158 0.160 0.165 0.165 | 0.167 0.169 0.172 0.174 | 0.179 0.181 0.183 0.183 | 0.188 0.190 0.193 0.195 | 0.197 0.199 0.202 0.204 |
| | | | | | | | | | | | | | | | | | 1 1 | | | | | | | | | | | | |
| Level Difference | 1.202 2.508 2.960 7.960 | 7.331 9.231 9.764 8.697 | 8.496 8.594 8.661 8.721 8.721 | 8.912 8.984 8.984 9.018 | 9.068 9.139 9.191 9.328 9.328 | 9.419 9.459 9.528 9.595 6715 | 9.739 9.762 9.832 9.880 9.980 | 10.020 10.081 10.151 | 10.244 10.328 10.374 10.443 | 10.511 10.551 10.615 10.650 | 10.715 10.765 10.823 10.867 | 10.946 10.955 11.034 11.099 | 11.193 11.212 11.296 11.323 | 11.444 11.519 11.560 11.629 | 11.688 11.758 11.805 11.866 | 11.889 11.948 12.037 12.088 | 12.152 12.190 12.271 | 12.299 12.354 12.425 12.488 12.497 | 12.550 12.689 12.673 12.781 12.840 | 12.815 12.940 12.690 13.015 | 12.862 12.920 12.977 13.035 | 13.150 13.207 13.264 13.322 | 13.380 13.437 13.494 | 13.547 13.502 13.323 13.012 | 13.012 12.567 11.988 11.334 10.680 | 10.025 9.371 8.716 8.176 7.906 | 8.286 8.286 10.371 8.801 | 5.996 3.972 3.677 2.811 | 2.031 1.680 0.844 0.090 |
| Horizontal Geometry | , | | | | | I | | | | | I | I | | L =1271. | .719 | | I | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| Vertical Geometry | G =-12.799% L =26.583 | R =750.000 K =7.500 L =91.681 | | | | | | | | | | | <u>G</u> =-0.574% L =909.051 | | | | | | | | | | | R =750.0 K =7.50 L =53.39 | 00 | | G =6.545% L =190.892 | | |
| | | | I | | | | | | | | | | | | | | | | | | | | | | Γ | | | | |

RIVER CROSSING - LONGSECTION SCALE: H 1:2000,V 1:2000. DATUM: -25.000

This drawing should not be scaled. Dimensions to be verified on site. Any discrepancies should be referred to the Engineer prior to work being put in hand. This drawing is the property of Waterman Infrastructure & Environment Limited, and the drawing is issued on the condition that it is not copied reproduced, retained or disclosed to any unauthorised person, either wholly or in part without the consent in writing of Waterman Lengthere the sector of the sector o Waterman Infrastructure & Environment Limited Pickfords Wharf, Clink Street, London SE1 9DG t 020 7928 7888 f 03333 444 501

GENERAL NOTES

- 1. THIS DRAWING IS TO BE READ IN CONJUNCTION WITH ALL ENGINEER'S, ARCHITECT'S OR OTHER RELEVANT DRAWINGS AND SPECIFICATIONS.
- 2. ALL DIMENSIONS AND LEVELS ARE TO BE CHECKED ON SITE BY THE CONTRACTOR PRIOR TO PREPARING ANY WORKING DRAWINGS OR COMMENCING ON SITE.
- THE CONTRACTOR MUST ENSURE AND WILL BE HELD RESPONSIBLE FOR THE OVERALL STABILITY OF THE BUILDING/STRUCTURE/EXCAVATION AT ALL STAGES OF THE WORK.
- 4. ALL WORK BY THE CONTRACTOR MUST BE CARRIED OUT IN SUCH A WAY THAT ALL REQUIREMENTS UNDER THE HEALTH AND SAFETY AT WORK ACT ARE SATISFIED.
- 5. ALL WORK IS TO BE CARRIED OUT IN COMPLIANCE WITH THE REQUIREMENTS OF THE RELEVANT STATUTORY AUTHORITIES AND REGULATIONS.

SITE COMPOUND LAYOUT KEY: 1. 50 KVA GENERATOR 2M X 2M

- 2. TOILET BLOCK 6M X 2M
- 3. DRY/CHANGE ROOM 6M X 2M 4. CANTEEN 6M X 2M
- 5. OFFICE 6M X 2M
- 6. OFFICE 6M X 2M 7. 21 TON TRACKED 360 EXCAVATOR
- 8. DRILL PIPE STORAGE 10M X 2M
- 9. HDD DRILL RIG 16M X 2M 10. POWER PACK 6M X 2M
- 11. CONTROL CABIN 6M X 2M
- 12. MUD LAB 3M X 2M
- 13. MUD ENTRY PIT 3M X 4M 14. HIGH PRESSURE MUD PUMP 6M X 2M
- 15. MUD MIXING TANK 7M X 2M
- 16. 350 KVA GENERATOR 5M X 2M
- 17. RECYCLING UNIT 6M X 2M 18. WATER STORAGE TANK 6M X 2M
- 19. DRY DRILLING FLUID STORAGE 4M X 10M
- 20. WORKSHOP 6M X 2M 21. STORES 6M X 2M

| II FRACOMBE T | DE GAUGE SITE |
|---------------------------|------------------------------|
| TIDE LEVELS | ORDNANCE DATUM NEWLYN (mAOD) |
| HIGHEST ASTRONOMICAL TIDE | 5.46 |
| MEAN HIGH WATER SPRINGS | 4.47 |
| MEAN HIGH WATER NEAPS | 2.19 |
| MEAN LOW WATER NEAPS | -1.69 |
| MEAN LOW WATER SPRINGS | -3.94 |
| LOWEST ASTRONOMICAL TIDE | -4.89 |

| GEOLOGY |
|-----------|
| BLOWN SA |
| DRIFT DEF |
| ESTUARIN |
| ROCK |
| |

| GEOLOGY KEY | |
|--------------------------|--|
| BLOWN SANDS (SAND DUNES) | |
| DRIFT DEPOSITS | |
| ESTUARINE DEPOSITS | |
| BOCK | |

1:2000 0 20m 40m 60m 80m 100m 120m 140m 160m 180m 200m

1:1 0 10 20 30 40 50 60 70 80 90 100

| RIVER TAW OUTLINE HDD PLAN AND PROFILE | | | | | | | |
|---|--|-----------------|-------------|--------------|------------|--|--|
| Client | FLC | DTATION | ENERG | Y LTD | | | |
| 1 | a |) w | ater | man | 1 | | |
| 5 | | | K 1 | | N | | |
| Broxden House | Broxden House Broxden Business Park Lamberkine Drive Perth PH1 1RA t: 01738 449 801 mail@watermangroup.com www.watermangroup.com | | | | | | |
| Suitability | OR F | PLANNIN | IG SUB | MISSION | | | |
| Designed By | LP | Director | CG | Waterman Ref | E12731-135 | | |
| Drawn By | LP | Date | 20.05.22 | Scales @ A0 | AS NOTED | | |
| Stockton Checker | | Stockton Approv | er | Date | | | |
| Project - Origir | nator - | Volume - Level | - Type - Ro | e - Number | Revision | | |
| 12731-1 | 12731-135-WIF-77-XX-M3-C-91003 P03 | | | | | | |


P0311.08.23SITE COMPOUND LAYOUTS REMOVED. RE-ISSUED FOR
INFORMATION AS PART OF PLANNING SUBMISSIONP0210.03.23TITLE UPDATED & DRAFT BANNER REMOVED

2 DRAFT ISSUE FOR INFORMATION ONLY


Amendments

WHITE CROSS FLOATING WINDFARM

A01 A1







TYPICAL ROW SECTION - 30m WIDTH

TYPICAL ROW SECTION SHOWING ROW ARRANGEMENT WITH CABLE SPACING @ MINIMUM 5m.

| | GENERAL NOTES |
|-------------------------------|--|
| 1. | |
| 2. | ALL DIMENSIONS AND LEVELS ARE TO BE CHECKED ON SITE THE CONTRACTOR PRIOR TO PREPARING ANY WORKING DRAWINGS OR COMMENCING ON SITE. |
| 3. | THE CONTRACTOR MUST ENSURE AND WILL BE HELD RESPONSIBLE FOR THE OVERALL STABILITY OF THE |
| 4. | BUILDING/STRUCTURE/EXCAVATION AT ALL STAGES OF THE WORK. ALL WORK BY THE CONTRACTOR MUST BE CARRIED OUT IN |
| 5. | SUCH A WAY THAT ALL REQUIREMENTS UNDER THE HEALTH SAFETY AT WORK ACT ARE SATISFIED. ALL WORK IS TO BE CARRIED OUT IN COMPLIANCE WITH TH |
| | REQUIREMENTS OF THE RELEVANT STATUTORY AUTHORITI AND REGULATIONS. |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| P03 | RE-ISSUED FOR INFORMATION |
| P02 P0 ² | 3 15.08.23 RE-ISSUED FOR INFORMATION LP 2 11.08.23 CONSTRUCTION STRIP WIDTH REDUCED. RE-ISSUED FOR INFORMATION LP 1 19.06.23 ISSUED FOR INFORMATION LP |
| P02 P0 ⁻ Rev | 3 15.08.23 RE-ISSUED FOR INFORMATION LP 2 11.08.23 CONSTRUCTION STRIP WIDTH REDUCED. RE-ISSUED FOR INFORMATION LP 1 19.06.23 ISSUED FOR INFORMATION LP 7 Date Description By Amendments |
| P02 P01 Rev | 3 15.08.23 RE-ISSUED FOR INFORMATION LP 2 11.08.23 CONSTRUCTION STRIP WIDTH REDUCED. RE-ISSUED FOR INFORMATION LP 1 19.06.23 ISSUED FOR INFORMATION LP 0 Date Description By Amendments |
| P02 P0' Rev Proj | 3 15.08.23 RE-ISSUED FOR INFORMATION LP 2 11.08.23 CONSTRUCTION STRIP WIDTH REDUCED. RE-ISSUED FOR INFORMATION LP 1 19.06.23 ISSUED FOR INFORMATION LP 0 Date Description By Amendments ect WHITE CROSS FLOATING WINDFARM |
| P02 P0 Rev | 3 15.08.23 RE-ISSUED FOR INFORMATION LP 2 11.08.23 CONSTRUCTION STRIP WIDTH REDUCED. RE-ISSUED FOR INFORMATION LP 1 19.06.23 ISSUED FOR INFORMATION LP 0 Date Description By Amendments ect WHITE CROSS FLOATING WINDFARM |
| P02 P0 ⁻ Rev | 3 15.08.23 RE-ISSUED FOR INFORMATION LP 2 11.08.23 CONSTRUCTION STRIP WIDTH REDUCED. RE-ISSUED FOR INFORMATION LP 1 19.06.23 ISSUED FOR INFORMATION LP 0 Date Description By Amendments ect ONSHORE CABLE ROUTE - TYPICAL CONSTRUCTION STR CROSS SECTION |
| P02 P07 Rev | 3 15.08.23 RE-ISSUED FOR INFORMATION LP 2 11.08.23 CONSTRUCTION STRIP WIDTH REDUCED. RE-ISSUED LP 1 19.06.23 ISSUED FOR INFORMATION LP 4 Date Description By Amendments ect ONSHORE CABLE ROUTE - TYPICAL CONSTRUCTION STR PROSS SECTION nt FLOTATION ENERGY LTD |
| P02 P07 Rev | 3 15.08.23 RE-ISSUED FOR INFORMATION LP 2 11.08.23 CONSTRUCTION STRIP WIDTH REDUCED. RE-ISSUED FOR INFORMATION LP 1 19.06.23 ISSUED FOR INFORMATION LP d Date Description By Amendments ect WHITE CROSS FLOATING WINDFARM ONSHORE CABLE ROUTE - TYPICAL CONSTRUCTION STR CROSS SECTION on FLOATION ENERGY LTD |
| P02 P0' Rev Proj | 3 15.08.23 RE-ISSUED FOR INFORMATION LP 2 11.08.23 CONSTRUCTION STRIP WIDTH REDUCED. RE-ISSUED LP 1 19.06.23 ISSUED FOR INFORMATION LP 4 Date Description By Amendments CONSHORE CABLE ROUTE - ONSHORE CABLE ROUTE - CONSHORE CABLE ROUTE - ONSHORE CABLE ROUTE - CONSTRUCTION STRUCTION ENERGY LTD Int FLOTATION ENERGY LTD |
| P02 P0' Rev Proj | 15:08:23 RE-ISSUED FOR INFORMATION LP 2 11:08:23 CONSTRUCTION STRIP WIDTH REDUCED. RE-ISSUED FOR INFORMATION LP 1 19:06:23 ISSUED FOR INFORMATION LP / Date Description By Amendments ect WHITE CROSS FLOATING WINDFARM ONSHORE CABLE ROUTE - TYPICAL CONSTRUCTION STRE CROSS SECTION of CONSTRUCTION STRE CROSS SECTION of Construction Energy LTD |
| P02 P0' Rev Proj | 15.08.23 RE-ISSUED FOR INFORMATION LP 2 11.08.23 CONSTRUCTION STRIP WIDTH REDUCED. RE-ISSUED FOR INFORMATION LP 1 19.06.23 ISSUED FOR INFORMATION LP 4 Date Description By Amendments ed ONSHORE CABLE ROUTE - TYPICAL CONSTRUCTION STR CROSS SECTION ONSHORE CABLE ROUTE - TYPICAL CONSTRUCTION STR CROSS SECTION Int FLOTATION ENERGY LTD Total construction energy LTD ONSHORE CABLE ROUTE - TYPICAL CONSTRUCTION STR CROSS SECTION ONSHORE CABLE ROUTE - TYPICAL CONSTRUCTION ENERGY LTD ONSTOCKCOON ONSTOCKCOON ONSTOCKCOON ONSTOCKCOON ONSTOCKCOON ONSTOCKCOON ONSTOCKCOON ONTO NOT NOT NOT NOT NOT NOT NOT NOT NOT |
| P02 P07 Rev Proj | 15:08:23 RE-ISSUED FOR INFORMATION LP 2 11:08:23 CONSTRUCTION STRIP WIDTH REDUCED. RE-ISSUED FOR INFORMATION LP 1 19:06:23 ISSUED FOR INFORMATION LP 4 Date Description By Amendments ed ONSHORE CABLE ROUTE - TYPICAL CONSTRUCTION STRE CROSS SECTION TONSHORE CABLE ROUTE - TYPICAL CONSTRUCTION STRE CROSS SECTION TONSHORE CABLE ROUTE - TYPICAL CONSTRUCTION STRE CROSS SECTION TONSHORE CABLE ROUTE - TYPICAL CONSTRUCTION STRE CROSS SECTION TOTATION ENERGY LTD Totation Energy LT2 TOTATION ENERGY LTD Totation Energy LT2 Totation Energy LT2 |
| Br Br Des Des Des | 15.08.23 RE-ASSUED FOR INFORMATION LP 2 11.08.23 CONSTRUCTION STRIP WIDTH REDUCED. RE-ISSUED FOR INFORMATION LP 1 19.06.23 ISSUED FOR INFORMATION LP 4 Date Description By Amendments ect WHITE CROSS FLOATING WINDFARM ONSHORE CABLE ROUTE - TYPICAL CONSTRUCTION STR CROSS SECTION TOTATION ENERGY LTD TOTATION ENERGY LTD TOTATION ENERGY LTD TotAL CONSTRUCTION STR CROSS SECTION TOTATION ENERGY LTD TOTATION TOTATION TOTATION TOT |



White Cross Offshore Windfarm Environmental Statement

Appendix 5.E: Onshore Substation Indicative Designs



Index of Figures

Figure 5.E 1: Floor Plan: Indicative GIS Enclosed Substation With Additional Equipment Space (Option A) (FLO-WHI-LAY-0005)

Figure 5.E 2: Elevation & Cross Section Drawing: Indicative GIS Enclosed Substation With Additional Equipment Space (Option A) (FLO-WHI-LAY-0006)

Figure 5.E 3: Layout Plan: Indicative GIS Enclosed Substation With Additional Equipment Space (Option A) (FLO-WHI-LAY-0007)

Figure 5.E 4: Floor Plan: Indicative AIS Enclosed Substation (Option B) (FLO-WHI-LAY-0001)

Figure 5.E 5: Elevation & Cross Section Drawing: Indicative AIS Enclosed Substation (Option B) (FLO-WHI-LAY-0002)


Figure 5.E 6: Layout Plan: Indicative AIS Enclosed Substation (Option B) (FLO-WHI-LAY-0003)

Figure 5.E 7: Floor Plan: Indicative AIS Enclosed Substation With Additional Equipment Space (Option C) (FLO-WHI-LAY-0009)


Figure 5.E 8: Elevation & Cross Section Drawing: Indicative AIS Enclosed Substation With Additional Equipment Space (Option C) (FLO-WHI-LAY-0010)

Figure 5.E 9: Layout Plan: Indicative AIS Enclosed Substation With Additional Equipment Space (Option C) (FLO-WHI-LAY-0011)






| NOT | | | | | | | |
|---|--|---|---|---|--|--|--|
| | TES | | | | | | |
| 1. | LAYOUT OF CONTROL BUILD SWITCHYARD CAN BE MODI ACCESS, TEE LINE OUTPUT PHILOSOPHY MUST BE KEPT | FIED T | to Ai | | | | |
| 2. | LAYOUT OF WATER TANK AND SEALED TANK MUST BE ADAPTED ACCORDING TO APPLICABLE LEGISLATION. | | | | | | |
| 3. | NUMBER OF CAPACITOR BA PERFORMANCE ENGINEERIN CALCULATION. | | | | | | |
| 4. | SPOTLIGHT PROJECTORS S ONLY FOR PLANNING PURPO AND LOCATIONS WILL DEPE | OSES. | FINA | L NUI | MBER | | |
| 5. | AUXILIARY SERVICE TRANSI TERMINALS SHALL BE OUTD TERMINAL. | | | | NGLE | | |
| 6. | PALISADE SECURITY GATE & PERIMETER OF SITE. | & FEN | CING | AROl | JND | | |
| 7. | MV CABLES TO BE PULLED 1 UNDER EAST SIDE OF CONT MV SWITCHGEAR ROOM. | | | | | | |
| 8. | EXPORT CABLES TO BE PUL LAID UNDER WEST SIDE OF TO EXPORT PYLON. | | | | | | |
| 9. | LAYOUT OF METERING ROO ACCORDING TO UTILITY REC | | | | TED | | |
| 10. | FOR SECTION A-A DETAILS F 808165-01-EL-LAY-0001-011 | REFER | R TO I | ORAW | /ING | | |
| | 0 5m 10m Scale 1:500 @ | 0 <u>5m 10m 15m 20</u> m Scale 1:500 @ A3 | | | | | |
| FLOATATION DRAWING NUMBER FLO-WHI-LAY-0005 | | | | | | | |
| | | NG N | | BER | | | |
| F | | NG N | | BER | | | |
| | FLO-WHI-LAY | NG N -000 | 5 aw | AW | 10.08.23 | | |
| E | FLO-WHI-LAY | NG N -000 | AW AW | AW AW | 10.08.23 06.07.23 | | |
| E | FLO-WHI-LAY | PMcG PMcG PMcG | AW AW MS | AW AW AW | 10.08.23 06.07.23 01.06.23 | | |
| E | FLO-WHI-LAY | NG N -000 | AW AW | AW AW | 10.08.23 06.07.23 | | |
| E | FLO-WHI-LAY | PMcG PMcG PMcG | AW AW MS | AW AW AW | 10.08.23 06.07.23 01.06.23 | | |
| E D C | FLO-WHI-LAY | PMcG PMcG PMcG PMcG PMcG | AW AW MS MS | AW AW AW | 10.08.23 06.07.23 01.06.23 05.05.23 | | |
| E D C B | FLO-WHI-LAY | PMcG PMcG PMcG PMcG PMcG PMcG | 5 AW AW MS MS | AW AW AW AW | 10.08.23 06.07.23 01.06.23 05.05.23 14.04.23 | | |
| E D C B A Rev | FLO-WHI-LAY | PMcG PMcG PMcG PMcG PMcG PMcG PMcG By | AW AW MS MS MS Chićd | AW AW AW AW AW | 10.08.23 06.07.23 01.06.23 05.05.23 14.04.23 28.03.23 | | |
| E D C B A Rev Job Ti | FLO-WHI-LAY | PMcG PMcG PMcG PMcG PMcG PMcG PMcG By DSSS NDF | AW AW MS MS MS Chićd | AW AW AW AW AW | 10.08.23 06.07.23 01.06.23 05.05.23 14.04.23 28.03.23 | | |
| E D C B A Rev Job Ti | FLO-WHI-LAY | PMcG PMcG PMcG PMcG PMcG PMcG PMcG PMcG | AW AW MS MS Chkd | AW AW AW AW AW Appid | 10.08.23 06.07.23 01.06.23 05.05.23 14.04.23 28.03.23 | | |
| E D C B A Rev Job Ti | FLO-WHI-LAY | PMcG PMcG PMcG PMcG PMcG PMcG PMcG PMcG | AW AW MS MS Chkd | AW AW AW AW AW Appid | 10.08.23 06.07.23 01.06.23 05.05.23 14.04.23 28.03.23 | | |
| E D C B A Rev Job Ti | FLO-WHI-LAY | PMcG PMcG PMcG PMcG PMcG PMcG PMcG PMcG | AW AW MS MS MS MS Chicd | AW AW AW AW AW Appid | 10.08.23 06.07.23 01.06.23 05.05.23 14.04.23 28.03.23 | | |
| E D C B A Rev Job Ti | FLO-WHI-LAY | PMcG PMcG PMcG PMcG PMcG PMcG PMcG By DSSS NDF AN GIS STA A) | AW AW MS MS MS Chird Silasgo | AW AW AW AW AW AW App'd N | 10.08.23 06.07.23 01.06.23 05.06.23 14.04.23 2803.23 Date | | |
| E D C B A Rev Job Ti | FLO-WHI-LAY | PMcG PMcG PMcG PMcG PMcG PMcG By DSSS NDF AN GIS STATA A) | AW AW MS MS MS Chicd | AW AW AW AW AW AW AW AW AW AW AW APP'd W N | 10.08.23 06.07.23 01.06.23 05.05.23 14.04.23 2803.23 Date | | |
| E D C B A Rev Job Ti Drg Tit | FLO-WHI-LAY | PMcG PMcG PMcG PMcG PMcG PMcG PMcG PMcG | AW AW MS MS MS Chicd | AW AW AW AW AW AW AW AW AW AW AW APP'd W N | 10.08.23 06.07.23 01.06.23 05.06.23 14.04.23 2803.23 Date | | |
| E D C B A Rev Job Ti | FLO-WHI-LAY DRAWING SCALE DANAGED TO 1500. NORTH ARROW & SCALE DANAGORD. BULDING SCESS STEPS AND BARPS ACCED. CENTER SAME ACCE. CENTER SAME ACCE. SUBSTATION SZE AMENDED. CONTROL BULDING FELCOATED. ACCESS ROADS & FENCELINES AMENDED. ISSUED FOR REVIEW Description ISSUED FOR REVIEW DESCRIPTION INDICATIVE ENCLOSED SUBS: (OPTION ISSUED FOR PL INDICATIVE ENCLOSED SUBS: (OPTION ISSUED FOR MENDED. ISSUED FOR PL | PMcG PMcG PMcG PMcG PMcG PMcG PMcG By PMcG By PMcG By PMcG CSSS NDF | AW AW MS MS MS Chird Chi | AW AW AW AW AW AW AW AW AW AW AW APP'd W N | 10.08.23 06.07.23 01.06.23 05.05.23 14.04.23 28.03.23 Date | | |





- 2. PALISADE SECURITY GATE & FENCING AROUND PERIMETER OF SITE.
- 3. AIR CONDITIONING VENTS SHOWN ARE INDICATIVE ONLY FOR PLANNING PURPOSES. FINAL NUMBER AND LOCATIONS WILL DEPEND ON FINAL BUILDING DESIGNS.
- SPOTLIGHT PROJECTORS SHOWN ARE INDICATIVE ONLY FOR PLANNING PURPOSES. FINAL NUMBER AND LOCATIONS WILL DEPEND ON FINAL DESIGN.


| 0 | 5m 10m | 15r | n | 20 | Эm | |
|----------------|---|--------------------|----------|-------|---------------|--|
| Ĩ | Scale 1:500 @ | | | | 1 | |
| | FLOATATION DRAWIN | JG N | LIM | RER | | |
| | FLO-WHI-LAY- | | | | - | |
| | | | | | | |
| G | KEY PLAN ROTATED 180 DEG. PROFILES VIEWS RENAMED. FINISHED GROUND LEVEL ADDED. | PMcG | AW | AW | 31.08.23 | |
| F | PINISHED GROUND LEVEL ADDED. DRAWING SCALE CHANGED TO 1:500. NORTH ARROW & SCALE BAR ADDED. | PMcG | AW | AW | 10.08.23 | |
| Е | PROFILE VIEWS 1, 2, 3 & 4 ADDED. SECTION A-A AMENDED. | PMcG | AW | AW | 06.07.23 | |
| D | CONTROL BUILDING HEIGHTS ADDED. | PMcG | MS | AW | 01.06.23 | |
| С | SUBSTATION RE-SIZED. CONTROL BUILDING RELOCATED. ACCESS ROADS & FENCELINES AMENDED. | PMcG | MS | AW | 05.05.23 | |
| В | SUBSTATION & CONTROL BUILDING LAYOUTS AMENDED. FLOTATION DRAWING NUMBER ADDED. | PMcG | MS | AW | 02.05.23 | |
| A | ISSUED FOR REVIEW | PMcG | MS | AW | 27.03.23 | |
| Rev Job Tit | Description | By | Chk'd | App'd | Date | |
| Drg Titl | | NDF | ARI | | | |
| | ELEVATION & CROSS SECTION DRAWING INDICATIVE GIS ENCLOSED SUBSTATION (OPTION A) | | | | | |
| | WOO |)(| 5 | • | | |
| s | t Vincent Plaza, 319 St Vincent St tel: +44 (0) 141 227 1700 ww | reet, G /w.wo | odplo | .com | 5LP | |
| Scale Drawn | 1:500 Date MM PMcG MS Appro | ARCH 2 ved A | 023 W | Size | 43 | |
| Status | PRELIMIN | AR | Y | | | |
| Drawir | ^{19 No.} 808165-01-EL-LAY-0 | 001- | 011 | | Revision G | |
| | | | | | | |




P:\6000\2022_Tasks\808165_Whitecross\808165-01-EL-LAY-0001-012-G.dwg


| U | KEY | <u> </u> | | | | |
|--|--|--|---|---|---|--|
| 248400E | | | | | | |
| 54 | | PROJECT RED | LINE | BO | UND | ARY |
| 132400N | | PERMANENT A | CCF | SS F | ROAF | , I |
| DA. | | | | 20 F | . UI 16 | · |
| | | | | | | |
| | | PROPOSED SU | IBST | ATIC | N | |
| | = | | | | | |
| | | | | וחדי | | |
| | | | UNS | NRU | | JN |
| | | | | | | |
| | | TEMPORARY C | ON.S | STRI | СТІС | л Г |
| | | ACCESS ROAD | | | | |
| THE REPORT | 1 | | | | | |
| | ≡ : | $\equiv :=$ EXISTING OVE | RHE | AD C | ABL | ES |
| | | | | | | |
| | | INDICATIVE BU | FFE | R SL | OPE | |
| | \vdash | | | | | |
| and the second sec | 1 | | | | | |
| | 1 | PROPOSED SUBS | | ON | | |
| | 1 | COORDINAT | - | | | |
| | 1 | | ORT | | | |
| | 1 | | 3219 | | | |
| | 1 | P2 248217.70E 1 | | | | |
| | 1 | | 3209 | | | |
| | 1 | P4 248111.20E 1 | 3214 | U.571 | N | |
| | ⊢ | <u> </u> | | | | |
| 132200N | 1 | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | 1 | | | | | |
| | 1 | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | 1 | 0 20m 40m 6 | 0m | 80 | m | 100m |
| | | | ÷ | | | |
| | | 0 1 1 0 | | | | |
| | | Scale 1:2500 | @ A3 | | | |
| | | [| | | | |
| | | FLOATATION DRAWIN | NG N | | BER | |
| | | [| NG N | | BER | 2 |
| | | FLOATATION DRAWIN FLO-WHI-LAY- | NG N | | BER | |
| | G | FLOATATION DRAWIN FLO-WHI-LAY- | NG N 0007 | 7 | | 10.08.23 |
| | G | FLOATATION DRAWIN FLO-WHI-LAY- | NG N 000 | 7 aw | AW | 10.08.23 |
| | G | FLOATATION DRAWIN FLO-WHI-LAY- SOLE BAR ACCED RED LINE STE BOUNDARY AMENDED. | NG N 000 PMcG PMcG | AW AW | AW AW | 10.08.23 03.08.23 |
| | G F E | FLOATATION DRAWII FLO-WHI-LAY- | NG N 000 | 7 aw | AW | 10.08.23 |
| | | FLOATATION DRAWIN FLO-WHI-LAY- SOLE BAR ADED RED LINE SITE BOUNDARY AMENDED. RED LINE SITE BOUNDARY AMENDED. | NG N 000 PMcG PMcG | AW AW | AW AW | 10.08.23 03.08.23 |
| 132000N | E | FLOATATION DRAWIN FLO-WHI-LAY- SOLE BUR ACCED RED LIKE STIE BOURDARY ADEXED. RED LIKE STIE BOURDARY ADEXED. RED LIKE STIE BOURDARY ADEXED. URINEL URI | NG N 0000 PMcG PMcG PMcG PMcG | AW AW AW AW | AW AW AW | 10.08.23 03.08.23 11.07.23 04.07.23 |
| 132000N | E | FLOATATION DRAWIN FLO-WHI-LAY- SOLE SWA ADDED RED LINE SITE BOURDARY AMENDED. RED LINE SITE BOURDARY AMENDED. SUBSTATION RECEIPE AND DORBOTATES UPDATE. SUBSTATION ACCESS ROAD THE AN AMENDED. LAYOUT AND ORDINITATION CHANNEED AND RELOCATED. SLOPE ZONE ADDED. | PMcG PMcG PMcG | AW AW AW | AW AW AW | 10.08.23 03.08.23 11.07.23 |
| 13200N | E | FLOATATION DRAWIN FLO-WHI-LAY- SOLE SUR ACCED RED LINE SITE BOURDARY AMENDED. RED LINE SITE BOURDARY AMENDED. SUBSTATION RACCESS ROAD THE AN AMENDED. LUXOUT AND ORIENTATION CHANNEED AND RELOCATED. SUBSTATION A SUBSTATION A SUBSTATION A SUBSTATION RACCESS ROAD THE AN AMENDED. SUBSTATION A SUBSTATION CHANNEED AND RELOCATED. SUBSTATION A SUBMED SA RELOCATAED. SUBSTATION A SUBMED SA RELOCATAED. | NG N 0000 PMcG PMcG PMcG PMcG | AW AW AW AW | AW AW AW | 10.08.23 03.08.23 11.07.23 04.07.23 |
| 13200N | E D C B | FLOATATION DRAWIN FLO-WHI-LAY- SOLE BAR ACED RED LINE SITE BOURDARY AMENGED. RED LINE SITE BOURDARY AMENGED. SUBSTATION ACCESS ROAD TIE-IN AMENGED. LINGTATION ACCESS ROAD TIE-IN AMENGED. LINGTATION ORIENTATION CHANGED AND RELOCATED. SUBSTATION A TEMP CONSTRUCTION COMPOUND AMENDED & RELOCATAED. FLOATATION DRAWING NUMBER ADDED. | PMcG PMcG PMcG PMcG PMcG PMcG | AW AW AW AW MS MS | AW AW AW AW AW | 10.08.23 03.08.23 11.07.23 04.07.23 18.05.23 14.04.23 |
| 13200N | E D C B | FLOATATION DRAWIN FLO-WHI-LAY- SOLE BUR ACCED RED LIKE STEE GOLRAMY ADEXED. RED LIKE STEE GOLRAMY ADEXED. RED LIKE STEE GOLRAMY ADEXED. SUBSTATION ACCESS ROAD TE: AN AMENGED. LIXOVIT AND ORIENTATION CHANGED AND RELOCATED. SUBSTATION ACCESS ROAD TE: AN AMENGED. SUBSTATION A TEMP CONSTRUCTION COMPOUND ADMENDED & RELOCATAED. FLOATATION DRAWING MUMBER ADDED. ISSUED FOR REVIEW | PMcG PMcG PMcG PMcG PMcG PMcG PMcG PMcG | AW AW AW AW MS MS | AW AW AW AW AW | 10.08.23 03.08.23 11.07.23 04.07.23 18.05.23 14.04.23 27.03.23 |
| 13200N | E D C B A Rev | FLOATATION DRAWII FLO-WHI-LAY- FLO-WHI-LAY- FLO-WHI-LAY- RED LHE STE BOUNDARY AMENDED. RED LHE STE BOUNDARY AMENDED. RED LHE STE BOUNDARY AMENDED. SUBSTATION RECORTE AND COMMANTES UPATED. SUBSTATION RECORTE AND COMMANTES SUBSTATION RECORTE ON ADMINISTRATION SUBSTATION AND REPROVING NUMBER ADDED. FLOATATION DAMING NUMBER ADDED. SUBSTATION AT THE CONSTRUCTION COMPOUND AND REMO CONSTRUCTION SUBSTATION AND REMO CONSTRUCTION SUBSTATION AND REMO CONSTRUCTION SUBSTATION ADMINISTRATION SUBJECT AND REMOVED SUBSTATION SUBJECT AND COMPOUND SUBJECT AND REMOVED SUBSTATION ADDED SATURATION SUBJECT AND REMOVED SUBSTATION ADDITION SUBJECT AND COMPOUND SUBJECT AND REMOVED SUBSTATION ADDITION SUBJECT AND REMOVED AND REMOVED SUBSTATION ADDITION SUBJECT AND COMPOUND SUBJECT AND REMOVED SUBSTATION ADDITION SUBJECT AND COMPOUND SUBJECT AN | PMcG PMcG PMcG PMcG PMcG PMcG | AW AW AW AW MS MS | AW AW AW AW AW | 10.08.23 03.08.23 11.07.23 04.07.23 18.05.23 14.04.23 |
| 13200N | E D C B | FLOATATION DRAWII FLO-WHI-LAY- FLO-WHI-LAY- FLO-WHI-LAY- RED LHE STE BOUNDARY AMENDED. RED LHE STE BOUNDARY AMENDED. RED LHE STE BOUNDARY AMENDED. SUBSTATION RECORTE AND COMMANTES UPATED. SUBSTATION RECORTE AND COMMANTES SUBSTATION RECORTE ON ADMINISTRATION SUBSTATION AND REPROVING NUMBER ADDED. FLOATATION DAMING NUMBER ADDED. SUBSTATION AT THE CONSTRUCTION COMPOUND AND REMO CONSTRUCTION SUBSTATION AND REMO CONSTRUCTION SUBSTATION AND REMO CONSTRUCTION SUBSTATION ADMINISTRATION SUBJECT AND REMOVED SUBSTATION SUBJECT AND COMPOUND SUBJECT AND REMOVED SUBSTATION ADDED SATURATION SUBJECT AND REMOVED SUBSTATION ADDITION SUBJECT AND COMPOUND SUBJECT AND REMOVED SUBSTATION ADDITION SUBJECT AND REMOVED AND REMOVED SUBSTATION ADDITION SUBJECT AND COMPOUND SUBJECT AND REMOVED SUBSTATION ADDITION SUBJECT AND COMPOUND SUBJECT AN | PMcG PMcG PMcG PMcG PMcG PMcG PMcG PMcG | AW AW AW AW MS MS | AW AW AW AW AW | 10.08.23 03.08.23 11.07.23 04.07.23 18.05.23 14.04.23 27.03.23 |
| 13200N | E D C B A Rev | FLOATATION DRAWIN FLO-WHI-LAY- SOLE BR AGED SOLE BR AGED RED LIRE STE BOUNDARY AMENGED. RED LIRE STE BOUNDARY AMENGED. BUBSTATION ACCESS ROAD TE AN AMENGED. LAYOUT AND ORIENTATION CHANGED AND REL CATE DOME ADDED SLOPE ZOME ADDE | PMcG PMcG PMcG PMcG PMcG PMcG PMcG By | AW AW AW AW MS MS Chk/d | AW AW AW AW AW | 10.08.23 03.08.23 11.07.23 04.07.23 18.05.23 14.04.23 27.03.23 |
| 13200N | E D C B A Rev | FLOATATION DRAWIN FLO-WHI-LAY- SCILE BAR ACCED RED LINE STE BOUNDARY AMENDED. RED LINE STE BOUNDARY AMENDED. RED LINE STE BOUNDARY AMENDED. SUBSTATION ACCESS ROAD TE: IN AMENDED. SUBSTATION AND CORENTATION CHANGED AND RELOCATED. SLOPE ZOME ADDED. SUBSTATION AND CORENTATION CHANGED AND RELOCATED. SLOPE ZOME ADDED. SUBSTATION AND CORENTATION CHANGED AND COMPOUND AMENDED & RELOCATAED. FLOATATION DRAWING NUMBER ADDED. SUBSTATION AREVEW Description Te | PMcG PMcG PMcG PMcG PMcG PMcG PMcG By | AW AW AW MS MS Chkd | AW AW AW AW AW AW | 10.08.23 03.08.23 11.07.23 04.07.23 18.05.23 14.04.23 27.03.23 |
| LI3200N | E D C B A Rev | FLOATATION DRAWIN FLO-WHI-LAY- SOLE BR AGED SOLE BR AGED RED LIRE STE BOUNDARY AMENGED. RED LIRE STE BOUNDARY AMENGED. BUBSTATION ACCESS ROAD TE AN AMENGED. LAYOUT AND ORIENTATION CHANGED AND REL CATE DOME ADDED SLOPE ZOME ADDE | PMcG PMcG PMcG PMcG PMcG PMcG PMcG By | AW AW AW MS MS Chkd | AW AW AW AW AW AW | 10.08.23 03.08.23 11.07.23 04.07.23 18.05.23 14.04.23 27.03.23 |
| 132000 | E D C B A Rev | FLOATATION DRAWIN FLO-WHI-LAY- SCILE BAR ACCED RED LINE STE BOUNDARY AMENDED. RED LINE STE BOUNDARY AMENDED. RED LINE STE BOUNDARY AMENDED. SUBSTATION ACCESS ROAD TE: IN AMENDED. SUBSTATION AND CORENTATION CHANGED AND RELOCATED. SLOPE ZOME ADDED. SUBSTATION AND CORENTATION CHANGED AND RELOCATED. SLOPE ZOME ADDED. SUBSTATION AND CORENTATION CHANGED AND COMPOUND AMENDED & RELOCATAED. FLOATATION DRAWING NUMBER ADDED. SUBSTATION AREVEW Description Te | PMcG PMcG PMcG PMcG PMcG PMcG PMcG By | AW AW AW MS MS Chkd | AW AW AW AW AW AW | 10.08.23 03.08.23 11.07.23 04.07.23 18.05.23 14.04.23 27.03.23 |
| 13200N | E D C B A Rev Job Ti | FLOATATION DRAWIN FLO-WHI-LAY- REVARENCED SOLE BUR ADDED WED LIKE STE BOUNDARY AMENDED. RED LIKE STE BOUNDARY AMENDED. RED LIKE STE BOUNDARY AMENDED. SUBSTATION RELOCATED AND COORDINATES UNATED. SUBSTATION AT THAN CONSTRUCTION COMPOUND AMENDED. SUBSTATION A TEMP CONSTRUCTION COMPOUND AMENDED. SUBSTATION AM | PMcG PMcG PMcG PMcG PMcG PMcG PMcG By | AW AW AW MS MS Chkd | AW AW AW AW AW AW | 10.08.23 03.08.23 11.07.23 04.07.23 18.05.23 14.04.23 27.03.23 |
| | E D C B A Rev | FLOATATION DRAWII FLO-WHI-LAY- FLO-WHI-LAY- SILE BOUNDARY AMENDED. RED LINE STEE BOUNDARY AMENDED. RED LINE STEE BOUNDARY AMENDED. SUBSTATION ACCESS ROAD TE-BI AMENDED. LAYOUT AND ORIENTATION CHANNED AND RELOCATED. SLOPE ZOME ADDED. SLOPE ZOME AD | MG N 0000 PMcG PMcG PMcG PMcG PMcG PMcG By | AW AW AW MS MS Chkd | AW AW AW AW AW AW | 10.08.23 03.08.23 11.07.23 04.07.23 18.05.23 14.04.23 27.03.23 |
| | E D C B A Rev Job Ti | FLOATATION DRAWII FLO-WHI-LAY- FLO-WHI-LAY- REVARENCED SOLE BAR ACCED RED LIKE STEE BOUNDARY AMENGED. RED LIKE STEE BOUNDARY AMENGED. RED LIKE STEE BOUNDARY AMENGED. SUBSTATION ACCESS ROAD TE-RI AMENGED. INSERTATION ACCESS ROAD TE-RI AMENGED. SLOPE ZOME ADDED SLOPE ZOME ADDED S | NG N 00007 PMcG PMcG PMcG PMcG PMcG PMcG PMcG PMcG | AW AW AW MS MS Chird | AW AW AW AW AW AW | 10.08.23 03.08.23 11.07.23 04.07.23 18.05.23 14.04.23 27.03.23 Date |
| | E D C B A Rev Job Ti | FLOATATION DRAWIN FLO-WHI-LAY- FLO-WHI-LAY- REVARENCED SOLE BUT ACCED HED LIKE STRE BUTWARENCED. RED LIKE STRE BUTWARENCED. RED LIKE STRE BUTWARENCED. SUBSTATION RELOCATED AND CORENATES UNATED. SUBSTATION AT THE CONSTRUCTION COMPOUND ALEMPEOS & RELOCATAGE LOCATATION BUTWARENCED. SUBSTATION A TEMP CONSTRUCTION COMPOUND ALEMPEOS & RELOCATAGE SUBSTATION A TEMP CONSTRUCTION SUBSTATION A TEMP CO | NG N 00001 PMcG PMcG PMcG PMcG PMcG PMcG By DSSS NDF | AW AW AW MS MS Chird | AW AW AW AW AW AW | 10.08.23 03.08.23 11.07.23 04.07.23 18.05.23 14.04.23 27.03.23 Date |
| | E D C B A Rev Job Ti | FLOATATION DRAWII FLO-WHI-LAY- FLO-WHI-LAY- REVARENCED SOLE BAR ACCED RED LIKE STEE BOUNDARY AMENGED. RED LIKE STEE BOUNDARY AMENGED. RED LIKE STEE BOUNDARY AMENGED. SUBSTATION ACCESS ROAD TE-RI AMENGED. INSERTATION ACCESS ROAD TE-RI AMENGED. SLOPE ZOME ADDED SLOPE ZOME ADDED S | NG N 00001 PMcG PMcG PMcG PMcG PMcG PMcG By DSSS NDF | AW AW AW MS MS Chird | AW AW AW AW AW AW | 10.08.23 03.08.23 11.07.23 04.07.23 18.05.23 14.04.23 27.03.23 Date |
| | E D C B A Rev Job Ti | FLOATATION DRAWIN FLO-WHI-LAY- FLO-WHI-LAY- REVARENCED SOLE BUT ACCED HED LIKE STRE BUTWARENCED. RED LIKE STRE BUTWARENCED. RED LIKE STRE BUTWARENCED. SUBSTATION RELOCATED AND CORENATES UNATED. SUBSTATION AT THE CONSTRUCTION COMPOUND ALEMPEOS & RELOCATAGE LOCATATION BUTWARENCED. SUBSTATION A TEMP CONSTRUCTION COMPOUND ALEMPEOS & RELOCATAGE SUBSTATION A TEMP CONSTRUCTION SUBSTATION A TEMP CO | NG N 00001 PMcG PMcG PMcG PMcG PMcG PMcG By DSSS NDF | AW AW AW MS MS Chird | AW AW AW AW AW AW | 10.08.23 03.08.23 11.07.23 04.07.23 18.05.23 14.04.23 27.03.23 Date |
| | E D C B A Rev Job Ti | FLOATATION DRAWIN FLO-WHI-LAY- FLO-WHI-LAY- REVARENCED SOLE BUT ACCED HED LIKE STRE BUTWARENCED. RED LIKE STRE BUTWARENCED. RED LIKE STRE BUTWARENCED. SUBSTATION RELOCATED AND CORENATES UNATED. SUBSTATION AT THE CONSTRUCTION COMPOUND ALEMPEOS & RELOCATAGE LOCATATION BUTWARENCED. SUBSTATION A TEMP CONSTRUCTION COMPOUND ALEMPEOS & RELOCATAGE SUBSTATION A TEMP CONSTRUCTION SUBSTATION A TEMP CO | NG N 00001 PMcG PMcG PMcG PMcG PMcG PMcG By DSSS NDF | AW AW AW MS MS Chird | AW AW AW AW AW AW | 10.08.23 03.08.23 11.07.23 04.07.23 18.05.23 14.04.23 27.03.23 Date |
| | E D C B A Rev Job Ti | FLOATATION DRAWIN FLO-WHI-LAY- FLO-WHI-LAY- REVARENCED SOLE BUT ACCED HED LIKE STRE BUTWARENCED. RED LIKE STRE BUTWARENCED. RED LIKE STRE BUTWARENCED. SUBSTATION RELOCATED AND CORENATES UNATED. SUBSTATION AT THE CONSTRUCTION COMPOUND ALEMPEOS & RELOCATAGE LOCATATION BUTWARENCED. SUBSTATION A TEMP CONSTRUCTION COMPOUND ALEMPEOS & RELOCATAGE SUBSTATION A TEMP CONSTRUCTION SUBSTATION A TEMP CO | NG N 00001 PMcG PMcG PMcG PMcG PMcG PMcG By DSSS NDF | AW AW AW MS MS Chird | AW AW AW AW AW AW | 10.08.23 03.08.23 11.07.23 04.07.23 18.05.23 14.04.23 27.03.23 Date |
| | E D C B A Rev Job Ti | FLOATATION DRAWIN FLO-WHI-LAY- INF ARMED SOLE BUT ACCED RED LIKE STE BOUNDARY AMENGED. RED LIKE STE BOUNDARY AMENGED. RED LIKE STE BOUNDARY AMENGED. SUBSTATION ACCESS ROAD TE-M AMENGED. SUBSTATION ACCESS ROAD TE-M AMENGED. SLORE ZOME ADDED SLORE ZOME ADDED SLOR | NG N 0000 PMcG PMcG PMcG PMcG PMcG PMcG By DSSS NDF | AW AW AW MS MS Chkd | AW AW AW AW AW AW AW APP'd | 10.08.23 03.08.23 11.07.23 04.07.23 18.05.23 14.04.23 27.03.23 Date |
| | E D C B A Rev Job Ti | FLOATATION DRAWIN FLO-WHI-LAY- INF ARMED SOLE BUT ACCED RED LIKE STE BOUNDARY AMENGED. RED LIKE STE BOUNDARY AMENGED. RED LIKE STE BOUNDARY AMENGED. SUBSTATION ACCESS ROAD TE-M AMENGED. SUBSTATION ACCESS ROAD TE-M AMENGED. SLORE ZOME ADDED SLORE ZOME ADDED SLOR | NG N 0000 PMcG PMcG PMcG PMcG PMcG PMcG By DSSS NDF | AW AW AW MS MS Chkd | AW AW AW AW AW AW AW APP'd | 10.08.23 03.08.23 11.07.23 04.07.23 18.05.23 14.04.23 27.03.23 Date |
| | E D C B A Rev Job Ti | FLOATATION DRAWIN FLO-WHI-LAY- INF ARMED SOLE BUT ACCED RED LIKE STE BOUNDARY AMENGED. RED LIKE STE BOUNDARY AMENGED. RED LIKE STE BOUNDARY AMENGED. SUBSTATION ACCESS ROAD TE-M AMENGED. SUBSTATION ACCESS ROAD TE-M AMENGED. SLORE ZOME ADDED SLORE ZOME ADDED SLOR | NG N 0000 PMcG PMcG PMcG PMcG PMcG PMcG By DSSS NDF | AW AW AW MS MS Chkd | AW AW AW AW AW AW AW APP'd | 10.08.23 03.08.23 11.07.23 04.07.23 18.05.23 14.04.23 27.03.23 Date |
| | E D C B A Rev Job Ti | FLOATATION DRAWIN FLO-WHI-LAY- FLO-WHI-LAY- REVARENCED SOLE BUT ACCED HED LIKE STRE BUTWARENCED. RED LIKE STRE BUTWARENCED. RED LIKE STRE BUTWARENCED. SUBSTATION RECORDING TO ADDED SUBSTATION ACCESS ROAD TEAM ANENCED. SUBSTATION AT THAT CONSTRUCTION COMPOUND AND AND THAT CONSTRUCTION COMPOUND AND AND THAT CONSTRUCTION COMPOUND AND AND THAT CONSTRUCTION COMPOUND AND AND AND AND AND AND AND AND AND A | NG N 0000 PMcG PMcG PMcG PMcG PMcG PMcG By DSSS NDF | AW AW AW MS MS Chkd | AW AW AW AW AW AW AW APP'd | 10.08.23 03.08.23 11.07.23 04.07.23 18.05.23 14.04.23 27.03.23 Date |
| | E D C A Rev Job Ti | FLOATATION DRAWIN FLO-WHI-LAY- SCALE BAR ACCED RED LAS STE BOUNDARY AMENDED. RED LAS STE BOUNDARY AMENDED. RED LAS STE BOUNDARY AMENDED. SUBSTATION ACCESS ROAD TE-AN AMENDED. SUBSTATION ACCESS ROAD TE-AN AMENDED. SLOPE ZOME ADDED. SUBSTATION AND CONSTRUCTION COMPOUND AND PARE ON STRUCTION COMPOUND AND PARE ON STRUCTION SUBSTATION AND PARE ON STRUCTION COMPOUND AND PARE ON STRUCTION COMPOUND AND PARE ON STRUCTION COMPOUND AND PARE ON STRUCTION SUBSTATION AND PARE ON STRUCTION COMPOUND AND PARE ON STRUCTION COMPOUND AND PARE ON STRUCTION SUBSTATION AND STRUCTION COMPOUND AND PARE ON STRUCTION COMPOUND AND PARE ON STRUCTION SUBSTATION AND STRUCTION COMPOUND AND PARE ON STRUCTURE COMPOUND AND PARE ON STRUCTU | NG N 0000 PMcG PMcG PMcG PMcG PMcG PMcG By DSSS NDF | AW AW AW AW AW AW MS MS Chkd | AW AW AW AW AW AW AW AW STA | 10.0823 03.0823 11.0723 04.0723 18.0523 14.0423 27.0323 Date |
| | E D C A Rev Job Ti | FLOATATION DRAWIN FLO-WHI-LAY- INF ARMED SOLE BUT ACCED RED LIKE STE BOUNDARY AMENGED. RED LIKE STE BOUNDARY AMENGED. RED LIKE STE BOUNDARY AMENGED. SUBSTATION ACCESS ROAD TE-M AMENGED. SUBSTATION ACCESS ROAD TE-M AMENGED. SLORE ZOME ADDED SLORE ZOME ADDED SLOR | NG N 0000 PMcG PMcG PMcG PMcG PMcG By DSSS NDF AN ED S | AW AW AW AW AW AW AW AW AW AW AW AW AW A | AW AW AW AW AW AW AW STA | 10.08.23 03.08.23 11.07.23 04.07.23 18.05.23 14.04.23 27.03.23 Date |
| | E D C A Rev Job Ti | FLOATATION DRAWIN FLO-WHI-LAY- SCALE MA ACCED RED LAW STE BOUNDARY AMENDED. RED LAW STE BOUNDARY AMENDED. RED LAW STE BOUNDARY AMENDED. SUBSTATION ACCESS ROAD TE-WAMENCED. LAYOUT AND ORIENTATION CHANGED AND RELOCATED. SLOPE ZOME ADDED SUBSTATION ACCESS ROAD TE-WAMENCED. LAYOUT AND ORIENTATION CHANGED AND RELOCATED. SUBSTATION APPO CONSTRUCTION COMPOUND AMENDED & RELOCATABD. FLOATATION DARWING NUMBER ADDED USUBSTATION APPO CONSTRUCTION COMPOUND AMENDED & RELOCATABD. FLOATATION DARWING NUMBER ADDED USUBSTATION AFMP CONSTRUCTION COMPOUND AMENDED & RELOCATABD. SUBSTATION AFMP COMPOUND AMENDAD. SUBSTATION AFMP COMPOUND AMENDED & RELOCATABD. SUBSTA | PMcG PMcG PMcG PMcG PMcG PMcG PMcG By DSSS NDF AN ED S AN | AW AW AW AW AW MS MS Chkd | AW AW AW AW AW AW AW STA | 10.08.23 03.08.23 11.07.23 04.07.23 18.05.23 14.04.23 27.03.23 Date |
| | E D C B A Rev Job Ti | FLOATATION DRAWIN FLO-WHI-LAY- SOLE BAR ACCED RED LINE STE BOUNDARY AMENDED. RED LINE STE BOUNDARY AMENDED. RED LINE STE BOUNDARY AMENDED. SUBSTATION ACCESS ROAD TE-WI AMENDED SUBSTATION ACCESS ROAD TE-WI AMENDED SLOPE ZOME ADDED SLOPE ZOME ADDED ZOME ADDED ZOM | NG N 0000 PMcG PMcG PMcG PMcG PMcG PMcG By DSSS NDF By DSSS NDF | AW AW AW AW MS MS Chkd SUB | AW AW AW AW AW AW AW AW AW AW STA | 10.08.23 03.08.23 11.07.23 04.07.23 18.05.23 14.04.23 27.03.23 Date |
| | E D C A A Rev Job Ti INE | FLOATATION DRAWIN FLO-WHI-LAY- SILE STANDAGED SOLE BUR ACCED HED LIKE STE BOUNDARY AMENOED. RED LIKE STE BOUNDARY AMENOED. SUBSTATION ACCESS ROAD TEA MAENOED. SUBSTATION AT ELMP CONSTRUCTION COMPOSITION FLOAT TO CHANGED AND RECOATED. SUBSTATION A TEAM CONSTRUCTION COMPOSITION TRANSFORMED SUBSTATION A TEAM CONSTRUCTION SUBSTATION A TEAM CONSTRUCTION SUBSTATION A TEAM CONSTRUCTION CONSTRUCTION TRANSFORMED SUBSTATION A TEAM CONSTRUCTION CONSTRUCTION SUBSTATION A TEAM CONSTRUCTION SUBSTATION A TEAM CONSTRUCTION A SUBSTATION A TEAM CONSTRUCTION SUBSTATION A TEAM CONSTRUCTION SUBSTATION A TEAM CONSTRUCTION SUBSTATION A TEAM CONSTRUCTION A SUBSTATION A TEAM CONSTRUCTION SUBSTATION A TEAM CONSTRUCTION A SUBSTATION A TEAM | PMcG PMcG PMcG PMcG PMcG PMcG PMcG By DSSS DDSS DDSS DDSS DDSS DDSS DDSS D | AW AW AW AW MS MS Chkd SUB | AW AW AW AW AW AW AW AW AW AW STA | 10.08.23 03.08.23 11.07.23 18.05.23 14.04.23 27.03.23 Date |
| | E D C B A Rev Job Ti INE Scale Drawn | FLOATATION DRAWIN FLO-WHI-LAY- SCALE BAR ADDED SCALE BAR ADDED SCALE BAR ADDED SCALE BAR ADDED SUBSTATION RECOVER AND COMMANTES UPATED SUBSTATION ACCESS ROAD TE: AN ARENCED LAYOUT AND ORIENTATION CHANGED AND RELOCATED. SUBSTATION AND AND TE: AN ARENCED LAYOUT AND ORIENTATION CHANGED AND COMPOUND AND PLO & RELOCATABD SUBSTATION AT AND ORIENTATION CHANGED AND COMPOUND AND PLO & RELOCATABD SUBSTATION AND AND COMPANY SUBSTATION AND AND COMPANY SUBSTATION AND AND COMPANY SUBSTATION AND COMPANY SUBSTATION AND AND COMPANY SUBSTATION AND AND COMPANY SUBSTATION AND COMPANY SUBSTATION AND COMPANY SUBSTATION AND COMPANY SUBSTATION AND COMPANY SUBSTATION AND AND COMPANY SUBSTATION AND COMPANY | PMcG PMcG PMcG PMcG PMcG PMcG PMcG PMcG | AW AW AW AW MS MS Chk'd Chk'd Slasgc odplc | AW AW AW AW AW AW AW AW AW AW STA | 10.08.23 03.08.23 11.07.23 18.05.23 14.04.23 27.03.23 Date |
| TIRON | E D C B A Rev Job Ti INE Scale Drawn Status | FLOATATION DRAWIN FLO-WHI-LAY- SILE STANDAGED SOLE BUR ACCED HED LIKE STE BOUNDARY AMENOED. RED LIKE STE BOUNDARY AMENOED. SUBSTANDA RELOCATED AND CONSTRUCTION UNITED. SUBSTANDA ACESS ROAD TEA MAENOED. SLOPE ZONE ADDED. SUBSTANDA ATEMP CONSTRUCTION COMPORT AND ORIENTATION CHANGED AND RELOCATED. SUBSTANDA ATEMP CONSTRUCTION COMPORT AND AND AND AND AND AND AND COMPORT AND AND AND AND AND AND AND SUBSTANDA AND AND AND AND AND AND AND SUBSTANDA AND AND AND AND AND AND AND SUBSTANDA AND AND AND AND AND AND AND AND AND | PMcG PMcG PMcG PMcG PMcG PMcG PMcG PMcG | AW AW AW AW MS MS Chk'd Chk'd Slasgc odplc | AW AW AW AW AW AW AW AW AW AW STA | 10.0823 03.0823 11.07.23 18.0523 14.0423 27.0323 Date |
| | E D C B A Rev Job Ti Job Ti INE S Scale Drawn Status | FLOATATION DRAWIN FLO-WHI-LAY- SILE STANDAGED SOLE BUR ACCED HED LIKE STE BOUNDARY AMENOED. RED LIKE STE BOUNDARY AMENOED. SUBSTANDA RELOCATED AND CONSTRUCTION UNITED. SUBSTANDA ACESS ROAD TEA MAENOED. SLOPE ZONE ADDED. SUBSTANDA ATEMP CONSTRUCTION COMPORT AND ORIENTATION CHANGED AND RELOCATED. SUBSTANDA ATEMP CONSTRUCTION COMPORT AND AND AND AND AND AND AND COMPORT AND AND AND AND AND AND AND SUBSTANDA AND AND AND AND AND AND AND SUBSTANDA AND AND AND AND AND AND AND SUBSTANDA AND AND AND AND AND AND AND AND AND | PMcG PMcG PMcG PMcG PMcG PMcG PMcG PMcG | AW AW AW AW AW MS Chk'd SIASQU | AW AW AW AW AW AW AW AW AW AW AW AW AW A | 10.08.23 03.08.23 11.07.23 18.05.23 14.04.23 27.03.23 Date |






| SWITCHYARD CAN BE MODIFIED TO ADAP ACCESS, TEE LINE OUTPUT DIRECTION ET PHILOSOPHY MUST BE KEPT UP. 2. LAYOUT OF WATER TANK AND SEALED TA MUST BE ADAPTED ACCORDING TO APPLIC LEGISLATION. | | | | | | |
|--|--|---------------------|--|--|--|--|
| MUST BE ADAPTED ACCORDING TO APPLIC LEGISLATION. | | | | | | |
| | 2. LAYOUT OF WATER TANK AND SEALED TANK MUST BE ADAPTED ACCORDING TO APPLICABLE | | | | | |
| 2. NUMBER OF CAFACITOR BANKS ACCORDIN PERFORMANCE ENGINEERING DEPARTMEN CALCULATION. | | 0 | | | | |
| 4. DISTANCES BETWEEN PHASES MUST BE HIGHER THAN 1.75m BUT NEVER HIGHER THAN THE | | | | | | |
| 5. THE BEDPLATE BUILT FOR MV CUBICLES H BE PREPARED TO INSTALL AN ADDITIONAL CUBICLE. | | | | | | |
| 6. AUXILIARY SERVICE TRANSFORMER MV TERMINALS SHALL BE OUTDOOR PLUG-IN / TERMINAL. | ANGL | .E | | | | |
| 7. THE CONNECTION BETWEEN THE HV/MV TRANSFORMER AND THE HV SURGE ARRE SHALL BE THROUGH CABLE, AVOIDING THE BARS CONNECTION. | | | | | | |
| 8. SPOTLIGHT PROJECTORS SHOWN ARE INI ONLY FOR PLANNING PURPOSES. FINAL NI AND LOCATIONS WILL DEPEND ON FINAL D | UMBE | R | | | | |
| 9. POST INSULATOR MUST BE INSTALLED. | | | | | | |
| | 00.47 | TED | | | | |
| 10. LAYOUT OF COUNTERS ROOM WILL BE LO ACCORDING TO UTILITY REQUIREMENTS | | Cυ | | | | |
| 11. FOR SECTION A-A DETAILS REFER TO DR | AWIN | ١G | | | | |
| 808165-01-EL-LAY-0001-007. | | | | | | |
| 0 5m 10m 15m | | 20m | | | | |
| Scale 1:500 @ A3 | | | | | | |
| FLOATATION DRAWING NUME | BER | | | | | |
| FLO-WHI-LAY-0001 | | | | | | |
| G DRAWING TITLE AMENDED. PMcG AW | AW | 10.08.23 | | | | |
| F BUILDING STEPS & ACCESS RAMPS ADDED. PMcG AW GENSET & DIESEL STARAGE AREA AMENDED. | AW | 07.07.23 | | | | |
| E EIGHTH MV SWITCHGEAR ADDED. PMcG MS SUBSTATION SIZE AMENDED. | AW | 01.06.2 | | | | |
| D CONTROL BUILDING RELOCATED. PMcG MS ACCESS ROADS & FENCELINES AMENDED. PMCG MS | AW | 17.05.23 | | | | |
| C ACCESS ROADS AMENDED TO SUIT. PMcG MS FLOATATION DRAWING NUMBER ADDED. | AW | 21.04.23 | | | | |
| B DRAWING TITLE AMENDED. PMcG MS | AW | 14.03.23 | | | | |
| A ISSUED FOR REVIEW PMcG MS | AW | 01.03.23 | | | | |
| | App'd | Date | | | | |
| WHITE CROSS OFFSHORE WINDFARM | | | | | | |
| FLOOR PLAN INDICATIVE AIS ENCLOSED SUBSTATION (OPTION B) | | | | | | |
| | wood. | | | | | |
| (OPTION B) | Þ | | | | | |
| (OPTION B) | | 2 5LP | | | | |
| (OPTION B) WOODd St Vincent Plaza, 319 St Vincent Street, Glasgo tel: +44 (0) 141 227 1700 www.woodpic Scale 1.500 Date | .com Size | | | | | |
| (OPTION B) Woodd St Vincent Plaza, 319 St Vincent Street, Glasgo tet: +44 (0) 141 227 1700 www.woodplc | .com Size | ² 5LP \ 3 | | | | |
| (OPTION B) WOOOd St Vincent Plaza, 319 St Vincent Street, Glasgo tel: +44 (0) 141 227 1700 www.woodplc Scale 1:500 Data MARCH 2023 Diam PMcG Checked MS Approved AW | .com Size | | | | | |
| (OPTION B) WOODOO St Vincent Plaza, 319 St Vincent Street, Glasgo tel: +44 (0) 141 227 1700 www.woodplc Stelle 1:500 Date Travn PMcG Checked MS Approved AW Status | .com Size | | | | | |





NOTES


. FOR LAYOUT PLAN VIEW REFER TO DRAWING No.




P:\6000\2022_Tasks\808165_Whitecross\808165-01-EL-LAY-0001-008-H.dwg

| 00E | <u>KE</u>) | (| | | | |
|--|---------------|--|--------------------|-------|-------|---------------|
| 248400E | | PROJECT REI | זארו ר | | חאוו | |
| N 132400N | | FINUJEUT KEL | | - 50 | UND | / 11 1 |
| 132400N | | PERMANENT | ACCE | SS F | Roae | |
| | 🚅 | <u></u> | | | | |
| | | PROPOSED S | UBST | ATIC | ON | |
| | | | | | | |
| | | TEMPORARY | CONS | STRU | JCTI | ОЛ |
| | | COMPOUND | | | | |
| | | TEMPORARY | CONS | STRL | JCTI | ОЛ |
| | | ACCESS ROA | | | | |
| | _ : | | ERHF | AD C | ARI | _{es} |
| BIBIBIBIS | | | | | | |
| | | INDICATIVE B | UFFE | R SL | OPE | |
| | | | | | | |
| | | PROPOSED SUB | STAT | ON | | |
| 18-11 - 10 AT 1/1 | | COORDINA | TES | | | |
| and the second second | | | NORT | | _ | |
| and the second s | | P1 248189.51E | 13219 13215 | | | |
| | | | 13209 | | | |
| | | P4 248107.42E | 13213 | 7.611 | N | |
| 132200N | _ | | | | | |
| 1322001 | | | | | | |
| | - | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| III HAII | 0 | 20m 40m 60r | n | 80m | 10 | 0m |
| | ' | Scale 1:2500 @ |) A3 | | | |
| | | FLOATATION DRAW | NG | IUM | BER | |
| | | FLOATATION DRAW | - | - | υĽΝ | - I |
| | | | | | | |
| | | | | | | |
| | Н | KEY AMENDED. SCALE BAR ADDED. | PMcG | AW | AW | 10.08.23 |
| | G | RED LINE BOUNDARY AMENDED. | PMcG | AW | AW | 03.08.23 |
| | F | RED LINE BOUNDARY ADDED. SUBSTATION RELOCATED AND COORDINATES UPDATED. | PMcG | AW | AW | 11.07.23 |
| | Е | SUBSTATION ACCESS ROAD TIE-IN AMENDED. | PMcG | AW | AW | 04.07.23 |
| | D | LAYOUT AND ORIENTATION CHANGED AND RELOCATED. | PMcG | MS | AW | 18.05.23 |
| 132000N | с | SLOPE ZONE ADDED. SUBSTATION & TEMP CONSTRUCTION COMPOUND AMENDED. | PMcG | MS | AW | 21.04.23 |
| | | FLOATATION DRAWING NUMBER ADDED. DRAWING TITLE AMENDED. | | | | |
| | В | CABLE CORRIDORS AMENDED. SUBSTATION COORDINATES ADDED. | PMcG | MS | AW | 14.03.23 |
| | A | ISSUED FOR REVIEW | PMcG | MS | AW | 01.03.23 |
| | Rev Job Ti | Description | Ву | Chk'd | App'd | Date |
| This a line | | | | | | |
| CALL E BOIL | | WHITE CR | oss | | | |
| 1 Martin | | OFFSHORE WI | NDF | ARI | М | |
| Sale VIDA | | | | | | |
| | Drg Tit | e | | | | |
| | | LAYOUT P | | | | |
| | ND | ICATIVE GIS ENCLOS | | SUE | 3ST/ | ATION |
| | | (OPTION | B) | | | |
| | | | | | | |
| A when a start the | | | | | | |
| | | | | | | |
| | | WOO | | | ŀ | |
| | | | | | • | |
| | L. | | | 21- | | |
| 131800N | | tel: +44 (0) 141 227 1700 w | street, 0 ww.wo | odplo | .com | : 5LP |
| A STATE A LOU | Scale | | IARCH 2 | 023 | Size | 13 |
| and the second of the | Drawn | PMcG MS Appr | roved A | w | | 43 |
| The Aller and | Status | PRELIMI | VAR' | Ý | | |
| BOOD BOOD BOOD BOOD BOOD BOOD BOOD BOOD | Drawi | | | | | Revision |
| 248400E | 8 | 0816501-01-EL-LAY | -000 | 1-00 | 8 | н |
| The second se | 1 | | | | | |






| NOTE | S | | | | |
|--|--|--|--|--|--|
| SWI ACC | Yout of control building Itchyard can be modifie Cess, tee line output dir Losophy must be kept uf | D TO | ADAP | T TO | |
| MUS | YOUT OF WATER TANK AND ST BE ADAPTED ACCORDING GISLATION. | | | | E |
| PEF | MBER OF CAPACITOR BANK RFORMANCE ENGINEERING I LCULATION. | | | | 0 |
| THA | STANCES BETWEEN PHASES AN 1.75m BUT NEVER HIGHEF TANCE BETWEEN PHASES D | r tha | N TH | Ξ | ER |
| BEI | E BEDPLATE BUILT FOR MV (PREPARED TO INSTALL AN A BICLE. | | | | 0 |
| TEF | XILIARY SERVICE TRANSFOR RMINALS SHALL BE OUTDOO RMINAL. | | | ANGL | .E |
| TRA SHA | E CONNECTION BETWEEN TI ANSFORMER AND THE HV SU ALL BE THROUGH CABLE, AV RS CONNECTION. | JRGE | ARRE | | |
| IND FIN/ | OTLIGHT PROJECTORS SHO ICATIVE ONLY FOR PLANNIN AL NUMBER AND LOCATIONS AL DESIGN. | IG PUI | RPOS | | ON |
| 9. PO | ST INSULATOR MUST BE INS | TALL | ED. | | |
| | AYOUT OF COUNTERS ROOM CCORDING TO UTILITY REQU | | | | ΈD |
| | DR SECTION A-A & PROFILE I AWING No.808165-01-EL-LAY- | | | FER | то |
| 0 5m 10m 15m 20m Scale 1:500 @ A3 | | | | | |
| F | Scale 1:500 @ A | 3 G NI | | | 0m ⊐ |
| F | Scale 1:500 @ A3 | 3 G NI | | | 0m ∃ |
| G | Scale 1:500 @ A FLOATATION DRAWIN FLO-WHI-LAY-(SWING THE AMENDED WORTH AREOND & SCALE BAR ADDED. | 3 G NI | | | 0m ∃ |
| G | Scale 1:500 @ A FLOATATION DRAWIN FLO-WHI-LAY-(2904996 THE AVENCED. | 3 G NI 0009 | JMB | ER | |
| G F E | Scale 1:500 @ A FLOATATION DRAWIN FLO-WHI-LAY-O SRAWNG THE AMENGED. WICHT MENON & SCALE WIR ADDED. SHORT & MONECUL BUILDING STEPS & ACCESS RAMPS ADDED. SENSET & DESE STRACE AREA AMENGED. SENSET & DESE STRACE AREA AMENGED. | 3 G NI)009 PMcG | JMB | ER | 10.08.23 |
| G F E D | Scale 1:500 @ A FLOATATION DRAWIN FLO-WHI-LAY-(WATH MEDVA 5CALE BUR ADDED. WATH MEDVA 5CALE BUR ADDED. WATH AND STEPS & ACCESS RAMPS ADDED. ENSIT & DESEL STANCE AREA ADDED. ENSIT & STANCE AREA ADDED. SIGNITAN WITCH STANCE ADDED. SIGNITAN WITCH STANCE ADDED. SIGNITAN WITCH STANDED. SIGNITAN WITCH STANDED. SIGNITAN WITCH STANDED. | 3 GNU 0009 PMcG PMcG | JMB aw aw | ER aw aw | 10.08.23 |
| G F E D C C | Scale 1:500 @ A: FLOATATION DRAWIN FLO-WHI-LAY-(SNINK TILL ANNER: NOTE A MENDED: SNILDING STEPS & ACCESS RAMPS ADDED. SINT DING STEPS AND STEPS ADDED. SINT DING STEPS ADDED. SINT D | 3 G NI 0009 PMcG PMcG PMcG | JMB AW AW MS | AW AW | 10.08.23 05.07.23 01.06.23 |
| | Scale 1:500 @ A2 FLOATATION DRAWIN FLO-WHI-LAY-C SINNES THE MEMORY WOTH AREVIS A SCALE ARA ADDED WOTH AREVIS A SCALE ARA ADDED WOTH AREVIS A SCALE ARA ADDED WOTH AREVIS A SCALE ARA ADDED SINTEN IS AND A SCALE ARA ADDED SIN | 3 GNU 0009 PMcG PMcG PMcG | AW AW MS MS | ER AW AW AW AW | 10.08.23 05.07.23 01.06.23 05.05.23 |
| G F E C C C C C C C C C C C C C C C C C C | Scale 1:500 @ A2 FLOATATION DRAWIN FLO-WHI-LAY-C STANMING THE AVENDED WATH ARKON & SCALE BUR ADDED. WATH ARKON & SCALE BUR ADDED. WATH ARKON & SCALE BUR ADDED. WATH AND AND ADDED. STATUM STEPS & ACCESS RAMPS A DEDED. STATUM STATUM STEPS & ACCESS RAMPS ADDED. STATUM STATUM STEPS & ACCESS REUCATED. COSTRO BUILDING REUCATED. COSTRO BUILDING REUCATED. COSTRO BUILDING REUCATED. COSTRO BUILDING REUCATED. COSTRO BUILDING REUCATED. TATICE & DYNAMIC COMPENSATOR REAS & LABELS ADDED. | 3 G NI D009 PMcG PMcG PMcG PMcG PMcG | JMB AW AW MS MS MS | ER AW AW AW AW | 10.08.23 05.07.23 01.06.23 05.05.23 14.04.23 20.03.23 |
| G F E C C C C A A IS Rev [| Scale 1:500 @ A: FLOATATION DRAWIN FLO-WHI-LAY-C SWIMMO THE AVENDED WORTS A MENDED WORTS A MENDED SWIMMO THE AVENDE AR ADDED. WIT S A MENDED SWIMMO STELE STANGE AREA ANDED. SWITCH SCALE STANGE AREA SWITCHEAR ADDED. SWITCHEAR ADDED. SWITCHEAR ADDED. CONTROL BUILDING RELOCATED. CONTROL BUILDING RELOCATED. CONTROL BUILDING RELOCATED. CONTROL BUILDING RELOCATED. CONTROL BUILDING RELOCATED. SUBJECT ON REVIEW Description | 3 G NI 0009 PMcG PMcG PMcG PMcG | AW AW MS MS | ER AW AW AW AW | 10.08.23 05.07.23 01.06.23 05.05.23 14.04.23 |
| G F E C SIC | Scale 1:500 @ A: FLOATATION DRAWIN FLO-WHI-LAY-C SWIMMO THE AVENDED WORTS A MENDED WORTS A MENDED SWIMMO THE AVENDE AR ADDED. WIT S A MENDED SWIMMO STELE STANGE AREA ANDED. SWITCH SCALE STANGE AREA SWITCHEAR ADDED. SWITCHEAR ADDED. SWITCHEAR ADDED. CONTROL BUILDING RELOCATED. CONTROL BUILDING RELOCATED. CONTROL BUILDING RELOCATED. CONTROL BUILDING RELOCATED. CONTROL BUILDING RELOCATED. SUBJECT ON REVIEW Description | 3 G NU 0009 PMcG PMcG PMcG PMcG PMcG PMcG By | AW AW MS MS MS Chkd | ER AW AW AW AW AW AW | 10.08.23 05.07.23 01.06.23 05.05.23 14.04.23 20.03.23 15.03.23 |
| G T F E C C C A A IS S A IS C C A A IS S A IS C A I | Scale 1:500 @ A ELOATATION DRAWIN FLO-WHI-LAY-C SHIMM THE ANEME NOTE AMENDED SUBJECT STATUS SUBJECT STAT | B B B B B B B B B B B B B B | AW AW MS MS MS MS Chird | ER AW AW AW AW AW AW APP'd | 10.08.23 05.07.23 01.06.23 05.05.23 14.04.23 20.03.23 15.03.23 Date |
| G T F E C C C A A IS S A IS C C A A IS S A IS C A I | Scale 1:500 @ A2 ELOATATION DRAWIN FLO-WHI-LAY-C SUMMO THE ANEXDED WITH AND ALL AND ALL SUMMO THE ANEXDED WITH AND ALL SUMMO THE ANEXDED SU | 3 G NI 0009 PMcG PMCG PMC | JMB AW AW MS MS MS MS MS Chk/d ARI SUB | ER AW AW AW AW AW AW APP'd | 10.08.23 05.07.23 01.06.23 05.05.23 14.04.23 20.03.23 15.03.23 Date |
| G E E E E E E E E E E E E E E E E E E E | Scale 1:500 @ A2 ELOATATION DRAWIN FLO-WHI-LAY-C SUMME THE ANEME: STATUS AND A STAT | 3 G NU 0009 PMcG PMCG PMC PMC PMC PMC PMC PMC PMC PMC | AW AW MS MS MS MS Chkd | ER AW AW AW AW AW AW AW AW AW AW STA | 10.08.23 05.07.23 01.06.23 05.05.23 14.04.23 20.03.23 15.03.23 Date |
| G E E E E E E E E E E E E E E E E E E E | Scale 1:500 @ A2 ELOATATION DRAWIN FLO-WHI-LAY-C SAMME THE AVENCE WITH AND A CONTRACT AND A CONT | 3 G NU 0009 PMcG PMcG PMcG PMcG PMcG PMcG PMcG PMcG PMcG C C C C C C C C C C C C C | AW AW MS MS MS MS Chkd | ER AW AW AW AW AW AW AW AW AW AW AW AW AW | 10.08.23 05.07.23 01.06.23 05.05.23 14.04.23 15.03.23 15.03.23 Date |
| G T F E E E E E E E E E E E E E E E E E E | Scale 1:500 @ A2 ELOATATION DRAWIN FLO-WHI-LAY-C WITE ANALORD SUBJECT OF THE STREAM OF THE OF | 3 G NI 0009 PMcG PMcG PMcG PMcG PMcG PMcG PMcG By PMcG By PMcG C PMcG C C C | AW AW MS MS MS MS Chkd | ER AW AW AW AW AW AW AW AW AW AW AW AW AW | 10.08.23 05.07.23 01.06.23 05.05.23 14.04.23 20.03.23 15.03.23 Date |
| G E E E E E E E E E E E E E E E E E E E | Scale 1:500 @ A2 ELOATATION DRAWIN FLO-WHI-LAY-C WINNE THE ANENEE SUPPORT OF A CESS FAMES ACCES SUPPORT ADDRES STANGE ARADED. USES TO SEE STANGE ARADED. U | 3 G NU 0009 PMcG PMcG PMcG PMcG PMcG PMcG PMcG PMcG PMcG PMcG C PMcG PMCG | AW AW MS MS MS MS Chkd | ER AW AW AW AW AW AW AW AW AW AW AW AW AW | 10.08.23 05.07.23 01.06.23 05.05.23 14.04.23 15.03.23 15.03.23 Date |




NOTES

- 1. FOR LAYOUT PLAN VIEW REFER TO DRAWING No. 808165-01-EL-LAY-0001-014.
- 2. PALISADE SECURITY GATE & FENCING AROUND PERIMETER OF SITE.
- 3. AIR CONDITIONING VENTS SHOWN ARE INDICATIVE ONLY FOR PLANNING PURPOSES. FINAL NUMBER AND LOCATIONS WILL DEPEND ON FINAL BUILDING DESIGNS.
- 4. SPOTLIGHT PROJECTORS SHOWN ARE INDICATIVE ONLY FOR PLANNING PURPOSES. FINAL NUMBER AND LOCATIONS WILL DEPEND ON FINAL DESIGN.



| St \ | St Vincent Plaza, 319 St Vincent Street, Glasgow, G2 5LP tel: +44 (0) 141 227 1700 www.woodplc.com | | | | |
|-----------|---|---------------|--------------------|----------|--|
| Scale | 1:500 | | Date MARCH 2023 | Size | |
| Drawn | PMcG | Checked MS | Approved AW | A3 | |
| Status | | PRELI | MINARY | | |
| Drawing I | No. | | | Revision | |
| 8 | 08165- | 01-EL-LA | Y-0001-01 | 5 н | |



P:\6000\2022_Tasks\808165_Whitecross\808165-01-EL-LAY-0001-016-G.dwg



White Cross Offshore Windfarm Environmental Statement

Appendix 5.F: Project Parameters Table





Appendix 5.F Project Parameters Table

Table 5F.1 shows the over-arching project parameters for Onshore Project.

Table 5F.1 Onshore Project parameters

| Parameters | Minimum | Maximum |
|---|------------|--------------------|
| Export Cables | | |
| Number cable circuits | 1 | 2 |
| Circuit voltage | 66kV | 132kV |
| No. drills per trenchless crossing | 1 | 2 |
| No. trenches for opencut | 1 | 2 |
| Offshore Export Cable | | |
| Total length Offshore Export Cable (installed above MLWS) (m) | N/A | 860 |
| Total horizontal length trenchless technique at Landfall (m) | 60 | 1,850 ¹ |
| Total horizontal length opencut technique at Landfall (m) | N/A | 800 ² |
| Transition Joint Bay dimensions (length x width x height) (m) | 20 x 5 x 2 | 20 x 8 x 2 |
| No. Transition Joint Bay | N/A | 1 |
| Onshore Export Cable | | |
| Total length (m) | N/A | 8,000 |
| Total length major trenchless crossings (m) | N/A | 2,500 ³ |
| Total length opencut (m) | N/A | 5,500 |
| Onshore Cable Corridor | | |
| Cable trench width per cable (m) | 0.89 | 4 |
| Cable trench depth (m) | 1.6 | 1.9 |
| Cable construction width (onshore corridor) (m) | 12 | 60 |



| Parameters | Minimum | Maximum |
|---|-----------|--------------|
| Cable construction width at trenchless crossings (m) | 7 | 15 |
| Depth to top of buried infrastructure (ducts) (m) | 1.2 | 1.5 |
| Depth to top of jointing bay (m) | 1.2 | 1.5 |
| Jointing bay dimensions (length x height) (m) | N/A | 12 x 4 x 1.5 |
| No. jointing bay | 15 | 30 |
| Link box dimensions (length x width x height) (m) | 2 x 2 x 1 | 3 x 3 x 2 |
| No. of link box | 15 | 30 |
| Compounds, haul road, working | width | |
| Construction compound areas (m2) ⁴ | 13,680 | 16,000 |
| Mobilisation areas (m ²) | N/A | 30,000 |
| Haul road width (m) | 5 | 8 |
| Haul road length (m) | N/A | 6,500 |
| Running track width | N/A | 4 |
| White Cross Onshore Substation | | |
| Substation operational footprint area (m ²) | 4,750 | 5,300 |
| Substation building dimensions (length x width) (m) | 59 x 23 | 71 x 24 |
| Substation building area (m ²) | 1,357 | 1,704 |
| Substation building height (m) | N/A | 10 |
| Control building dimensions (length x width) (m) | N/A | 35 x 9 |
| Control building height (m) | N/A | 8 |
| Control building area (m ²) | N/A | 315 |
| External equipment height (m) | N/A | 10 |
| Finished Floor Level (m AOD) | N/A | 6.73 |
| Building platform area (m ²) | N/A | 7,700 |



Footnotes:

I – Landfall Option 3 includes 1,000m below MLWS which is assessed in the Offshore ES $% \left({{{\rm{S}}_{\rm{B}}} \right)$

2 – Opencut include 700m on the beach/intertidal area, and 100m onshore

3 – Combined length Golf Course and Taw Estuary

Crossings

4 – Includes all compounds to support the Onshore Project



White Cross Offshore Windfarm Environmental Statement

Appendix 5.G: Crossing Schedule





Appendix 5.G Crossing Schedule

Table 5G.1 shows crossing schedule for the Onshore Export Cable. It should be viewed alongside the Onshore Cable Route – Working Width Alignment Sheets (*Figures 6 to 10* within **Appendix 5.D**)

| Crossing Number | Cable Installation Method | Haul Road Crossing Method |
|----------------------------|---------------------------|--------------------------------|
| RDX 1 | Major Trenchless | N/A |
| DX 1/1 | Opencut | Culvert |
| DX 1/2 | Opencut | Culvert |
| DX 1/3 | Opencut | Culvert |
| DX 1/4 | Opencut | Culvert |
| DX 1/5 | Opencut | Culvert |
| DX 1/6 | Opencut | Culvert |
| DX 1/7 | Opencut | Culvert |
| DX 1/8 | Opencut | Culvert |
| DX 1/9 | Opencut | Culvert |
| DX 1/10 | Opencut | Culvert |
| RDX 2 (Sandy Lane) | Trenchless | Crossing Point (Access 8a/b) |
| DX 2/1 | Trenchless | Bridge |
| DX 2/3 ¹ | Opencut/Trenchless | Culvert /Bridge/ Floating Road |
| DX 2/4 ¹ | Opencut/Trenchless | Culvert /Bridge/ Floating Road |
| DX 2/5 ² | Opencut/Trenchless | Culvert /Bridge |
| TX 2/1 ² | Opencut/Trenchless | Culvert /Bridge |
| DX 2/6 ² | Opencut/Trenchless | Culvert /Bridge |
| DX 2/7 | Opencut | Culvert |
| DX 2/8 ³ | Opencut/Trenchless | Culvert /Bridge |
| TX 2/2 ³ | Opencut/Trenchless | Culvert /Bridge |
| DX 2/9 ³ | Opencut/Trenchless | Culvert /Bridge |
| RDX 3 | Major Trenchless | N/A |
| RVX 1 (River Taw) | Major Trenchless | N/A |
| DX 3/1 | Opencut | Culvert |

Table 5G.1 Onshore Export Cable crossing schedule



| Crossing Number | Cable Installation Method | Haul Road Crossing Method |
|----------------------|---------------------------|-------------------------------|
| DX 3/2 | Opencut | Culvert |
| TX 3/1 (Tarka Trail) | Trenchless | Crossing Point (Access 16a/b) |
| DX 3/2 ⁴ | Trenchless | N/A |
| OH ELEC ⁴ | Trenchless | N/A |
| DX 3/3 | Trenchless | N/A |
| TX 3/2 (Tarka Trail) | Trenchless | N/A |

Footnotes:

I – construction techniques within the Braunton Marshes will be confirmed following detailed design and may include trenchless techniques and bridges/floating roads

2 - these are all in close proximity and crossing method would be determined following detailed design, if crossed as a group trenchless/bridge crossing methods would be used

3 – these are all in close proximity and crossing method would be determined following detailed design, if crossed as a group trenchless/bridge crossing methods would be used

4 – trenchless technique will be used to reduce risks associated with working in close proximity to overhead lines, haul road would be constructed using appropriate safety measures (such as 'goal posts')